





EX·LIBRIS  
LEWIS·S·ROSE







MORPHOLOGY OF GYMNOSPERMS

THE UNIVERSITY OF CHICAGO PRESS  
CHICAGO, ILLINOIS

**Agents**

THE BAKER & TAYLOR COMPANY  
NEW YORK

---

CAMBRIDGE UNIVERSITY PRESS  
LONDON AND EDINBURGH

# MORPHOLOGY OF GYMNOSPERMS

BY

JOHN M. COULTER, Ph.D.

PROFESSOR OF BOTANY IN THE UNIVERSITY OF CHICAGO

AND

CHARLES J. CHAMBERLAIN, Ph.D.

ASSISTANT PROFESSOR OF BOTANY IN THE UNIVERSITY OF CHICAGO

WITH 462 FIGURES

THE UNIVERSITY OF CHICAGO PRESS  
CHICAGO, ILLINOIS

COPYRIGHT 1910 BY  
THE UNIVERSITY OF CHICAGO

---

All Rights Reserved

---

Published October 1910

Composed and Printed By  
The University of Chicago Press  
Chicago, Illinois, U.S.A.



## PREFACE

In 1901 our *Morphology of Spermatophytes*, Part I, was published, which comprised a presentation of the gymnosperms. It had grown out of a special course given to graduate students for several successive years, and although most of the ground had been traversed in this way several times, the larger part of the material in the book was taken from the contributions of other investigators. There was some new material included, but the chief contributions of the book were certain illustrations and the organized presentation of the group as a whole for research students.

During the last decade the special course referred to has been continued for successive generations of graduate students, with a constantly widening range of material and from new points of view. In addition to this extensive and repeated critical examination of material, a number of special investigations have been carried on in the laboratory. These investigations have been planned so that there might be not only a research contact with all regions of the gymnosperm series, but also a clearing up of unknown or doubtful forms. These special contributions from the laboratory have aggregated twenty-six since 1901, and have dealt with fourteen genera, distributed as follows: in Cycadales, *Dioon*, *Microcycas*, *Encephalartos*, *Ceratozamia*, and *Zamia*; in Ginkgoales, *Ginkgo*; in Coniferales, *Pinus*, *Thuja*, *Torreya*, *Phyllocladus*, *Podocarpus*, and *Dacrydium*; in Gnetales, *Ephedra* and *Gnetum*. This has enabled us to present the living groups from an entirely different standpoint, and to use many illustrations prepared in this laboratory. The present account, therefore, is based upon our own work, supplemented by the work of other investigators, rather than a compilation from literature, supplemented by occasional personal observations.

Furthermore, the last decade has been one of unprecedented activity in the investigation of gymnosperms, as a comparison of the bibliography of the volume of 1901 with that of the present one will indicate. In this period the number of titles has increased from 112 to 420, some of the additions being accounted for by the larger

inclusion of paleobotanical material. Aside from a far more complete knowledge of the living groups, including as it does now at least the salient facts in reference to almost every genus, there have been two notable advances. In the first place, during this period vascular anatomy has developed as a subject of first importance, and some of its most conspicuous contributions have been in connection with the origin and relationships of gymnosperms. In the second place, paleobotany has brought to light during the last decade more facts of importance in reference to the history of gymnosperms than in reference to any other group of plants. This has enabled us to treat of the extinct groups in a way that was impossible ten years ago.

Attention is called to the fact that on the basis of new knowledge we have reorganized our presentation of the gametophyte, by recognizing the spore as its first cell, rather than the mother cell, as in the previous volume. This needs no explanation, as it seems clear that the sporophyte generation ends and the gametophyte generation begins with the appearance of the spore. The plan of grouping the special literature of each great division in chronological order at the end of its presentation, and the general literature of gymnosperms in alphabetical order at the end of the volume, is continued. Such illustrations as have been copied are not only credited, but also referred to the publications in which they first appeared.

The authors appreciate, perhaps more keenly than anyone, that a book of this nature in a certain sense is out of date as soon as it has left the press. Papers will continue to appear which would have been of great service in this volume, and yet perhaps no great group of plants is just now in better condition for a presentation which professes to be only a concise summary of knowledge, useful in stimulating and guiding further research.

JOHN M. COULTER

CHARLES J. CHAMBERLAIN

THE UNIVERSITY OF CHICAGO

May 1910

## CONTENTS

	PAGE
CHAPTER I. CYCADOFILICALES . . . . .	I
1. Vegetative organs . . . . .	3
Vascular anatomy of Pteridophytes . . . . .	4
Vascular anatomy of Cycadofilicales . . . . .	12
Leaf . . . . .	21
2. Spore-producing members . . . . .	25
Microsporangium . . . . .	25
Megasporangium . . . . .	31
3. Gametophytes . . . . .	48
Female gametophyte . . . . .	48
Male gametophyte . . . . .	49
4. History and distribution . . . . .	51
5. Relationship to ferns . . . . .	51
Paleozoic ferns . . . . .	52
Origin of Cycadofilicales . . . . .	55
6. Relationship to other gymnosperms . . . . .	58
Literature cited . . . . .	60
CHAPTER II. BENNETTITALES . . . . .	65
1. Vegetative organs . . . . .	66
Vascular anatomy . . . . .	70
Leaf . . . . .	71
2. Spore-producing members . . . . .	72
Strobilus . . . . .	72
Microsporangium . . . . .	75
Megasporangium . . . . .	78
3. Gametophytes . . . . .	82
4. Embryo . . . . .	83
5. History and distribution . . . . .	85
6. Relationship to other gymnosperms . . . . .	86
Literature cited . . . . .	89

	PAGE
CHAPTER III. CYCADALES . . . . .	91
1. Vegetative organs . . . . .	93
Vascular anatomy . . . . .	93
Leaf . . . . .	108
Root . . . . .	112
2. Spore-producing members . . . . .	114
Microsporangium . . . . .	114
Megasporangium . . . . .	121
3. Gametophytes . . . . .	132
Female gametophyte . . . . .	132
Male gametophyte . . . . .	139
Fertilization . . . . .	148
4. Embryo . . . . .	150
5. History and distribution . . . . .	156
6. Relationship to other gymnosperms . . . . .	157
Literature cited . . . . .	158
CHAPTER IV. CORDAITALES . . . . .	163
1. Vegetative organs . . . . .	164
Vascular anatomy . . . . .	165
Leaf . . . . .	168
Root . . . . .	171
2. Spore-producing members . . . . .	172
Strobilus . . . . .	172
Microsporangium . . . . .	172
Megasporangium . . . . .	174
3. Gametophytes . . . . .	178
4. History and distribution . . . . .	180
5. Relationship to other gymnosperms . . . . .	180
Literature cited . . . . .	183
CHAPTER V. GINKGOALES . . . . .	185
1. Vegetative organs . . . . .	185
Vascular anatomy . . . . .	187
Leaf . . . . .	189



	PAGE
2. Spore-producing members . . . . .	190
Microsporangium . . . . .	191
Megasporangium . . . . .	194
3. Gametophytes . . . . .	203
Female gametophyte . . . . .	203
Male gametophyte . . . . .	206
Fertilization . . . . .	209
4. Embryo . . . . .	210
5. History and distribution . . . . .	215
6. Relationship to other gymnosperms . . . . .	216
Literature cited . . . . .	217
 CHAPTER VI. CONIFERALES (Pinaceae) . . . . .	 220
1. Vegetative organs . . . . .	222
Vascular anatomy . . . . .	228
Leaf . . . . .	235
2. Spore-producing members . . . . .	238
Microsporangium . . . . .	240
Megasporangium . . . . .	244
3. Gametophytes . . . . .	259
Female gametophyte . . . . .	259
Male gametophyte . . . . .	272
Fertilization . . . . .	284
4. Embryo . . . . .	287
Proembryo . . . . .	288
Suspensor and embryo . . . . .	295
5. Distribution . . . . .	301
6. History . . . . .	303
7. Interrelationship of tribes . . . . .	308
8. Relationship to other gymnosperms . . . . .	309
 CHAPTER VII. CONIFERALES (Taxaceae) . . . . .	 313
1. Vegetative organs . . . . .	315
Vascular anatomy . . . . .	315
Leaf . . . . .	317

2. Spore-producing members . . . . .	319
Microsporangium . . . . .	319
Megasporangium . . . . .	321
3. Gametophytes . . . . .	329
Female gametophyte . . . . .	329
Male gametophyte . . . . .	335
Fertilization . . . . .	344
4. Embryo . . . . .	346
Proembryo . . . . .	346
Suspensor and embryo . . . . .	348
5. History and distribution . . . . .	349
6. Relationship to other gymnosperms . . . . .	350
List of genera . . . . .	353
Literature cited . . . . .	353
 CHAPTER VIII. GNETALES . . . . .	 363
1. Vegetative organs . . . . .	364
Vascular anatomy . . . . .	366
Leaf . . . . .	369
2. Spore-producing members . . . . .	370
Microsporangium . . . . .	371
Megasporangium . . . . .	376
3. Gametophytes . . . . .	384
Female gametophyte . . . . .	384
Male gametophyte . . . . .	389
Fertilization . . . . .	391
4. Embryo . . . . .	393
5. History and distribution . . . . .	402
6. Relationships . . . . .	402
Literature cited . . . . .	404
 CHAPTER IX. EVOLUTIONARY TENDENCIES AMONG GYMNOSPERMS . . . . .	 406
Phylogeny . . . . .	407
Vascular anatomy . . . . .	411
Leaf . . . . .	412
Strobilus . . . . .	413

# CONTENTS

xi

	PAGE
Stamen . . . . .	415
Ovule . . . . .	416
Female gametophyte . . . . .	419
Male gametophyte . . . . .	421
Fertilization . . . . .	423
Embryo . . . . .	426
SUMMARY OF LITERATURE CITED . . . . .	431
INDEX . . . . .	453





## CHAPTER I

### CYCADOFILICALES

The discovery of this paleozoic group of gymnosperms has been one of the remarkable achievements of the present decade. Including, as it does, the most fernlike assemblage of seed plants, the discovery is of enormous importance to phylogeny. A brief sketch of the development of our knowledge of the group will serve as an introduction to the fuller account.

The Carboniferous period is notable for its fernlike vegetation (11), which has been estimated (56) to make up at least one-half of the known flora. The classification of the leaves is based upon form and venation, and a number of frond genera have been described, which, although necessarily artificial, are sufficient for the cataloguing of material. The association of sporangia with these fronds is by no means general; in fact, an enumeration (11) of the frond species from the British Carboniferous showed an association of fronds and sporangia in less than one-fifth of them. It was assumed, without question, that the sporangium-bearing fronds must be those of ferns, and the opinion became current that the sporangia indicated that these ferns were of the general *Marattia* type. Hence there arose the belief that the most dominant vegetation of the Carboniferous could be spoken of as a *Marattia* plexus, including a far greater diversity of forms over a far wider geographical range than do the Marattiaceae of the present flora. This view involved also the belief that the relative age of eusporangiate and leptosporangiate ferns had been settled by the sure testimony of history.

In 1883 STUR (7) had become so impressed by the fact that the large majority of the carboniferous fronds remained persistently sterile, in spite of the increasing accumulation of material, that he suggested that these forms might not be ferns. In view of the subsequent discoveries, this statement, based only upon persistent negative evidence, appears like a prophecy. However, a few years later (11) sporangia were discovered upon the persistently sterile fronds of a species of one of the largest of the frond genera (*Sphenopteris*),

which seemed to represent clearly the synangial habit of the Marattiaceae. Furthermore, the anatomy of the petioles of other frond genera was described as being much like that of the petioles of the Marattiaceae. Such results seemed to confirm the old view that the sterile frond genera were not only ferns, but also ferns of the *Marattia* type.

In 1887 WILLIAMSON (5, p. 299) first recognized "the presence in the carboniferous flora of plants combining the characters of ferns and cycads" (86); and in 1896 WILLIAMSON and SCOTT (18) described the anatomy of *Lyginodendron* and *Heterangium*. In the same year WEBER and STERZEL (17) described the anatomy of *Medullosa*. These are prominent stem genera, which belong to some of the sterile frond genera; and these observers discovered in them an anatomical structure distinctly intermediate between that of ferns and that of cycads. In view of this fact, in 1899 POTONIÉ (20) named the group *Cycadofilices*, basing it upon anatomical features, its composite character being indicated by the name. The striking anatomical feature of the *Cycadofilices* is the association of secondary wood with a fernlike vascular system. There was no occasion, on this account, to remove *Cycadofilices* from pteridophytes, as secondary wood occurs in *Sphenophyllum*, *Lepidodendron*, *Calamodendron*, etc., and also in existing species of *Isoetes*, *Selaginella*, *Psilotum*, and *Equisetum*. Nor would this character even remove the group from ferns, for a cambium occurs in *Marattia*, *Angiopteris*, *Ophioglossum*, and *Botrychium* (63). In fact, secondary wood evidently originated independently in many groups and at many times (50), and therefore could not be made the basis of an important segregation.

In 1903, however, OLIVER and SCOTT (39) announced that certain characteristic seeds belonged to the fronds of *Lyginodendron Oldhamium*, and the association with pteridophytes was at an end. In the same paper the group name *Pteridosperms* was proposed, to include those *Cycadofilices* that bear seeds. Since then other seed-bearing fronds have been discovered, until now all of the prominent frond genera are involved.

Finally, in 1905 KIDSTON (54) announced the discovery of the microsporangia of *Lyginodendron Oldhamium*, and all of the important

structures, of this form at least, had been assembled. These microsporangia at once suggested that the sporangia heretofore thought to demonstrate the occurrence of paleozoic ferns of the *Marattia* type might be the microsporangia of pteridosperms. In this way the dominant *Marattia* plexus has disappeared, and the question has been raised as to the evidence of ferns in the Paleozoic. In any event, the pteridosperms have replaced the ferns as a dominant paleozoic group. SCOTT (56) has stated that scarcely 20 per cent of the "fern fronds" of the Carboniferous offer any real evidence of being true ferns; and that 30 to 40 per cent of the unassigned remainder may be assumed to fall in the same ratio. In consequence of this, he suggests that since the Carboniferous has been described as the "Reign of the higher cryptogams," remembering that Cordaitales were associated with pteridosperms, it had better be characterized as the "Reign of the primitive seed plants."

It seems impossible at present to recognize a group of pteridosperms as distinct from Cycadofilices, and there is a growing impression that the two groups are coextensive. As SCOTT (82) remarks, the pteridosperms "have proved much more extensive, and also more remote from the ferns, than at first realized." Under the circumstances, it would seem proper to retain for the group the older name. It seems clear, also, that it should take its place as a group of gymnosperms coordinate with Cordaitales, Cycadales, Coniferales, etc., for it is impossible as yet to construct a definition which would exclude it from gymnosperms on the basis of characters of so high an order as those which separate gymnosperms from angiosperms. For this reason, we have appended to the older name the termination that makes it conform to the names of groups of similar rank, and shall refer to it hereafter as the *Cycadofilicales* (84).

### 1. The vegetative organs

The general fernlike aspect of the Cycadofilicales was the conspicuous feature of their habit, an aspect due to their foliage (fig. 1). The evidence indicates that there were climbers and trees among them, as well as the more usual habit among modern ferns. In order to understand the combination of fernlike and cycad-like characters exhibited by the vegetative structures of the Cycadofilicales,

it is necessary to present briefly the vascular anatomy of the pteridophytes, and especially that of the ferns. This will serve not

only as an introduction to Cycadofilicales, but also to the vascular anatomy of gymnosperms in general.

#### VASCULAR ANATOMY OF PTERIDOPHYTES

The most important recent advance in our knowledge of the vascular groups has been made by the students of vascular anatomy. Morphology had become almost entirely restricted to a study of the structures associated with reproduction, for these structures seemed to offer the only clue to the larger relationships. An enormous mass of facts had been accumulated in reference to the anatomy of the vegetative structures, but it was not organized so as to be of service to the morphologist. Now vascular anatomy has emerged



FIG. 1.—*Neuropteris*: impression of frond.—  
From photograph by KIDSTON.

as a subject organized upon a morphological basis, and its value in supplementing the older morphology cannot be overestimated. In fact, it is really the extension of morphology to include the vascular system.

The three conspicuous kinds of vascular axis among pteridophytes are (1) the *protostele* (fig. 2), which is a single, solid, concentric vascular cylinder; (2) the *siphonostele* (fig. 3), which is a hollow vascular



cylinder inclosing pith (medulla); and (3) the *polystele* (fig. 5), which contains several concentric vascular strands. There are two kinds of siphonostele: one (fig. 3) with internal as well as external phloem (*amphiphloic*; often called *solenostele*), the other (fig. 4) with only external phloem (*ectophloic*). The question as to the phylogenetic




FIG. 2.—*Gleichenia pubescens*: transverse section of stem, showing the protostele;  $\times 35$ .—After COULTER (88).

connection of these types has given rise to considerable diversity of opinion, but for our purpose the general situation seems clear.

The protostele is accepted as the most primitive type of stele. In the study of sporelings it has been shown that the protostele is the first stage in the development of the stele of ferns, whatever may be the adult character (13, 31, 36). Among ferns the young protostelic stage usually passes into the siphonostelic, but it persists, for example,

in the adult stems of species of *Gleichenia* (fig. 2), *Hymenophyllum*, *Lygodium*, and the paleozoic *Botryopteris* (36).

Which of the two kinds of siphonostele has been derived directly from the protostele is a question under discussion. One view (31) is that the amphiphloic condition was the first to appear, and that by the gradual reduction of the internal phloem the ectophloic stage



FIG. 3.—*Adiantum pedatum*: transverse section of stem, showing the amphiphloic siphonostele;  $\times 25$ .—After COULTER (88).

was reached. The other view (36) is that pith appeared first in the solid stele (protostele), without any internal phloem, which would make the ectophloic siphonostele more primitive than the amphiphloic. The investigators concerned with these views have arranged such convincing series that it seems reasonable to suppose that both kinds of siphonostele may have arisen directly from the protostele. In any event, the sporeling of such a fern as *Adiantum* begins with a pro-

tostelic stem, which merges directly into a siphonostelic condition with internal phloem; while in *Osmunda*, although there is usually in the adult stem a siphonostele without internal phloem, in *O. cinnamomea* (27, 31) occasionally internal phloem is found. Neither type of siphonostele is extensively displayed among ferns (36), the




FIG. 4.—*Osmunda cinnamomea*: transverse section of stem, showing the ectophloic siphonostele;  $\times 25$ .—After COULTER (88).

amphiphloic type occurring, for example, in *Adiantum*, *Matonia*, *Loxsonia*, *Aneimia mexicana*, etc., and the ectophloic type in *Osmunda* (fig. 4), *Platyzoma*,<sup>‡</sup> *Schizaea*, etc.

The prevailing type of stele among the ordinary ferns is the polystelic (10), occurring in most Polypodiaceae, Dicksoniaceae, Cyatheaceae, Marattiaceae, etc. (36). The type is well illustrated by *Pteris*

<sup>‡</sup> A monotypic genus regarded by some taxonomists as a species of *Gleichenia*.



*aquilina* (fig. 5), the figure referred to showing nine smaller peripheral vascular strands and four much larger central ones. It has been shown (31) that the young stem of *Pteris* is not polystelic, but that the vascular cylinder is an amphiphloic siphonostele, like that of *Adiantum*. In growing to the adult stage it passes gradually into the poly-




FIG. 5.—*Pteris aquilina*: transverse section of stem, showing the polystele;  $\times 10$ .—After COULTER (88).

stelic condition by the overlapping of elongated leaf gaps (see below), and also by the passing of peripheral vascular strands into the pith.

It is evident that the various types of stele are not restricted to different groups of ferns, but may be found as the adult condition at all levels. For example, in existing gymnosperms the ectophloic siphonostele, made up of collateral bundles, is the characteristic type of cylinder. Whether this was attained by way of the polystelic condition, as has been suggested (36), or directly from a siphonostelic condition, may not be clear; in any event, it would seem to be the most advanced type of cylinder, but it is found at various levels among

pteridophytes, as for example in Osmundaceae among ferns. In the usual sequence of fern families, the polystelic condition is found at both extremes; and the confessedly primitive protostelic condition persists in the midst of the fern series. The inference is that in various ways, along various lines, changes in the primitive protostelic condition have developed. To arrange all the types of stele in a linear, phylogenetic series seems to be not only unnecessary, but also contrary to all previous experience with phylogenies.

Assuming that the polystele is merely a split-up siphonostele (31, 36), there are just two types of central cylinder, the protostele and the siphonostele, the former being the more primitive. JEFFREY has shown (31) that siphonosteles are of two fundamental types: (1) those with both leaf and branch gaps (*phyllosiphonic*), and (2) those with branch gaps alone (*cladosiphonic*). The phyllosiphonic condition is associated with large leaves, and the cladosiphonic with small ones; and therefore JEFFREY recognizes two great primitive stocks of vascular plants: the *Lycopsida*, which are cladosiphonic and microphyllous; and the *Pteropsida*, which are phyllosiphonic and megaphyllous. To the latter stock belong the ferns, gymnosperms, and angiosperms. This association of ferns and gymnosperms is a strong confirmation of the conclusion reached in other ways as to their phylogenetic connection.

The leaf gap, characteristic of the Pteropsida, should be understood clearly. A transverse section of the vascular cylinder of *Adiantum*, passing through a leaf gap, shows two crescentic vascular strands facing each other (fig. 6), one being a section of the leaf trace, the other a section of the siphonostele which the leaf gap has made incomplete. At the edge of the gap the external and internal phloems become continuous. Farther up the stem the gap closes, and the cylinder becomes complete again. There is sometimes danger of mistaking a branch gap for a leaf gap, but the latter should be recognized by the fact that it occurs immediately above the leaf trace to which it belongs. A true leaf gap is always related to a single trace, so that if several traces appear in relation to a gap in the vascular cylinder, and especially if they are related to the sides of the gap, it is not a true leaf gap. It should also be noted that gaps in the vascular cylinder may occur where the vascular tissues are much reduced

in amount and break up into a loose network, and these hold no necessary relation to the vascular strands of leaves or branches (80).

Vascular bundles have also been characterized by SCOTT (24) according to the relation of the protoxylem to subsequent xylem elements. The procambium strand that appears in the plerome does not develop vascular tissue simultaneously throughout its whole

transverse section, but begins at one or more definite points, and from each of these points the subsequent xylem extends in one or more directions. This first group of vessels (spiral and annular) constitutes the *protoxylem*, and the subsequently formed xylem of the primary bundle constitutes the *metaxylem*. If the protoxylem is in contact with the phloem, the metaxylem thus being all centripetal, the bundle is called *exarch* (fig. 7); if the protoxylem is surrounded by metaxylem, the bundle is called *mesarch* (fig. 8); if the protoxylem is in contact with the pith (or at the center of a solid



FIG. 6.—*Adiantum pedatum*: transverse section of stem; the smaller bundle is a leaf trace, opposite the leaf gap in the central cylinder;  $\times 16$ .—After JEFFREY (37).

xylem strand), the metaxylem thus being all centrifugal, the bundle is called *endarch* (fig. 9). These types are not rigidly restricted to different great groups, but they are very serviceable in combination with other characters. In general, exarch wood is considered to be the most primitive type, characteristic of roots, common in the stems of lycopods, and occasional in the stems of ferns. Mesarch wood is very characteristic of ferns, so much so that when it occurs in any part of the vascular system of gymnosperms, it is spoken of



as a fern character. Among seed plants the prevailing type of wood is endarch, and on this account it may be regarded as the most advanced condition.




FIG. 7.—Exarch position of protoxylem.—After WORSDELL (36).




FIG. 8.—Mesarch position of protoxylem.—After WORSDELL (36).

It is important to understand what is meant by the transition from the concentric to the collateral bundle, and from the mesarch to the endarch condition of the xylem. Starting with a siphonostele made up of mesarch concentric bundles, which are thus of distinctly fern type, it is supposed that there has been a gradual reduction of the inner tissues. When the whole of the internal phloem has disappeared, the concentric bundle has become collateral, but it is still mesarch. Later, when the whole of the centripetal metaxylem has disappeared, the mesarch xylem has become endarch. In some cases there may be internal secondary wood, and that disappears after the internal phloem and before the centripetal metaxylem. When the endarch collateral condition is reached, the vascular cylinder is distinctly of the gymnosperm type. Therefore, when mesarch xylem is found among gymnosperms, it is regarded as a primitive feature; but not so primitive as would be the occurrence of concentric bundles.




FIG. 9.—Endarch position of protoxylem.—After WORSDELL (36).

Students should be warned that it is not always easy to distinguish metaxylem elements, especially in very young tissue and in the foliar extremities of bundles.

#### VASCULAR ANATOMY OF CYCADOFILICALES

The anatomical peculiarity of this group is that it displays the vascular types described above as characterizing the ordinary ferns, and in each case adds to them the formation of secondary wood. The best known of these stems will be considered briefly.




FIG. 10.—*Heterangium Grievii*: transverse section of stem;  $x$ , central mass of primary wood;  $x^2$ , secondary wood beginning to form; next the phloem and pericycle;  $ic$ , inner cortex ( $x$  in this zone is a sclerotic group);  $lt$ , leaf traces;  $r$ , base of an adventitious root;  $oc$ , outer cortex, present only in places;  $pet$ , base of petiole;  $\times$  about 5.—After SCOTT (87).

**HETERANGIUM.**—The stems referred to this genus occur from the base of the Carboniferous into the Permian, one of the oldest and best investigated species being *H. Grievii* (18). The slender stems, not over 1.5 cm. in diameter, are ribbed by the decurrent bases of petioles. The vascular axis is a protosteles (fig. 10), very similar to that of *Gleichenia pubescens* (fig. 2), the single vascular cylinder being

solid and concentric. Near the periphery of the included xylem there occur small strands of protoxylem, which determine the mesarch character of the bundle. Thus far, the structure is distinctly fernlike; but in addition there is a narrow zone of secondary wood about the primary xylem cylinder. The elements of this secondary wood are radially arranged, with numerous (multiseriate) bordered pits, and the zone is traversed by pith rays. The large leaf traces are collateral at their junction with the vascular cylinder, but they become concentric before entering the petiole. Although the leaf trace is single in *H. Grievii*, in other species of the genus it becomes double.

LYGINODENDRON.<sup>1</sup>—One of the most common stems preserved in the British Coal-measures is *Lyginodendron Oldhamium*, fully described by WILLIAMSON and SCOTT (18), and possibly including a group of species. The stems are long, slender (3 mm. to 4 cm. in diameter), and branching. The vascular axis is a siphonostele, without internal phloem (fig. 11), as in *Osmunda* (fig. 4), the cylinder inclosing a large pith. A variable number (5-9) of isolated primary xylem strands occur next to the pith, being distinctly mesarch, with the larger part of the metaxylem centripetal (fig. 12). While most of the tracheids of the metaxylem have bordered pits, those next to the spiral elements are usually scalariform (87). The main part of the vascular cylinder, however, consists of a broad zone of secondary wood, whose tracheids, with multiseriate bordered pits, occur in regular radial arrangement, and which is traversed by pith rays. Very evident gaps in the vascular cylinder are associated with the leaf traces, so that the siphonostele is phyllosiphonic and is thus definitely related to the siphonostele of Filicales. The leaf traces near the central cylinder are single and collateral, but soon they fork and gradually become concentric, so that in the petiole (once called *Rachiopteris aspera*) a pair of concentric bundles occurs. The association of collateral bundles in the stem with concentric bundles in the leaves is a distinct *Osmunda* character, and is met also among the cycads. Occasionally in *L. Oldhamium* there is a development of vascular bundles with reversed orientation (xylem next to that of the primary bundle) in the pith. Outside the cambium there is also evident a zone of phloem, broken up by the pith rays (fig. 13).

<sup>1</sup> The generic name sometimes used is *Lyginopteris* Potonié.



The roots of *L. Oldhamium*, long known as *Kaloxylon Hookeri*, have been preserved so perfectly that their structure has been deter-



FIG. 11.—*Lyginodendron Oldhamium*: the large pith contains numerous dark masses of sclerotic cells; bordering upon the pith at various places may be seen the primary wood (*p*), comparatively scanty in amount; next is the secondary wood (*s*), constituting almost the entire mass of the woody cylinder; a narrow zone of phloem surrounds the secondary wood, and just outside the phloem, in the inner cortex (*i*), are the leaf traces (*t*); next is the outer cortex (*o*), with numerous radially arranged bands of sclerenchyma;  $\times 3$ .—From photograph by KIDSTON.

mined with great completeness. There are usually three to eight alternating xylem and phloem strands, and in the larger roots there is distinct secondary growth, every stage in its development having

been observed. SCOTT (24) remarks that "it is certainly a fact of great interest that the roots of our fossil, which in their primary condition much resemble those of marattiaceous ferns, or of *Helminthostachys* among Ophioglossaceae, should exhibit a mode of secondary tissue-formation absolutely indistinguishable from that of typical dicotyledons or gymnosperms." At that time it was not realized that *L. Oldhamium* was a gymnosperm. There are cases in which




FIG. 12.—*Lyginodendron Oldhamium*: part of transverse section of stem showing a primary xylem strand and adjacent tissues; *px*, protoxylem; *x*, centripetal primary wood; *x¹*, centrifugal primary wood; *x²*, secondary wood; *r*, medullary rays; *p*, pith; *ss*, secretory sac;  $\times 100$ .—After WILLIAMSON and SCOTT (18).

the growing point has been preserved so perfectly that it is evident there was no such definite apical cell (87) as characterizes most fern roots.

**MEGALOXYLON.**—This stem genus occurs in the British Lower Coal-measures, and has been described by SEWARD (21). The vascular cylinder only is preserved, being 4 to 5 cm. in diameter, and is a protosteles, as in *Heterangium*; but the secondary wood is more abundant and resembles that of *Lyginodendron*. The most interesting feature, however, is the exarch structure of the primary wood, in contrast with the mesarch structure of both *Heterangium* and *Lyginodendron*. The exarch structure occurs in some ferns, as in *Lygodium*, and SEWARD remarks that "in anatomical characters the



two genera *Lyginodendron* and *Heterangium* approach most nearly to the Osmundaceae and Gleicheniaceae respectively; in *Megaloxylon*, on the other hand, the structure of the primary xylem affords evidence that the *Lygodium* type of stem was also represented in the cycad-fern alliance which played so prominent a part in paleozoic vegetation." Another characteristic feature of *Megaloxylon* is the structure of the metaxylem, which is usually made up of very short tracheids, often broader than long, interspersed with parenchyma,




FIG. 13.—*Lyginodendron Oldhamium*: part of transverse section of outer portion of stele;  $x^2$ , secondary wood;  $r$ , medullary rays;  $cb$ , cambium;  $ph$ , primary phloem;  $ph^2$ , secondary phloem;  $ss$ , secretory sac;  $pd$ , periderm;  $\times 52$ .—After WILLIAMSON and SCOTT (18).

a structure suggesting a storage rather than a conducting region. This feature is shared by the Permian *Zallesskya*, which has been shown to be a primitive member of the Osmundaceae (87).

CYCADOXYLON.—The stems of this genus have been reported from the Lower Coal-measures and from the Permian, and it is evident that the type was an important one during the Paleozoic. Some of the preserved vascular cyl-

inders are large enough (14 cm. in diameter) to suggest stems as large as those of small trees. The anatomy resembles that of *Lyginodendron*, in fact one of the species was described as *L. robustum*. There is the same siphonostele, with abundant secondary wood traversed by broad pith rays and containing elements of the same character. Two differences, however, are notable. One is the endarch character of the primary vascular strands. This character is not clear in all the forms, and in some a small amount of centripetal xylem is claimed; but in any event, the

group as a whole shows the complete or nearly complete elimination of centripetal xylem in the primary strands. The other notable difference is the development of regular zones of secondary xylem between the primary cylinder and the pith (fig. 14). These centripetally developed zones have reversed orientation, and two or more successive ones may appear. It will be recalled that this feature of




FIG. 14.—*Cycadoxylon robustum*: part of transverse section of stele showing inner portion of normal wood, with two anomalous zones of wood and bast;  $x^2$ , normal secondary wood;  $x^3$ ,  $ph^3$ , first inverted band of xylem and phloem;  $x^4$ ,  $ph^4$ , second band;  $p$ , pith;  $\times 12$ .—After SCOTT (87).

*Cycadoxylon* appears in certain specimens of *Lyginodendron Oldhamium*, the two genera evidently being closely related.

MEDULLOSA.—The stems of this important type are found throughout the Carboniferous and Permian deposits, culminating in the latter and then disappearing, and it seems to have been one of the most abundant of the Cycadofilicales. Some of the species were large trees of fernlike habit, and others had long slender stems. In every case the stems were clothed by the sheathing bases of leaves.

The oldest known species of *Medullosa*, and the simplest in its stem structure, is *M. anglica*, from the Lower Coal-measures of England, and described in detail by SCOTT (22). The stems average 7 to 8 cm. in diameter, and are distinctly polystelic (fig. 15), resembling *Pteris* (fig. 5) in this regard. The vascular bundles are usually three in number and are concentric, each one of the xylem strands being surrounded by a zone of secondary wood. This combination of polystely and secondary wood is the chief anatomical feature of the group, and is said to distinguish it from all living plants. The secondary xylem elements resemble




FIG. 15.—*Medullosa anglica*: transverse section of stem showing three large leaf bases (*a*, *b*, *c*); *ab*, *bc*, position of next leaf bases above; *st*, the three steles; *lt*, leaf traces; *an*, accessory rings of wood and bast; *pd*, periderm, forming a ring around the steles; *r*, adventitious root; *oc*, hypodermis; sclerenchyma band between leaf base and stem; slightly reduced.—After SCOTT (22).

those of *Heterangium* and *Lyginodendron*, being radially arranged tracheids with bordered pits on the radial walls. In fact, each one of the several steles of *Medullosa* so closely resembles the single one of *Heterangium*, that the *Medullosa* type is believed by some (36, 72) to have been derived directly from the *Heterangium* type; and to have given rise in turn to the *Lyginodendron* type by the organization of the polystele into a compact cylinder (siphonostele), accompanied by the degeneration of the internal vascular tissues. The opposing view claims that the polystelic condition of *Medullosa* is derived from the siphonostelic, as in ferns (*Pteris*, 31); and that the *Medullosa* type is to be regarded as a modification of the *Lyginodendron* type,

rather than intermediate between the *Heterangium* and *Lyginodendron* types. The polystely of *Medullosa*, however, is said (87) to differ from that of the ferns (such as *Pteris*), in that apparently it holds no relation to the presence of leaf gaps. The absence of leaf gaps in *Medullosa* and its allies has suggested that polystely arose within the family, quite independent of polystely among ferns. Occasionally vascular strands appear also in the cortex, as among the cycads.

The leaf trace of *Medullosa* is at first concentric and with secondary wood; but later the secondary tissue disappears, the bundle branches repeatedly, and the branches become collateral and exarch. According to SCOTT (24), "each leaf stalk received a large number of vascular bundles, as many as 70 to 80 in all, derived from the repeated ramification of several of the principal leaf traces. The supply of bundles did not all enter the leaf base from the stem at the same level; they passed in successively in groups corresponding to the various principal leaf traces from which they were derived."

The later species of *Medullosa*, so far as their structure is known, are more complex anatomically than *M. anglica*, the vascular bundles being more numerous, and differentiated into an inner group of smaller bundles and a more or less complete peripheral zone of larger ones (fig. 16). All the bundles have the same general structure as those of *M. anglica*. In the older stems of certain forms, however, there is an excessive development of secondary wood on the outer side of the peripheral bundles, so that a section of the stem shows a broad zone of secondary wood surrounding the relatively inconspicuous inner region.

In a specimen of *M. stellata gigantea*, whose vascular region is over 45 cm. in diameter, in addition to the large mass of secondary wood developed on the outer side of the peripheral bundles, there




FIG. 16.—*Medullosa Solmsii*: part of transverse section of stele; *st*, "star rings"; *pla*, outer zone of bundles; *pli*, inner zone of bundles; *a* and *b*, bundles which have branched off from the inner zone;  $\times 2$ .—After WEBER and STERZEL (17) in POTONIÉ (20).



are three concentric cortical layers of wood, a succession of cortical cambiums appearing, similar to that found in certain genera of living cycads. In this form numerous bundles also occur in the pith, which is another feature of some of the modern cycads.

CLADOXYLON and COLPOXYLON are other stem genera with polystelic structure as in *Medullosa*. In the former genus, a devonian form, the vascular structure is complex, the steles often being elongated and curved in section, and sometimes fusing, but each stele has its own zone of secondary wood, in which the tracheids are scalariform. The latter genus is permian, and is interesting in that the stems are protostelic below and polystelic above.

Recently SCOTT (68) has described a SUTCLIFFIA (*S. insignis*) from the Lower Coal-measures, which he regards as "a new type of Medulloseae." If so, it is like a *Medullosa* reduced to the *Heterangium* condition, for it is protostelic and there is only a slight amount of secondary thickening, but from this main axial stele secondary steles become detached at intervals. Moreover, the xylem is exarch, as contrasted with the mesarch condition in *Medullosa*. However, the leaf traces are numerous, complexly branching, and anastomosing. Such a complex leaf structure connected with a protostelic stem cylinder is said to be a unique combination, and suggests a reduction of the central cylinder. The *Medullosa* connection is still further suggested by the mucilage canals and reticulate peripheral bands of sclerenchyma.

CALAMOPITYS is a stem genus of the Devonian and Lower Carboniferous that is very suggestive of *Lyginodendron*, with small pith, few and comparatively large mesarch primary bundles, a thick zone of secondary wood, and a leaf trace that forks on leaving the cylinder. The leaf traces are quite distinct, however, in being concentric in the cortex and in dividing on entering the leaf, so that the petiole contains several bundles.

PROTOPITYS is a remarkable isolated form of the Devonian and Lower Carboniferous with an abundant development of secondary wood. The large pith (elliptical in section) is surrounded by a continuous zone of primary wood, of unequal thickness but not broken into bundles.

The preceding stem genera are not all known with certainty to



belong to Cycadofilicales, but they include forms known to be such (*Lyginodendron*, *Heterangium*, *Medullosa*); others almost certainly such because of their evident relationships (*Colpoxylon*, *Sutcliffia*, *Megaloxylon*, *Calamopitys*, *Cycadoxylon*); and others possibly such because they are Cycadofilices. Each of the genera cited represents a stem family of the same name, except that *Heterangium* is included in the Lyginodendrineae (Lyginodendreae), and *Colpoxylon* and *Sutcliffia* in the Medullosineae (Medulloseae). Cycadofilicales are known to extend beyond the range of these stem genera, for seed-bearing fronds have been discovered the structure of whose stems is unknown. The stems already described, however, show a wide anatomical range for the group, being protostelic (*Heterangium* and *Sutcliffia*), siphonostelic (*Lyginodendron*, *Megaloxylon*, *Cycadoxylon*, etc.), and polystelic (*Medullosa*, *Cladoxylon*, *Colpoxylon*, etc.); while the xylem of the stem ranges from exarch (*Sutcliffia*), through mesarch (the general condition), to endarch (*Cycadoxylon*). The leaf traces also range from the usual simple forking to a profuse branching and anastomosing. So far as vascular anatomy is concerned, therefore, the Cycadofilicales exhibit as wide a variation and the same kind of variation as do the existing ferns, and they add to these characteristics those of existing gymnosperms.

#### THE LEAF OF CYCADOFILICALES

To distinguish the leaves of Cycadofilicales among the innumerable paleozoic "fronds" that have been preserved is at present impossible. It has been suggested (60) that the prevailing dichotomy of paleozoic fronds may be indicative of Cycadofilicales rather than of ferns, but such a character cannot be used with any definiteness. In fact, SCOTT has said recently (82) that from the frond alone it cannot be told whether a paleozoic plant is a fern or one of the Cycadofilicales. The best that can be done is to select those leaves whose connection with stems or with seeds testifies to their nature. In this way most of the large frond genera have contributed representatives to the Cycadofilicales, but it may be that some of their other members are ferns. At least, so artificial an assemblage as a large frond genus would suggest such a possibility. The certain or probable cases of leaves belonging to the Cycadofilicales are as follows:

The foliage of *Heterangium* and of *Lyginodendron* has been shown to be of the *Sphenopteris* type, one of the great and heterogeneous




FIG. 17.—*Sphenopteris elegans* (probably foliage of *Heterangium Grievii*): part of frond;  $\times \frac{3}{4}$ .—After STUR (7).

frond genera of the Paleozoic, in general habit like *Asplenium* (82). The foliage of *Heterangium Grievii* is probably *Sphenopteris elegans*, the leaf being large and stalked, several times pinnately compound, and with numerous small leaflets (fig. 17). SCOTT (24) describes

*H. Grievii* as "a fernlike plant, with a long, upright or perhaps trailing, ribbed stem, bearing large and graceful, finely divided fronds, much resembling those of some recent *Asplenium*." The foliage of *Lyginodendron Oldhamium* is *Sphenopteris Höninghausii*, the leaves being very large and pinnately dissected. The leaflets are described (86) as fleshy and incurved, with often dilated vascular endings as though connected with glands, and suggesting plants of the salt water swamps of today. SCOTT (24) thinks that it was probably "a climbing plant of the scrambler type, a suggestion which is confirmed by the presence of spines on the stem, and on all parts of the compound leaves."<sup>1</sup> To this *Sphenopteris* type of foliage have been referred numerous sporangia, both those supposed to be of ferns and those of Cycadofilicales. It has been suggested (82) that the species with forked rachis are probably Cycadofilicales, and that some of the others are probably ferns.

No leaves have been definitely associated with the stem genus *Cycadoxylon*, but the associated occurrence of distinctly cycadean leaves, resembling those of *Dioon* and of *Zamia*, suggests the possibility that the foliage was of that type.

Among the leaves referred to *Medullosa* and its associates, the most abundant and conspicuous are those described under the great frond genera *Neuropteris* (fig. 18) and *Alethopteris* (*A. lonchitica* is probably the leaf of *M. anglica*), all of whose species probably belong to Cycadofilicales (82). These frond genera, along with *Odontopteris* and *Dictyopteris*, are often grouped as the frond family Neuropterideae, and are thought to be generally seed-bearing. The leaves are very large, several times pinnate, and with ovate or oblong leaflets. Their petioles, often of great length and repeatedly branching, have been described under the form genus *Myeloxylon*, the structure being very much like that found in cycads.

One of the largest of the frond genera, including many of the most striking of the carboniferous "fronds," is *Pecopteris*. Through the researches of GRAND'EURY (52) it is known that one of the species (*P. Pluckenetii*) is seed-bearing; and the sporangia (as *Dactylothea*, for example) borne by other species are probably the microsporangia

<sup>1</sup> As many tree ferns are very spiny, the presence of spines in *Lyginodendron* cannot be used as evidence of a climbing habit.

of Cycadofilicales. SCOTT (87) concludes that "on present evidence there is every reason to believe that a large proportion of the fernlike paleozoic plants with pectopterid foliage will find their place, like *P. Pluckenetii*, among seed-bearing plants." There is also good evidence that other species represent the foliage of carboniferous tree ferns, though of course different from our Cyatheaceae; the sporangia of other species suggest the Marattiaceae; and still different



FIG. 18.—*Neuropteris heterophylla*: part of frond; slightly enlarged.—From photograph by KIDSTON (64).

characters of other species join with all the preceding to indicate that *Pecopteris* is a most heterogeneous assemblage of foliage.

*Aneimites* (or *Adiantites*) is a frond genus characteristic of the Lower Coal-measures (Devonian to Middle Coal-measures), whose leaflets resemble those of *Adiantum*. It has not been found attached to a stem, and there is no knowledge of its vascular anatomy; hence the leaves continued to be regarded as those of ferns until WHITE (49) discovered specimens bearing seeds.

Even the devonian genus *Archaeopteris* (or *Palaeopteris*), once referred by some to Hymenophyllaceae and by others to Marattiaceae,



is now thought by KIDSTON (64) to belong most probably to the Cycadofilicales.

From the above statement it is evident that all of the so-called "fern fronds" of the Paleozoic may well be "under suspicion." At the same time, the actual proof of their connection with Cycadofilicales applies to so few species that it is very unsafe to assume that there is no residuum of ferns among them.

## 2. The spore-producing members

### THE MICROSPORANGIUM

The microsporangia of Cycadofilicales were naturally regarded at first as the sporangia of ferns, and it was not until 1905 that a definite connection with one of the Cycadofilicales was announced (54). The microsporangia were those of *Lyginodendron Oldhamium*, thus completing in a remarkable way our knowledge of that form. The original announcement (54) by KIDSTON was followed later (64) by his full description and discussion.

The stamen referred to proved to belong to ZEILLER's form genus *Crossotheca*, to which "fructifications" of a certain type have been referred, and constituted a new form species (*C. Höninghausii*). The sporangium-bearing frond is dimorphic, but the fertile pinnules are associated in the same frond with the sterile ones. To apply the terms microsporophyll and stamen to this situation may be confusing without an explanation. The whole frond is not strictly a microsporophyll, and therefore not a stamen, but it well represents a frond on its way to becoming a microsporophyll. In fact, only certain pinnules bear microsporangia, and for convenience these fertile pinnules may be spoken of as microsporophylls or stamens. Each of these primitive stamens (pinnules) has a very stout pedicel, which is bent at its union with the oval blade, on the under surface of which six or seven bilocular sporangia are developed (fig. 19). The sporangia are fusiform and pointed (about 3 mm. long and 1.5 mm. in maximum breadth), and apparently entirely free from one another. The long axis of the sporangium is attached to the surface of the blade, presumably in connection with a veinlet, and at the margin of the blade the free tip is bent downward. When young, the free ends bend inward, and the group of sporangia resembles a hemispherical



radiate sorus (fig. 20). At maturity, the tips spread apart, forming a hanging fringe from the under surface of the blade, which then "resembles an epaulet" (fig. 21). In transverse section each sporangium is seen to be composed of two loculi, circular in section and separated by a thin partition. The accompanying diagrams (figs. 22



FIG. 19.—*Crossotheca Höninghausii*: portion of frond with several "stamens," some of which show the individual sporangia;  $\times 4$ .—From photograph by KIDSTON (64).

and 23) show longitudinal and transverse sections of this stamen. Dehiscence takes place by a longitudinal slit along the adaxial face, the spores of both loculi thus being liberated simultaneously. The microspores are 50 to 75  $\mu$  in diameter, having a surface rough with blunt points.

The discovery described above raised the question whether all

the species of *Crossotheca* are stamens of Cycadofilicales. Recently Miss BENSON has announced (83) the discovery of a new species of *Crossotheca* (*C. Grievii*), which is described as the stamen of *Heterangium Grievii*. There are now recognized, therefore, nine species, and all of them have the general "epaulet" character described for *C. Höninghausii*. They differ only in such details as the form of the sporangium-bearing blade (oval, cordate, or lobed), and in the number and form of the sporangia. So similar are these species that it seems safe to infer that they are all stamens of Cycadofilicales. The foliage of all of them is known, except that of *C. Hughesiana*, and includes species of *Pecopteris* (as *P. exigua*) as well as of *Sphenopteris* (*Lyginodendron*).

In 1887 KIDSTON (11) described fronds of *Neuropteris heterophylla* (*Medullosa*) in which both the pinnae and axis end in slender, naked, dichotomously divided branchlets, each ultimate division terminated by a four-valved body. At the time these bodies were regarded simply as the "fructifications" of a fern. Since the seeds of this species have now been



FIG. 20.—*Crossotheca Höninghausii*: portion of frond with six young stamens;  $\times 2.5$ .—From photograph by KIDSTON (64)

discovered, it is apparent that these bodies must represent its microsporangiate structures. "Fructifications" of this kind, terminal on naked, ultimate branchlets of a more or less modified frond, with valves more or less united at base, have been referred to the form genus *Calymmatotheca*. At least some of them are sporangia more or less united below and free above, and in some cases the dehiscence (internal) and the spores have been found. Of course such a structure is a synangium,<sup>\*</sup> but its terminal relation to ultimate branches of the frond is quite different from that of the synangia of existing Marattiaceae. There is danger of confusing these structures with the cupule-like investment of such seeds as

\* This term is used with no implication of an opinion as to the nature of the structure.

*Lagenostoma* (*Lyginodendron*), and perhaps they may be spoken of as the "cupule" style of stamen, in contrast with the "epaulet" style of *Crossothea*. In fact, it is altogether probable that *Calymmatotheca Stangeri* (STUR in 1877), a stellate, six-rayed structure, represents the cupule-like investment of a seed that had dropped. On the other hand, ARBER (77) described from the coal fields of Germany




FIG. 21. — *Crossothea Höninghausii*: portion of microsporophyll with mature microsporangia;  $\times 2.5$ .—From photograph by KIDSTON (64).

what he regarded as a remarkably small seed (*Carpolithus Nathorstii*) occurring on the frond of a *Sphenopteris*; later NATHORST (81) investigated its structure, and found it to be not a seed, but a microsporangiate structure. Miss BENSON (41) has described a genus (*Telangium*) of this *Calymmatotheca* type, to include certain digitate clusters of the Paleozoic, which she referred, from indirect evidence, to *Lyginodendron Oldhamium*; but since the stamen of that form has now been determined by direct evidence, *Telangium* remains to be connected, possibly with some other form included under the same name. *Telangium* was described as terminal on ultimate branches of the leaf, but SCOTT (87) has concluded that the synangial group of long and pointed sporangia was "seated on a flat disk or lamina, quite comparable to the fertile pinnule of *Crossothea*. SELLARDS (40, 74), also, has described a spore-bearing structure (*Codonotheca*) from the Coal-measures of Illinois, which is a cup-shaped body composed of six bladelike valves united below and free above, and bearing spores liberated on the inside (fig. 24). The association of these structures with the remains of *Neuropteris* suggests that they are stamens belonging to some species of that frond genus. The stamens of *Aneimites* are unknown, but intimately associated with the seed-bearing fronds there

what he regarded as a remarkably small seed (*Carpolithus Nathorstii*) occurring on the frond of a *Sphenopteris*; later NATHORST (81) investigated its structure, and found it to be not a seed, but a microsporangiate structure. Miss BENSON (41) has described a genus (*Telangium*) of this *Calymmatotheca* type, to include certain digitate clusters of the Paleozoic, which she referred, from indirect evidence, to *Lyginodendron Oldhamium*; but since the stamen of that form has now been determined by direct evidence, *Telangium* remains to be connected, possibly with some other form included under the same name.

*Telangium* was described as terminal on ultimate branches of the leaf, but SCOTT (87) has concluded that the synangial group of long and

occur structures of the *Calymmatotheca* type. It must be confessed that while the *Crossotheca* or "epaulet" type of stamen is distinct



FIGS. 22, 23.—*Crossotheca Höninghausii*: fig. 22, diagrammatic longitudinal section of stamen; fig. 23, diagrammatic transverse section of stamen; *l*, limb; *s*, sporangia; *m*, rock matrix.—After KIDSTON (64).

enough, the so-called *Calymmatotheca* or "cupule" type is in confusion, and so far as it represents microsporangiate structures at all, they may be referred ultimately to *Crossotheca* or to ordinary marattiaceous synangia, like those of *Kaulfussia*.

Although actual organic connection of stamens with plants known to be seed-bearing has been discovered as yet in only two or three forms, it is evident that a much wider range of forms is indicated. All structures of the *Crossotheca* type may fairly be considered probable stamens of Cycadofilicales, and some of the *Calymmatotheca* structures, so far as they are distinct from large marattiaceous synangia, are doubtless such also. It must be noted, however, that the frond genera and the sporangium genera cross one another's boundaries. For example, *Crossotheca* occurs on both *Sphenopteris* and *Pecopteris*; while *Calymmatotheca* (or its equivalents) occurs on *Neuropteris*, *Sphenopteris*, and probably *Aneimites*. The dimorphic character of the fronds is quite marked in all these cases, and it suggests the question whether other dimorphic fronds, bearing sporangia of a different type, may not belong to Cycadofilicales. Furthermore, the great frond genus *Pecopteris*, one of whose species, at least, is known to belong to the Cycadofilicales, possesses all the types of spo-



FIG. 24.—*Codonotheca*;  $\times 2$ .—After SELLARDS (40).



rangia once supposed to belong to the paleozoic Marattiaceae. This throws suspicion on all sporangia of paleozoic "fronds."

It is to be expected that among the Cycadofilicales there will be found microsporangiate structures indistinguishable from the sporangia of paleozoic ferns. This statement is emphasized by the fact that even the stamens of the mesozoic Bennettitales bear synangia closely resembling those of existing Marattiaceae. It would be useless to consider here the numerous "fructifications," mostly those of *Pecopteris*, which may or may not prove to be microsporangia; this has been done recently by SCOTT (82). It is well to note, however, that there is every gradation from naked branches bearing abundant free sporangia (as *Urnatopteris*, whose sporangia have apical pores, and which is strongly suspected of belonging to the Cycadofilicales), to free and often solitary (*Dactylothea*, also probably one of the Cycadofilicales) sporangia on ordinary leaves, and finally to synangia of various kinds (the radiate or *Kaulfussia* type prevailing). In *Pecopteris Pluckenetii*, whose seeds have been found, GRAND'EURY reports (62) "stellate groups" of sporangia on the margins of pinnules, a description applicable to the sori or incomplete synangia of marattiaceous ferns.

The danger of too hasty reference of sporangia to Cycadofilicales is illustrated by *Stauropteris Oldhamia*, investigated by SCOTT (57). Its very slender and numerous ultimate branchlets occurred "in dense faggot-like groups," and bore terminal sporangia. The fact that the ovules of Cycadofilicales are also often terminal on ultimate branchlets, and that some of the Cordaitales bear microsporangia in the same way, made it tempting to infer that *Stauropteris* belonged to the Cycadofilicales. Later, however, SCOTT (70) was fortunate enough to secure preparations of the sporangia of *Stauropteris* containing germinating spores, which showed distinctly their fernlike character. The great interest of *Stauropteris* in connection with Cycadofilicales, therefore, is to show that the terminal position of sporangia on ultimate branchlets occurred among ferns.

In any event, it is evident that the synangial microsporangia of Cycadofilicales and the synangia of marattiaceous ferns were so much alike as to imply common origin (74).

## THE MEGASPORANGIUM

Numerous detached paleozoic seeds have been discovered, but it must be remembered that they include the seeds of both Cordaitales and Cycadofilicales. The seeds definitely connected with Cycadofilicales are comparatively very few, but the structure of at least two of them is known with remarkable completeness.

LAGENOSTOMA.—In 1903 OLIVER and SCOTT (39) announced that a species of this seed genus is the seed of *Lyginodendron Oldhamium*, and in the following year the full account appeared (48). The seed species was a new one, and was described as *Lagenostoma Lomaxii* (fig. 25). The seeds were not found in actual organic con-



FIG. 25.—*Lagenostoma Lomaxii* (restored): the seed is surrounded by a glandular cupule.—After OLIVER and SCOTT (48).



FIG. 26.—*Lagenostoma Sinclairii*: two seeds on branches of the rachis, each seed surrounded by a cupule.—After ARBER (51).

nection with the foliage (*Sphenopteris*) of *Lyginodendron*, but the numerous and peculiar capitate glands borne on the cupule correspond in every detail to those on the vegetative organs of the associated *Lyginodendron*, and represent a character not possessed by any other associated plant. There seemed to be no doubt that the reference of the seed to *Lyginodendron* was fully justified, a conclusion further confirmed by a comparison of the anatomical details. Another species of *Lagenostoma* (*L. ovoides*) was known; and later ARBER (51) described *L. Kidstonii* and *L. Sinclairii* from casts, but important in that the seeds were connected with branching axes that represent naked branches of a frond (fig. 26). It is

evident, therefore, that the leaves of *Lyginodendron* were dimorphic, one form being the familiar sterile foliage of the *Sphenopteris* type,

the other a form reduced wholly or partly to naked branches, whose ultimate branchlets bore terminal seeds of the *Lagenostoma* type. There was no more organization of a strobilus than in existing ferns with dimorphic leaves. Additional species have been described also by GRAND'EURY (53), who found in the Lower Coal-measures a very large number of small *Lagenostoma*-like seeds associated with species of *Sphenopteris* under conditions that seem to make it certain that they belonged together.




FIG. 27.—*Lagenostoma Lomaxii*: longitudinal section through apex of seed; *o*, opening at top of pollen chamber; *i*, integument; *n*, central core of nucellus; *n'*, outer hard layer of nucellus; *p*, pollen chamber; *g*, pollen grains; *n''*, part of nucellus supporting the pollen chamber; *m*, megaspore membrane;  $\times$  about 50.—After OLIVER and SCOTT (48).

The structure of *Lagenostoma Lomaxii* has been described in full by OLIVER and SCOTT (39, 48). The seeds occur in the Lower Coal-measures, and each one is invested by a lobed cupule "springing from the pedicel just below the base of the seed and extending above the micropyle, at least in young specimens. The cupule appears to have been ribbed below and deeply lobed above, and in form it may be roughly compared to the husk of a hazelnut, of course on a very small scale" (fig. 25). The integument, which is free only in the region of the pollen chamber, is a remarkably complex structure. A transverse section shows an outer heavy zone, and an inner one consisting of several chambers (usually nine) filled with parenchyma,

each chamber being traversed longitudinally by a single vascular strand, the strands being connected with the main bundle that enters the chalaza. The pollen chamber is peculiar in that it is not the usual open cavity in the beak of the nucellus, but is a cylindrical (bell-shaped) crevice between the epidermis of the free tip of the nucellus and its central core of tissue (fig. 27). The archegonia probably

occurred in a ring beneath this crevice. Our preparations of *L. ovoides* from LOMAX show the method of formation of this peculiar pollen chamber (figs. 28 and 29). The free beak of the nucellus is covered by an epidermal layer whose cells have thick, resistant walls. Within this layer, near the base of the beak, the thin-walled tissue begins to break down; and this breaking down extends upward beneath the epidermis to the apex of the beak, resulting in the characteristic crevice-like pollen chamber surrounding a central core of tissue.

A diagrammatic longitudinal section of the seed is shown in fig. 30; and diagrammatic transverse sections at various levels through the pollen chamber, in figs. 31-34. The contrast of this *Lagenostoma* method of pollen chamber-formation with the ordinary method, such as occurs in the *Stephanospermum* type of seeds (see below), in the cycads, etc., is striking. In the latter case the pollen chamber begins to develop at the tip of the nucellus and is central; while in *Lagenostoma* it begins to develop at the base of the nucellar beak and is peripheral. It must be understood, therefore, that the



FIG. 28.—*Lagenostoma ovoides*: longitudinal section of a seed;  $\times 12$ .—From photomicrograph by LAND.



"nucellar beak," which is said to "arise from the floor of the pollen chamber," is in reality a core of tissue left intact in the formation of the pollen chamber. An important feature to note in the seeds of this group is that the open tube of the pollen chamber projects a little through the micropyle, so that the passage for the entrance of the pollen grains is not furnished by the micropyle, but by the protruding nucellar beak (86, 87).





FIG. 29.—*Lagenostoma ovoides*: longitudinal section through apex of seed shown in fig. 28, illustrating an early stage in the formation of the pollen chamber; *n*, central portion of nucellus which becomes the core shown in fig. 27; *n'*, outer hard part of nucellus; *p*, beginning of pollen chamber; *m*, megaspore membrane; *i*, integument;  $\times 36$ .

The impression described as *Lagenostoma Sinclairii* (51) shows the same type of seed (fig. 26), so far as external characters are concerned, and furthermore it shows its connection with foliage of the *Sphenopteris* type.

It is evident that in comparing these seeds with those of living gymnosperms they must be regarded as resembling those of cycads, with decided peculiarities of their own. It is still further evident that such seeds are very far from being primitive in structure, and are no more suggestive of the origin of seeds in general than are the seeds of existing seed plants.

PHYSOSTOMA.—Recently OLIVER (85) has restored this genus, described first by WILLIAMSON (2), but later referred by him (3) to


his new genus *Lagenostoma* as *L. physoides*. This species OLIVER restores as *Physostoma elegans*, and associates with it ARBER'S *Lagenostoma Kidstonii* (51). *P. elegans* is also the *Sporocarpion ornatum* of WILLIAMSON (4, 8), as well as his *S. anomalum* (8, 19). It is thought to belong to some one of the Lyginodendrineae (Lyginodendreae) not yet distinguished.



FIGS. 30-34.—*Lagenostoma Lomaxii*: fig. 30, diagrammatic longitudinal section of ovule with its investing cupule; figs. 31-34, transverse section at the levels A, B, C, D, respectively; *n*, central portion of the nucellus, and *n'* the outer hardened portion, with the pollen chamber (*p*) between; *i*, integument; *c*, cupule; *b*, vascular bundles.—After OLIVER (55a).

The seed is small and oval (5.5 to 6 mm. by 2 mm.) with a narrowed base, usually ten-ribbed, and circular in section. There is no trace of a cupular sheath as in *Lagenostoma*. A very remarkable feature, however, is that the integument, free only in the region of the pollen chamber, is broken up into ten "tentacles," the direct prolongations of the ten ribs (figs. 35-39). Ribs and tentacles are covered by long, club-shaped hairs. These tentacles of *Physostoma*

seem to be the units that make up the chambered integument ("canopy") of *Lagenostoma*, and this has suggested to OLIVER the multiple origin of the integument. No stony layer is developed by the testa, and the distribution of the vascular strands is practically as in *Lagenostoma*, a single strand ascending deep in each rib and



FIGS. 35-39.—*Physostoma elegans*: fig. 35, diagrammatic median longitudinal section; figs. 36-39, transverse sections at the levels A, B, C, D, respectively; b, vascular bundles; t, "tapetum."—After OLIVER (85).

passing on into the corresponding tentacle. The pollen chamber consists of the same circular crevice as in *Lagenostoma*, but the embryo sac develops into the nucellar projection (fig. 35), so that the pollen chamber really invests the upper end of the sac ("like the incurved bottom of a wine bottle"). The peripheral region of the nucellus, from the chalaza to the top of the embryo sac, is occupied by a remarkable "secretory zone," made up of thin, oblong, tabular cells, and representing what OLIVER regards as the retention of a feature present

in the vegetative organs. Between the secretory zone and the embryo sac, and entering into the cap of the sac within the pollen chamber, is a region of six or more radially compressed layers of cells, which is regarded as a "tapetum," but which may be only the region of the nucellus compressed by the enlarging embryo sac.

THE LAGENOSTOMA GROUP.—Associated with *Lagenostoma* and *Physostoma* there is the seed genus *Conostoma* (3), and also the recently announced genus *Sphaerostoma* (83), based upon WILLIAMSON'S *Conostoma ovale* and the oldest paleozoic ovule known structurally. These four genera form what may be regarded as a natural group, belonging to the Lyginodendrineae. *Lagenostoma Lomaxii* alone, of the petrified seeds of this group, is definitely connected with a species of *Lyginodendron* (*L. Oldhamium*); while *L. Sinclairii* and *L. Kidstonii* (*Physostoma Kidstonii*) are impressions which are connected with foliage of the *Sphenopteris* type. *Lagenostoma ovoides*, *Physostoma elegans*, and *Conostoma* all occur as petrifications, but they have not been referred to definite species of *Sphenopteris* or of *Lyginodendron*. It had been inferred from association that one of the species of *Conostoma* might be the seed of *Heterangium*, and now Miss BENSON (83) has shown it to be probable that the new seed genus *Sphaerostoma* (*Conostoma ovale*) belongs to *Heterangium Grievii*.

In 1885 RENAULT (9) described *Gnetopsis elliptica*, in which there are four seeds (two often abortive) inclosed in a cupule consisting of two partly fused bracts, each of which becomes five-toothed above. The integument expands around the micropyle and forms a chamber, and bears two long feathery appendages. There is a central core of tissue within the pollen chamber, and the neck of the chamber divides into lobes. The endosperm and two distinct archegonia are preserved. The two fused bracts doubtless suggested to RENAULT a relationship to Gnetales, but the general structure is much more suggestive of a seed of the *Lagenostoma* type (87).

The four seed genera referred to agree in the amount of freedom of nucellus and integument, in the peculiar character of the pollen chamber with its projecting beak, in the composition of the free portion of the integument (distinct lobes to lobes "fused"), in the covering of mucilage hairs, in the distribution of the vascular strands, and



in the character of the pollen grains (described below). OLIVER (85) sees in *Physostoma elegans*, with its "tentacles" and "secretory nucellar zone," the most primitive condition. The following series<sup>1</sup> on the basis of freedom or coalescence of the integument lobes is attractive: in *Physostoma* they are free and the body of the seed is ribbed; in *Conostoma* the body is ribbed below and smooth above, and the integument lobes are united, but show a tendency to separate; in *Lagenostoma* the body is completely smooth and the integument lobes are completely united to form the characteristic chambered "canopy." The numbers of the units of integument structure vary as follows: 10 in *Physostoma elegans*, 9 in *Lagenostoma Lomaxii*, 8 in *L. ovoides*, 7 in *Conostoma oblonga*, about 6 in *L. Kidstonii* (*P. Kidstonii*).

The characters of Lyginodendrineae given in the preceding pages make it possible to outline the probable features of the group. SCOTT (87) has suggested in effect the following tentative description: leaves fernlike (*Sphenopteris* or *Pecopteris*); stem monostelic and with xylem mesarch; leaf trace and main leaf bundle single or double, concentric in the petiole; reproductive organs on somewhat modified pinnae; microsporangiate organs of the *Crossotheca* type; seeds radial, cycadean, with nucellus and integument free only in the region of the nucellar beak and with a singular vascular system, and often inclosed (singly or several together) in a cupule.

MEDULLOSA.—In 1904 KIDSTON (44, 45) announced the discovery of three fragments of *Neuropteris heterophylla*, each of which bore a seed "as large as a hazelnut" on a pedicel terminating a pinna (fig. 40). These seeds are about 3 cm. long, oblong in outline but tapering to a point, and invested by a fibrous envelope. Their internal structure is not known, but they belong to a general type of paleozoic seeds quite different in structure from the *Lagenostoma* type. The relation of the seeds to the fronds is the same as in *Lyginodendron*, but there is no evidence of such extreme dimorphism, the seeds being terminal on the naked tip of a pinna which otherwise does not differ from the ordinary pinnae. That this *Neuropteris* is the foliage of a *Medullosa* is clear, and there is enough evidence to indicate that all the members of this stem genus were seed-bearing, and that the seeds were borne terminally upon more or less modified pinnae.

<sup>1</sup> The description of *Sphaerostoma* is not yet available.


ANEIMITES.—In 1904 WHITE (49) announced the discovery of seeds upon fronds of *Aneimites* (*Adiantites*) from West Virginia, the seeds having been used to establish the seed genus *Wardia*. *Aneimites* is represented in the Lower Coal-measures, the general habit of the leaf and its cuneate ultimate divisions strongly suggesting



FIG. 40.—*Neuropteris heterophylla*: seed (*Rhabdocarpus*) attached to a short pedicel bearing foliage;  $\times 2$ .—From photograph by KIDSTON (44).

*Adiantum* (figs. 41 and 42). The seeds are borne upon somewhat reduced fronds, occurring singly or in pairs upon pedicels that replace ultimate pinnules. They are rhomboidal in outline and thin lenticular in transverse section, the outer covering (cupule or integument) being latera'ly dilated and winged, especially below the middle (fig. 43), possibly fibrous or slightly fleshy, and inclosing the less rhomboidal and nutlet-like structure within; unfortunately no internal structure is preserved. Such seeds have been found in all stages of

development, are associated with *Aneimites* in most of the deposits observed (Lower Pottsville of the Virginia region), and have been found in organic connection with the fronds of two species. They



FIGS. 41-43.—*Aneimites fertilis*: fig. 41, fragment of pinna with seed (s); fig. 42, seed on long pedicel connected with foliage; fig. 43, seed showing wings, the latter somewhat exaggerated;  $\times 2$ .—After WHITE (49).

seem to represent a very different type of seed (platysperms) from those found in connection with *Lyginodendron* and *Medullosa*.

PECOPTERIS.—In 1905 GRAND 'EURY (52) announced the discovery of seeds on *P. Pluckenetii*. A mass of sterile and fertile pinnules was found, the latter bearing hundreds of seeds. These are not borne at the extremities of naked branchlets, the seed-bearing pinnules being very slightly modified and bearing a seed hanging freely at

the extremity of the principal veinlet of each lobe (fig. 44). SCOTT (58) speaks of this as "the most striking instance of a 'seed-bearing fern' yet brought to light." The seeds are small (about 5 mm. long), oval, and with narrow wings. The winged habit of these seeds and of the seeds of *Aneimites* suggests the seeds of Cordaitales, and it becomes evident that fossil seeds can no longer be assigned with certainty except on evidence of organic connection. The discovery that a species of *Pecopteris* was a seed-bearing plant was one of very great interest, for it was the last great frond genus to join the Cycadofilicales, and it is the most conspicuous genus in the variety of sporangia it bears.

PROBABLE SEEDS OF CYCADOFILICALES.—In the preceding cases the evidence of the seed-bearing habit is direct and convincing; but in addition there is a possible range of inferences that are worth considering. GRAND 'EURY (53) has called attention to the great



FIG. 44.—*Pecopteris Pluckenetii*: portion of fertile pinna with seeds attached at ends of lobes of pinnules;  $\times 3$ .—After GRAND 'EURY (43).

number and diversity of "fern seeds." In the assured cases, the relation of seed to frond varies from seeds suspended on the under surface of unmodified leaves (as in *Pecopteris*), to seeds in rows on a special rachis (as in *Neuropteris*), and finally to seeds isolated at the ends of ultimate branchlets (as in *Sphenopteris*). Beyond these few definite cases there lies the vast assemblage of paleozoic seeds which have constituted several times as many seed genera as frond genera, which incidentally is another indication of the heterogeneous character of the latter. It is evident, therefore, that there are seeds enough for all the fronds known; and also that the seed habit discovered in one or even several species of a large frond genus need not be imposed upon all the species. At the same time, it is becoming increasingly apparent that large numbers of frond species and of unassigned seeds must belong to Cycadofilicales.

KIDSTON's discovery of specimens of *Neuropteris heterophylla* bearing seeds is the only direct evidence that *Neuropteris* in general was seed-bearing; and yet the investigations of GRAND'EURY (43) on the plants of the Coal-measures of France showed such a constant association of definite types of seeds with definite fronds of *Neuropteris* that the inference seems justified that the species of *Neuropteris* in general were seed-bearing plants. Among the better known seeds thus referred are *Pachytesta*, sometimes reaching the size of a hen's egg, and *Trigonocarpum* (one of whose species is probably the seed of *Medullosa anglica*). In this general characterization the frond genera known as *Alethopteris*, *Odontopteris*, *Linopteris*, *Lonchopteris*, etc., are also included.

Among the *Lyginodendron*-like forms, the seeds (*Lagenostoma Lomaxii*) of *L. Oldhamium* stand as the only direct evidence of the seed-bearing habit; and yet *Heterangium* and other stem genera with *Sphenopteris* foliage are evidently so nearly related to *Lyginodendron* that one can hardly doubt that many of the species of *Sphenopteris* were seed-bearing. In fact, the genus *Sphaerostoma* (*Conostoma ovale*) is in all probability the seed of *Heterangium*.

The species of *Pecopteris* are much more uncertain, and for many reasons no sweeping inference as to the seed-bearing habit of this great frond genus is justified. The single known seed-bearing species (*P. Pluckenetii*) is said to be an aberrant one in its frond characters.



PALEOZOIC SEEDS.—Our knowledge of the internal structure of seeds known positively to be those of Cycadofilicales is restricted to the *Lagenostoma* group; but there is much larger knowledge of detached paleozoic seeds, some of which may well belong to Cycadofilicales. At least it is not out of place to consider the general characters of paleozoic seeds. Numerous detached seeds occur in the Carboniferous, and they have naturally been referred to gymnosperms. Although called seeds, they have been preserved evidently at the stage just preceding or soon after fertilization, and are ovules in the modern sense. Especially in the Permian beds of France are these seeds remarkably well preserved, having been elaborately described by BRONGNIART (6) and RENAULT (16). Seeds from the English beds, usually less well preserved, have been described by WILLIAMSON (2, 3). The whole subject, however, has lately been reopened by OLIVER (38), in connection with the recent rapid development of our knowledge of gymnosperms.

BRONGNIART for convenience referred all paleozoic seeds to two categories, which OLIVER has named *radiosperms* and *platysperms*, the seeds of the former being circular in transverse section or radially symmetrical, those of the latter flattened or bilateral. Some of the platysperms have been referred definitely to the Cordaitales, and the same connection has been inferred for the rest of them; but the seeds of *Aneimites* and of *Pecopteris*, described above, suggest that this reference has been too sweeping. The radiosperms have had no such definite assignment, until recently some of them have been found to belong to Cycadofilicales. It is evident that BRONGNIART's two types hold no relation to the two paleozoic groups of gymnosperms.

There are certain general features belonging to some of the paleozoic radiosperms that deserve special mention in connection with their possible relation to Cycadofilicales. For this purpose the seed genus *Stephanospermum*, formerly referred to Cordaitales but now probably to be assigned to the Medullosineae, may be used, both because it is the simplest and because it has been described in great detail by OLIVER (47). The seed of *S. akenioides* (fig. 45) is cylindrical and pointed, the testa being differentiated apparently into an outer stony layer and an inner fleshy layer.<sup>1</sup> The nucellus is entirely free from

<sup>1</sup> An outer fleshy layer might be expected, but either it has not been preserved or has not been recognized.

the integument or testa, in striking contrast with the ovules of living gymnosperms, in which the integument and nucellus are free only in the region of the pollen chamber or nucellar beak. A long and strong nucellar beak extends into the micropyle, and within it a pollen chamber of great relative size is developed. The vascular strand entering the chalaza expands into a plate, whose margin is continued as a tracheal mantle investing the nucellus beneath the epidermis and extending to the pollen chamber, "the floor of which is paved with tracheids." OLIVER sees in this distribution of vascular elements a mechanism for the conduction of water for the use of swimming sperms in the pollen chamber. While the pollen chamber is associated with swimming sperms, there is no evidence that a supply of water is necessary.

Contrasting *Stephanospermum* with *Lagenostoma*, it is evident that the latter approaches the structure of cycadean seeds more nearly than does the former, especially in the lack of freedom of nucellus and integument, and in the greater simplicity of the vascular system. On the other hand, the pollen chamber of *Stephanospermum* is more cycadean, as well as the testa in the development of the three characteristic layers. It should be remembered that *Lagenostoma* is lower carboniferous, while *Stephanospermum* is permo-carboniferous, so that historically the former is much the older, but its structure shows it to have been far from the simplest type of seed. In living gymno-




FIG. 45.—*Stephanospermum akenioides*: partial restoration; *m*, micropyle; *b*, beak of nucellus; *p*, pollen chamber; *a*, outer (sclerotic), and *i*, inner layer of integument, which is free from nucellus to base of seed; *t*, tracheal mantle; *a*, archegonia; *w*, megaspore membrane;  $\times 10$ .—After OLIVER (47).



tions may occur in the nucellar tracheal mantle, which may be replaced by a vascular network or by distinct vascular strands. Later, SCOTT and MASLEN (73) described two species of *Trigonocarpum* (*T. Parkinsonii* was probably the seed of *Medullosa anglica*) from the Coal-measures (figs. 46-48) which conform fully to the *Stephanospermum* type of structure, in these cases the three layers of the testa being distinguished, and the vascular strands occurring in two sets (an outer system in the outer fleshy layer, and an inner system traversing the periphery of the free nucellus), both distinctly cycadean characters. The inner vascular system forms a "practically continuous sheath" in the lower part of the nucellus, and is traceable through the whole length of the nucellus, almost to the base of the pollen chamber. A remarkable feature of these winged seeds is the conspicuous micropylar




FIG. 47.—*Trigonocarpum Parkinsonii*: diagrammatic transverse section through the micropyle at about the level of *pcb* in fig. 46; for lettering see fig. 48.




FIG. 48.—*Trigonocarpum Parkinsonii*: diagrammatic transverse section at about the level of *mm* in fig. 46; lettering for figs. 46-48: *sa*, sarcotesta; *l*, its limiting layers; *sc*, sclerotesta; *mi*, micropyle; *it*, remains of "inner flesh"; *sab*, sarcotestal bundles; *pc*, pollen chamber; *pcb*, its beak; *s*, septum at bottom of pollen chamber; *ne*, nucellar epidermis; *nt*, nucellar tracheal system; *mm*, megaspore membrane; *td*, tracheal disk at chalaza; *chb*, chalazal bundle; *r1* and *r2*, principal and secondary ridges; all  $\times$  about 3.—MASLEN in SCOTT (87).



beak, which is an extension of the ribbed bony layer often as long as the body of the seed (in some specimens twice as long) and bears two broad wings.

It is evident that at least two types of structure are known among paleozoic seeds, which may be called the *Lagenostoma* type and the *Stephanospermum* type, the former known to belong to the Cycadofilicales, the latter very probably including seeds that must be referred to the same group. There are certain features in common, however, that should be noted.

A character shared by all paleozoic seeds whose structure is known is the presence of a pollen chamber. Occurring as a circular crevice in *Lagenostoma* and as a broad chamber in *Stephanospermum*, it indicates in both the existence of swimming sperms. So far as the evidence goes, therefore, the abandonment of swimming sperms by seed plants did not begin until after the Paleozoic. It is noteworthy that the largest pollen chambers seem to have been attained by the *Stephanospermum* type as displayed in the Permian, a type which perhaps has no successors.

Perhaps the most puzzling fact discovered in connection with paleozoic seeds is the entire absence of any indication of an embryo. That embryos are preserved in petrifications is evidenced by their abundant occurrence in the seeds of the mesozoic Bennettitales. OLIVER (38) has suggested that perhaps the long intraseminal period of the embryo of seed plants had not been developed in the Paleozoic; but the abundant endosperm invested by an efficient testa seems to be against this view. Accepting the absence of embryos from paleozoic seeds as a fact, it should be remembered that the proembryo of the more primitive gymnosperms is quite extensive, and that even were it preserved it would hardly be recognized as an embryo. So far as any record to the contrary has shown, all this proembryonic development may have taken place in the preserved paleozoic seeds. It seems possible, therefore, that the paleozoic seeds matured (developing testa) before fertilization, became detached after pollination, and subsequently developed a proembryo which did not invade the endosperm before germination, or invaded it in a very feeble way as compared with the extensive invasion in modern gymnosperms. Checking the growth of the embryo, if it is related to the organization of a

testa, may occur at any stage; and if the testa is formed before fertilization (as may have been true in paleozoic seeds), the growth of the embryo may well have been checked at some stage of the proembryo, in which case there would be no recognizable embryo. That even a well-organized testa does not check the growth of the embryo, however, is evidenced by the fact that even among existing gymnosperms, as cycads, the true embryo (as distinct from an extensive proembryo) may escape from the seed as soon as it is developed and grow as continuously as do the embryos of pteridophytes. In such a case, however, the chance of finding preserved a recognizable embryo invested by the testa would be as exceptional as of finding any very brief stage in the life history. It would seem, therefore, that in paleozoic seeds there was either no resting period between intraseminal and extraseminal development of the very young plant, or it occurred in the proembryonic stages. SCOTT (86) has suggested as "probable that the nursing of the embryo had not yet come to be one of the functions of the seed, and that the whole embryonic development was relegated to the germination stage."

Since belief in the absence of embryos from paleozoic seeds rests as yet upon negative evidence, it should not be forgotten that the sections of suitably preserved seeds are far too few in number to overcome the uncertainty of negative evidence or the possibility of abortive seeds. In fact, comparatively few seeds have been found attached to the shoots that bore them, and seeds that have fallen off at the immature stages suggested by all published figures of sections would be abortive seeds, so far as experience with living seed plants is concerned. Only good seeds remain on the plant, and there is no record of a section of an attached paleozoic seed. Moreover, if the seeds germinated at once, as do those of the cycads, no embryos would be found except in attached seeds. The seeds of Bennettitales that show conspicuous embryos are all attached seeds, and it is altogether probable that such seeds of Cycadofilicales and of Cordaitales will also show embryos.

SCOTT (28) has described a seedlike megasporangium (*Lepidocarpon*) belonging to the lycopods of the Lower Coal-measures, which may well represent a primitive seed condition. These detached megasporangia had already been described as seeds, but their occur-

rence in an undoubted strobilus of a lycopod made the relationship clear. An integument or testa, growing from the surface of the sporophyll, completely invests the megasporangium except for a slitlike micropyle. To discover an embryo in such a structure, however, would be very unlikely, for it develops continuously into the sporeling. It would seem impossible to avoid the conclusion that a prolonged period of intraseminal rest (as distinct from intraseminal growth) must have been established gradually, and therefore that it may not have been attained by paleozoic seeds in general.

In comparing the majority of known paleozoic seeds with those of angiosperms, it is evident that the latter have advanced in the reception of pollen by the micropyle, and in the nutrition of the embryo (86); but that the general structure of paleozoic seeds is much more complex, with their elaborate vascular system, pollen chamber, and often highly differentiated testa. It has been suggested that the seed is "an organ which required to be much more elaborate in the days of spermatozoid fertilization, now only lingering in a few archaic survivals from the past" (86), as among cycads and in *Ginkgo*.

### 3. The gametophytes

#### THE FEMALE GAMETOPHYTE

The structure of the female gametophyte is largely a matter of inference. In some cases delicate, collapsed tissue has been seen in the embryo sac, but no archegonia, unless *Stephanospermum* (fig. 45) and RENAULT'S *Gnetopsis elliptica* (p. 37) belong to the Cycadofilicales, of which there can be little doubt. The similarity in the general development of the gametophyte of such heterosporous pteridophytes as *Selaginella* and *Isoetes* and of cycads suggests that the endosperm of Cycadofilicales was of the same general nature in development and structure.

The embryo sac enlarges in the usual way, and is remarkable in *Physostoma* in growing into the nucellar core of tissue which is surrounded by the pollen chamber. In other known gymnosperms with pollen chambers this core is either destroyed, resulting in a large pollen chamber, or remains solid (as in *Lagenostoma*). If the extension of the embryo sac into the nucellar beak of *Physostoma* should become filled with permanent endosperm tissue, there would be an

approximation to the endosperm beak ("tent pole") that occurs among the Cordaitales and in *Ginkgo* (85).

In the *Lagenostoma* group the megaspore membrane varies from "robust" in *Lagenostoma*, to very delicate (only occasionally seen) in *Physostoma*, and indistinguishable in *Conostoma* (85); in *Trigonocarpum* it is distinct (73).

#### THE MALE GAMETOPHYTE

In the majority of cases the pollen chambers have contained pollen grains in more or less abundance, and these pollen grains, whenever any internal structure is evident, contain a tissue of numerous cells. In *Lagenostoma Lomaxii* "multicellular pollen grains" have been observed (38); and in *L. ovoides* germinating grains have been found in the pollen chamber (fig. 49) associated with bodies interpreted as sperms (78). These sperms are further interesting in agreeing in form and general appearance with those of living cycads and of *Ginkgo* rather than with those of ferns. In *Physostoma elegans* (85) the same cell plexus occurs in the much smaller pollen grains (fig. 51), recalling that of *Stephanospermum* (described below); and here also certain associated subreniform bodies are interpreted as sperms. In this species a differentiation of the cells in size was observed by OLIVER, who suggests that the larger cells, at least, produced sperms, and that the smaller cells might be prothallial.

In *Stephanospermum akenioides* (47) numerous pollen grains are constantly found within the pollen chambers, and OLIVER succeeded




FIG. 49.—*Lagenostoma ovoides*: pollen chamber and contents; *nl*, portion of central core of nucellus; *nw*, wall of nucellus; *p1*, *p2*, *p3*, *p4*, four pollen grains; *a*, sperm; *a1*, sperm cut across; *e*, protruision of endospore; *t*, tissue probably fungal;  $\times 155$ .—After Miss BENSON (78).



in obtaining sections of them, showing the internal structure (fig. 50). The cavity of the grain is completely filled (allowing for shrinkage) with a tissue of about twenty cells, arranged in five rows radially disposed about a central axis. In another species of *Stephanospermum* the same observer (47) has described pollen grains containing only two cells in addition to the large tube cell, a structure at once suggesting that found in existing gymnosperms.

Since the pollen grains of certain undoubted Cordaitales have long been known to contain a tissue similar to that just described for the Cycadofilicales, the inference is strong that this represents a




FIG. 50. — *Stephanospermum akenioides*: transverse section of pollen grain showing internal walls;  $\times 180$ .—After OLIVER (47).

FIG. 51. — *Physostoma elegans*: section of pollen grain showing internal walls; the dotted area is the exospore where it has not been ground away;  $\times 480$ .—After OLIVER (85).

general condition of the male gametophyte among paleozoic gymnosperms. Even among existing gymnosperms there are cases of excessive prothallial tissue (as among the podocarps and araucarians) and of excessive spermatogenous tissue (as in *Microcycas*); so that the internal tissue of the paleozoic pollen grains may be either mainly prothallial or mainly spermatogenous; or both tissues

may occur in more equal proportion. In our specimens of the pollen grains of *Physostoma*, the internal tissue is not restricted to one pole of the spore, as is true of all male prothallial tissue among living gymnosperms, but is just as conspicuous in the middle region of the spore. We are inclined to the belief, therefore, that most of these internal cells are spermatogenous. However this may be, the chief interest lies in the fact that the male gametophyte of the paleozoic gymnosperms is a more extensive tissue than in most living gymnosperms; and that in all probability it is not restricted to the production of two sperms. That these sperms were discharged into the cavity of the pollen chamber, after its base had broken down to the necks of the archegonia, can scarcely be questioned. There is no evidence of the development of pollen tubes as sperm carriers; and that they did

not exist even as haustoria is evidenced by the fact that pollen grains with no tubes are found in contact with the megaspore membrane.

SCOTT (87) has called attention to the very interesting fact that in 1887 RENAULT (12), in describing the structure of *Aetheotesta*, a seed allied to *Stephanospermum*, anticipated through inference the discovery of swimming sperms among gymnosperms. In both of these genera the walls of the pollen grains are perforated, and RENAULT suggested "that these perforations served for the passage of motile bodies analogous to antherozoids." He adds, "we do not regard as impossible the existence in the past of pollen grains which, instead of effecting fertilization by means of a tube, discharged into the pollen chamber of the appropriate seeds antherozoids capable of performing this function."

#### 4. History and distribution

That Cycadofilicales were a dominant group during the Carboniferous, and that they were to be found in abundance wherever the vegetation of the Coal-measures occurred, are facts that seem to be clearly established. It is scarcely less clear that they existed during the Devonian. KIDSTON (64) thinks that they are plainly represented in remains of the Upper Devonian; and there are suggestions of still greater age. This means that they can be traced to a time so remote that no other group of vascular plants, or at least fernlike plants, is known to antedate them. The type is distinctly paleozoic, for, although it culminates during the Coal-measures, no trace of it has been discovered in the Mesozoic. From their history, their structure, and their resemblance to ferns, therefore, the Cycadofilicales may be regarded as the most archaic group of spermatophytes known.

#### 5. Relationship to ferns

At the first discovery of fernlike seed plants, it was natural to infer that this group must have arisen from the so-called *Marattia* plexus which was thought to be dominant in the Carboniferous. Subsequent discoveries of seed-bearing plants made serious inroads upon this "plexus," and finally the discovery of the fernlike microsporangiate structures of the Cycadofilicales left the whole question of paleozoic

ferns in a very uncertain state. It seems certain, at least, that no such dominant *Marattia* plexus existed during the Paleozoic as has been supposed; for an overwhelming number of the "ferns" constituting it have been placed among the Cycadofilicales, either on direct or on probable evidence. The character of paleozoic ferns, therefore, has become a question bound up with the origin of Cycadofilicales.

#### PALEOZOIC FERNS

The present status of knowledge in reference to paleozoic ferns has been presented recently by ARBER (60), KIDSTON (64), and SCOTT (82). For a time, the existence of paleozoic ferns was called in question. The increasing number of known and inferred Cycadofilicales from the Carboniferous, and the fact that the earlier the period the less the evidence of ferns, raised a question as to the presence of ferns in the Lower Carboniferous and Devonian. There is general consent now (59, 61, 82) that ferns existed during the Paleozoic, but not as a dominant group and many of them not to be referred to existing groups of ferns. In fact, SCOTT (82) states that the evidence is decidedly in favor of the view that a considerable group of *Marattia*-like ferns existed during the Upper Coal-measures and Permian, side by side with Cycadofilicales of similar habit, but not known to extend to the Lower Carboniferous. When representatives of the living eusporangiate and leptosporangiate ferns are sought among paleozoic plants, they are not recognizable. There is an abundance of annulate and exannulate sporangia; and in general the former have been regarded as standing for leptosporangiate ferns, and the latter for eusporangiate ferns. But some of the exannulate sporangia have been discovered to be the microsporangia of Cycadofilicales; and the annulate sporangia are very different, both in the character of the annulus and in the structure of the sporangium wall, from those of the modern leptosporangiate ferns. SCOTT (69, 82) has established the sporangium genus *Pteridotheca* to receive the unassigned, petrified, paleozoic sporangia bearing an annulus or with other characters indicating their affinity with ferns; and he thinks that doubtless some of the species belong to true ferns. The paleozoic ferns in general, which were neither leptosporangiate nor eusporangiate ferns in the modern sense, have been called *Primofilices* by ARBER

(60), an ancestral race which combined the characters of the modern groups. In fact, the existence of leptosporangiate ferns, in the modern sense, has not been recognized until the Permian, and during the Mesozoic the group was a dominant one and its modern families became differentiated; while evidence of the existence of eusporangiate ferns, in the modern sense, is not satisfactory until the Tertiary (60, 61).

PALEOZOIC MARATTIACEAE (82).—The very large proportion of synangia belonging to the carboniferous flora led to the inference that the Marattiaceae were conspicuously represented. All types of sporangia, from free to united (synangia), occur on leaves referred to *Pecopteris*, and one *Pecopteris* (*P. Pluckenetii*) has been found to be seed-bearing. It was natural to raise the question whether all of the sporangia referred to Marattiaceae are not microsporangia. But *Pecopteris* is a very large frond genus, and such sporangium genera as *Ptychocarpus*, *Asterotheca*, *Scolecopteris*, and *Daneites*, which are synangia borne on the ordinary foliage, have every right to be regarded as belonging to the Marattiaceae until there is absolute proof to the contrary. Such forms are characteristic of the Permian and Upper Coal-measures, and are not known to occur in the Lower Carboniferous.

In addition to this evidence of the existence of paleozoic Marattiaceae, which may be regarded as negative, there is positive evidence from the anatomy of *Psaronius*, a stem genus occurring at the same horizons. The fronds borne by this stem were of the *Pecopteris* type (42), as shown by constant association, and are identical with those bearing such sporangia as *Asterotheca* and *Scolecopteris*. Repeated investigation of the anatomy of these stems and leaves has strongly confirmed the belief that the species of *Psaronius* were stems of arborescent members of the Marattiaceae. Some of these permo-carboniferous trees were of great size, reaching a height of 18 to 20 m. The stems were complex polystelic and the roots polyarch, the whole structure more nearly resembling the vascular structure of the Marattiaceae than of any other known stems. A species (*P. Renaultii*) from the Lower Coal-measures is of exceptional antiquity and simplicity, being monostelic, a single endarch vascular cylinder inclosing pith.



The general conclusion is that "ferns with marattiaceous affinities formed an important constituent of the permo-carboniferous flora, especially toward the close of that period" (82).

PRIMOFILICES.—Only one family of Primofilices has been distinguished clearly, and that is the peculiar group Botryopterideae, brought to light by SCOTT (24), and probably extensively displayed during the Paleozoic. The structure of all the important organs of two of the genera (*Zygopteris* and *Botryopteris*) is fairly well known. The stems are monostelic; those of *Botryopteris* being endarch protostelic and the vascular cylinder circular in section; while those of *Zygopteris* are exarch protostelic and the vascular cylinder has a lobed (five-rayed) section. In the latter genus the stele is differentiated into a peripheral region of large tracheids, and a central region (once thought to be pith) of small tracheids; and there is both internal and external protoxylem. Among Botryopterideae, therefore, there is both exarch and endarch protostely (79), and these conditions vary in a single group. For example, one of the two groups of the family contains *Botryopteris*, which is endarch; *Tubicaulis*, all or nearly all of whose xylem is centripetal; and *Grammatopteris*, which is exarch. The exarch protostele of *Tubicaulis* and *Grammatopteris* has been regarded as the most primitive type of vascular strand found in the axis of a vascular plant (75). The range of vascular structure displayed by the Botryopterideae is said (65, 75) to be sufficient to serve as a starting point for the modern groups of ferns and for Cycadofilicales.

The sporangia of *Zygopteris* and *Botryopteris* are elongated sacs, with walls at least two layers of cells thick, each with a short pedicel, and borne in terminal tufts (3–8) on a common peduncle (fig. 52) from a branching rachis of a dimorphic leaf (1a). In *Zygopteris* there is a vertical annulus band, several cells wide (multiseriate), on each side of the sporangium (figs. 53 and 54); while in *Botryopteris* there is such a band only on one side. That these sporangia are those of ferns is further indicated by the fact that in *Stauropteris*, whose affinities are probably with the Botryopterideae, germinating spores of undoubted fern character have been found (70).

The conclusion is (82) that in habit, anatomy, and sporangia, the Botryopterideae show that they are ferns, which in all probability

have given rise at least to the more modern leptosporangiate and eusporangiate ferns. It is a type older than the paleozoic *Marattiaceae* described above, and it is interesting to note that the sporangia were free, rather than in synangia; the conclusion having been drawn (82) that "the fossil evidence, on the whole, supports the view that free sporangia represent the original form of filicinean fructification,



FIGS. 52-54.—*Zygopteris* sp.: fig. 52, four sporangia on a common pedicel;  $\times 10$ ; fig. 53, transverse section through the middle of a single sporangium, showing sections of the multiseriate vertical annulus;  $\times 20$ ; fig. 54, longitudinal section of single sporangium cut in plane of vertical annulus;  $\times 20$ .—After RENAULT (1a).

and that their cohesion to form synangia was a secondary modification, though one which took place in certain groups at a very early period." It must be remembered that Filicales are probably so ancient that all of our evidence is relatively modern.

Two main anatomical types of ferns, therefore, probably existed during the Paleozoic: (1) the complex-polystelic, *Marattia*-like tree ferns represented by the *Psaronius* stems, which SCOTT calls the *Paleo-Marattiaceae*; and (2) the low, much simpler, monostelic forms, represented by *Botryopterideae*, and constituting the very ancient synthetic group *Primofilices*.

#### ORIGIN OF CYCADOFILICALES

Just as it was tempting at first to derive the Cycadofilicales from the *Marattia* plexus of the Carboniferous, so it was tempting later to derive them, along with modern ferns, from the *Botryopterideae* (64). To search for the actual ancestral forms of the Cycadofilicales seems to be futile (50), for remains of the group have been traced

as far back as any of the Primofilices. That the group arose from fernlike ancestors seems evident from their foliage, anatomy, and microsporangiate structures (61). We are confronted by two alternatives: either the Cycadofilicales were derived from the Primofilices, or the two groups had a common origin far back in the Paleozoic. It would seem to make very little difference which alternative is selected, for either would explain the similarities, and neither can be proved.

**MICROSPORANGIATE STRUCTURES.**—The resemblance of the microsporangiate structures of all the cycadophytes (see below) to the sori and synangia of ferns is so evident that further statement seems hardly necessary. KIDSTON (64) has called attention to the resemblance between the sorus known as *Dactylothea* and the microsporangiate sorus known as *Crossothea*. There is the same relation to the pinnules, the same radiate arrangement of the sporangia; and if the sporangia of *Dactylothea* were extended beyond the margin of the pinnule into a free tip which bent downward, the *Crossothea* type would be reached. Of course, *Dactylothea* may prove to belong to the Cycadofilicales, but it represents a soral structure that belongs to undoubted ferns. The terminal sporangial tufts of *Botryopteris* and of *Zygopteris* are easily related to the *Calymmatothea* type of terminal synangium; while ordinary synangia borne upon the comparatively unmodified foliage leaves of Cycadofilicales (and even Bennettitales) are exact duplicates of the synangia of Paleo-Marattiaceae and modern Marattiaceae. In microsporangiate structures, therefore, the Cycadofilicales, and even the cycadophytes, can hardly be regarded as above the level of ferns.

**MEGASPORANGIATE STRUCTURES.**—While the vascular anatomy and microsporangiate structures of the Cycadofilicales may be shown to be so closely related to the corresponding structures of the Primofilices and Marattiaceae that a phylogenetic connection seems clear, no such claim can be made for the seeds. As SCOTT has said (67), "the discovery of seeds [of Cycadofilicales] hardly touches the problem of the origin of gymnosperms, for the discovered seeds are well developed, on the cycad level; therefore they are too much advanced to throw light on the origin of a seed, and the question of the origin of gymnosperms remains practically as it was before the discovery

of pteridosperms." Theoretically, there remains a stage of progress entirely lacking in our records, and that is the heterosporous fernlike forms that preceded the evolution of seeds. The gap between the homosporous Primofilices (or their unknown ancestors) and the seed-bearing Cycadofilicales is an enormous one, including the evolution of both heterospory and the seed.

Proceeding on purely hypothetical grounds, the most natural inference is that homosporous sporangia began to differentiate into the heterosporous condition; that the microsporangia continued with relatively little change throughout the cycadophyte phylum; and that the megasporangia developed with comparative rapidity into ovules. Miss BENSON (41) has suggested that the ovule is a transformed sorus, explaining the peculiar integument of *Lagenostoma* by regarding the tissue-filled chambers as the sterilized peripheral sporangia of a radiate sorus or synangium. OLIVER (85) infers from the free integument lobes of *Physostoma* that the integument of the *Lagenostoma* group originated as a multiple structure, the nature of the units (free lobes in *Physostoma*, coalescent chambers in *Lagenostoma*) being an open question. His suggestion is that they have arisen as new formations, without any phylogenetic connection, being related to the encasement of reproductive structures that so frequently precedes or follows fertilization. This view would mean that the origin of the integument was contemporaneous with the origin of the seed itself; and that the cupule (as in *Lagenostoma*) is a second such encasement. However true either of these suggestions may be with reference to *Lagenostoma*, the relation of the seeds to the fronds and a comparison of the position of seeds with that of microsporangiate sori compel the belief that ovules often may have arisen by the transformation of sori, a transformation probably introduced by restricting a sorus to a single sporangium. If, as seems possible, a sorus of free sporangia is a more primitive condition of ferns than a synangium, it may be that free sporangia not grouped in a sorus represent a still more primitive condition, and that neither synangium nor sorus holds any relation to the origin of the ovule. After all, the important and obvious fact is that an ovule is a transformed sporangium, and that the phylogenetic stages in this transformation are absolutely lacking.



## 6. Relationship to other gymnosperms

When OLIVER and SCOTT (39, 48) proposed the name *Pteridospermae*, "to embrace those paleozoic plants with the habit and much of the internal organization of ferns, which were reproduced by means of seeds," it was with the claim, implied in the name, that it represented a third great group of seed plants, coordinate with gymnosperms and angiosperms. Fuller knowledge and a stricter definition of the group was awaited with interest. Later, SCOTT (58) said that a strict definition was not possible as yet, but that the following provisional one was suggested: "Plants with the habit and certain of the anatomical characters of ferns, bearing on fronds only slightly differentiated from the vegetative foliage seeds of a cycadean type of structure." There seemed to be no sufficient reason for establishing a group coordinate with gymnosperms upon such comparative features; for it certainly possessed the important character of gymnospermy. Still later, SCOTT (69) formulated his reasons for regarding pteridosperms as worthy of separation from gymnosperms, under two categories: (1) megasporophylls and microsporophylls little modified from ordinary vegetative fronds; (2) anatomical structure more fernlike than in gymnosperms. The cycadophytes as a whole have equally fernlike foliage and sporophylls, and the anatomical peculiarities can nearly all be duplicated among the more primitive gymnosperms. The group is then defined as follows: "Male and female sporophylls little differentiated from the vegetative foliage; no cones formed; anatomy of either stem, or leaf, or both, of a filicinean type, as was also the habit." It is hard to see that such characters are more important than those which distinguish the acknowledged groups of gymnosperms, and of equal importance with those that distinguish gymnosperms from angiosperms. We are compelled to regard pteridosperms as the most primitive known group of gymnosperms, and our reasons for calling them Cycadofilicales have been given above (p. 3).

There is no more suggestion of the organization of a strobilus, and no more extreme differentiation of a sporophyll, than among ferns; so that in these respects the group has remained at the fern level. Among living cycadophytes, the megasporophylls of cycads do not always form a compact strobilus, and every gradation is found

from loosely arranged sporophylls that have retained features of the foliage, to the very compactly arranged and much modified sporophylls of such a strobilus as that of *Zamia*. It is this tendency among the cycads that may be added to the burden of testimony indicating the origin of all cycads from a group in which no strobili were organized and no sporophylls differentiated.

It may be said that in microsporangiate structures the Cycadofilicales made very little progress; but these are also fernlike in both Bennettitales and Cycadales. In megasporangiate structures, the Cycadofilicales are far advanced, for the seeds are distinctly of the so-called cycadean type, and so far removed from the fern level that we seem to be no nearer the origin of seeds than before the discovery of the group.

The relationship of Cycadofilicales to Bennettitales and Cycadales seems so evident, the historical sequence being as definite as the morphological, that NATHORST and WORSDELL (72) have adopted the name *Cycadophyta* for the phylum including these three groups. It would seem as if this gymnosperm phylum, extending from early Paleozoic to the present time, is thoroughly well established.

The relationship of Cycadofilicales to the other gymnosperm groups is by no means so clear, but their intimate association with the Cordaitales, as well as the morphological resemblances of the two groups, suggests that Cordaitales may be the beginning of another gymnosperm phylum which diverged from Cycadofilicales much earlier than did the cycad phylum. The presentation of this testimony will be given under Cordaitales.

In any event, there seem to have been two great phyla of gymnosperms, both differentiating from the Cycadofilicales, or each arising independently from the progenitors of the Cycadofilicales. One of these phyla has already been called the *Cycadophytes*, and includes the Cycadofilicales, Bennettitales, and Cycadales; the other, which arose either from the more ancient Cycadofilicales or their immediate ancestors, and includes Cordaitales, Ginkgoales, and Coniferales, may be called the *Coniferophytes*. The reasons for excluding Gnetales from these connections will appear in the discussion of that group; but as between the two phyla proposed, the Gnetales would certainly be related to the second.

## LITERATURE CITED

1. WILLIAMSON, W. C., On the organization of the fossil plants of the Coal-measures. IV. *Dictyoxylon*, *Lyginodendron*, and *Heterangium*. Phil. Trans. Roy. Soc. London B **163**:377-408. *pls.* 22-31. 1873.
- 1a. RENAULT, B., Recherches sur la fructification de quelques végétaux provenant des gisements silicifiés d'Autun et de Saint Etienne. Ann. Sci. Nat. Bot. VI. **3**:5-29. *pls.* 1-4. 1876.
2. WILLIAMSON, W. C., On some fossil seeds from the Lower Carboniferous beds of Lancashire. Rep. 45th Meeting British Assoc. (1875):159-160. 1876.
3. ———, On the organization, etc. VIII. Ferns (continued) and gymnospermous stems and seeds. Ann. Mag. Nat. Hist. **18**:268-273. 1876 (preliminary notice); Proc. Roy. Soc. London **25**:68-73. 1877 (abstract); Phil. Trans. Roy. Soc. London B **167**:213-270. *pls.* 5-16. 1878 (full paper).
4. ———, On the organization, etc. X. Phil. Trans. Roy. Soc. London B **171**:493-539. *pls.* 14-21. 1880.
5. ———, On the organization, etc. XIII. Phil. Trans. Roy. Soc. London B **178**:289-304. *pls.* 21-24. 1887 (p. 299).
6. BRONGNIART, A., Recherches sur les graines fossiles silicifiées. Paris. 1881.
7. STUR, D., Zur Morphologie und Systematik der Kuhl- und Karbonfarne. Sitzungsab. Akad. Wiss. Wien **88**: pp. 214. *figs.* 4. 1883.
8. WILLIAMSON, W. C., On the organization, etc. XII. Phil. Trans. Roy. Soc. London B **174**:459-475. *pls.* 27-34. 1883.
9. RENAULT, B., Cours de botanique fossile. Paris. 1880-1884.
10. VAN TIEGHEM, PH., et DOULIOT, H., Sur la polystellie. Ann. Sci. Nat. Bot. VII. **3**:275-322. *pls.* 13, 14. 1886.
11. KIDSTON, R., On the fructifications of some ferns from the Carboniferous formation. Trans. Roy. Soc. Edinburgh **33**:137-156. *pls.* 8. *figs.* 7. 1887.
12. RENAULT, B., Note sur le genre *Aetheotesta*. Mém. Soc. Hist. Nat. Saône-et-Loire, pp. 156, 158. 1887.
13. SABLON, LECLERC DU, Recherches sur la tige des fougères. Ann. Sci. Nat. Bot. VII. **11**:1-16. *pls.* 1, 2. 1890.
14. WILLIAMSON, W. C., On the organization, etc. XVII. Phil. Trans. Roy. Soc. London B **181**:89-106. *pls.* 12-15. 1890.
15. KIDSTON, R., On the various divisions of British Carboniferous rocks, as determined by their fossil floras. Proc. Roy. Soc. Edinburgh **12**:183-257. 1893-1894.
16. RENAULT, B., Bassin houiller et Permien d'Autun et d'Épinac. IV. Flore fossile. Part II. pp. 578. *pls.* 62. Paris. 1896.
17. WEBER, O., und STERZEL, J. T., Beiträge zur Kenntnis der Medulloseae. XIII. Ber. Naturwiss. Gesell. Chemnitz. pp. 102. *pls.* 9. *figs.* 33. 1896.
18. WILLIAMSON, W. C., and SCOTT, D. H., Further observations on the organization of the fossil plants from the Coal-measures. III. *Lyginodendron* and

- Heterangium*. Phil. Trans. Roy. Soc. London B 186:703-779. pls. 18-21. 1896.
19. BUTTERWORTH, J., Some further investigation of fossil seeds of the genus *Lagenostoma* (WILLIAMSON) from the Lower Coal-measures. Mem. and Proc. Manchester Lit. and Phil. Soc. 41:1-4. 1897.
  20. POTONIÉ, H., Lehrbuch der Pflanzenpalaeontologie. Berlin. 1899.
  21. SEWARD, A. C., Notes on the Binney collection of Coal-measure plants. II. *Megaloxylon*, gen. nov. Proc. Cambridge Phil. Soc. 10:158-174. pls. 5-7. 1899.
  22. SCOTT, D. H., On the structure and affinities of fossil plants from the paleozoic rocks. III. *Medullosa anglica*, a new representative of the Cycadofilices. Proc. Roy. Soc. London 64:249-253. 1899 (abstract); Phil. Trans. Roy. Soc. London B 191:81-126. pls. 5-13. 1899 (full paper).
  23. ———, Note on the occurrence of a seedlike fructification in certain paleozoic lycopods. Proc. Roy. Soc. London 67:306-309. 1900.
  24. ———, Studies in fossil botany. London. 1900.
  25. WILD, G., On *Trigonocarpum olivaeforme*. Trans. Manchester Geol. Soc. 26: pp. 16. pls. 2. 1900.
  26. ZEILLER, R., Eléments de palaeobotanique. 1900.
  27. FAULL, J. H., The anatomy of the Osmundaceae. Bot. Gazette 32:381-420. pls. 14-17. 1901.
  28. SCOTT, D. H., On the structure and affinities of fossil plants from the paleozoic rocks. IV. The seedlike fructification of *Lepidocarpus*, a genus of lycopodiaceous cones from the Carboniferous formation. Phil. Trans. Roy. Soc. London B 194:291-333. pls. 38-43. 1901.
  29. BENSON, MARGARET, On a new lycopodiaceous seedlike organ. New Phytologist 1:58, 59. fig. 3. 1902.
  30. ———, The fructification of *Lyginodendron Oldhamium*. Annals of Botany 16:575, 576. figs. 31. 1902.
  31. JEFFREY, E. C., The structure and development of the stem in the Pteridophyta and Gymnosperms. Phil. Trans. Roy. Soc. London B 195:119-146. pls. 1-6. 1902.
  32. LOMAX, J., Some new features in relation to *Lyginodendron Oldhamium*. Annals of Botany 16:601, 602. 1902.
  33. NATHORST, A. G., Beiträge zur Kenntnis einiger mesozoischen Cycadophyten. Handl. Kgl. Svensk. Vetensk.-Akad. 36:1-28. pls. 1-3. 1902.
  34. OLIVER, F. W., On some points of apparent resemblance in certain fossil and recent gymnospermous seeds. New Phytologist 1:145-154. figs. 4-6. 1902.
  35. POTONIÉ, H., Cycadofilices in ENGLER und PRANTL's Natürlichen Pflanzenfamilien 1:780-798. 1902.
  36. WORSDELL, W. C., The evolution of the vascular tissue of plants. Bot. Gazette 34:216-223. figs. 7. 1902.



37. JEFFREY, E. C., Vascular anatomy in COULTER and CHAMBERLAIN'S Morphology of angiosperms. New York. 1903.
38. OLIVER, F. W., The ovules of the older gymnosperms. Annals of Botany **17**:451-476. *pl.* 24. *figs.* 20. 1903.
39. ———, and SCOTT, D. H., On *Lagenostoma Lomaxii*, the seed of *Lyginodendron*. Proc. Roy. Soc. London **71**:477-481. 1903; reprint in Annals of Botany **17**:625-629. 1903.
40. SELLARDS, E. H., *Codonotheca*, a new type of spore-bearing organ from the Coal-measures. Amer. Jour. Sci. IV. **16**:87-95. *pl.* 8. 1903.
41. BENSON, MARGARET, *Telangium Scottii*, a new species of *Telangium* (*Calymmatotheca*) showing structure. Annals of Botany **18**:161-177. *pl.* 11. 1904.
42. GRAND'EURY, C., Sur les rhizomes et les racines des fougères fossiles et des Cycadofilices. Compt. Rend. Acad. Sci. Paris **138**:607-610. 1904.
43. ———, Sur les graines des Neuropteridées. Compt. Rend. Acad. Sci. Paris **139**:23-27, 782-786. 1904.
44. KIDSTON, R., On the fructification of *Neuropteris heterophylla* Brongniart. Proc. Roy. Soc. London **72**:487. 1904 (abstract); Phil. Trans. Roy. Soc. London B **197**:1-5. *pl.* 1. 1904 (full paper).
45. OLIVER, F. W., A new pteridosperm. New Phytologist **3**:32. 1904.
46. ———, Notes on *Trigonocarpum* Brongn. and *Polylophospermum* Brongn., two genera of paleozoic seeds. New Phytologist **3**:96-104. *pl.* 2. 1904.
47. ———, On the structure and affinities of *Stephanospermum* Brongniart, a genus of fossil gymnosperm seeds. Trans. Linn. Soc. London Bot. II. **6**:361-400. *pls.* 41-44. 1904.
48. ———, and SCOTT, D. H., On the structure of the paleozoic seed *Lagenostoma Lomaxii*, with a statement of the evidence upon which it is referred to *Lyginodendron*. Proc. Roy. Soc. London, Jan. 21, 1904 (abstract preprint); Phil. Trans. Roy. Soc. London B **197**:193-247. *pls.* 4-10. 1904 (full paper).
49. WHITE, DAVID, The seeds of *Aneimites*. Smithson. Miscell. Coll. **47**:322-331. *pls.* 47, 48. 1904.
50. ———, Fossil plants of the group Cycadofilices. Smithson. Miscell. Coll. **47**:377-390. *pls.* 53-55. 1904.
51. ARBER, E. A. NEWELL, On some new species of *Lagenostoma*, a type of pteridospermous seed from the Coal-measures. Annals of Botany **19**:326-328. 1905 (abstract).
52. GRAND'EURY, C., Sur les graines trouvées attachées au *Pecopteris Pluckenetii* Schlot. Compt. Rend. Acad. Sci. Paris **140**:920-923. *figs.* 2. 1905.
53. ———, Sur les graines de *Sphenopteris*, sur l'attribution des *Codonospermum*, et sur l'extrême variété des graines des fougères. Compt. Rend. Acad. Sci. Paris **141**:812-815. 1905.
54. KIDSTON, R., Preliminary note on the occurrence of microsporangia in organic connection with the foliage of *Lyginodendron*. Proc. Roy. Soc. London **76**:358-360. *pl.* 6. 1905.

55. KIDSTON R., The early history of seed-bearing plants as recorded in the carboniferous flora. Wilde Lecture. Mem. and Proc. Manchester Lit. and Phil. Soc. **49**:no. 12. pp. 32. pls. 3. 1905.
- 55a. OLIVER, F. W., Ueber die neuentdeckten Samen der Steinkohlenfarne. Biol. Centralbl. **25**:401-418. figs. 6. 1905.
56. SCOTT, D. H., What were the carboniferous ferns? Jour. Roy. Micr. Soc. **1905**<sup>2</sup>:137-149. pls. 1-3. figs. 32, 33.
57. ———, The sporangia of *Stauropteris Oldhamia* Binney. New Phytologist **4**:114-120. figs. 2. 1905.
58. ———, The fernlike seed plants of the carboniferous flora. Sci. papers Internat. Bot. Congress Vienna. 1905.
59. ZEILLER, R., Une nouvelle classe de Gymnospermes: les Pteridospermées. Rev. Gén. Sci. **16**:718-727. figs. 7. 1905.
60. ARBER, E. A. NEWELL, On the past history of ferns. Annals of Botany **20**:215-232. 1906.
61. ———, "The origin of gymnosperms"; a discussion at the Linnean Society. New Phytologist **5**:68-76, 141-148. 1906.
62. GRAND'EURY, C., Sur les inflorescences des fougères avec graines, etc. Compt. Rend. Acad. Sci. Paris **143**:764. 1906.
63. HILL, T. G., On secondary thickening in recent Pteridophyta. New Phytologist **5**:208-214. 1906.
64. KIDSTON, R., On the microsporangia of the Pteridospermae, with remarks on their relationships to existing groups. Phil. Trans. Roy. Soc. London B **198**:413-445. pls. 25-28. 1906.
65. OLIVER, F. W., "The origin of gymnosperms"; a discussion at the Linnean Society. New Phytologist **5**:68-76, 141-148. 1906.
66. ———, Pteridosperms and angiosperms. New Phytologist **5**:232-242. 1906.
67. SCOTT, D. H., "The origin of gymnosperms"; a discussion at the Linnean Society. New Phytologist **5**:68-76, 141-148. 1906.
68. ———, On *Sutcliffia insignis*, a new type of Medulloseae from the Lower Coal-measures. Trans. Linn. Soc. London II. **7**:45-68. pl. 4. 1906.
69. ———, The present position of paleozoic botany. Progressus rei botanicae (J. P. LOTSÝ) **1**<sup>1</sup>:139-217. figs. 37. 1906.
70. ———, The occurrence of germinating spores in *Stauropteris Oldhamia*. New Phytologist **5**:170-172. 1906.
71. STOPES, M. C., A new fern from the Coal-measures: *Tubicaulis Sutcliffii*, spec. nov. Mem. and Proc. Manchester Lit. and Phil. Soc. **50**:1-30. pls. 1-3. 1906.
72. WORSDELL, W. C., The structure and origin of the Cycadaceae. Annals of Botany **20**:129-159. figs. 17. 1906.
73. SCOTT, D. H., and MASLEN, ARTHUR J., The structure of the paleozoic seeds *Trigonocarpus Parkinsonii* Brongniart and *Trigonocarpus Oliveri*, sp. nov. I. Annals of Botany **21**:89-134. pls. 11-14. 1907.

74. SELLARDS, E. H., Notes on the spore-bearing organ *Codonotheca* and its relationship with the Cycadofilices. *New Phytologist* **6**:175-178. 1907.
75. TANSLEY, A. G., Lectures on the evolution of the filicinean vascular system. II. The Botryopterideae. *New Phytologist* **6**:53-68. *figs.* 22. 1907.
76. THOMAS, ETHEL N., A theory of the double leaf trace founded on seedling structure. *New Phytologist* **6**:77-91. *figs.* 4. 1907.
77. ARBER, E. A. NEWELL, On a new pteridosperm possessing the *Sphenopteris* type of foliage. *Annals of Botany* **22**:57-62. *pl.* 6. 1908.
78. BENSON, MARGARET, On the contents of the pollen chamber of a specimen of *Lagenostoma ovoides*. *Bot. Gazette* **45**:409-412. *figs.* 2. 1908.
79. BROWNE, LADY ISABEL, The phylogeny and interrelationships of the Pteridophyta. V. Filicales. *New Phytologist* **7**:230-253. 1908.
80. JEFFREY, E. C., Are there foliar gaps in the Lycopsidea? *Bot. Gazette* **46**:241-258. *pls.* 17, 18. 1908.
81. NATHORST, A. G., Palaeobotanische Mitteilungen. IV. Ueber die Untersuchung kutinisierte fossiler Pflanzenteile. *Handl. Kgl. Svensk. Vetensk.-Akad.* **43**:1-13. *pls.* 1, 2. 1908.
82. SCOTT, D. H., Studies in fossil botany. Second edition. Vol. I. London. 1908.
83. BENSON, MARGARET, Report of Proc. Roy. Soc. London in Nature **80**:239. 1909.
84. COULTER, JOHN M., Evolutionary tendencies among gymnosperms. *Bot. Gazette* **48**:81-97. 1909.
85. OLIVER, F. W., On *Physostoma elegans* Williamson, an archaic type of seed from the paleozoic rocks. *Annals of Botany* **23**:73-116. *pls.* 5-7. *figs.* 10. 1909.
86. SCOTT, D. H., The paleontological record. II. Plants. Darwin and modern science, pp. 200-222. Cambridge University Press. 1909.
87. ———, Studies in fossil botany. Second edition. Vol. II. London. 1909.
88. COULTER, J. M., BARNES, C. R., and COWLES, H. C., A textbook of botany. New York. 1910.

## CHAPTER II

### BENNETTITALES

Bennettitales are as characteristic of the mesozoic flora, from the Trias to the Lower Cretaceous, as are the Cycadofilicales of the paleozoic. The historical and morphological succession is so distinct that there seems to be no reasonable doubt of the phylogenetic connection of the two groups. The Mesozoic has long been called "the age of cycads," but it was recognized that the mesozoic forms differ so much from the modern ones as to justify speaking of them as "anomalous" or "aberrant" cycads. The type genus, *Bennettites*, was described by CARRUTHERS (2) in 1867, and in 1870 he established (4) the group Bennettiteae as an assemblage of aberrant Cycadales.

The best known foreign localities for the remains of Bennettitales are in Western Europe and India; but by far the richest display of these forms has been found in the United States and Mexico. These North American forms have been described chiefly by WARD (11, 12), and their structure has been skilfully investigated and set forth in great detail by WIELAND (22). The three prominent American localities that have yielded material are in Maryland, in the Black Hills of South Dakota and Wyoming, and in the Freezeout Hills of Wyoming; while the recently discovered Mexican locality is in the mountains of western Oaxaca (30). The remarkable Mexican deposits were discovered by WIELAND (30) in 1909, and they bid fair to surpass in abundance of remains and in interest even those of the United States. The region is a great plateau of Oaxaca on the southern edge of the Cordilleras facing the Pacific, and known locally as "Mixteca Alta." A section through 2,000 feet of "Rhät-Liassic" is full of the remains of cycadophytes, and among them there is a profusion of the strobili of *Williamsonia*, a most interesting addition to the cycadophyte flora of America. Unfortunately, silicified remains have not yet been found.

The best known and largest genera of the group are *Bennettites*, *Cycadeoidea*, and *Cycadella*; other genera (not American) are *Bucklandia*, *Williamsonia* (also Mexican), *Cycadocephalus*, *Yatesia*,



*Platophyllum* (from India), etc. There is more or less confusion as to generic limitations, and the names cited are not applied uniformly by all writers. For example, the *Cycadeoidea* Buckland of American authors is a synonym of *Bennettites* Carruthers of European authors, but it is convenient to use the two names at present to distinguish American and European material of the genus. To the morphologist the group is a very consistent one, and at this stage of knowledge the differences among genera and their nomenclature are of minor importance.

### 1. The vegetative organs

The habit of Bennettitales was much more diversified than that of existing Cycadales. The tuberous type of trunk (fig. 55) prevails among the known forms, and short columnar trunks also occur, both of which types of body are familiar among cycads; but there are also tall and slender forms, as *Williamsonia gigas* (fig. 56); and branching forms occur, commonly resulting in multiple crowns (as in *Dioon* and *Zamia*), and in the case of *Williamsonia angustifolia* (*Anomozamites*, 17), a form which flourished in the early Triassic of southern Sweden, and probably represented in Mexico (30), the body was slender and widely branching (fig. 57). The recently described (31) *Wielandiella*, from the Jurassic beds of England, is also slender and widely branching. The largest specimens are from the Black Hills region, huge tuberous bodies of *Cycadeoidea* occurring over a meter in height and more than half that in diameter; while the species of *Cycadella* from the Freezeout Hills are said to average only 35 cm. in height and 20 cm. in diameter. The columnar trunks from the United States are over a meter in height, and in the case of *Cycadeoidea Jenneyana* such trunks reach a height of three to four meters.

The compact forms are covered by an armor of closely imbricated persistent leaf bases, and a crown of cycad-like leaves. Among these leaf bases numerous short, axillary branches are wedged, each bearing a terminal strobilus that projects more or less beyond the armor (fig. 55). These numerous axillary, cone-bearing dwarf shoots, borne on a monopodial trunk, are in sharp contrast with the habit of Cycadales, whose sympodial trunks bear a succession of terminal

strobili. A possible relation between the two is evident when it is remembered that in reality the apparently terminal strobili of Cycadales are borne on a succession of branches which build up the sympodial trunk. If the cone-bearing branches of Bennettitales were restricted more and more to the tip of the axis, the cycad condition



FIG. 55.—*Cycadeoidea Wielandii*: upper part of a large trunk found near Hermosa, South Dakota; numerous strobili project more or less through the armor; the dark circular holes are cavities from which strobili have fallen; height of specimen, 54 cm.—From photograph by THIESSEN.

might follow. In fact, there are cases which may be interpreted as showing this tendency among the Bennettitales, and occasionally cycads develop lateral groups of strobili, as in *Encephalartos* (p. 121).

The restoration of *Williamsonia gigas* (4), from the Lower Oolite of the Yorkshire coast, long known as *Zamia gigas* (1, 3), shows (fig. 56) a slender columnar shaft bearing a crown of large leaves, the

whole habit suggesting that of one of the taller species of *Cycas*. The stem was covered with rhomboidal scars, and the strobili were borne on long (20–30 cm.) stalks covered with spirally arranged scale



FIG. 56.—*Williamsonia gigas*: restoration showing stem with leaf scars, crown of leaves, and two spherical and peduncled strobili.—After WILLIAMSON (3).

leaves, and arising within the crown of leaves. This species of *Williamsonia* differs from the other Bennettitales chiefly in these long peduncles. In *Williamsonia angustifolia* (fig. 57), whose leaves have been called *Anomozamites minor*, the small strobili occur singly in

forks of the widely spreading branches (also in *Wielandiella*), evidently being terminal structures, and the narrow pinnate leaves, only 7–8 cm. long, form rosettes about the forks. In general habit, therefore, the Bennettitales show a range that may well connect the more open, branching forms of the Cycadofilicales with the very compact and usually simple body of the Cycadales. It has been suggested (29) that *Bennettites* (*Cycadeoidea*) and *Williamsonia* may be regarded as representatives of two groups of Bennettitales.



FIG. 57.—*Williamsonia* (*Anomozamites*) *angustifolia*: branching trunk, with rosettes of leaves and strobili at the forks; about  $\frac{1}{3}$  natural size.—After NATHORST (17).

A second striking external feature of the Bennettitales is the occurrence of scales densely packed between the leaf bases and about the strobili, and also covering the crown. This is distinctly the so-called ramentum of ferns, the scales being one layer of cells thick, except in the central region, the cells becoming much elongated (fig. 58). In certain species of *Cycadella*, a dwarf genus distinguished by its abundant ramental covering, WARD and WIELAND describe the ramentum and armor of leaf bases as making up half the bulk of many trunks. While ramentum is not lacking in any of the Bennettitales, so far as known, there is every gradation in its abundance,



some trunks bearing but little. Among the cycads, certain genera, as *Dioon*, *Encephalartos*, etc., produce long one-celled or two-celled

hairs which may be regarded as replacing in a general way the ramentum of ferns and of Bennettitales, but they are so different from the scales that make up the ramentum that the latter must be regarded as a very distinct feature of the Bennettitales.



FIG. 58. — *Cycadella ramentosa*: transverse section of the ramentum of the leaves;  $\times 66$ .—After WIELAND (22).

#### VASCULAR ANATOMY

The anatomy of the stem is very much like that of the stem of Cycadales. A transverse section shows a very thick cortex, usually a comparatively thin vascular cylinder, and a large pith with mucilage or gum canals or reservoirs. The vascular cylinder is made up of collateral endarch bundles, so that

the most advanced type of gymnosperm cylinder had been attained; in fact, it had been attained by some of the Cycadofilicales. In *Cycadeoidea Jenneyana* and *C. ingens* the vascular cylinder is so massive (22) as to suggest the cylinder of Cordaitales, being made up of successive woody zones. Among the cycads there is sometimes a succession of vascular zones which arise from a succession of cortical cambiums; but in these species of *Cycadeoidea* the cylinder is so compact that it suggests a persistent primary cambium.

The vascular cylinder of Bennettitales and of Cycadales is regarded by WORSDELL (23) as giving clear evidence of its derivation from the *Medullosa* type of cylinder among the Cycadofilicales. His proofs are largely obtained from investigations of the cotyledonary node and strobilar axis of certain cycads, polystely having been found in the cotyledonary node of a species of *Encephalartos*, and a very irregular orientation of bundles in the peduncle of *Stangeria*. According to this view, the cycadean cylinder has been built up by the regular

arrangement of the separate steles of *Medullosa*, accompanied by the elimination of internal vascular tissues out to the protoxylem. In any event, the type of cylinder displayed by *Lyginodendron*, which according to this view was formed in the same way, would be the immediate progenitor of the cycadean cylinder, the only change necessary being a transition from the mesarch to the endarch condition, a transition completely or at least very nearly attained by *Cycadoxylon*, and seen in the seedling of *Ceratozamia*. It was in this connection that WORSDELL (23) extended the very useful group named Cycadophyta, suggested by NATHORST, to include the Cycadofilicales, Bennettitales, and Cycadales, NATHORST's "cycadophytes" including the mesozoic plexus of cycadean forms and the living cycads.

The leaf traces, at first endarch near the vascular cylinder, soon become mesarch, as in cycads, and this structure characterizes the foliar bundles. It is altogether probable that the mesarch condition passes into the exarch in the ultimate foliar branches of the vascular system, for this is evident among cycads as the bundles become simpler; but the prevailing mesarch type of leaf trace and leaf bundle is an important reminder of fern connections. It is in connection with the leaf traces, however, that a striking contrast between Bennettitales and Cycadales appears. In the latter group, several vascular strands leave the cylinder and enter a single leaf, two of them following a more or less devious route through the cortex, resulting in the so-called "girdles." Among Bennettitales a single bundle leaves the vascular cylinder, and in passing directly through the cortex toward its leaf breaks up into numerous smaller bundles that enter the leaf. The "girdle" habit will be discussed under Cycadales, but at this point it is important to note that the direct course of the leaf trace, characteristic of the mature stems of Bennettitales, is found in the vascular connections of the sporophylls and cotyledons of Cycadales.

#### THE LEAF

The leaves, arising in a crown from the top of the tuberous or columnar trunks, closely resemble those of *Dioon*, *Zamia*, etc., both in form and in structure. In fact, the abundant detached leaves found in certain mesozoic deposits have suggested the establishment of such leaf genera as *Zamites*, *Dioonites*, and *Cycadites*; while *Otozamites* and

*Anomozamites* are leaves differing from those of any living cycads. The mature fronds of *Cycadeoidea ingens* are estimated (22) to have attained a length of three meters. The leaves of the slender and widely branching *Williamsonia angustifolia* (*Anomozamites*) seem to have occurred in clusters at the ends of branches and at the forks, each cluster surrounding a small terminal strobilius (fig. 57), and composed of leaves which were linear in general outline and pinnate with short, broad lobes.

The absence of scale leaves from the crown of the tuberous and columnar forms, alternating with the foliage leaves, has been remarked; but scale leaves are related to strobili. Among Cycadales the terminal strobili necessarily involve the association of their enveloping scales or bracts with the crown of foliage leaves; among Bennettitales the lateral position of the strobili prevents any association of their scale leaves with the foliage of the crown, and such leaves or bracts form the characteristic husklike covering of the strobili. Among Cycadales the enveloping bracts are much more open, but they are as definitely related to individual strobili as among the Bennettitales.

## 2. The spore-producing members

### THE STROBILUS

Perhaps the most important result of WIELAND'S investigations (7, 8, 9, 16, 22) was the discovery of the bisporangiate character of the strobilus. At first it was supposed that this might be an exceptional condition in the group, but it has now been found in so many genera and species that it is known to represent the general condition. In a recent examination of certain species of Bennettitales from the Jurassic beds of England, NATHORST (31) concludes that two species of *Williamsonia* and *Cycadocephalus Sewardii* bore monosporangiate strobili, but the general occurrence of bisporangiate strobili seems assured. WIELAND found bisporangiate strobili not only in numerous sections of American material, but examined the best known European forms (*Cycadeoidea etrusca*, *C. Reichenbachiana*, *Williamsonia gigas*, and *W. angustifolia*) and found bisporangiate strobili in all of them (26). The microsporophylls (stamens) have disappeared when the seeds are mature, but in seed-bearing strobili the former position of the

stamens is always shown by a distinct "shoulder" or "hypogynous disk" on the receptacle between the enveloping sterile bracts and the seed-bearing structures. This interpretation is confirmed by the fact that in strobili containing mature stamens the ovulate structures are always present in a very young stage. It may be presumed that when the stamens were mature, the ovules were ready for pollination. The period between pollination and the appearance of a fully formed embryo is usually long enough among gymnosperms to account for the absence of stamens from the strobili of Bennettitales bearing mature seeds. It may be unsafe to assume, as yet, that there were few Bennettitales with monosporangiate strobili, but at present the bisporangiate strobilus is one of the outstanding features of the group.



FIG. 59.—*Cycadeoidea*: restoration of an unexpanded strobilus, with part of the enveloping hairy bracts removed; 18 folded fronds are shown as in *C. dacotensis*; about natural size, or not nearly so large as various examples.—Figure and description after WIELAND (22).

The general structure of the strobilus is as follows: The tip of the axillary dwarf branch or peduncle is expanded into a hemispherical receptacle or is continued more or less as a thick axial receptacle. Upon this receptacle three sets of members are developed in spiral



succession (fig. 59): (1) the outermost (lowest), a series of heavy, imbricated bracts completely inclosing the structures within; (2) next a series of the characteristic leaflike microsporophylls (10-20 in number); (3) on the top of the hemispherical receptacle, or on the conelike tip of the axial one, a large number of remarkable ovulate sporophylls intermixed with still more numerous sterile ones ("inter-seminal scales"). The recorded length of the larger ovoid strobili is 4 to 7 cm.; while smaller ones (as those of *Cycadella*) range down to 1 cm.

A strobilus of this type, characterizing an extensively displayed group of mesozoic gymnosperms, has tempted to much speculation as to its relation to the flowers of angiosperms, which seem to have begun to emerge into notice during the same time. Following WIELAND'S original suggestion (22), OLIVER (21), and ARBER and PARKIN (24) have further elaborated the same thesis, and SCOTT (28) has expressed the opinion that "the affinities between mesozoic Cycadophyta and the angiosperms appear extremely significant," and that it is "difficult to resist the conviction that the ancestry of the angiosperms, so long shrouded in complete obscurity, is to be sought among the great plexus of cycad-like plants which dominated the flora of the world in mesozoic times." OLIVER has suggested *angiocycads* as the phyletic name of Bennettiales (or some allied stock) as possible ancestors of angiosperms. ARBER and PARKIN have analyzed the strobilus situation and given it a terminology. An *anthostrobilus* is a bisporangiate strobilus in which the megasporophylls are above the microsporophylls, as in Bennettiales and all angiosperms. The earlier form of this strobilus is called the *proanthostrobilus*, in which there is gymnospermy and the microsporophylls have not reached the real stamen form; a definition evidently constructed to describe the strobilus of Bennettiales. The later form of anthostrobilus is the *euanthostrobilus* (or "flower"), in which angiospermy has been attained and a well-marked perianth has been developed. This phylogenetic suggestion further supposes a hypothetical group of plants to intermediate between the Bennettiales (or their equivalents) and the angiosperms, to which the name *hemiangiosperms* is given. LIGNIER (25) has dissented from this view of the origin of angiosperms, for he regards the strobilus of

Bennettitales as an "inflorescence" rather than a "flower"; and he has enriched the terminology of the strobilus further by adding *pteridostrobilus* as a stage before the proanthostrobilus, to include the grouping of fernlike microsporophylls and megasporophylls in monosporangiate strobili. WIELAND (30) has also dissented from the substitution of the new term hemiangiosperms for the long-used *proangiosperms* of SAPORTA. The possible relationship of gymnosperms to angiosperms does not come within the province of this volume, but in connection with the structure of the strobilus of Bennettitales its responsibility for speculation in reference to the origin of the angiosperms should be known.

In any event, it is safe to conclude that if the Cycadofilicales gave rise to the strobilus-bearing cycadophytes, there were at least two lines of development: one leading to forms with bisporangiate strobili (Bennettitales), and the other to forms with monosporangiate strobili (Cycadales).

#### THE MICROSPORANGIUM

WIELAND's investigations (22) of *Cycadeoidea* indicate that the microsporophylls (stamens) are remarkably uniform in character. In number they range from ten (*C. Jenneyana*) to twenty (*C. dactensis*). In form they are elongated, pinnate, fernlike leaves, with about twenty slender pinnae, beneath which there are borne two lateral rows of close-set synangia (fig. 60). It has been suggested that these sporophylls should be called bipinnate, on the ground that the synangia represent ultimate pinnules. The only advantage to be gained from this somewhat doubtful interpretation is that it serves to distinguish the microsporophylls of *Cycadeoidea* (so far as studied) from the simpler ones of *Williamsonia*. The sporophylls are united at base into a "disk" and become free and pinnate above the ovuliferous apex of the receptacle. The condition might be described as that of monadelphous stamens, and it suggests the monadelphous stamens of *Welwitschia* (*Tumboa*), in which the strobilus is also bisporangiate. All the microsporophylls are inflexed, so that the upper third lies with its back against the ovuliferous apex of the receptacle, and its synangia against those of the rest of the sporophyll (figs. 59 and 60). We must imagine the straightening and possible

spreading of these remarkable stamens during the shedding of pollen (fig. 60). The strobili of *Williamsonia gigas*, regarded by WILLIAMSON as "male flowers," have been reinvestigated by LIGNIER (18), who has discovered them to contain a stout pyriform axis from which the seeds had probably become detached after maturity, and also



FIG. 60.—*Cycadeoidea dacotensis*: semi-diagrammatic sketch of strobilus; the ovulate cone in the center is covered by short-stalked ovules and interseminal scales; one staminate sporophyll expanded, and one still folded; outside the staminate sporophylls are hairy bracts; a little less than natural size.—After WIELAND (22).

traces of the stamen set. Recently NATHORST (31) has found additional "male flowers" of *Williamsonia* on the Yorkshire coast, and confirms the view that they are bisporangiate strobili of the cycadeoidean type. About the same time WIELAND (30) discovered a well-preserved staminate disk of *Williamsonia* in the Mexican deposits, which he describes as being a "reduced campanulate form," comprising eight to ten small and strictly once-pinnate sporophylls,

which project only 1.5 cm. beyond the disk, each bearing two lateral rows of synangia along the rachis. This remarkable "reduction" of the stamen set, as compared with that in *Cycadeoidea*, has intensified the suggestion of an angiosperm connection.

That the stamens of Bennettitales bore synangia of the ordinary *Marattia* type (fig. 61) has been shown to be true of all the forms



FIG. 61.—*Cycadeoidea dacotensis*: part of transverse section through unexpanded microsporophyll, showing synangia with loculi arranged in two rows; some of the loculi contain pollen grains;  $\times 25$ .—After WIELAND (22).

examined, including the older known European species. The structure of the synangia seems to be almost identical with those of *Marattia* or of *Danaea* (fig. 62). Superficially there is a wall of heavy cells, and between it and the sporangial chambers there is a more delicate tissue. The sporangial chambers are separated from one another by partitions consisting each of a single plate of cells, and form two rows, between which the synangium dehisces in two valves. It is evident that this structure has advanced little beyond the fern level, and might well belong to Cycadofilicales or to Filicales. In fact, the free portion of a microsporophyll, if detached, would certainly be mistaken for a *Marattia*-like fern. This relatively stationary character of the microsporangiate structures appears throughout the



whole cycadophyte phylum, including even the Cycadales, and is one of its striking features.

#### THE MEGASPORANGIUM

If the microsporangiate structures of Bennettitales have advanced little beyond the fern level, no such claim can be made for the megasporangiate structures. They are not only remarkably different from the corresponding structures among Cycadofilicales, but they are even more different from those of the Cycadales.



FIG. 62.—*Cycadeoidea da-cotensis*: longitudinal section of synangium, showing stalk, hard outer layer of cells, portions of wall layers of cells, and two chambers containing pollen grains;  $\times 40$ .—After WIELAND (22).

The description of *Bennettites Gibsonianus*, as given by CARRUTHERS (2), SOLMS-LAUBACH (5, 6), and SCOTT (10), may be used as an introduction to the situation (fig. 63). From the convex surface of the hemispherical receptacle a great number of slender stalks arise, which pass vertically upward, or diverge slightly toward the curved surface of the "fruit." The central stalks are the longest, the outer ones gradually diminishing in length, so that the general outline is oblong or obovate. Each of these stalks bears at its tip a single erect seed, with the micropyle directed outward. The seeds are so placed that the long axis meets the surface approximately at right angles. The spaces among the stalks are packed with scales, which are dilated at tip, between the seeds, so as to form a continuous envelope, interrupted only by the small pits through which the micropylar tubes project.

The corresponding structures of the beautifully preserved *Cycadeoidea Wielandii* (fig. 64) have been more fully described by WIELAND (22). They conform to the description of *Bennettites* given above, but many additional details are given. In the lower part of the ovulif-

erous region only interseminal scales occur; above this there are usually five or six scales packed around each seed pedicel (fig. 65). The scales are slender (filiform) at base and gradually thicken upward in prismatic form to the seeds, where the faces are hollowed to receive them. Above the seeds the scales enlarge again and their tips form a complete mosaic, perforated only by the micro-pylar tubes.

In the group of species with more or less elongated receptacles, as *Cycadeoidea dacotensis* (fig. 66), the numerous scales and pedicels are relatively short and of uniform length, so that in a young stage the conical tip of the axis, as WIELAND suggests, appears like a brush.

There are two interpretations of these scales and pedicels. LIGNIER (25) maintains that the scales are bracts in whose axils the pedicels appear; and that therefore the pedicel is an axial structure bearing an ovulate "flower" reduced to its lowest terms. This view necessarily regards the strobilus of Bennettitales as an "inflorescence," which, in so far as

it means a compound (branching) strobilus, is represented among gymnosperms by the ovulate strobili of certain of the Pinaceae and by both strobili of the Gnetales. The same investigator (19) has also satisfied himself, by an examination of *Bennettites Morieri*, that in all the scales which enter into the composition of the strobilus the terminal enlargement is due to hypertrophy and is not a reduction stage.




FIG. 63.—*Bennettites Gibsonianus*: diagram of seed-bearing strobilus; the seeds, each containing a dicotyledonous embryo, are borne on long pedicels; between the seeds are the interseminal scales with dilated ends; surrounding seeds and scales are overlapping bracts.—Modified by SCOTT (10) after SOLMS-LAUBACH (5) and POTONIE (6a).

The general and apparently inevitable interpretation has become more assured since the discovery of Cycadofilicales. In that group many




FIG. 64.—*Cycadeoidea Wielandii*: radial longitudinal section of seed-bearing strobilus, with partially restored bract tips; the arrow indicates direction vertical to the trunk, the section passing through the exact median and vertical plane of the axis of fructification; *m*, *x*, *p*, and *c*, respectively the medulla, xylem, phloem, and cortex of the trunk as seen in radial longitudinal section; *a*, insertion of armor on cortex; *l*, old leaf bases; *d*, insertion of dehiscent hypogynous disk; *s*, erect seed; *b*, hair-covered bract.—Figure and description after WIELAND (22).

of the seeds are borne terminally upon reduced filiform branches of a modified frond; and it is natural to infer that the seed pedicel of Bennettitales represents such a frond reduced to its lowest terms, that is to a single seed-bearing stalk. This means that the seed pedicel is a foliar rather than an axial structure, and that it is a case of excessive reduction, which has resulted in a simple, one-seeded megasporophyll (carpel). There seems to be no better way of disposing of the interseminal scales than to regard them as sterile and specialized megasporophylls. One of the most striking features of Bennettitales, as contrasted with Cycadofilicales, is the relatively slight reduction of the microsporophylls, associated with the very great reduction of the megasporophylls.

The structure of the seed is what has come to be spoken of as the cycadean type (figs. 67–69). There is a distinctly three-layered testa (outer and inner fleshy layers and a middle stony layer), which is evident chiefly in the region of the integument free from the nucellus (29). The inner layer of the testa is said to form the lining of the long micropylar tube, which reaches to the surface of the ovulate



structure. A most interesting feature is the occurrence of a basal cupule, for it suggests a remnant of the completely investing cupules of certain seeds (*Lagenostoma*) of Cycadofilicales. The usual nucellar beak and large pollen chamber, characteristic of this type of ovule,




FIG. 65.—*Cycadeoidea Wielandii*: transverse section of a portion of the seed-bearing strobilus, showing seed-stalks with their central bundles, and interseminal scales packed between.—From photograph by BEECHER of section made by WIELAND.

are evident, and also a heavy megaspore membrane. It must be recognized that the structure of the seeds of Bennettitales is not known with such completeness as is that of *Lagenostoma*, so that a definite comparative statement is impossible at present. The conjectural situation is possibly the true one, which the abundance of material should soon establish.



### 3. The gametophytes

In his examination of pollen grains, WIELAND (22) discovered appearances of cell structure, but it was not determined whether these appearances belonged to the wall or not. If they are internal cells, a series was obtained from the cutting off of one lenticular cell up to five cells. Since the pollen grains of Cycadofilicales and Cor-



FIG. 66.—*Cycadeoidea dacotensis*: longitudinal section through strobilus, from a photograph;  $\times 2$ .—After WIELAND (22).

daiales are known to have become multicellular, it would not be surprising to find in the pollen grains of Bennettitales a more extensive tissue than is developed in the pollen grains of Cycadales. The formation of swimming sperms cannot be doubted, on account of the structure of the ovule and the relationship of the group.

No recognizable trace of a female gametophyte has been observed, for all of the sections of strobili have shown either very young and structureless ovules or mature seeds with fully developed embryos.

#### 4. The embryo

One of the characteristic features of Bennettitales is the large dicotyledonous embryo completely filling the embryo sac, in fact filling the whole seed to the testa, with the exception of the nucellar beak (figs. 67-69). The numerous sections of strobili that have been made show that this remarkable embryo, much the larger part of whose bulk consists of two cotyledons, was quite uniform in appearance and was very favorable for preservation. Unlike the embryo of any other known gymnosperm, it destroyed practically all of the endosperm during its intraseminal development. Unusual as this is, however, it is merely a difference of degree, since the embryos of all gymnosperms encroach more or less upon the endosperm. The contrast in this feature between Bennettitales and Cycadofilicales is all the more remarkable from the fact that the former group is believed to have been derived from the latter. If this view is a true one, a remarkable change in the intraseminal development of the embryo has been supposed to have taken place during the passage of cycadophytes from the Paleozoic into the Mesozoic; but it should be remembered that probably the embryos of Bennettitales are in evidence because the strobili remained attached to the plant (p. 47).

It has also attracted attention that this bulky, dicotyledonous embryo gives no evidence of the long, slender, and tortuous suspensor characteristic of all living gymnosperms except *Ginkgo*. Those who are familiar with sections of the seeds of Cycadales and Coniferales,




FIG. 67. — *Bennettites Gibsonianus*: mature seed showing embryo with two somewhat unequal cotyledons; the testa shaded with parallel radial lines; at the base of the seed and in the pedicel the vascular supply is shown. — After SOLMS-LAUBACH (5).

however, will recognize the fact that this is negative testimony. In a fully developed embryo the suspensor may have become scarcely




FIG. 68




FIG. 69

FIG. 68.—*Bennettites Morieri*: longitudinal section of seed; *a*, micropylar tube; *b*, prismatic layer; *c*, pulpy tissue; *d*, "corpuscular" mass; *e*, interseminal scale; *j*, embryo space; *g*, remains of nucellus; *h*, chalaza; *i*, tubular envelope; *k*, micropylar canal; *l*, nucellar beak; *m*, pollen chamber; *n*, fibrous stratum; *o*, basal expansion of *n*; *p*, pedicel bundle.—After WIELAND'S reproduction (22) of LIGNIER'S figure (18).

FIG. 69.—*Cycadeoidea Wielandii*: longitudinal section of seed; *a*, micropylar tube; *b*, expanded summit of interseminal scale; *c*, slightly palisaded layer of heavy-walled cells, which forms the true external coat of the seed, but is covered in all the basal region of the seed by the woody and tubular cells of the cuplike extension (*k*) of the cortex of the seed pedicels; *e*, wall of nucellus ending below the chalaza in an expanded cup-shaped base; *f*, a structureless zone or simply a space between *e* and *g*; *g*, stringy remains of cells expanding into a cup below; *h*, chalaza; *i*, woody scalariform tissue; *k*, continuation of the heavy-walled tubular cells forming the outer layer of the seed pedicels, which overlaps the outer layer of the seed (*c*) and forms the cuplike seed support or husk; *l*, central bundle of pedicel; *m*, remnant of aborted seed and micropylar tube at the center of summit of interseminal scale;  $\times 12$ .—Figure and description after WIELAND (22).

recognizable, except to one very familiar with the situation; and there may be many sections that would not show any trace of it. The obliteration of the suspensor would be even more extreme in the case of an embryo that has completely or approximately obliterated all the tissues within the testa. At the same time, the embryo of *Ginkgo* suggests the possibility that the embryo of Bennettitales may have lacked an elongated and slender suspensor, and that there was simply a suspensor-like elongation of the massive proembryo. In certain sections WIELAND (20) has discovered the seed filled with a tissue which suggested to him proembryonic tissue. It is altogether unlikely that the embryo in its proembryonic stage would have destroyed all the endosperm. The tissue in question is probably that of the embryo, through which both transverse and longitudinal sections are possible that would not show the dicotyledonous character, or the figure published might indicate three cotyledons.

It is tempting to cite the embryo of Bennettitales as evidence that the primitive embryo of gymnosperms was dicotyledonous. Recent investigations, however, have shown that Bennettitales cannot be used for or against this view until the anatomical structure of its cotyledons has been determined. The embryo of this group, as we know it, is probably far from representing even the most primitive embryo of mesozoic gymnosperms; and behind the Mesozoic there stretches the long series of paleozoic Cycadofilicales, whose embryos are unknown.

### 5. History and distribution

This characteristic mesozoic type ranges from the early Triassic into the Lower Cretaceous, being extraordinarily abundant during the Jurassic. In the United States the remains of Bennettitales are known from the Triassic of Pennsylvania and North Carolina, through the Jurassic of Colorado and the Potomac formation of Maryland, to the Upper Jurassic and Lower Cretaceous of the Black Hills of South Dakota and Wyoming. The recently discovered Mexican remains of the group occur in the Lower Jurassic (Lias) of the mountains of western Oaxaca (30). The known historical range of the group in Europe is even greater, beginning with the early Triassic (*Williamsonia angustifolia*) of southern Sweden.

The remains have been found in abundance wherever favorable



mesozoic deposits occur, ranging through North America, Europe, and Asia, and extending into the arctic regions; so that Bennettitales were evidently a world-wide type of great prominence. It is to be expected that investigations in the southern hemisphere, and especially in the mountainous region of western China, may much extend our knowledge of the group.

### 6. Relationship to other gymnosperms

The question of the gymnosperm relationship of Bennettitales is concerned with the relation to Cycadofilicales and Cycadales, the two other members of the cycadophyte phylum. It is hardly worth while at present to consider the vague suggestions of relationship to the Cordaitales, to the Ginkgoales, and even to the Gnetales. The present evidence for such connections is too slight to merit serious discussion.

There seems to be no good reason for doubting that the mesozoic Bennettitales were derived from the paleozoic Cycadofilicales. This view has been expressed by including both groups in the cycadophyte phylum, and this view seems to be justified by both history and structure. The Bennettitales began to rise into prominence as the Cycadofilicales declined, and undoubtedly lingering members of the latter group continued into the early Mesozoic, and early members of the former group existed during late Paleozoic; so that Bennettitales may be said to have carried forward into the Mesozoic many of the primitive features of the Cycadofilicales, associating with these features others of more advanced type in the phylum.

A summary of these primitive features will serve to emphasize the connection with Cycadofilicales. The ramentum is a character that indicates the general connection of both groups with ferns. The vascular anatomy and the direct leaf traces of the Bennettitales agree so closely with those of the siphonostelic Cycadofilicales that the relationship seems obvious. The lateral branching of a monopodial axis is a feature of both groups, the more open and widely branching bodies of Cycadofilicales being carried forward into the Bennettitales in such forms as *Williamsonia angustifolia* (*Anomozamites*) and *Wielandiella*, but becoming much compacted in the later members of the group. This more compact body arose in connection with the organization of

strobili and a restriction of the function of the branches. Instead of remaining elongated, foliage-bearing branches, with sporangia borne on more or less modified leaves, they became short branches, without foliage, but with bracts and sporophylls arranged in a strobilus by the shortening of the axis. That the short, lateral, strobilus-bearing branches of Bennettitales have been derived from elongated branches with foliage more or less modified to bear sporangia appears to be a safe conclusion. The bisporangiate character of the strobilus is probably to be explained by the bisporangiate character of the fronds of those Cycadofilicales which gave rise to Bennettitales.

In addition to ramentum, vascular anatomy, direct leaf trace, and lateral branching, a conspicuous feature which the Bennettitales have carried forward from the Cycadofilicales is the microsporophyll, both in form and in the structure of its sporangia. In fact, the modification of the ordinary *Marattia*-like frond is much more extreme among certain of the Cycadofilicales. So clear is the resemblance of these microsporophylls to "fertile fronds" of ferns and of Cycadofilicales, that it is not disguised by their monadelphous character, which is probably related to the development of such large organs upon a shortened axis. The so-called "disk" or "basal union" of the stamens, it must be remembered, is due to a final simultaneous growth of the whole zone of tissue from which the stamens began to arise as separate members.

The change in the megasporophylls was more extreme, but it does not differ in kind from that observed in the microsporophylls. It is simply a still greater reduction, which in this case is carried to an extreme; a naked branching rachis bearing terminal ovules upon its ultimate branches, common among the Cycadofilicales, has become a single ovule-bearing stalk. The connection is still more evident when it is noted that the cupule investing the seeds of certain Cycadofilicales has become a basal cupule in the well-protected seeds of Bennettitales. The extreme modification has been attained in the differentiation of sterile and fertile megasporophylls, and their organization into a single fruitlike body.

The most inexplicable feature in this supposed connection of the two groups is the transition from a seed with no evident embryo to one containing relatively the largest embryo among gymnosperms.

However, even if this is really a difference (pp. 46, 47), it deals with the common condition of seed plants during the Paleozoic, and would belong to the development of seed plants in general.

The resemblance of Bennettitales to Cycadales is so evident that reasons for keeping the two groups separate are more necessary than reasons for claiming that they are genetically related. The vegetative body in external appearance, and in the anatomical structure of both stem and leaf, seems to be so exact a reproduction of that of Cycadales that an intimate relationship of the two groups is an unavoidable conclusion. If this were the only testimony, no one would suggest a separation of Bennettitales and Cycadales; and, as it is, this testimony justifies the belief that the two groups are more intimately related to one another than to any other gymnosperm group.

The divergent characters of Bennettitales, however, are very striking, and force the conclusion that the two groups, although undoubtedly of common origin, are divergent groups, and that "transitions" from the Bennettitales to the Cycadales, in the important differences between the two groups, need not be expected. In such a feature as its fernlike ramentum, the Bennettitales might be regarded as on the way to Cycadales. The direct leaf traces, also, may be associated with the monopodial habit, and this might be conceived of as passing into the slow-growing sympodial habit of Cycadales, which may hold some causal relation to the formation of "girdles." Even the lateral branching, represented by numerous dwarf fertile shoots, may be conceived of as being more and more restricted to the apical region until the condition in Cycadales is attained. In fact, this restriction has apparently reached the cycad level in *Williamsonia gigas*, whose strobili are borne on "peduncles" arising from within the crown of *Zamia*-like leaves.

In the strobili, however, extreme specialization is met in almost every feature. The bisporangiate character, the closely enveloping bracts, the monadelphous and pinnate microsporophylls bearing synangia, the admixture of sterile and fertile megasporophylls, the reduction of the fertile megasporophyll to a single pedicel bearing a terminal erect ovule, the organization of both kinds of megasporophylls into a compact fruiting body, the development of an embryo which destroys completely the endosperm during its intraseminal develop-

ment, all taken together present a combination of characters that serves to set the group very distinctly apart from other gymnosperms, and suggests that it represents the end of a gymnosperm phylum.

The testimony, on the whole, indicates that the Cycadofilicales gave rise to at least two mesozoic phyla: one with monosporangiate strobili, represented in the present flora by Cycadales; the other with bisporangiate strobili, which culminated in the Bennettitales and is probably not represented in the present flora. Whether there was first a common stock from the Cycadofilicales, which later differentiated into the two groups, or the two groups emerged from the Cycadofilicales independently, is a question that can be discussed rather than decided (27).

## LITERATURE CITED

1. LINDLEY, J., and HUTTON, J., Fossil flora of Great Britain. 1830.
2. CARRUTHERS, W., On gymnospermatous fruits from the secondary rocks of Britain. *Journal of Botany* 5:1-21. 1867.
3. WILLIAMSON, W. C., Contributions towards the history of *Zamia gigas*. *Trans. Linn. Soc. Bot.* 26:663-674. *pls.* 52, 53. 1870.
4. CARRUTHERS, W., On fossil cycadean stems from the secondary rocks of Great Britain. *Trans. Linn. Soc. Bot.* 26:675-708. *pls.* 54-63. 1870.
5. SOLMS-LAURACH, H., Ueber die Fructification von *Bennettites Gibsonianus* Carr. *Bot. Zeit.* 48:789-798, 805-815, 821-833, 843-847. *pls.* 9, 10. 1890.
6. ———, Fossil botany. English translation. Oxford. 1891.
- 6a. POTONIÉ, H., Lehrbuch der Pflanzenpalaeontologie. Berlin. 1899.
7. WIELAND, G. R., A study of some American fossil cycads. I. The male flower of *Cycadeoidea*. *Amer. Jour. Sci.* IV. 7:223-226. *pls.* 2-4. 1899.
8. ———, A study of some American fossil cycads. II. The leaf structure of *Cycadeoidea*. *Amer. Jour. Sci.* IV. 7:305-308. *pl.* 7. 1899.
9. ———, A study of some American fossil cycads. III. The female fructification of *Cycadeoidea*. *Amer. Jour. Sci.* IV. 7:383-391. *pls.* 8-10. 1899.
10. SCOTT, D. H., Studies in fossil botany. London. 1900.
11. WARD, LESTER F., The Cretaceous formation of the Black Hills as indicated by the fossil plants. 19th Annual Report U.S. Geol. Survey. 1900.
12. ———, Description of a new genus and twenty new species of fossil cycadean trunks from the Jurassic of Wyoming. *Proc. Wash. Acad. Sci.* 1:253-300. *pls.* 14-21. 1900.
13. ———, Elaboration of the fossil cycads in the Yale Museum. *Amer. Jour. Sci.* IV. 10:327-345. *pls.* 2-4. 1900.
14. WIELAND, G. R., The Yale collection of fossil cycads. *Yale Sci. Monthly* 6:1-11. *pl.* 1. 1900.



15. WORSDELL, W. C., The affinities of the mesozoic fossil *Bennettites Gibsonianus*. *Annals of Botany* **14**:717-721. 1900.
16. WIELAND, G. R., A study of some American fossil cycads. IV. On the microsporangiate fructification of *Cycadeoidea*. *Amer. Jour. Sci.* IV. **11**:423-436. 1901.
17. NATHORST, A. G., Beiträge zur Kenntnis einiger mesozoischen Cycadophyten. *Handl. Kgl. Svensk. Vetensk.-Akad.* **36**+: pp. 28. *pls.* 3. 1902.
18. LIGNIER, O., Le fruit du *Williamsonia gigas* Carr. et les Bennettitales, documents nouveaux et notes critiques. *Mém. Soc. Linn. Normandie* **21**:19-56. *figs.* 9. 1903.
19. ———, Notes complémentaires sur la structure du *Bennettites Morieri*. *Bull. Soc. Linn. Normandie* V. **8**:3-7. *figs.* 3. 1905.
20. WIELAND, G. R., The proembryo of the Bennettiteae. *Amer. Jour. Sci.* IV. **18**:445-447. *pl.* 20. 1904.
21. OLIVER, F. W., Pteridosperms and angiosperms. *New Phytologist* **5**:232-242. 1906.
22. WIELAND, G. R., American fossil cycads. Publ. No. 34, Carnegie Institution of Washington. pp. 296. *pls.* 50. *figs.* 138. 1906.
23. WORSDELL, W. C., The structure and origin of the Cycadaceae. *Annals of Botany* **20**:129-159. *figs.* 17. 1906.
24. ARBER, E. A. NEWELL, and PARKIN, JOHN, On the origin of angiosperms. *Jour. Linn. Soc. London Bot.* **38**:29-80. 1907.
25. LIGNIER, O., Le fruit des Bennettitées et l'ascendance des Angiospermes. *Bull. Soc. Bot. France* IV. **8**:1-17. 1908.
26. WIELAND, G. R., Historic fossil cycads. *Amer. Jour. Sci.* IV. **25**:93-101. 1908.
27. COULTER, JOHN M., Evolutionary tendencies among gymnosperms. *Bot. Gazette* **48**:81-97. 1909.
28. SCOTT, D. H., The paleontological record. II. Plants. Darwin and modern science, pp. 200-222. Cambridge University Press. 1909.
29. ———, Studies in fossil botany. Second edition. Vol. II. London. 1909.
30. WIELAND, G. R., The Williamsonias of the "Mixteca Alta." *Bot. Gazette* **48**:427-441. *figs.* 10. 1909.
31. NATHORST, A. G., Palaeobotanische Mitteilungen. VIII. *Handl. Kgl. Svensk. Vetensk.-Akad.* **45**: no. 4. 1910.

## CHAPTER III

### CYCADALES

The living cycads form a small natural group containing only nine genera and less than one hundred species, all of which are tropical or subtropical. Four of the genera belong exclusively to the western hemisphere and the other five to the eastern.

Of the western genera, *Zamia* contains about thirty species and ranges from southern Florida to Chili. The three other genera are very limited both in number of species and in distribution: *Microcycas* is monotypic and confined to western Cuba; *Dioon*, with three species, is found only in southern Mexico; and *Ceratozamia*, with two or perhaps more species, has about the same range as *Dioon*, with which it is associated in some localities.

Of the five eastern genera, *Cycas* is the most prominent, both in number of species and in distribution, its sixteen species ranging from Japan to Australia. The four other genera are very restricted: *Macrozamia*, with fourteen species, and the monotypic *Bowenia* belong to Australia; while *Encephalartos*, with twelve species, and *Stangeria*, with two or more species, belong to southeastern Africa.

The genera are sharply defined, but such species as are based only upon leaf characters are open to suspicion, because the leaves vary greatly with the age of the plant. In 1901, when the first edition of this book was written, little was known of the morphology of any of the cycads except the widely ranging and consequently easily accessible *Cycas* and *Zamia*. Since then, *Dioon*, *Ceratozamia*, and *Microcycas* have been studied, so that the life histories of all the occidental genera are quite well known. Some additional information in regard to the oriental genera is also available, but many important features in the life histories of the Australian and African forms are still unknown. This increased knowledge of the cycads themselves, together with extensive studies of the Cycadofilicales and Bennettitales, allows a more satisfactory presentation of the group than was possible a few years ago.

The cycads are distinguished from the other living gymnosperms

and from the Cordaitales by the unbranched stem, with a terminal rosette of comparatively few, large, branched leaves, which gives the



FIG. 70.—*Dioon edule*: ovulate plant on rocky hillside at Chavarrillo, Mexico; the trunk is 1.5 m. high, and shows the armor of leaf bases throughout its entire length.—After CHAMBERLAIN (46).

columnar forms the habit of the tree ferns or palms (fig. 70). The definitely organized strobili readily separate the cycads from the

Cycadofilicales, and the monosporangiate strobilus separates them from the Bennettitales. The multiciliate sperm, now demonstrated for all the genera except *Macrozamia*, *Bowenia*, and *Encephalartos*, and certainly present in these three also, is a character shared by *Ginkgo*, and doubtless by all of the extinct orders.

### 1. The vegetative organs

The stems are columnar or tuberous, the former kind prevailing and often becoming quite tall. The Australian *Cycas media* reaches a height of more than twenty meters; the Mexican *Dioon spinulosum* (fig. 71) becomes twelve meters high; the Cuban *Microcycas* is nearly as tall; while *Encephalartos*, *Ceratozamia*, and some species of *Macrozamia* form trunks of considerable size. In the tuberous forms the stem is either entirely subterranean or appears more or less above the surface. All stems are typically unbranched, but branched individuals are not rare in cultivation and are readily found in the field (fig. 72). Doubtless all the genera have their branching individuals, but most of the branching is due probably to injuries or to the germination of seeds in the nest formed by the crown of leaves.

A striking feature of the cycad trunk, especially in the columnar forms, is the investing armor of leaf bases, recalling the large persistent leaf bases of the marattiaceous ferns. In some forms, as in *Dioon edule*, the armor is so persistent that even in an old plant the number of leaves which it has produced can be determined with reasonable accuracy. From the number of leaf bases, the average number of leaves in a crown, and the duration of the crown, the age of a plant can be estimated. The plant shown in fig. 70, with a trunk less than two meters high, is probably about 1,000 years old. In the smaller tuberous forms and in some species of *Cycas*, the armor is not so persistent, and may be visible for only a short distance below the crown, the lower portion of the stem becoming quite smooth and free from leaf bases.

### VASCULAR ANATOMY

A transverse section of the stem of a cycad (fig. 73) shows a large pith, a relatively thin vascular cylinder of collateral endarch bundles, and a very thick cortex containing the numerous conspicuous "girdles"



(leaf traces). The contrast with stems of Ginkgoales and Coniferales is striking, these groups having relatively small pith, very thick



FIG. 71.—*Dioon spinulosum*: on the Hacienda de Joliet near Tierra Blanca (Mexico), March 1908; the tallest plant is about 10 m. in height.—After CHAMBERLAIN (64).

vascular cylinders, and a comparatively thin cortex. Systems of mucilage canals occur in the cortex and in the pith, connecting with




FIG. 72.—*Microcycas calocoma*: three plants; the one at the right (9.5 m. high) shows neither crown nor base; the height of the middle branching specimen is suggested by the two men, one of whom is standing on the ground.—After CALDWELL (52).

one another through the foliar gaps. The presence of foliar gaps is an evidence of fern connection, and this is confirmed by the usual occurrence of mesarch bundles and sometimes of concentric bundles in all regions of the vascular system outside of the primary cylinder. If such bundles as occur in leaf traces, leaves, peduncles, and cotyledons, were present in the primary cylinder, it would correspond to that of *Lyginodendron*, which is that of Filicales except for the secondary wood.



FIG. 73.—*Zamia floridana*: transverse section of stem, showing the large pith, rather narrow zone of xylem and phloem, and the thick cortex traversed in various directions by oblique sections of the leaf traces (girdles); about natural size.—After COULTER (75).

A historical résumé of the development of knowledge in reference to the vascular anatomy of the stem of Cycadales has been published by WORSDELL (20), from which the following facts are obtained. In 1829 BRONGNIART (1) described the stem of *Cycas revoluta*, refuting the idea that cycadean stems are similar to those of monocotyledons. In 1832 VON MOHL (2) investigated *Cycas* and *Encephalartos*, discovering in a species of the latter genus the meshwork of vascular



bundles in the pith. In 1841 MIQUEL (3) published his monograph of the group, and included the anatomy of several genera. In 1861 METTENIUS (4) published the account of cycadean stems which long remained the chief source of information concerning them, including *Cycas*, *Encephalartos*, *Dioon*, and *Zamia*, and discovering in the last two genera none of the secondary cortical bundles characteristic of the first two. In 1885 CONSTANTIN and MOROT (14) investigated *Cycas siamensis*, and stated that the cortical cambium has its origin in the pericycle. In 1890 SOLMS-LAUBACH (16) traced the vascular bundles of *Stangeria* from the peduncles to the stem cylinder, and



FIG. 74.—*Cycas revoluta*: transverse section of stem, showing pith, two concentric zones of xylem, cortex, and armor of leaf bases; one-half natural size.—After BRONGNIART (1).

found no evidence of cortical bundles. In 1891 STRASBURGER (17) brought together the knowledge of stem anatomy with reference to *Cycas*, but did not include other genera. Then came the work of WORSDELL on *Macrozamia* (20) and *Bowenia* (30), and that of SCOTT (23) on the peduncles of cycads. Since 1900 the vascular anatomy of cycads has been investigated with increased intensity, including every region of the body, and especially the seedling.

The primary cambium may be short-lived, as in *Cycas*; or it may be persistent, as in *Zamia*, *Dioon*, and *Stangeria*. Even when it is persistent, the accumulation of secondary xylem is very slow, and there are no growth rings even when the stem is several years old. In case the cambium is short-lived, a succession of secondary cambiums in the cortex produce cortical cylinders (fig. 74). The first cortical



cambium produces a vascular cylinder as prominent as the primary one; the second develops much smaller and more widely separated bundles; and this continues with diminishing constructive power until the outermost cylinder is recognized only by the appearance of a small bundle here and there. These cortical bundles are produced in *Cycas*, *Encephalartos*, *Macrozamia*, and *Bowenia*; and in *Cycas* they are concentric. In *Macrozamia* and *Bowenia* WORSDELL (20, 30) discovered a tertiary cambium, appearing between the successive secondary cambiums, and giving rise to small intermediate bundles with reversed orientation, the xylem being directed toward the xylem of the next outer bundles. This suggested that the original structure of all the cortical bundles of these genera was concentric, and that in the layers of concentric bundles the meristem of the inner portion of each bundle became gradually less functional, until in most cases the concentric bundles have become collateral. The cortical concentric bundles of *Cycas*, the concentric bundles in the peduncles and leaves of several genera, the evidence of incomplete concentric bundles in the cortical cylinders of *Macrozamia* and *Bowenia*, all indicate derivation from an ancient stem type in which layers of concentric bundles were developed, such a type as exists among the Cycadofilicales (23).

In *Encephalartos* and *Macrozamia* a system of bundles is also developed in the pith, forming a dense network, each bundle being accompanied by a mucilage canal in contact with the phloem. Some of the smaller bundles pass out through the leaf gaps, the xylem and phloem strands joining the corresponding elements of the primary cylinder, and the mucilage canals passing on to join the cortical canal system.

An account of the anatomy of the seedlings of *Ceratozamia*, *Dioon*, *Microcycas*, and *Zamia* will furnish a basis of comparison. *Ceratozamia* is peculiar in the fact that one of the cotyledons is abortive, but it has been made to develop by eliminating the influence of gravity (58). The seedling has been investigated by SISTER HELEN ANGELA (59), the outline of whose results is as follows. The vascular plate of the transition region is irregularly four-cornered, all of the xylem being in the center, sometimes in a solid mass, sometimes interspersed with pith cells (fig. 75). This protostelic condition may

persist above the plate more or less, in one case for a distance of 1.6 mm., above which a siphonostele is established. The development of the tetrarch root is delayed, its four protoxylem poles being inserted upon the cotyledonary bundles, and the entire xylem system of the root being bordered peripherally by cambium. The single cotyledon, which is often lobed at tip, is multifascicular, usually with alternating mucilage ducts, but all the vascular strands are derived from three bundles that connect with the vascular plate (figs. 76, 77).

These three strands are not of the same rank, and their relation to the vascular plate of the transition region should be understood. Two of the angles of this plate

are directed toward the center of the two cotyledons (the usual abortion of one cotyledon in *Ceratozamia* does not affect this orientation), and therefore may be called *cotyledonary*; and the other two are in the plane between the two cotyledons, and therefore may be called *intercotyledonary*. The median vascular strand that enters a cotyledon is connected directly with the adjacent cotyledonary angle or pole of the vascular plate, and therefore is a




FIG. 75.—*Ceratozamia mexicana*: transverse section of vascular plate of seedling, showing the protostelic condition; *px*, protoxylem;  $\times 225$ .—After SISTER HELEN ANGELA (59).

primary strand. The two lateral strands that enter a cotyledon are branches of the two primary strands that are connected with the two intercotyledonary angles or poles, and therefore are secondary strands. The primary strand from an intercotyledonary angle follows a very short radial course and then forks, the branches taking a tangential course in opposite directions and passing into opposite cotyledons. Each primary intercotyledonary strand, therefore, sends a branch




FIG. 76.—*Ceratozamia mexicana*: diagram representing connection of cotyledonary bundles with the vascular plate; A, B, C, D, the four main cotyledonary bundles; C, median bundle of developed cotyledon; D, median bundle of aborted cotyledon; a, a', lateral bundles of aborted cotyledon; b, b', lateral bundles of developed cotyledon; f<sup>1</sup>, f<sup>2</sup>, f<sup>3</sup>, f<sup>4</sup>, the four principal groups of foliar bundles; c, cotyledon; l, leaf.—After SISTER HELEN ANGELA (59).

into each cotyledon; while each primary cotyledonary strand is connected with a single cotyledon as its median strand. This median strand usually does not fork until well within the cotyledon of *Ceratozamia*; in some other cycads it forks sooner; and in others it is said to be double from the beginning. This variation in the forking of the median strand accounts for the reports of three or four vascular bundles occurring at the base of each cotyledon. In *Ceratozamia* the lateral strands and also the bifurcated median strand branch, so that the cotyledon becomes multifascicular. The xylem of the

cotyledonary strands is mesarch at the base of the cotyledon, but becomes exarch in the upper part.

In the early stages of the seedling several groups of extrafascicular cambium appear (fig. 78), but in seedlings two years old only the slightest trace of them can be found. The stem develops as a sympodium, and the number of vascular strands entering successive leaves increases, sometimes with great regularity, as from three in the cotyledon to seven in the fourth leaf. The origin of these leaf strands is exceedingly complex, as they represent a few of the ultimate branches from four (or three by the fusion of two) original foliar bundles con-

nected with the central cylinder (fig. 79). There is no girdling of leaf traces in the younger stages, the traces being at first vertical; but with the radial increase of the inclosed leaves and stem tip girdling becomes apparent. The xylem of the leaf traces is endarch, but it becomes mesarch in the base of the leaf and remains so to the tips of the pinnae. In a later study (66) the extrafascicular cambium of the seedling of *Ceratozamia* was investigated. In over eighty seedlings, ranging in age from a few months to over two years, only one small extrafascicular bundle was found, although the central cylinder was surrounded by several groups of cambium cells. If these groups should function in the production of vascular bundles, the result would be strongly suggestive of polystely. The innermost extrafascicular cambium groups arise in the pericycle, near the transition region, but the others appear later.

The vascular anatomy of the seedling of *Dioon edule* has been investigated by THIESSEN (62), and illustrates the origin and course of the leaf traces of cycads, concerning which there has been much misapprehension. The vascular plate of the transition region is four-cornered in section, with a protoxylem group at each corner, and, as in *Ceratozamia*, it is protostelic and soon passes into the siphonostelic condition in the seedling stem. The four protoxylem groups of the vascular plate are continuous with those of the root, which is therefore tetrarch. The primary strands from the intercotyledonary angles of the transition plate are related to the cotyledons exactly as described above for *Ceratozamia*, but the primary strand from each cotyledonary angle forks, so that four strands enter the base of each cotyledon (fig. 80).

The connections of the leaf traces of *Dioon* are simpler. The




FIG. 77.—*Ceratozamia mexicana*: diagram of vertical view of vascular supply of cotyledons, where the usually aborting cotyledon has been made to develop; A, B, C, D, the four main cotyledonary bundles. —Made for this work by SISTER HELEN ANGELA.






FIG. 78.—*Ceratozamia mexicana*: transverse section of hypocotyl slightly below exit of cotyledonary traces; the diagram shows the position of the stele, surrounded by three large groups of extrafascicular cambium (*a*, *b*, *s*), and some smaller groups like *e* and *r*; the drawing shows a portion of the section indicated in the diagram, including one of the groups of extrafascicular cambium (*a*), parts of *b* and *s*, and also the smaller groups (*e* and *r*); the bundles of the stele are mesarch, with considerable centripetal xylem.—After SISTER HELEN ANGELA (66).

current statement has been that two leaf traces leave the vascular cylinder on the side away from the leaf they are to enter, swing around to left and right in wide curves through the cortex, forming the characteristic girdles, and so pass to the leaf. This needs amendment as follows. As usual in cycads, a variable number of scales succeed the cotyledons before true foliage leaves are developed, but the traces of scales and leaves are the same. In *Dioon* four strands leave the central cylinder for each scale or leaf, at indefinite but well-distributed points. Two of them leave approximately on the side of the cylinder toward the leaf, and without branching pass more or less directly through the cortex to the petiole. The two other strands leave the central cylinder approximately on the opposite side, describe wide right and left curves about it through the cortex, and so enter the petiole, where they begin to branch freely (fig. 81). The leaf traces of the cycads, therefore, include not only "girdles," but also direct traces. The vascular

strands of both leaves and cotyledons are endarch at their junction with the cylinder, but gradually become mesarch, and in the upper stretches of leaf or cotyledon the exarch condition is approached more or less completely. This transition from endarch to mesarch and perhaps exarch seems to be a common feature of the foliar strands of cycads.

The origin of the "girdle" is a very obscure problem. In connection with *Ceratozamia* it was stated that the girdling became evident in connection with the diameter increase of the inclosed group of leaves and stem. It would be a natural inference that the curve of the girdle is produced by the growth of the group of organs within; but in *Dioon* it is evident that the girdle is established in the procam-




FIG. 79.—*Ceratozamia mexicana*: diagram of vascular plate of seedling, showing origin of leaf bundles; *d*, *d'*, lateral traces of first leaf; *e*, *e'*, middle traces of same; rest of lettering as in fig. 76.—After SISTER HELEN ANGELA (59).




FIG. 80.—*Dioon edule*: semi-diagrammatic reconstruction of part of vascular system of embryo; *cot*, cotyledon; *tb*, tubular part of cotyledons; *cs*, cotyledonary strands;  $l_1-l_1$ , foliar strands of first leaf;  $l_2-l_2$ , foliar strands of second leaf; *vp*, vascular plate; *a*, protoxylem elements continuing downward into the hypocotyl.—After THIESSEN (62).

bial stage of the strand, and that its final course is laid down from the beginning.

The seedlings of *Zamia* (*Z. floridana* and *Z. integrifolia*) have been studied recently by MATTE (68) and are found to confirm the results obtained from the preceding genera. The vascular plate of the cotyledonary node is a protostele, and each cotyledon receives three vascular strands, as described for *Ceratozamia*. At the base of the cotyledon the strands are mesarch or even concentric, but in the middle region they become exarch and remain so to the tip, where transfusion tissue occurs and probably has replaced the centripetal xylem. The tap root is of the usual tetrarch type, becoming reduced to triarch or even diarch toward the tip.

The study of the seedlings of *Microcycas* by SISTER HELEN ANGELA (65) confirms the general situation described for *Ceratozamia*, *Dioon*, and *Zamia*, and shows some interesting variations. *Microcycas* is peculiar in the extensive

fusion of its cotyledons. They arise as two distinct organs, but in the older embryos the fusion is so complete that serial sections from the apex downward almost to the apex of the plumule do not reveal the characteristic "seam," in many cases the abutting epidermal layers having disappeared. As in *Ceratozamia*, there is no "resting stage" of the embryo, which emerges from the testa as soon as it is formed. In *Ceratozamia*, *Dioon*, *Microcycas*, and *Zamia*, and presumably in other cycads, the root is much delayed in its development, not being formed when the base of the embryo ruptures the testa and exposes a small brown disk of disorganized tissue, which represents the remains of the once extensive coleorhiza, and through which the root may not penetrate until the soil is reached or even until after the exit of the plumule.

An interesting deviation is shown in *Microcycas* by the vascular cylinder of the transition region, which is not a protostelic plate, as in the preceding cases, but is siphonostelic from the beginning (fig. 82). The four cotyledonary strands remain distinct, and




FIG. 81.—*Dioon edule*: semi-diagrammatic reconstruction of part of vascular system of embryo, to show especially the girdling;  $l_1, l_2$ , traces of first and second leaves ( $L^1, L^2$ );  $vp$ , vascular plate;  $px$ , protoxylem groups;  $a$ , xylem elements continuing from protoxylem groups of plate to form the protoxylem of the primary root.—After THIESSEN (62).



their elements become continuous with those of the four poles of the root, which is at first tetrarch, but may become triarch toward the tip. Each cotyledon contains eight or ten vascular strands, with alternating mucilage ducts, the strands being all derived from the branching of three main bundles that join the central cylinder. In the young stem four large groups of leaf traces alternate with the four cotyledonary groups, and just above the cotyledonary node they close together




FIG. 82.—*Microcycas calocoma*: semi-diagrammatic transverse section of the central vascular system of the seedling above the cotyledonary node, composed of four groups of leaf traces ( $f^1$ ,  $f^2$ ,  $f^3$ ,  $f^4$ ); A, B, C, D, main cotyledonary traces.—After SISTER HELEN ANGELA (65).

to form the central cylinder. In this case, also, the course of the girdle is evident in its procambial stage; and all the strands change from the endarch condition to the mesarch and finally the exarch in passing from the central cylinder toward the tip of the cotyledon or leaf, and transfusion tissue is abundant in close connection with the centripetal xylem. In *Microcycas* also there are remnants of a broken up cambial zone in the

cortex of the young stem, not so distinct as in *Ceratozamia* and never forming an extrafascicular bundle.

The seedlings of these four genera may be regarded as representative of the seedlings of cycads in general, and the situation may be summarized as follows: At the cotyledonary node there appears a quadrangular protostelic plate or a siphonostelic grouping of four sets of cotyledonary strands (*Microcycas*), in both cases connecting with the four poles of the tetrarch root, which later may become triarch or even diarch. At the base of the cotyledon three or four vascular strands occur, connected with three of the poles of the quadrangular vascular plate. In *Zamia* and *Dioon edule* these strands seldom

branch, so that the cotyledons contain only four vascular strands, and this seems to be true also of some species of *Cycas*, of *Macrozamia*, and of *Stangeria*; but in *Ceratozamia* the branching may reach twelve cotyledonary strands; and in *Dioon spinulosum*, *Microcycas*, and *Bowenia* the branching is even more extensive. When the root is diarch, as in some species of *Cycas*, it is the intercotyledonary poles that are suppressed, and although the corresponding strands are represented in each cotyledon, their basal endings are free in the cortex. The leaf traces are usually four in number; the two inner ones arising from the proximal side of the central cylinder and being more or less direct; the two outer ones arising from the distal side of the central cylinder and forming the characteristic girdles of the cortex in their course to the leaf.

In a general review of seedling anatomy Miss THOMAS (57) concludes that in all cycads four or six vascular strands enter the cotyledon, and that the primary root is prevailing tetrarch, with a strong tendency to become reduced toward the apex to the triarch or diarch condition. For example, in *Cycas siamensis* there are four cotyledonary strands, but in connecting with the root two of the strands (the intercotyledonary ones) die out and the root is diarch.

In a similar review of the seedling anatomy HILL and DE FRAINE (67) conclude that the number of vascular bundles at the base of each cotyledon ranges from two to eight; that these bundles in general are mesarch and become exarch; that the transition phenomena occur so rapidly that most of the hypocotyl shows root structure; that the cotyledonary strands are not of equal value in the production of root structure; and that after the initial root structure is attained the number of poles may be increased at lower levels.

Certain occasional situations have been recorded, which are interesting not only in what they imply, but also in suggesting a search for their wider occurrence. For example, the concentric bundles at the base of the cotyledons in *Stangeria*, the polystelic condition in the earlier stages of the peduncle of *Encephalartos*, the cortical strands in the base of the peduncle of *Dioon* (61), and the mucilage canals in the root of *Dioon* are all features that fit into the general anatomical condition of the cycads, as described above.

In his conclusions from an investigation of the vascular anatomy

of cycads MATTE (40) lays special stress on foliar strands, which he regards as of more phylogenetic importance than the vascular axis of the stem, his unit of structure being the "meriphyte." In this work the leaves and sporophylls of representative species of all the genera were examined, and the seedlings of *Cycas*, *Dioon*, and *Encephalartos*. The well-known omega ( $\Omega$ ) outline of the foliar arc was found to hold for the whole group, even the complex arrangement of the strands of *Bowenia* (43) being referable to it. He also discovered in the ovulate sporophyll of *Ceratozamia* (35) three or more accessory vascular strands near the abaxial surface, in addition to the usual transverse row of strands; and inferred from their inverse orientation (xylem abaxial) that the sporophyll is really a union of two sporophylls.

#### THE LEAF

The crown of large leaves at the apex of the stem gives the cycad its palmlike or fernlike aspect. In *Dioon edule*, as it grows in the field, a new crown of foliage leaves is produced every other year. When just unfolding, the new crown is easily distinguished from the previous one (fig. 83), but a few months later, after the new crown has fully expanded, the presence of two crowns can scarcely be noticed. In fig. 70 the leaves of the new crown are obliquely erect, while those of the previous crown are horizontal or somewhat reflexed. Below this older crown may be seen some midribs of leaves of a still older crown, the leaflets having fallen off. Below these naked ribs may be found all stages down to the typical crown of persistent leaf bases. It is certain that in greenhouses a crown of *Dioon edule* may persist much longer than two years. In *Cycas revoluta* it is said that a crown is formed every other year, but information in regard to the duration of crowns, as they occur in the field, is scanty and uncertain. In seedlings there is only one leaf, or occasionally two, and for a considerable period the leaves appear singly at irregular intervals, the production of a whole crown of leaves at one time being a feature of the later history of the individual.

The leaves are once-pinnate in all the genera except *Bowenia*, in which they are twice-pinnate. They vary in length from 10 cm. in *Zamia pygmaea* to more than 3 m. in some species of *Cycas*. The number of leaflets varies greatly even in adult leaves, which in *Dioon*



*edule* often have more than 100 leaflets on each side of the rachis. The number increases gradually with the age of the plant, the first




FIG. 83.—*Cycas revoluta*: the crown; in the center the new crown of foliage leaves still nearly erect; leaves of previous crown already beginning to droop; between the two a set of scale leaves may be seen.—After COULTER in *Plant Structures*.

leaf of *Ceratozamia* having two or four leaflets, while the leaf of a fully grown plant has as many as 100. The margins of the leaflets are entire or variously serrate (figs. 84-89), while in *Macrozamia heteromera* they are dichotomously branched. In *Dioon edule* the



leaflets of the seedling are conspicuously spinulose, like the adult leaflets of *D. spinulosum*, but in older plants the margins are perfectly smooth, the spinulose condition of the seedling of *D. edule* being a juvenile character indicating an ancestry with spinulose leaves (figs. 84-87). The venation is various; for example, the leaflets of *Cycas* have only a midrib without any branches; those of



FIGS. 84-89.—Pinnules of cycads: fig. 84, part of leaf of seedling of *Dioon edule*; fig. 85, part of adult leaf of same; fig. 86, part of leaflet of seedling of *Dioon spinulosum*; fig. 87, part of adult leaf of same; fig. 88, part of adult leaf of *Zamia floridana*; fig. 89, detail of venation of leaf of *Zamia floridana*; figs. 84-88, one-half natural size; fig. 89,  $\times 4$ .

*Stangeria* have a midrib with numerous veinlets; those of other genera have no midrib, but form more or less parallel veins, some of which run the entire length of the leaflet without branching, while others branch dichotomously and often anastomose (fig. 89). Circinate vernation, characteristic of ferns, appears in the midrib and pinnules of *Cycas* and in the midrib of *Stangeria*, *Ceratozamia*, and *Zamia*, but otherwise it does not occur.

The leaflets are tough and leathery, a texture due to thick-walled

hypodermal cells. The epidermis is strongly cutinized, as in conifers, and the stomata, which in all the genera except *Bowenia* occur only on the under surface, are deeply sunken. In most forms the mesophyll is differentiated into palisade and spongy parenchyma, both rich in chlorophyll, but in addition to this some leaves, as in *Cycas*, have colorless cells, elongated parallel with the leaf surface, lying between the palisade and the spongy parenchyma. A general view of the structure of a leaflet is shown in figs. 90, 91.




FIG. 90.—*Cycas revoluta*: part of transverse section of pinnule, showing the chlorophyll-bearing palisade layer, the elongated colorless cells in the middle region, beneath this a few layers of mesophyll, and the lower epidermis with two stomata.

FIG. 91.—*Dioon edule*: part of transverse section of pinnule, showing palisade layer, lower mesophyll region without elongated colorless cells, and lower epidermis with two stomata.

The first leaves of the seedling are almost always scale leaves, one or more of which form a protection for the first foliage leaf. Succeeding leaves are similarly protected, and when crowns begin to be produced each young crown is covered by a large number of thick, brownish, hairy scale leaves. Young cones are similarly protected, the scale leaves covering the young staminate cone of *Dioon edule* being as thick, fleshy, and hairy as the ovulate sporophylls, and in such cases they form an appreciable part of the armor. In some species of *Macrozamia* there are no scale leaves at all.

## THE ROOT

The primary root continues as a strong tap root, with a scanty display of branches (fig. 92), but with numerous small secondary roots. Although dichotomous branching has been thought to be restricted to the secondary roots, under conditions described below, HILL and DE FRAINE (67) state that in *Stangeria* the primary root may branch dichotomously. The soil about the roots is full of low algal



FIG. 92.—*Zamia floridana*: entire plant, showing strong tap root.

and fungal forms, and in many, perhaps all, of the genera, some of the secondary roots become infected, in which case they become negatively geotropic. Near the surface of the ground they branch profusely and dichotomously, forming the so-called "root tubercles" which occur in coralloid masses just above or a little below the surface (fig. 93). A study of sections shows that the dichotomy so conspicuous to the naked eye is only apparent, the root apex remaining between the two branches. REINKE (6), SCHNEIDER (18), and LIFE (31) have contributed mostly to our knowledge of these peculiar

roots. LIFE found that at the very inception of a branch, bacteroid forms effect an entrance and multiply rapidly in the cells of the apical region. The presence of the bacteroids causes a considerable enlargement of the intercellular spaces and a disorganization of some of the cells. Algae soon appear in the intercellular spaces and their multiplication still further enlarges them. In its fully developed condition the algal zone, in transverse



FIG. 93.—*Cycas revoluta*: negatively geotropic roots in coralloid masses, as they appear just above the surface of the soil; about natural size.




FIG. 94.—*Cycas revoluta*: transverse section of a "root tubercle," showing the conspicuous algal zone;  $\times 20$ .—After LIFE (31).

section, appears as a conspicuous ring about midway between the stele and the periphery (fig. 94). The alga has been described as an *Anabaena*, but looks more like a *Nostoc*, although it is possible that there may be more than one alga. LIFE believes that the tubercles serve both in aerating and in assisting in nitrogen assimilation.

From a recent study ZACH (73) has concluded that a fungus is not the cause of the tubercles, although a mycelium is abundant in them;



and that it is not a symbiont, but rather a parasite against which the cell reacts as a phagocyte.

## 2. The spore-producing members

### THE MICROSPORANGIUM


All the living cycads are strictly dioecious. The staminate strobili



FIG. 95.—*Dioon edule*: upper portion of plant with staminate cone; photographed at Chavarrillo, Mexico, September 1906; one-third natural size.—After CHAMBERLAIN (63).

usually occur singly in the center of the crown (fig. 95), but several may appear at once, as is frequently the case in *Zamia* and *Encephalartos*. The first cone produced by a plant is always terminal, but all subsequent ones are lateral. Growth from an apical meristem is continuous until a cone is produced, in which case the meristem is used up in the production of the cone, and a new meristem appearing at the base continues the growth, pushing aside the cone and assuming the erect position. Miss F. GRACE SMITH (56) has shown that the trunk of *Zamia* is really a sympodium, the production of a cone being followed by the development of a branch which quickly becomes erect, so that the trunk does not appear to be branched (figs. 96–98). In *Encephalartos Friderici-Guilielmi* and in *E. Altensteinii* PEARSON (47) has described a group of three to six cones arranged symmetrically about the apex, so that in these cases there is

no sympodium, the summit of the vegetative axis continuing the growth of the stem. Such a condition among the cycads connects with the branching habit among Bennettitales.



FIGS. 96-98.—*Zamia floridana*: fig. 96, longitudinal section of apex of stem, showing a young staminate cone; *v*, lateral stem tip; *f*, very young leaf; fig. 97, longitudinal section of apex of stem, showing two young staminate cones; *v*, stem tip; *l*, young leaves; fig. 98, diagrams based upon preparations like those shown in figs. 96 and 97; *a*, sympodium, showing relations of strobili, crowns, and trunk; *b*, the same with internodes shortened; *c*, internodes shortened until the cones are on a level, as in *Zamia*.—After F. GRACE SMITH (56).

The length of the staminate cones varies from 2 cm. in some species of *Zamia* to more than 50 cm. in species of *Encephalartos* and *Cycas*.

The sporophylls are spirally arranged in a compact strobilus, and show only slight traces of the pinnate character of the vegetative leaves. At the apex and base of the cone the sporophylls are sterile, and the remaining sporophylls bear abaxial sporangia in two more or less distinct groups separated by a median sterile line (fig. 99). In the median region of the cone the sporangia cover the entire abaxial surface of the sporophylls and sometimes even their margins. In all the genera the sporangia occur in soral groups of five, four, or three;



FIG. 99.—*Dioon edule*: photograph of two microsporophylls;  $\times \frac{1}{2}$ .—After CHAMBERLAIN (63).

but some sori may contain only two sporangia, and in the more highly specialized forms some of the sporangia may occur singly. The sori are surrounded by one-celled or two-celled hairs, and such hairs appear even on the lower portion of the sporangia (figs. 100, 111).

The number of sporangia on a sporophyll corresponds roughly to the size of the sporophyll. The following estimates have been made by Miss F. GRACE SMITH (56) and by CHAMBERLAIN (63): *Dioon spinulosum* 750, *Cycas circinalis* 700, *Encephalartos Caffer* 700, *Macrozamia Miquelii* 600, *Encephalartos villosus* 500, *Dioon edule* 300, *Ceratozamia mexicana* 250–300, *Stangeria paradoxa* 260, *Microcycas calocoma* about 120, *Bowenia spectabilis*

67. A large number of sporangia on a sporophyll, and also the larger number in a sorus, may be regarded as primitive features, while fewer sporangia on a sporophyll and fewer in a sorus are probably due to reduction.

The first full account of the development of the microsporangium was published by TREUB (11) in 1881, who investigated especially *Zamia muricata*. LANG'S (22) work on *Stangeria paradoxa* confirmed TREUB'S results in a general way and cleared up some doubtful points. Later, Miss F. GRACE SMITH (56) studied abundant material of very

young staminate cones of *Zamia floridana* and CHAMBERLAIN (63) described spermatogenesis in *Dioon edule*.

The sporophylls first appear as minute papillae, giving the young cone a wavy contour as seen in longitudinal sections (figs. 96, 97). According to Miss SMITH, there is in *Zamia* a single archesporial cell, the first division of which may be either periclinal or anticlinal, but in any case primary wall cells and primary sporogenous cells are soon formed (figs. 101-104). In *Stangeria* LANG (22) first recognized the archesporium as a hypodermal plate of four cells (figs. 105-109). By comparing these figures with those of Miss SMITH, it is evident



FIG. 100.—Microsporophylls of cycads: A, *Cycas circinalis* (a, entire sporophyll, showing sporangia on under surface; b, four groups of sporangia; c, same as b after the pollen has been shed); B, *Zamia integrifolia* (a, entire sporophyll; b, c, clusters of sporangia).—Ab, Ac, after BLUME; the rest after RICHARD; the whole figure taken from ENGLER and PRANTI'S *Natürlichen Pflanzenfamilien*.


that *Stangeria* develops like *Zamia*, the hypodermal plate having come from a single cell. The later stages are essentially the same in both accounts. A sporangium wall several cells in thickness is developed, and also a large mass of sporogenous tissue, from the periphery of which the tapetum is differentiated. While the origin of the tapetum was not studied in *Dioon*, fig. 110 would indicate that it is more probably derived from the wall cells. The resemblance of the cycadean sporangia to those of the marattiaceous fern *Angiopteris* is quite striking, the principal difference being the comparatively scanty development of the tapetum in the cycad (fig. 111). As the spores mature, the epidermal layer of the sporangium becomes thick-



ened, and the layers between the epidermis and the spores disorganize, as in the sporangia of ferns. Two rows of elongated thin-walled

cells bordered by cells with thick walls give the dehiscence much the appearance of that of *Angiopteris*.


The formation of microspores from the mother cell has been described by JURANYI (5) and by Miss F. GRACE SMITH (56) for *Ceratozamia*, and by TREUB (11) for *Zamia muricata*. With the appearance of the cell plate in the first division, a ringlike thickening of cellulose appears on the wall of the mother cell, and proceeding from this ring a thick wall develops between the two daughter cells. Each of these two cells divides and heavy walls are formed again, and within this heavy four-celled and often lobed case the microspores are organized. The number of chromosomes in the pollen mother cells of *Ceratozamia* and *Zamia* is 12; other numbers (7, 17) have been reported for *Ceratozamia*, but technic at that time was hardly adequate to meet the trying



FIGS. 101-104.—*Zamia floridana*: early stages in the development of the microsporangium; fig. 101, single hypodermal archesporial cell; fig. 102, first periclinal division; fig. 103, usual divisions following stage shown in previous figure; fig. 104, longitudinal section of a sporangium in a more advanced stage; all figures  $\times 920$ .—After F. GRACE SMITH (56).

demands of such difficult nuclei. Miss F. GRACE SMITH counted 50 cases in *Ceratozamia*, and in forty-six found 12 chromosomes, in three

11 chromosomes, and in one case 13 chromosomes; in *Zamia* 25 nuclei were examined and all showed 12 chromosomes. CHAMBERLAIN (46, 63) found 12 chromosomes in the pollen mother cells of *Dioon edule*, 12 at the mitosis which gives rise to the ventral canal and egg nuclei, and 12 in cells of the endosperm.



FIGS. 105-109.—*Stangeria paradoxa*: development of microsporangium; fig. 105, section showing two of the four cells forming the archesporial plate; fig. 106, each cell of the plate divided into an inner primary sporogenous cell (shaded) and an outer primary wall cell; fig. 107, a more advanced stage; fig. 108, still more advanced stage, showing tapetum (shaded) and sporogenous cells (s); fig. 109, mature microsporangium; t, tapetum; w, crushed cells of the wall; figs. 105-108,  $\times 266$ ; fig. 109,  $\times 66$ .—After LANG (22).

The output of spores has been estimated by Miss F. GRACE SMITH (56) and by CHAMBERLAIN (63). When spores are very small and closely packed together, and the spore mass is nearly spherical, the number in a sporangium may be estimated by the formula  $\frac{4}{3}\pi R^3$ . To apply the formula it is necessary only to count the number of spores in a radius from the center of the sporangium to the tapetum, substitute this number for  $R$  in the formula, and make the calculation. There is some error because the spore mass may not be exactly

spherical, and because the formula does not regard the small spaces between spores, but the error is far less than the variation in the out-




FIG. 110.—*Dioon edule*: microsporangium; detail showing thickened epidermis, wall cells, tapetum, and sporogenous tissue;  $\times 250$ .—After CHAMBERLAIN (63).

put of individual sporangia of average size. It is recognized that this formula could be used only when spores are very small and sporangia very large. Estimating in this way, CHAMBERLAIN (63) found the output of spores in *Dioon edule* to be 30,000; Miss F. GRACE SMITH found it to be 26,000 in *Encephalartos villosus*, 8,000 in *Ceratozamia*, and 500–600 in *Zamia floridana*. In general the results favor the view that the output is larger in the more primitive forms and decreases toward the more highly specialized forms.




FIG. 111.—*Dioon edule*: microsporangium; two of the sporangia of a sorus, showing extensive sporogenous tissue and scanty tapetum; two-celled hairs growing on the base of the sporangium;  $\times 55$ .—After CHAMBERLAIN (63).

Since the spore is regarded as the first cell of the gametophyte generation, it will be considered in the section on the male gametophyte.

## THE MEGASPORANGIUM

The ovulate strobili usually occur singly in the center of the crown (fig. 112), but sometimes, especially in *Encephalartos*, two or more may be produced. The ovulate strobili of cycads are the largest known, those of *Dioon spinulosum* reaching a diameter of 23 cm., with a length of 50 cm. and a weight of 14 kg. The long and comparatively slender strobilus of *Microcycas* sometimes reaches a length of 94 cm., but is not so heavy; the weight of 9.5 kg. as well as the length of 94 cm. reported by CALDWELL (52) is exceptional. The strobili of *Encephalartos* and *Macrozamia* are not quite so large, and in *Ceratozamia* they are seldom more than 26 cm. in length; in the remaining genera they are comparatively small, perhaps the smallest being that of *Zamia pygmaea*, in which they may be less than 3 cm. in length. If the group of ovulate sporophylls of *Cycas* be regarded as a strobilus, it may be the largest and heaviest of all; but we have not had an opportunity to weigh it or to measure a fully grown specimen.

In all the genera except *Cycas* the megasporophylls are in compact strobili, the first strobilus being terminal on the primary axis of the plant, while all the others terminate secondary axes. PEARSON (47) states that in *Encephalartos Friderici-Guilielmi* and in *E. Altensteinii* there are three to six cones symmetrically arranged around the apex, so that there is no sympodium, but the vegetative apex continues the growth of the stem, as already noted in the staminate plants of these species. In *Cycas* the sporophylls bear considerable resemblance to the foliage leaves, and are arranged like an ordinary crown of foliage leaves, with the bud for the next crown in the center (fig. 113); hence the trunk of the ovulate plant of *Cycas* is always a continuation of the primary axis, and never a sympodium as in all other cycads, including the staminate plant of *Cycas* itself, and also excepting cases in which several cones may be arranged around a persistent vegetative apex. It can hardly be doubted that the compact strobili are a later development from the *Cycas* type. Occasionally, even in compact strobili, the meristem, instead of producing the stunted sporophylls which usually terminate the strobilus, produces sporophylls resembling foliage leaves; and in *Encephalartos* WIELAND (51) figures a strobilus with transitions between the sporophylls and the



ordinary pinnate leaves. The *Cycas* condition resembles that of the Cycadofilicales, and not at all that of the Bennettitales. How-



FIG. 112.—*Dioon edule*: ovulate cone (30 cm. in length) in the center of the crown; some of the leaves have been trimmed away.—After CHAMBERLAIN (46).

ever, the staminate sporophylls of the Bennettitales are borne like the ovulate sporophylls of *Cycas*, the principal difference being that

in the Bennettitales the meristem, after producing the staminate sporophylls, produces an ovulate strobilus which terminates that axis; while in *Cycas* the meristem, after producing ovulate sporophylls, produces vegetative leaves.

In *Cycas revoluta* the megasporophylls are more nearly like the



FIG. 113.—*Cycas revoluta*: loose ovulate strobilus, Kochi, Fosa, Japan, August 4, 1909.—From photograph by MIYAKE.

vegetative leaves than in any other cycad (fig. 114). *C. circinalis* and *C. Normanbyana* show more reduction, but the pinnate character of the vegetative leaf is still conspicuous. In *Dioon edule* the pinnate character is not conspicuous, but the blade is still leaflike, and the strobilus has to some extent the loose arrangement of sporo-

phylls characteristic of *Cycas* (figs. 112, 114). In *D. spinulosum* and in *Stangeria* the sporophylls are still less leaflike, and the strobilus



FIG. 114.—Megasporeophylls of cycads: A, *Cycas revoluta*; B, *Cycas circinalis*; C, *Cycas Normanbyana*; D, *Dioon edule*; E, *Encephalartos Preissii*; F, *Zamia integrifolia*; G, *Ceratozamia mexicana*.—A, after SACHS; C and F, after VON MÜLLER; E, after MIQUEL; F, after RICHARD; B, D, and G, drawn for ENGLER and PRANTL'S *Nat. Pflanzenj.*, from which the entire plate is taken.

is much more compact; while in the remaining genera the sporophylls show very little of the leaflike character and are organized into hard compact strobili (fig. 92).




FIG. 115.—*Cycas siamensis*: sporophyll with two ovules; in the upper part of the sporophyll the pinnules are united into a solid mass, but the lower pinnules are still free; one-half natural size. — After Miss STOPES (42).

In *Cycas revoluta* several ovules are borne on the margins of the sporophyll (fig. 114), as is also the case in *C. circinalis*, in which the leafy portion is more reduced; but even in the genus *Cycas* the number of ovules becomes reduced to two, as in *C. Normanbyana* and *C. siamensis* (fig. 115). Two ovules are characteristic of all the other genera, with only occasional exceptions. The two ovules are really borne on the margins, but the sporophylls are so reduced that they seem to be borne on the under surface of a peltate structure (fig. 114, F, G). In all the genera the ovules are sessile, but in *Dioon* the crowding of the ovules in the strobilus results in a stretching of the tissue of the sporophyll so that it resembles a stalk (fig. 116).



The size, color, and surface of the ovules differ in the various genera and even in the species of a genus. The largest ovules are




FIG. 116.—*Dioon edule*: longitudinal section of strobilus, showing crowding of ovules and consequent development of false stalks; this strobilus is 33 cm. in length.—After CHAMBERLAIN (46).

formed in *Cycas circinalis*, in which they become 6 cm. long and 4 cm. wide. The ovules of *Dioon spinulosum* are almost as large, and from these dimensions all sizes are found down to the tiny ovules of species



of *Zamia*, which are less than 3 mm. in length. The color is as various as the size, white, creamy, pink, and various shades of red predominating. Within the same species there is not nearly so much




FIG. 117.—*Dioon edule*: longitudinal section of ovule after pollination, but about three months before fertilization: *a*, abscission layer; *e*, endosperm; *i*, inner fleshy layer (between *s* and *n*); *ib*, bundle of inner vascular system; *m*, micropyle; *n*, free portion of nucellus; *o*, outer fleshy layer of integument; *ob*, bundle of outer fleshy layer; *p*, basal papilla; *s*, stony layer of integument;  $\times 2$ .—After CHAMBERLAIN (46).

variation in color of ovules as in size. Some ovules are densely hairy, as those of *Cycas revoluta*; while others, as those of *Dioon*, are perfectly smooth. The general topography of the ovule, which is fairly well known in all the genera, is shown in fig. 117.

Important among the earlier contributions are those of WARMING (8, 9) on *Cycas* in 1877 and 1879, and of TREUB (11, 13) on *Ceratozamia* and *Zamia* in 1881 and 1884. Later, WORSDELL (27a) paid particular attention to the anatomy of the sporophylls of most of the genera. LANG (22) studied several stages in the development of the ovule of *Stangeria*, and OLIVER (36) made a comparative study of the ovules of the older gymnosperms. In 1904 MATTE (40) and Miss STOPES (42) published independently and almost simultaneously very comprehensive accounts of the vascular anatomy of the sporophylls and ovules of all the genera. MATTE's account treats of the entire vas-

cular structure of the Cycadales, while Miss STOPES deals particularly with the ovules, and includes a discussion of the integument as well as of the vascular system. In 1906 CHAMBERLAIN (46) described the ovule of *Dioon edule*, paying particular attention to the structure of the integument and nucellus.

The earliest stages in the development of the strobilus, sporophylls, and ovules have not been studied in any of the genera, even so late a stage as the row of megaspores having been noted only in *Stangeria*, *Ceratozamia*, and *Zamia*.


In these genera the megaspore mother cell when first recognized was deep-seated in the nucellus and surrounded by a mass of cells doubtless homologous with the "spongy tissue" of conifers. In *Stangeria* (29) and *Ceratozamia* (11) the mother cell gives rise to a row of three cells, and in *Zamia* (74) to a row of four cells, the innermost of which becomes the functioning megaspore (figs. 118-120), the first cell of a new gametophyte.

There is a single massive integument, and the nucellus is free only for a short distance.


At the apex of the nucellus, some time before the shedding of pollen, a vigorous growth results in the formation of the character-



118



119




120

FIGS. 118-120.—Megaspores of cycads: fig. 118, *Stangeria paradoxa*, showing the functional megaspore enlarging at the expense of two functionless cells of the megaspore row;  $\times 250$ ; fig. 119, *Ceratozamia longifolia*, showing row of three cells, the lowest (functional megaspore) beginning to enlarge;  $\times 266$ ; fig. 120, *Zamia floridana*, the row of four megaspores.—FIG. 118, after LANG (29); fig. 119, after TREUB (11); fig. 120, after F. GRACE SMITH (74).

istic beak, which is forced up into the micropyle; while in the center of the beak and below it cells break down and form the beginning of the pollen chamber. After the reception of the pollen the beak closes and hardens, effectively shutting in the pollen grains; while the pollen chamber continues to enlarge for several months by the

breaking-down of adjacent tissue, until it finally extends entirely through the nucellus, leaving no obstruction between the pollen tubes and the female gametophyte (figs. 121, 122).

The integument consists of three easily recognized layers: an outer and an inner fleshy layer of rather simple structure, and a very complex stony layer between them. Many of the cells of the stony layer are elongated in various directions and are often curved, thus making not only a very hard but also a very tenacious tissue. The two sets of vascular bundles are found in the fleshy layers. Whether the single integument has always been single or has arisen from the fusion of two structures, as if the cupule of a *Lagenostoma* had fused with the integument, is an open question. The cupule of *Lagenostoma* was doubtless fleshy, and contained vascular bundles which might correspond to the outer vascular bundles of the cycadean ovule;



FIGS. 121, 122.—*Dioon edule*: general view of the nucellus with pollen tubes; fig. 121, pollen chamber and pollen tubes (November 20) about two months after pollination;  $\times 40$ ; fig. 122, pollen tubes (in May) after the pollen chamber has extended entirely through the nucellus;  $\times 10$ .—After CHAMBERLAIN (63).

while the single fleshy layer of the integument, within the stony layer, contained the inner bundles. The structure of the stony layer, however, is very different, being simply a modified epidermis in *Lagenostoma*, while it is an extremely complex tissue several cells thick in cycads.

If there is a boundary between the inner fleshy layer and the nucellus, it is not conspicuous, but the innermost layer of cells next the

endosperm is differentiated into an endosperm jacket or tapetum as conspicuous as the tapetum of any fern or angiosperm microsporangium. In the mature seed the outer fleshy layer remains fresh for a while, and then either dries or decays. All the sporophytic tissue within the stony layer, including the inner fleshy layer, the nucellus, and the base of the ovule, becomes reduced to a thin dry membrane in which the bundles of the inner vascular system are the most noticeable feature.



FIGS. 123-125.—*Dioon edule*: photographs of ovules after allowing eosin to enter the bundles; fig. 123, vertical view showing 14 bundles; the eosin has spread and exaggerated the size of the outer bundles; fig. 124, photographed after the endosperm and part of the inner fleshy layer had been removed; fig. 125, transverse section; s, stony layer; o, outer fleshy layer, showing cut ends of bundles of outer vascular system; i, inner fleshy layer with bundles; n, inner fleshy layer and fused portion of nucellus; e, endosperm; all  $\times 2$ .—After CHAMBERLAIN (46).

The vascular anatomy of the ovule in its broader features is quite uniform throughout the group. There is an outer set of vascular strands, consisting of a few bundles, that traverses the outer fleshy layer of the integument and extends with little or no branching from the base of the ovule to the micropyle; and an inner set traversing the fleshy layer just within the stony coat, extending to the free portion of the nucellus, branching dichotomously, and often anastomosing. A general view of the two systems of bundles is shown in figs. 123-125. After investigating all the genera except *Microcycas* and *Ceratozamia*, WORSDELL (27a) states that two bundles leave the vascular



cylinder of the cone axis and branch, so that usually there are found in the stalk of the sporophyll four bundles, the two outer ones of which supply the two ovules (fig. 126). The bundle passing to the ovule divides twice before the outer and inner vascular systems of the ovule are established. Miss STOPES (44) finds that the inner system belongs to the inner fleshy layer of the integument rather than to the nucellus, because the bundles, especially in *Cycas*, continue in the inner fleshy layer beyond the free portion of the nucellus




FIG. 126.—*Stangeria paradoxa*: diagram of the vascular system of the megasporophyll.—After WORSDELL (27a).




FIG. 127.—*Cycas circinalis*: diagrammatic longitudinal section of nearly mature seed; *o*, outer fleshy layer, with a bundle (*o'*) of the outer vascular system; *s*, stony layer; *i*, inner fleshy layer, with a bundle (*i'*) of the inner vascular system; *c*, central vascular strand.—After Miss STOPES (42).

and extend into the free portion itself. She concludes


also that these bundles, in the simplest cases, are the branches of a single central strand, only a few branches coming from the side bundles (fig. 127). The relation of the inner and outer sets of vascular strands to the bundles of the sporophyll may be seen by studying figs. 128–131, taken from MATTE'S monograph on the vascular anatomy of cycads (40).

The vascular bundles of the sterile portion of the sporophyll above the ovules are generally mesarch, as in the foliage leaves; and in the bundles of the outer fleshy layer of the integument the mesarch

character prevails; but in the rather feebly developed bundles of the inner set of strands of the ovule it is not always easy to distinguish the protoxylem. These weaker bundles are collateral, with but




128



129



130



131

FIGS. 128-131.—Diagrams of course of vascular bundles in sporophyll and ovule: fig. 128, *Encephalartos villosus*, course of bundles in megasporophyll; *o*, *o'*, *o''*, three bundles passing to the ovule; fig. 129, small portion of the upper part of the ovule on a larger scale; fig. 130, *Microcycas calocoma*, vascular supply of ovule and sporophyll; fig. 131, *Ceratozamia mexicana*, vascular supply of ovule and sporophyll.—After MATTE (40).


little phloem, and when mesarch the development of centripetal xylem is very slight. The large central bundle, which in *Cycas* and some other genera gives rise to most of the inner set of vascular strands, is concentric or nearly so.

### 3. The gametophytes

#### THE FEMALE GAMETOPHYTE

The megaspore is the first cell of the female gametophyte. It germinates immediately, a prolonged period of free nuclear division


being accompanied by a much greater increase in the size of the embryo sac than in the quantity of cytoplasm, resulting in the formation of a large central vacuole which presses the cytoplasm with its nuclei against the megaspore membrane. Although cell-formation has not been studied among cycads, it is evident that it begins at the periphery of the embryo sac and advances toward the center, as has been described for other gymnosperms (figs. 132-134). From the figure it will be seen that cell-division is more vigorous at the periphery. Even after the gametophyte has become cellular throughout, sugar is the principal food content of the cell; but as the ovule approaches its full size, starch becomes increasingly



FIGS. 132-134.—*Dioon edule*: stages in the development of the endosperm; fig. 132, small portion of periphery of endosperm some time after it has become cellular throughout; fig. 133, still later; the two rows (a) have come from a single row (like a) of the preceding figure; fig. 134, mature endosperm, showing thick megaspore membrane at the left, the outer row of cells with little or no starch, the next row with small starch grains, and the rest with large starch grains; the evenly shaded cell contains tannin; all  $\times 88$ .—After CHAMBERLAIN (46).

abundant, and in the mature seed it occupies almost the entire cell. The cells of the outermost layer are sharply differentiated from the rest, not only by their smaller size, but also by their almost

entire lack of starch. The layer next within is also somewhat differentiated, its cells being much larger than those of the outer layer, but much smaller than those of the ordinary endosperm cells of the remaining vegetative portion of the gametophyte. Many cells, like the evenly shaded one in fig. 134, contain tannin.



FIGS. 135-138.—*Dioon edule*: development of the archegonium; fig. 135, the archegonium initial (November); fig. 136, central cell and neck cell (December); fig. 137, archegonium in January; fig. 138, upper portion of archegonium in March; all  $\times 88$ .—After CHAMBERLAIN (46).


The development of the archegonium has been described for *Cycas revoluta* by IKENO (27) and for *Dioon edule* by CHAMBERLAIN (46); isolated stages are known in other forms. In *Dioon edule* the archegonium initials, usually four or five in number, may be seen early in November, more than five months before fertilization. The initial soon divides, giving rise to a primary neck cell and a central



cell. The central cell is all that remains of the "axial row" of bryophytes and pteridophytes, true neck canal cells having been eliminated from the history of the archegonium. The primary neck cell divides almost immediately, forming the two neck cells which are characteristic of the whole group. After remaining for about three months with little change, the neck cells grow rapidly and project prominently above the general level of the surrounding tissue (figs. 135-138).

For some time the central cell increases in size much faster than in cytoplasmic content, so that a large vacuole presses the scanty cytoplasm into a thin layer against the cell wall. As the central cell approaches full size, its cytoplasmic content increases and it receives various food substances from the surrounding tissue. This accumulation of food substances by the central cell may be spoken of as the nutrition of the egg, although in a strict sense the term egg cannot be used before the mitosis which gives rise to the egg nucleus and the ventral canal nucleus. During the enlargement of the central cell its wall becomes greatly thickened and chemically modified, containing besides the original cellulose both pectin and amyloid substances. The wall also becomes conspicuously pitted, and this thick pitted wall is called the egg membrane. Through the pits in this membrane food materials from the surrounding tissue enter the central cell, although during its earlier developmental stages it receives material by the ordinary methods of transferring substances from one cell to another. GOROSCHANKIN (12) described pits with fine strands of protoplasm connecting the jacket cells and the egg, and a year later TREUB (13) saw the pits in *Cycas circinalis*. In his work upon *Cycas revoluta* IKENO (27) investigated this subject and found that large quantities of food material pass through the pits into the central cell. He likens this process to the passage of food materials from the follicle cells into the eggs in many animals. In the Abietineae ARNOLDI (28) describes even the passage of entire nuclei through the pits. Miss ISABEL SMITH (41) investigated the egg membrane of *Zamia floridana* and found that the cytoplasm of the egg protrudes through the pits into the jacket cells and forms processes which she called haustoria, and showed that the structures described as nuclei by ARNOLDI might have been tangential sections of the enlarged ends of haustoria. STOPES and FUJII (50) found that a delicate membrane


closes the pit and that communication between the jacket cells and the central cell is only through fine strands of protoplasm (*Plasmodesmen*) traversing the pit-closing membrane, and claim that it would be absurd to suggest that protein granules travel from the jacket cells to the central cell. In *Dioon edule*, according to CHAMBERLAIN (46),



FIGS. 139-144.—Haustoria of cycads: fig. 139, *Cycas revoluta*;  $\times 150$ ; fig. 140, the same  $\times 375$ ; figs. 141-143, *Dioon edule*;  $\times 800$ ; fig. 144, *Encephalartos Lehmanii*, showing the *Plasmodesmen*; from a free-hand section which had been treated with sulphuric acid;  $\times 1,100$ .—Figs. 139, 140, after IKENO (27); figs. 141-143, after CHAMBERLAIN (46); fig. 144, after STOPES and FUJII (50).

substances pass from the jacket cells into the haustoria as readily as from one part of the cell into another. Doubtless a pit-closing membrane exists here, as elsewhere, during the earlier development of the central cell, but as the haustoria grow larger and project into the cells of the jacket, the closing membrane is ruptured. The situation may be better understood from a series of figures by the various investigators (figs. 139-144).

A ventral canal cell in cycads was first described by STRASBURGER (7) in 1876 for *Cycas sphaerica*, and the next year WARMING (8) described one in *Ceratozamia robusta*, but soon concluded that he had been mistaken. TREUB (13) in 1884 failed to find any ventral canal cell in *Cycas circinalis*, and from that time it was generally believed that the cycads have no ventral canal cell. In 1898, however, IKENO (27) made an unmistakable demonstration of the critical




FIGS. 145-147.—The ventral nucleus in cycads: fig. 145, *Cycas revoluta*; mitosis which produces ventral canal nucleus and egg nucleus;  $\times 375$ ; fig. 146, *Dioon edule*; later stage, showing that no cell plate is appearing in connection with the spindle;  $\times 350$ ; fig. 147, *Dioon edule*; the ventral canal nucleus disorganizing, while the egg nucleus is increasing in size (no wall has been formed between the nuclei);  $\times 41$ .—Fig. 145, after IKENO (27); figs. 146, 147, after CHAMBERLAIN (46).

mitosis in *Cycas revoluta* (fig. 145), his figures showing that no wall is formed between the ventral canal nucleus and the egg. WEBBER (26) in 1897 reported a small cell cut off from the apex of the archegonium in *Zamia*, but in 1903 COULTER and CHAMBERLAIN (33) showed that here too there is only a nuclear division. More recently, CHAMBERLAIN (46) has shown that there is a ventral canal nucleus in *Dioon* and in *Encephalartos* (figs. 146, 147). The figure of *Dioon* shows not only that there is a nuclear division that gives rise to the ventral canal nucleus and egg nucleus, but also that wall-formation between the two nuclei has been so completely suppressed that no trace of its initiation is seen in the spindle.

It is probable that this condition is characteristic of the cycads, with the possible exception of *Microcycas*. Doubtless this free nuclear condition is less primitive than that shown by *Pinus* and some other gymnosperms, in which a wall is formed between the ventral canal nucleus and that of the egg. CALDWELL (52) states that in *Microcycas* there are often two or three free nuclei in the archegonium, and suggests that the extra nuclei may have arisen from the division of the free ventral canal nucleus, but more probably from the fusion of two or more archegonia. From a study of CALDWELL'S figures, LAND (54) suggests that these archegonia are not primitive, but are homologous with the multinucleate "archegonial tubes" of *Welwitschia*, so that the condition would be intermediate between that which prevails in gymnosperms and that which characterizes angiosperms. The fact that the neck of the archegonium in *Microcycas* is only feebly developed seems to favor this view. The archegonium situation in *Microcycas* is shown in figs. 148-150.

During the early stages in the development of the archegonia there is not only no archegonial chamber, but the archegonial region of the gametophyte is slightly elevated.

Later, the rim of the elevation grows rapidly, while the growth of the elevation itself is checked, so that what was at first the most elevated portion becomes the bottom of the archegonial chamber



FIGS. 148-150.—*Microcycas calocoma*: fig. 148, general view of transverse section of endosperm, showing numerous scattered archegonia;  $\times 3$ ; fig. 149, archegonium with one nucleus;  $\times 75$ ; fig. 150, archegonia with three nuclei, "probably resulting from the fusion of three archegonia";  $\times 270$ .—After CALDWELL (52).



(fig. 151). The number of archegonia varies considerably: in *Cycas revoluta* there are two to eight, with three the most frequent number; and in *Dioon edule*, one to ten, with four the most frequent. All the cycads that have been examined fall within these limits, with the single exception of *Microcycas*. In this genus




FIG. 151.—*Dioon edule*: development of the archegonial chamber; *d*, the condition in December, the endosperm somewhat elevated over the archegonia; *f*, in February, the chamber appearing as a slight depression; *a*, in April, shortly before fertilization; all natural size. — After CHAMBERLAIN (46).

archegonia scattered over the entire surface of the gametophyte, and some of them may even open into the median cleft where the centripetal growth of the gametophyte has not completely replaced the large central vacuole. Usually the archegonia are grouped at the micropylar end of the gametophyte.

In the heterosporous pteridophytes the megaspore wall is thick and highly differentiated, and it has long been known that the endosperm of *Cycas* is surrounded by a membrane which is the homologue of the spore coat of the pteridophytes. With the retention of the megaspore in the sporangium, the spore coat would naturally become reduced as the retention became more and more pronounced, so that the thickness of the megaspore coat, or megaspore membrane as it is more usually called, is one of the factors to be considered in estimating the relative antiquity of the different forms. At present, however, little dependence can be placed upon this factor, because the thickness of the membrane differs decidedly at different stages in the development of the ovule. In *Dioon edule* (46) the thickness of the membrane during free nuclear division in the endosperm is about  $3\ \mu$ , just before the beginning of the archegonial chamber about  $5\ \mu$ , while in the germinating seed it has increased to  $9\text{--}10\ \mu$ . Not enough stages have been measured in any other form to make comparisons reliable.

The most extended investigation of this subject is that of THOMSON (45), who studied not only cycads, but also the other living groups of gymnosperms. He finds that the membrane is differentiated into two layers, an exospore, which is suberized, and an endospore of complex composition. The inner region of the endospore, next

to the endosperm, contains a substance related to pectin, toward the middle the pectin is replaced by cellulose, and the cellulose is replaced in turn by suberin in the outer part of the endospore, where it borders upon the suberized exospore. In structure the endospore is rather homogeneous, while the exospore is formed of little columns or fibrillae, which give it a distinctly striated appearance (fig. 152). The outer walls of the endosperm cells bordering upon the endospore become suberized, and might sometimes be mistaken for a part of the endospore itself. The membrane in *Dioon edule* is shown in figs. 136, 137, where it is in contact with the endosperm above the archeogonia; and in fig. 153, which shows the comparatively homogeneous endospore and the exospore consisting of club-shaped bodies with an ovoidal outer portion connected with the endospore by a stalk. In sections more than 1 or 2  $\mu$  in thickness, the region of the stalks appears as a nearly black line, so that there seem to be three layers, the extra layer being only an optical effect due to the stalk region.



FIGS. 152, 153.—The megaspore membrane of the cycads: fig. 152, *Cycas revoluta*; three free nuclei of the endosperm at the left, cells of the endosperm jacket at the right, and the megaspore membrane (4.5  $\mu$  thick) between them; fig. 153, *Dioon edule*; section of megaspore membrane showing inner homogeneous layer and outer layer of club-shaped bodies;  $\times 1,200$ .—Fig. 152, after THOMSON (45); fig. 153, after CHAMBERLAIN (46).

#### THE MALE GAMETOPHYTE

The microspore is the first cell of the male gametophyte. The peculiar thickening of the wall of the microspore mother cell, making it resemble a heavy, four-celled case containing the four spores, has been described by JURANYI (5) for *Ceratozamia longifolia*, and by TREUB (11) for *Zamia muricata* (fig. 154). JURANYI (5) gave also a fairly full account of the germination of the microspore of *Cera-*

*tozamia longifolia*. His material, which was secured by growing the spores upon juicy pears, showed four cells in the spore, and no further divisions seem to have occurred during such early stages in the formation of the pollen tube as could be obtained in this way. In 1896, in a preliminary paper (19), followed by the full paper (27) in 1898, IKENO presented a detailed account for *Cycas revoluta*; while in 1897 (26) and 1901 (32) WEBBER published his results for *Zamia integrifolia*. More recently CALDWELL (52) has described the male gametophyte of *Microcycas calocoma*, and CHAMBERLAIN (63, 70) that of *Dioon edule*.





FIG. 154.—*Zamia muricata*: three stages in the development of microspores from the mother cell, the lowest figure showing the four microspores within the thick-walled structure; lowest figure,  $\times 466$ ; other two,  $\times 596$ .—After TREUB (11).

The microspore has two sharply differentiated coats, the exine and the intine. The exine is thickest in the basal region of the spore, and becomes very thin toward the apex, where the pollen tube is to emerge; while the intine is thinnest in the basal region, where it is in contact with the thickest portion of the exine, and thickest along the sides of the spore (figs. 155-159).

The microspore germinates while still in the microsporangium, the nuclear division forming two unequal cells, a small persistent prothallial cell, and a larger cell, the antheridium initial. Immediately afterward the nucleus of the larger cell divides, forming two unequal cells, one a small cell

so closely applied to the prothallial cell that it looks as if it had arisen by the division of the prothallial cell itself, and the other the tube cell. This second small cell has been called the generative cell, although it is probable that it cannot be regarded as the primary spermatogenous cell, since one of its daughter cells (the stalk cell) has proved to be persistently sterile throughout gymnosperms. In *Cycas revoluta*, *Zamia floridana*, *Encephalartos villosus*, and *Dioon edule* the pollen is shed in this three-celled condition (fig. 156); the other genera have not been studied with sufficient thoroughness to warrant any statement as to the shedding condition.

It is generally accepted that the cycads are wind-pollinated. PEARSON (47), however, observed insects dusted with the pollen of *Encephalartos villosus*, and believes it is probable that they effect



FIGS. 155-159.—*Dioon edule*; the germination of the microspore; fig. 155, the nucleus in early prophase of the first mitosis, exine and intine sharply differentiated (August 14, 1905); fig. 156, the shedding stage (September 1906); fig. 157, beginning of the pollen tube; *t*, tube nucleus; *g*, generative cell; *p*, prothallial cell; fig. 158, the generative cell divided (October 21, 1907), giving rise to stalk cell (*s*) and body cell (*b*), no blepharoplasts visible; fig. 159, later stage (November 20, 1906), the body cell much elongated and the blepharoplasts with very conspicuous radiations; figs. 155-157,  $\times 1,260$ ; fig. 158,  $\times 1,000$ ; fig. 159,  $\times 630$ .—After CHAMBERLAIN (63).

pollination. In *Dioon edule* (63), when the pollen is shed, a large pollination drop oozes from the micropyle, just as in gymnosperms which are known to be wind-pollinated, and in this case, also, insects dusted with pollen were found in the staminate cones, but there was nothing further to indicate that pollination was being effected through




their agency. Until insect pollination is proved, it is safer to assume that the pollen is carried by the wind, as is generally supposed.

Whether in artificial culture or in the pollen chamber, the pollen tube begins to grow at once, but in cultures the growth is very limited, neither JURANYI (5) nor STRASBURGER (7) having been able to get the division of the generative cell. Under natural conditions the development continues without interruption from pollination to fertilization, a period of about four months in *Cycas revoluta*, about five months in *Zamia floridana*, and about six months in *Dioon edule*. The pollen grain end is pushed into the open cavity of the pollen chamber, while the haustorial end penetrates the nucellus, branching occasionally and running so near the surface that the brown lines due to the tubes are easily visible to the naked eye. Starch is abundant in the pollen grain and during all stages in the development of the pollen tube.

The generative cell soon divides, forming two cells which have been called the stalk and body cells on account of their usual relations to each other in most gymnosperms. In IKENO's figures of *Cycas revoluta* (27) these two cells lie side by side, and it would seem that either might function further; while in *Zamia*, *Dioon*, *Microcycas*, and *Ceratozamia* they have the more usual fore and aft position (fig. 159). The stalk cell does not divide again, but increases greatly in size and becomes filled with large starch grains; and since it has been found to be sterile in all gymnosperms, it may be regarded as representing the actual stalk cell of an antheridium. In that case, the body cell is the real primary spermatogenous cell. The body cell increases both in size and cytoplasmic content, but contains little or no starch. As these two cells enlarge, the prothallial cell behaves in a peculiar way, pushing into the stalk cell until it often presses against the wall between the stalk and body cells (figs. 158, 159).

The most interesting feature in the development of the male gametophyte is the fact that motile sperms are produced. The cilia by which the sperms swim are the culmination of the development of a small body called the blepharoplast, which appears in the body cell several months before the latter divides. When first unmistakably distinguishable, there are two blepharoplasts, one at each pole of the nucleus of the body cell, but occasionally they may be nearer together


(fig. 166). The blepharoplast is surrounded by a beautiful system of radiations, so that the whole structure has exactly the appearance of a centrosome with its aster. In *Dioon edule*, during early stages, the rays appear very coarse on account of globules which become



FIGS. 160-165.—*Cycas revoluta*: fig. 160, pollen grains at shedding stage;  $\times 500$ , fig. 161, later stage, showing prothallial cell (*p*) and generative cell (*g*), the tube nucleus not shown;  $\times 200$ ; fig. 162, generative cell divided, giving rise to stalk and body cells;  $\times 500$ ; fig. 163, the stalk nucleus (*s*) being crowded out, and blepharoplasts appearing in the body cell (*b*);  $\times 500$ ; fig. 164, the body cell shortly before division, showing two well-developed blepharoplasts;  $\times 750$ ; fig. 165, the two male cells resulting from the division of the body cell; the beaks of the nuclei are attached to the cilia-bearing bands;  $\times 200$ .—After IKENO (27).

attached and spread along them (fig. 159); later they become smooth and even. During the earlier stages in the development of the body cell, when it is more or less elongated in the direction of the long axis of the pollen tube, the blepharoplasts lie in the plane of the long axis; but as the pollen tube enlarges, the body cell gradually becomes nearly

spherical and the blepharoplasts rotate through  $90^{\circ}$ , so that they become transverse to the long axis of the tube (figs. 159-169). The body cell divides in the plane of the long axis of the tube, giving rise to two sperm mother cells. As division of the body cell approaches,




FIGS. 166-169.—*Zamia floridana*: fig. 166, end of pollen tube with prothallial and stalk cells, and the body cell with young blepharoplasts; fig. 167, later stage, showing blepharoplasts in fore and aft position; fig. 168, division of body cell; in section the blepharoplasts appear as broken circles; fig. 169, the two cells resulting from the division of the body cell; the blepharoplast elongating into a band.—After WEBBER (32).

the blepharoplast becomes very much vacuolated, and during the division it breaks up into a large number of granules which fuse together and thus initiate the formation of a spiral band (figs. 168, 169). While the band is being formed, it is intimately connected with the nucleus (fig. 165), and when completed it is a spiral of five or six turns, lying just below the surface and giving rise to numerous

cilia that pass through the outer border of the sperm and project for some distance.

It has been claimed that the two cells formed by the division of the body cell become ciliated and are themselves the sperms. IKENO



FIGS. 170-172.—Sperms of cycads, represented as not formed within mother cells, but as consisting of the entire transformed halves of body cells; fig. 170, *Zamia*; pollen tube with sperms just before they begin to swim;  $\times 90$ ; fig. 171, *Cycas revoluta*; the sperms at the beginning of movement; fig. 172, *Cycas revoluta*; the sperms swimming freely in the tube;  $\times 88$ .—Fig. 170, after WEBBER (32); figs. 171, 172, after MIYAKE (48).

(27) described the sperms of *Cycas* as perfectly naked, and WEBBER (32) found the same condition in *Zamia*, where he was unable to find any inclosing mother cell, although he looked for it. MIYAKE (48) also looked for an inclosing cell in *Cycas* and saw a thin mem-



brane, but could not determine whether it belonged to the sperms or might be only the *Hautschicht* of the cytoplasm of the pollen tube. In such a case the two sperms would simply become loosened from the stalk cell and swim away (figs. 170-172). In *Dioon edule*, according to CHAMBERLAIN (63), the division of the body cell gives rise to





FIG. 173.—*Dioon edule*: photomicrograph of end of pollen tube, showing that the two sperms are formed within sperm mother cells; the walls of the mother cells can be seen between the sperms and surrounding them;  $\times 720$ .—After CHAMBERLAIN (63).

two sperm mother cells, inside of which the sperms are organized and from which they are discharged. This conclusion is based upon an examination of both living material and sections. The photomicrograph reproduced in fig. 173 shows the two sperms within their mother cells.

In *Cycas*, *Zamia*, and *Dioon* two sperms are formed in the pollen

tube; but in *Microcycas* CALDWELL (52) describes and figures sixteen to twenty sperms (figs. 174, 175), and four sperms are found occasionally in *Ceratozamia* (53). It is evident that in *Microcycas* the body cell has given rise to eight or ten spermatogenous cells, each of which has produced two sperms. *Cupressus Goveniana*, described



FIGS. 174, 175.—*Microcycas calocoma*: fig. 174, pollen tube showing nine spermatogenous cells, in most of which the blepharoplasts are seen;  $\times 160$ ; fig. 175, later stage showing sections of 15 sperms;  $\times 450$ .—After CALDWELL (52).

by JUEL (39), has four to twenty sperms, all derived from the body cell. The large number of sperms is doubtless a primitive character, as both investigators suggest, but the cases seem somewhat different, since in *Microcycas* the condition may have persisted from earlier forms, while in *Cupressus Goveniana* it is more likely to be a reversion.

The sperms of cycads are remarkably large, in fact larger than any

known in other plants or in animals. They are usually slightly longer than broad, in *Zamia floridana* being 222–332  $\mu$  in length and 222–306  $\mu$  in width; in *Dioon edule* 300  $\mu$  in length and 230  $\mu$  in width; in *Cycas revoluta* 180–210  $\mu$  in width; and in *Microcycas calocoma* about 60  $\mu$  in width. As shown in fig. 173, the nucleus is very large, with only a thin sheath of cytoplasm. Such large bodies, of course, are easily visible to the naked eye, and since the pollen tubes are transparent, it is easy to observe the movements of the sperms.

The cilia begin to move while the sperms are still within the mother cells, and their movement is accompanied by pulsating and amoeboid movements of the cytoplasm and nucleus. The peripheral portion of the partition between the sperms soon breaks down, and the two sperms, still attached to one another, often begin to swim in the old body cell before they escape into the general cavity of the tube. When free from one another, the principal movement is straight ahead, with a rotation on the long axis. The movements may continue for several hours before the sperms are discharged from the tube. For some time before the sperms are discharged, the portion of the pollen tube which projects into the pollen chamber becomes more and more turgid, until finally a rupture occurs at or near the wall of the pollen grain which still caps the end of the tube. One sperm escapes in two or three seconds, but the other may be half a minute in getting out. Experiments have been made to determine whether the sperms are chemotactic or not, but so far with only negative results.

#### FERTILIZATION

When the pollen chamber breaks through the base of the nucellar cap, the portion of the megaspore membrane covering the archegonial chamber is ruptured, so that the two chambers form one continuous cavity. The archegonial chamber is moist, but contains no liquid until the turgid pollen tubes begin to discharge. The sperms swim in the liquid discharged from the pollen tubes and enter the necks of the archegonia (fig. 176).

Fertilization has been described in three cases: in *Cycas revoluta* by IKENO (27), in *Zamia floridana* by WEBBER (32), and in *Dioon edule* by CHAMBERLAIN (70), who has also observed it in *Ceratozamia*



*mexicana*. In these four forms the entire sperm enters the egg, but the nucleus soon slips out from the cytoplasmic sheath, and leaving it with its ciliated band in the upper part of the egg moves toward



FIG. 176.—*Dioon edule*: upper part of ovule at time of fertilization, showing integument, nucellus, and both male and female gametophytes; reconstructed from sections of several ovules.—After CHAMBERLAIN (73).

the egg nucleus. The ciliated band was observed by LANG (29) in the upper part of the egg of *Stangeria*, so that in this form also it is evident that the sperms are motile and that the whole sperm enters the egg. The sperm nucleus is much smaller than that of the egg, and it penetrates some distance into the egg nucleus before the bound-



ary between the two becomes indistinct (fig. 177). Nothing is known of the behavior of chromatin during fertilization.

The prominent development of the pollen tube as an absorbing





FIG. 177.—*Zamia floridana*: fertilization; the smaller sperm nucleus has pressed into the egg nucleus, but still retains its contour; the ciliated band is still visible at the top of the egg;  $\times 20$ .—After WEBBER (26).

organ suggests a question as to its original significance. In the Cycadofilicales the pollen grains are in close proximity to the egg, and there is nothing to indicate that any pollen tube was formed. In the cycads and in *Ginkgo* the pollen tube in the earlier stages of its development functions only as a haustorium. The pollen grain end, with its cell complex, projects into the pollen chamber and gradually approaches the egg, not by actively invading any tissue, but merely by elongating into the enlarging pollen chamber. The portion which actively invades the nucellus is somewhat longer than the part in the pollen chamber, but has a much smaller diameter and never carries the sperms. In all other living seed plants, the pollen grain remains just where it falls, and the pollen tube acts both as a haustorium, actively invading the tissue, and as a sperm carrier. It seems safe to assume

that the pollen tube was originally a haustorium, and that its function as a sperm carrier was developed later.

#### 4. The embryo

In 1877 WARMING (8) described some of the later stages in the development of the embryo of *Ceratozamia*, but in all cases the embryo had already passed through the base of the egg and invaded the endosperm. In 1884 TREUB (13) gave a comparatively full account of the embryogeny of *Cycas circinalis*, and this account was to some extent confirmed and supplemented by IKENO'S (27) study of *Cycas revoluta*. Later, COULTER and CHAMBERLAIN (33) investigated *Zamia floridana* (figs. 178-181), and more recently CHAMBERLAIN (70) has described the embryogeny of *Dioon edule* (figs. 183-185).



FIGS. 178-181.—*Zamia floridana*: fig. 178, free nuclei of proembryo;  $\times 16$ ; fig. 179, tissue at base of proembryo;  $\times 24$ ; fig. 180, differentiation into suspensor and embryo;  $\times 20$ ; fig. 181, young embryo showing long suspensor, natural size.—After COULTER and CHAMBERLAIN (33).

After fertilization there is a prolonged period of free nuclear division, in which the mitotic figures are intranuclear and the spindles very conspicuous (fig. 178). Since some have regarded the blepharoplast as a centrosome, these figures have been examined with great care, and it can be stated confidently that no centrosomes are concerned in their formation. The free nuclear divisions are simultaneous, just as in




FIG. 182.—*Cycas circinalis*: beginning of wall-formation in proembryo;  $\times 25$ .—After TREUB (13).

the germination of the megaspore or in the early development of endosperm in most angiosperms. The number of successive free nuclear divisions in *Zamia floridana* (33) was estimated as eight, giving 256 free nuclei before any walls begin to appear. In *Cycas revoluta* no estimate was made, but there are certainly as many as 256 nuclei and very probably more. In *Dioon edule* (70) there are at least nine successive divisions, giving 512 nuclei, but the divisions become irregular and not perfectly simultaneous; hence one cannot assume that if the number is over 512 it will be 1024.

In *Cycas circinalis*, according to TREUB (13), a large central vacuole appears and crowds all the nuclei to the periphery, so that they form a parietal layer (fig. 182). In *Cycas revoluta* IKENO (27) gives a different account of the formation of the central vacuole, stating that a large number of small vacuoles are formed, and that the cytoplasm of the

central portion of the proembryo with its contained nuclei then disorganizes, leaving a parietal layer of cytoplasm and nuclei, while a single large vacuole occupies the center. IKENO's account is doubtless true for *Cycas revoluta*, and probably holds for *C. circinalis* also. It is evident that the proembryo becomes a sac, somewhat thickened at the base, but with the wall composed of one or two layers. In *Cycas revoluta*, after this stage has been reached, there are a few



FIGS. 183-185.—*Dioon edule*: development of proembryo; fig. 183, base of proembryo, showing character of segmentation at a stage when the entire egg is segmented;  $\times 108$ ; fig. 184, diagram of entire proembryo at the stage shown in fig. 183; the segmentation is disappearing in the upper region;  $\times 20$ ; fig. 185, permanent walls at the base, but as yet no differentiation into regions; free nuclei above; membrane (*m*) of egg not yet ruptured;  $\times 108$ .—After CHAMBERLAIN (70).



simultaneous free nuclear divisions at the base of the proembryo before walls begin to appear, and at the same time amitotic divisions may take place in the upper portion. The peripheral walls of the proembryo are a new formation, entirely independent of the wall of the egg. At this point the work of IKENO stops, and beyond it WARMING and TREUB give very little detail.

In *Zamia floridana* COULTER and CHAMBERLAIN (33) found a different condition, no central vacuole being present even at a rather late period, when the suspensor has begun to elongate (fig. 180).



FIG. 186.—*Dioon edule*: longitudinal section of mature seed, showing embryo with two cotyledons and plumule, endosperm, inner fleshy layer represented only by a line, stony layer shaded, and outer fleshy layer; natural size.—After CHAMBERLAIN (70).

Walls begin to appear at the base of the proembryo, just as in the beginning of wall-formation in the endosperm of most angiosperms.

In *Dioon edule* (70), at the close of the free nuclear period, walls appear simultaneously throughout the whole egg, but the walls are weak and evanescent, except at the base of the proembryo, where they become permanent (figs. 183–185). *Dioon* resembles *Zamia* in having no central vacuole during the proembryo stages, but at a very late stage, like that shown in fig. 182, the egg becomes empty and preserves its contour only on account of its very thick membrane.


After wall-formation has become established at the base of the proembryo, the sequence seems to be about the same in all the forms which have been studied. The cells bordering upon the large central vacuole, as in *Cycas*, or upon the free nuclear area, as in *Zamia* and *Dioon*, undergo little or no change in form, while the cells immediately below them become greatly elongated, constituting the suspensor (fig. 180). The cells at the tip remain meristematic, and from this apical region the embryo proper is organized.

The suspensor is massive and tortuous and is remarkably long (fig. 181), that of *Dioon edule*, when straightened out, frequently reaching a length of 70 mm., but it has never been observed to branch or to bear more than one embryo. The suspensors start separately from the

several archegonia, but soon become twisted together, so that what appears to be a single suspensor is composed of two or three or more suspensors in its upper portion, each terminated by an abortive embryo, while beyond the region of abortive embryos stretches the single successful suspensor with its embryo. It is this twisting together in the upper part that makes the whole structure look like one suspensor with several eggs at one end and a single embryo at the other. During these stages the tissue in the archegonial region disorganizes, so that there is formed a large cavity which later becomes packed with the tortuous suspensor.

The single successful embryo rapidly invades the endosperm, and for a time increases in size with little internal differentiation. At the base of the embryo there develops a conspicuous and peculiar structure, the coleorrhiza, and at the opposite end the stem tip and two cotyledons, while the root appears rather late (fig. 186).

The usual number of cotyledons is two, but three united throughout their entire length have been found in *Encephalartos* (71). In 1879 WARMING (9) described the single peculiar cotyledon of *Ceratozamia*, and an examination of abundant material from the field confirms the description, but SISTER HELEN ANGELA (58) noticed that the strobilus disintegrates and frees the seeds before the cotyledon has



FIGS. 187-194.—*Ceratozamia mexicana*: embryo and germination of the seed; figs. 187, 188, normal embryos with a single lateral cotyledon;  $\times 5$ ; fig. 189, embryo with two cotyledons, from seed which had been on a clinostat during the entire period of cotyledon development;  $\times 8$ ; figs. 190-194, successive stages in germination;  $\times \frac{1}{2}$ ; in all figures, *c*, cotyledon; *cl*, coleorrhiza; *l*, scale leaf; *f*, first foliage leaf; *r*, root; *s*, suspensor.—After SISTER HELEN ANGELA (58, 59).

begun to develop. Suspecting that gravity might be concerned in the suppression of one of the cotyledons, she placed seeds upon a clinostat during the entire period of cotyledon development, and these seeds developed regularly two cotyledons (figs. 187-194).

The mature seed has a fleshy and variously colored outer coat, developed from the outer portion of the integument, and an inner stony coat, extremely hard and tough, derived mostly from the middle region of the integument. Within the stony layer is a thin, dry membranous layer derived partly from the nucellus and partly from the inner fleshy layer of the integument and containing the inner vascular system of the ovule. In *Encephalartos*, *Cycas*, *Ceratozamia*, and perhaps other genera, the ovule often reaches its full size and seed-like appearance whether pollination has taken place or not. In *Dioon*, ovules which have not been pollinated usually abort, and consequently greenhouse material, and even cones in the field, if widely separated from staminate plants, are likely to have only abortive ovules.

Seeds germinate readily if simply placed on the surface of moist soil. If covered by the soil, they are raised to the surface, but not much above it, by the cotyledons, which always remain within the seed coats.

In *Dioon*, *Zamia*, *Ceratozamia*, *Microcycas*, and probably in all the other genera, the intraseminal development may be followed immediately by the germination of the seed, no resting period being necessary. The coleorhiza, which in early stages constitutes a considerable portion of the embryo, becomes reduced to a thin, hard, brown cap which protects the more delicate structures while the micropylar portion of the stony coat is being ruptured and the young seedling is emerging. After the coleorhiza has broken through the seed coat, the tardy root pierces it and soon thickens into a stout tap root.

## 5. History and distribution

That representatives of the Cycadales existed during the Mesozoic, side by side with the predominant Bennettitales, is a safe inference, but the evidence is extremely meager. Strobili thought to be staminate cones of cycads have been used as the basis of the form genus *Androstrobus*. The structure of a few of these species suggests a possible connection with cycads, but NATHORST (60) has shown that

one of them is the strobilus of a heterosporous lycopod, which he has named *Lycostrobus*. SCOTT (69) regards the evidence of the existence of mesozoic cycads on the basis of staminate strobili as not convincing.

The testimony from ovulate strobili is more definite. The evidence of *Zamia*-like forms is unsatisfactory, but megasporophylls like those of *Cycas* are recorded from various strata of the Mesozoic, in one case with a seed attached. While the occurrence of *Cycas*-like forms seems to be established, NATHORST (55) has found that the pinnae of several of them contain double vascular bundles, rather than the single one of the living *Cycas*, and for these he has proposed the genus *Pseudocycas*.

Fragments of the vegetative structures cannot be used to differentiate Cycadales and Bennettitales, so that strobili are essential and these must be well preserved. In summing up the evidence for the existence of mesozoic cycads, therefore, SCOTT (69) says that the whole question "is in an unsatisfactory condition and the evidence is singularly meager."

In view of the above statements, it is evident that there are no facts as to the distribution of mesozoic cycads. That they were widely distributed may be inferred from their relationship to the Bennettitales, from the increasing abundance of cycads in more recent deposits, and from the present distribution of the group. The distribution of the living cycads has been stated at the first of the chapter.

## 6. Relationship to other gymnosperms

The relationship of Cycadales to Bennettitales and Cycadofilicales is the only one that needs consideration, since the other gymnosperm groups can be connected with it only by way of the Cycadofilicales. Under Bennettitales (p. 86) this subject was discussed somewhat in detail, and little need be added here.

That Cycadales are connected with the Bennettitales in origin seems clear; in fact, no two great gymnosperm groups have so many features in common. The transition from the trunks of *Cycadeoidea*, with their numerous lateral strobili, through such a form as *Williamsonia gigas*, with its several strobili appearing from the center of a crown of leaves, to the cycads, with a usually solitary and terminal strobilus, seems natural, and suggests that the Cycadales are



an offshoot from the Bennettitales. And yet, the striking differences in the strobili of the two groups seem to contradict such an easy disposition of the question, and suggest independent origin from the Cycadofilicales.

The bisporangiate strobilus of Bennettitales, with its pinnate stamens and stalked ovules, suggests an origin from the groups of Cycadofilicales with stalked ovules and marattiaceous microsporophylls. The Cycadales, on the other hand, taking *Cycas* and *Pseudocycas* as its oldest known representatives, suggest an origin from groups of Cycadofilicales bearing ovules as did *Pecopteris Pluckenetii*. This separate origin is further emphasized by the fact that in the one case bisporangiate strobili are developed, with a characteristic relation of microsporophylls and megasporophylls; and in the other monosporangiate strobili are produced, with the dioecious habit; and still further by the fact that in the one case a monopodial stem with direct leaf traces is maintained; and in the other a sympodial stem with its characteristic "girdles" is established. It is recognized that such differentiations from Bennettitales are conceivable, but it is easier to conceive of them as having arisen from such a synthetic group as the Cycadofilicales than from such an extremely specialized group as the Bennettitales. The historical testimony that will answer this question will be forthcoming only when the actual connections with Cycadofilicales are discovered.

The Cycadales are remarkable in the retention of more primitive characters than are possessed by any living group of gymnosperms. The swimming sperms are shared by Ginkgoales, and the structure of the ovule that goes with them, but the vegetative structures are more fernlike than in any other living group. In this sense it is proper to speak of Cycadales as the most primitive of living gymnosperms; but it must be remembered that they are probably not so old as either the Ginkgoales or the Coniferales.

#### LITERATURE CITED

1. BRONGNIART, A., Recherches sur l'organisation des tiges des Cycadées. Ann. Sci. Nat. I. 16:389-402. pls. 20-22. 1829.
2. VON MOHL, HUGO, Ueber den Bau des Cycadeen-Stammes. Abh. K. Acad. München 1:397-442. 1832; republished and revised in Vermischte Schriften, pp. 195-211. 1845.

3. MIQUEL, F. A. W., Monographia Cycadearum. 1841.
4. METTENIUS, G. H., Beiträge zur Anatomie der Cycadeen. Abh. K. Sachs. Gesell. Wiss. 7:565-608. pls. 1-5. 1861.
5. JURANYI, L., Bau und Entwicklung des Pollens bei *Ceratozamia longijolia* Miq. Jahrb. Wiss. Bot. 8:382-400. pls. 31-34. 1872.
6. REINKE, J., Parasitische *Anabaena* in Wurzeln der Cycadeen. Gött. Nachr. 107. 1872.
7. STRASBURGER, E., Ueber Zellbildung und Zelltheilung. 1876.
8. WARMING, E., Recherches et remarques sur les Cycadées. Oversigter Vidensk. Selsk. Forh. 1877.
9. ———, Contributions à l'histoire naturelle des Cycadées. Oversigter Vidensk. Selsk. Forh. 1879.
10. SOKOLOWA, MILE C., Naissance de l'endosperme dans le sac embryonnaire de quelques gymnospermes. Moscou. 1880.
11. TREUB, M., Recherches sur les Cycadées. Ann. Jard. Bot. Buitenzorg 2:32-53. pls. 1-7. 1881 (date of reprint, volume date being 1885).
12. GOROSCHANKIN, J., Zur Kenntniss der Corpuscula bei den Gymnospermen. Bot. Zeit. 41:825-831. pl. 7A. 1883.
13. TREUB, M., Recherches sur les Cycadées. 3. Embryogenie du *Cycas circinalis*. Ann. Jard. Bot. Buitenzorg 4:1-11. pls. 1-3. 1884.
14. CONSTANTIN, J., et MOROT, L., Sur l'origine des faisceaux libéro-ligneux supernuméraires dans la tige des Cycadées. Bull. Soc. Bot. France 32:173. 1885.
15. GOEBEL, K., Outlines of classification and special morphology. English translation, p. 316. 1887.
16. SOLMS-LAUBACH, H., Die Sprossfolge der *Stangeria* und der übrigen Cycadeen. Bot. Zeit. 48:177-187, 193-199, 209-215, 225-230. 1890.
17. STRASBURGER, E., Histologische Beiträge 3:151. 1891.
18. SCHNEIDER, A., Mutualistic symbiosis of algae and bacteria with *Cycas revoluta*. Bot. Gazette 19:25-32. pl. 3. 1894.
19. IKENO, S., Das Spermatozoid von *Cycas revoluta*. Bot. Mag. Tokyo 10:367, 368. 1896.
20. WORSDELL, W. C., Anatomy of stem of *Macrozamia* compared with that of other genera of Cycadeae. Annals of Botany 10:601-620. pls. 27, 28. 1896.
21. IKENO, S., Vorläufige Mittheilung über die Spermatozoiden bei *Cycas revoluta*. Bot. Centralbl. 69:1-3. 1897.
22. LANG, W. H., Studies in the development and morphology of cycadean sporangia. I. The microsporangia of *Stangeria paradoxa*. Annals of Botany 11:421-438. pl. 22. 1897.
23. SCOTT, D. H., The anatomical characters presented by the peduncles of Cycadaceae. Annals of Botany 11:399-419. pls. 20, 21. 1897.
24. WEBBER, H. J., Peculiar structures occurring in the pollen tube of *Zamia*. Bot. Gazette 23:453-459. pl. 40. 1897.

25. WEBBER, H. J., The development of the antherozoids of *Zamia*. Bot. Gazette **24**:16-22. 1897.
26. ———, Notes on the fecundation of *Zamia* and the pollen tube apparatus of *Ginkgo*. Bot. Gazette **24**:225-235. pl. 10. 1897.
27. IKENO, S., Untersuchungen über die Entwicklung der Geschlechtsorgane und der Vorgang der Befruchtung bei *Cycas revoluta*. Jahrb. Wiss. Bot. **32**:557-602. pls. 8-10. 1898.
- 27a. WORSDELL, W. C., The vascular structure of the sporophylls of the Cycadaceae. Annals of Botany **12**:203-241. pls. 17, 18. 1898.
28. ARNOLDI, W., Beiträge zur Morphologie der Gymnospermen. IV. Was sind die "Keimbläschen" oder "Hofmeister's-Körperchen" in der Eizelle der Abietineen? Flora **87**:194-204. pls. 6, 7. 1900.
29. LANG, W. H., Studies in the development and morphology of cycadean sporangia. II. The ovule of *Stangeria paradoxa*. Annals of Botany **14**:281-306. pls. 17, 18. 1900.
30. WORSDELL, W. C., The anatomical structure of *Bowenia spectabilis*. Annals of Botany **14**:159, 160. 1900.
31. LIFE, A. C., The tubercle-like roots of *Cycas revoluta*. Bot. Gazette **31**:265-271. figs. 10. 1901.
32. WEBBER, H. J., Spermatogenesis and fecundation of *Zamia*. U.S. Dept. Agric., Bur. Pl. Ind., Bull. 2. pp. 100. pls. 7. 1901.
33. COULTER, JOHN M., and CHAMBERLAIN, C. J., The embryogeny of *Zamia*. Bot. Gazette **35**:184-194. pls. 6-8. 1903.
34. ENRICO, C. V., Contribuzione alla conoscenza della morfologia e dello sviluppo del fascio vascolare delle foglie delle Cicadacee. Annales di Bot. **1**:109-121. pls. 8, 9. 1903.
35. MATTE, H., Une anomalie de structure dans l'écaille ovulifère de *Ceratozamia mexicana*. Bull. Soc. Linn. Normandie V. **7**:52-54. 1903.
36. OLIVER, F. W., The ovules of the older gymnosperms. Annals of Botany **17**:451-476. pl. 24. figs. 20. 1903.
37. COKER, W. C., On the spores of certain Coniferae. Bot. Gazette **38**:206-213. figs. 24. 1904.
38. COULTER, JOHN M., and CHRYSLER, M. A., Regeneration in *Zamia*. Bot. Gazette **38**:452-458. figs. 8. 1904.
39. JUEL, H. O., Ueber den Pollenschlauch von *Cupressus*. Flora **93**:56-62. pl. 3. 1904.
40. MATTE, H., Recherches sur l'appareil libéro-ligneux des Cycadées. pp. 233. pls. 16. figs. 264. 1904.
41. SMITH, ISABEL S., The nutrition of the egg in *Zamia*. Bot. Gazette **37**:346-352. figs. 6. 1904.
42. STOPES, MARIE C., Beiträge zur Kenntniss der Fortpflanzungsorgane der Cycadeen. Flora **93**:435-482. figs. 37. 1904.
43. MATTE, H., Compléments à la structure mérophytaire du *Bowenia spectabilis* Hord. Compt. Rend. Assoc. Fr. Adv. Sci. 1905:409-416.

44. STOPES, MARIE C., On the double nature of the cycadean integument. *Annals of Botany* **19**:561-566. 1905.
45. THOMSON, R. B., The megaspore membrane of the gymnosperms. Univ. Toronto Biol. Series no. 4. pp. 64. *pls.* 5. 1905.
46. CHAMBERLAIN, CHARLES J., The ovule and female gametophyte of *Dioon*. *Bot. Gazette* **42**:321-358. *pls.* 13-15. *figs.* 9. 1906.
47. PEARSON, H. H. W., Notes on the South African cycads. I. *Trans. S. African Phil. Soc.* **16**:341-354. *pls.* 6-8. 1906.
48. MIYAKE, K., Ueber die Spermatozoiden von *Cycas revoluta*. *Ber. Deutsch. Bot. Gesell.* **24**:78-83. *pl.* 6. 1906.
49. SEWARD, A. C., Notes on cycads. *Proc. Cambridge Phil. Soc.* **13**:293-302. 1906.
50. STOPES, M. C., and FUJII, K., The nutritive relations of the surrounding tissues to the archegonia in gymnosperms. *Beih. Bot. Centralbl.* **20**:1-24. *pl.* 1. 1906.
51. WIELAND, G. R., American fossil cycads. Publ. No. 34, Carnegie Institution of Washington. pp. 296. *pls.* 50. *figs.* 138. 1906.
52. CALDWELL, OTIS W., *Microcycas calocoma*. *Bot. Gazette* **44**:118-141. *pls.* 10-13. *figs.* 14. 1907.
53. CHAMBERLAIN, CHARLES J., Preliminary note on *Ceratozamia*. *Bot. Gazette* **43**:137. 1907.
54. LAND, W. J. G., Fertilization and embryogeny in *Ephedra trifurca*. *Bot. Gazette* **44**:273-292. *pls.* 20-22. 1907.
55. NATHORST, A. G., Palaeobotanische Mitteilungen. I. *Pseudocycas*, eine neue Cycadophytengattung aus den cenomanen Kreideablagerungen Grönlands. *Handl. Kgl. Svensk. Vetensk.-Akad.* **42**:1-11. *pls.* 1-3. 1907.
56. SMITH, FRANCES GRACE, Morphology of the trunk and development of the microsporangium of cycads. *Bot. Gazette* **43**:187-204. *pl.* 10. 1907.
57. THOMAS, ETHEL N., A theory of the double leaf trace founded on seedling structure. *New Phytologist* **6**:77-91. *figs.* 4. 1907.
58. DORETY, HELEN A. (SISTER HELEN ANGELA), The embryo of *Ceratozamia*; a physiological study. *Bot. Gazette* **45**:412-416. *figs.* 7. 1908.
59. ———, The seedling of *Ceratozamia*. *Bot. Gazette* **46**:203-220. *pls.* 12-16. 1908.
60. NATHORST, A. G., Palaeobotanische Mitteilungen. III. *Lycostrobus Scottii*, eine grosse Sporophyllähre aus den rätischen Ablagerungen Schonens. *Handl. Kgl. Svensk. Vetensk.-Akad.* **43**:1-12. *pls.* 1, 2. 1908.
61. SOUTH, F. W., and COMPTON, R. H., On the anatomy of *Dioon edule* Lindl. *New Phytologist* **7**:222-229. 1908.
62. THIESSEN, REINHARDT, The vascular anatomy of the seedling of *Dioon edule*. *Bot. Gazette* **46**:357-380. *pls.* 23-29. 1908.
63. CHAMBERLAIN, CHARLES J., Spermatogenesis in *Dioon edule*. *Bot. Gazette* **47**:215-236. *pls.* 15-18. *figs.* 3. 1909.
64. ———, *Dioon spinulosum*. *Bot. Gazette* **48**:401-413. *figs.* 7. 1909.



65. DORETY, HELEN A. (SISTER HELEN ANGELA), Vascular anatomy of the seedling of *Microcycas calocoma*. Bot. Gazette **47**:139-147. pls. 5, 6. 1909.
66. ———, The extrafascicular cambium of *Ceratozamia*. Bot. Gazette **47**:150-152. pl. 7. 1909.
67. HILL, T. G., and DE FRAINE, E., On the seedling structure of gymnosperms. III. Annals of Botany **23**:433-458. pl. 30. 1909.
68. MATTE, H., Sur la structure de l'embryon et des germinations du genre *Zamia* L. Bull. Soc. Sci. et Med. de l'Ouest **18**: nos. 2 and 3. 1909.
69. SCOTT, D. H., Studies in fossil botany. Second edition. London. 1909.
70. CHAMBERLAIN, CHARLES J., Fertilization and embryogeny of *Dioon edule*. Bot. Gazette **50**:December 1910.
71. SAXTON, W. T., The development of the embryo of *Encephalartos*. Bot. Gazette **49**:13-18. pl. 2. 1910.
72. PAVOLINI, A. F., La *Stangeria paradoxa* Th. Moore. Nuovo Giorn. Bot. Ital. **16**:335-351. 1909.
73. ZACH, FRANZ, Studie über Phagocytose in den Wurzelknöllchen der Cycadeen. Oesterreich. Bot. Zeitschr. **60**:49-55. pl. 2. 1910.
74. SMITH, FRANCES GRACE, Development of the ovulate strobilus and young ovule of *Zamia floridana*. Bot. Gazette **50**:128-141. figs. 22. 1910.
75. COULTER, J. M., BARNES, C. R., and COWLES, H. C., A textbook of botany. New York. 1910.

## CHAPTER IV

### CORDAITALES

The Cordaitales were brought into recognition as a great group of paleozoic gymnosperms by GRAND 'EURY (2) and RENAULT (3). For a long time they were regarded as the dominant gymnosperm group of the Paleozoic, but since the discovery of Cycadofilicales it has become evident that these two gymnosperm groups were equally prominent in Paleozoic times, although the Cordaitales may still be regarded as the prevailing gymnosperm forest type. Side by side the two groups appear in our earliest records, culminated in a great diversity of forms and in an astonishing display of individuals during the Carboniferous, and then disappeared.

The detached parts of Cordaitales were long known from Carboniferous and Devonian deposits, and had received various generic names. For example, the petrified wood was called *Araucarioxylon* (showing a structure resembling that of *Araucaria*) and *Dadoxylon*; casts of the pith cavity were called *Artisia* or *Sternbergia*; the roots were known as *Amyelon*, etc.; shoots bearing the large, parallel-veined leaves were called *Cordaïtes*, and other similar generic names with various prefixes; the catkin-like clusters of strobili formed the genus *Antholithus*; the individual strobili ("flowers") were called *Cordaïanthus*, etc.; and a multitude of seeds constituted such genera as *Cordaïcarpus* (*Cardiocarpus*), *Cycadinocarpus*, etc. The assembling of these fragments was begun when WILLIAMSON (1) found *Sternbergia* casts inclosed in *Araucarioxylon* wood; and it was continued when GRAND 'EURY found the *Antholithus* "inflorescence" in connection with the leaf-bearing shoots of *Cordaïtes*. Finally stems, roots, leaves, strobili, and seeds were brought together and Cordaitales became permanently established through the extended researches of GRAND 'EURY (2) and RENAULT (3). Unfortunately, during the last thirty years little additional information concerning the structure of the group has been obtained. The details of vegetative structure are as clear as those of any group of fossil plants; but the record of

the details of the reproductive structures is a very scanty one for so great a group, and leaves very much to be desired.

### 1. The vegetative organs

The Cordaitales were tall and slender trees, the trunks often reaching a height of 10 to 30 m. before branching (fig. 195). This long



FIG. 195.—*Dorycordaites* sp.: restoration, showing roots, trunk, and crown, the latter composed of branches bearing large lanceolate leaves and clusters of strobili.—From SCOTT's (25) modification of GRAND'EURY's figure; the modification consists principally in shortening the trunk, which is many times longer than represented here.

slender shaft (60 cm. or more in diameter) bore a dense crown of branches, on which were produced a great abundance of large and simple leaves. No such habit is known among existing gymnosperms. SCOTT says (8) that the short-leaved species might suggest *Agathis* or some forms of *Podocarpus*, both coniferous genera of the southern hemisphere; "but the large-leaved species must have had a habit very different from anything which we are accustomed to associate with gymnosperms at the present day." The branching habit, at least, suggests Coniferales rather than any of the cycadophytes; and the same may be said of the simple leaves, but their size is far beyond that attained by the leaves of conifers.

## VASCULAR ANATOMY

A transverse section of the stem of Cordaitales shows a combination of cycad and conifer characters (figs. 196, 197). The relatively large pith, sometimes reaching nearly 10 cm. in diameter, is a cycadean feature, and is peculiar in being discoid; while the thick vascular cylinder is as distinctly coniferous. The cylinder is collateral endarch in the forms originally described, in contrast with the mesarch condition of such a type as *Lyginodendron* (Cycadofilicales); but SCOTT (25) has found occasional centripetal xylem in certain stems. There is no distinction evident in transverse section between primary and secondary wood, but radial sections show a more extensive transition region than usual, from the narrow spiral vessels of the protoxylem to the pitted tracheids that form the bulk of the secondary wood.




FIG. 196.—*Cordaites Sutcliffii*: transverse section of stem; *m*, pith; *x*, xylem; *p*, phloem; *l*, double leaf traces; *c*, cortex; natural size.—From photograph of section made by I.OMAX.

The secondary wood is really indistinguishable from that of *Araucaria* (20, 21), the large proportion of paleozoic wood referred to *Araucarioxylon* and *Dadoxylon* having been found to be that of Cordaitales. Such wood is recognized by the fact that the bordered pits, restricted to the radial walls, are densely crowded in two or more rows (multiseriate), becoming hexagonal in outline. While in general "annual rings" may not be recognizable, in certain specimens the occurrence of such rings is strongly suggested (fig. 197). The medullary rays are narrow, usually one or two cells thick, or the principal rays may become three cells thick.

The leaf traces are usually, perhaps always, double, a feature characteristic of the Cycadofilicales, and plainly seen in *Lyginodendron*, in which form, however, the two strands unite before joining the central cylinder (fig. 198). The collateral endarch leaf trace becomes collateral mesarch in the leaves, a well-known cycadean



combination; and as the bundles approach their terminations in the leaf the centrifugal xylem may "die out" (8), resulting in an exarch bundle. In fact, Miss STOPES (13) states that the exarch bundle is apparently characteristic of the majority of cordaitean leaves. In modern cycads this dying out of centrifugal xylem may occur at

any level in the leaf, so that exarch bundles are not necessarily restricted to vascular terminations.



FIG. 197.—*Cordaites* sp. (?): transverse section of stem; the pith is small and the extensive wood shows rings that resemble growth rings; the structures outside the secondary xylem have not been preserved; natural size.—From photograph of section made by LOMAX.

The vascular anatomy of *Cordaiteales* evidently connects the group, by descent or common origin, with such *Cycadofilicales* as the *Lyginodendrineae*; but this connection is made still more evident by the occurrence of whole series of anastomosing forms (24). One of the most notable of these is *Poroxylon*, whose beautifully preserved anatomical structure has been described in detail by RENAULT and BERTRAND (3, 4). It was originally found in the Permo-Carboniferous of France, a period much too recent to be regarded

as containing members of the phylogenetic series leading to *Cordaiteales*.

The stems of *Poroxylon* are slender (approximately 1.5 cm. in diameter), with a complex branch system, and bear spirally arranged and simple leaves separated by rather long internodes. The pith is relatively large and continuous, and the vascular cylinder is collateral exarch according to BERNARD and RENAULT. Furthermore, the leaf trace is double, the two strands being separate and mesarch to the central cylinder; and they remain collateral mesarch in both cortex and leaf. In *Lyginodendron*, it will be remembered, the collateral strands of the leaf trace become concentric when they enter the

petiole. If the cordaitan leaves of *Poroxylon* (see below) are added to this combination of the vascular anatomy of *Lyginodendron* and *Cordaite*s, there seems to be good ground for regarding *Poroxylon* as one of the Cordaitales with strong *Lyginodendron* affinities; the foliage will hardly permit the converse alternative. Certain stems recently discovered in the Lower Coal-measures of England were referred at first to *Poroxylon* (25), but these, together with certain other stems referred to *Cordaite*s, have been made by SCOTT and MASLEN (27) the basis of the new genus *Mesoxylon*, whose name



FIG. 198.—*Cordaite*s sp.: part of transverse section of stem; *p*, pith; *x*, xylem; *ph*, phloem; *lt*, leaf trace; *c*, cortex;  $\times 6$ .—After SCOTT (25).

suggests its intermediate character. The pith is relatively large and discoïd (as in *Cordaite*s); the leaf traces are double at first, but divide further before entering the leaf; and the leaf traces are mesarch from the first (as in *Poroxylon*). The genus is regarded by its authors "to completely bridge the gap, so far as anatomy is concerned, between the Poroxyleae and the Cordaiteae."

From the Lower Carboniferous of Scotland, SCOTT (9) has obtained evidence of stems that show a connection between Cycadofilicales and Cordaitales even more clearly than does *Poroxylon*, and they have the advantage of being in a far better historical position to play the rôle of actual connecting forms. The group of stems considered

is usually referred to Cordaitales, but they differ from other known stems of Cordaitales in certain important features. *Pitys* is known as yet only from its pith and wood, the latter being araucarian (and therefore cordaitan) in type, but with remarkably broad medullary rays. The principal feature, however, is the occurrence of numerous small mesarch strands which are imbedded in the pith at some distance from the cylinder of wood, and which must represent the primary xylem. The araucarian cylinder of secondary wood and the mesarch primary cylinder is a combination of features belonging to Cordaitales and *Lyginodendron*. *Dadoxylon Spencersi*, probably from the Upper Carboniferous, also has mesarch primary wood, cordaitan secondary wood, and double leaf traces. SCOTT (9) says that this stem "suggests, perhaps more strongly than any of the other species described, a truly gymnospermous stem, which may well have belonged to one of the Cordaitae, but which still retains the last relics of the primary wood structure characteristic of the Poroxyleae and Lyginodendreae." He is of the opinion (25) that *Pitys* and *Dadoxylon* probably belong to a plexus of forms connecting Cycadofilicales of the *Lyginodendron* type with *Cordaites*, but nearer to the latter. Therefore, he proposes to recognize Cordaitales as including the three groups Poroxyleae, Pityeae, and Cordaitae, in which there are all gradations from primary wood that is distinctly mesarch to that which is completely endarch. In our terminology these three names would be Poroxyleae, Pityneae, and Cordaitineae.

#### THE LEAF

The leaves are borne in spiral succession on ultimate branches. They are usually simple, elongated, with parallel and repeatedly dichotomous venation (except in the grasslike forms). Naturally they were first thought to be the leaves of monocotyledons. They occur sometimes in dense masses, packed together in layers "like damp beech leaves on the ground of our forests" (5).

There is considerable diversity of form, which has been made the basis for generic distinctions. For example, the leaves of *Cordaites* are spatulate with blunt ends (fig. 199), reaching a meter in length and about 15 cm. in width; those of *Dorycordaites* are lanceolate and sharp pointed (fig. 195), and little inferior in length; those of *Poacor-*



*daites* are grasslike, not over half a meter long and about a centimeter wide. In still other cases, the leaves are said to be comparatively



FIG. 199.—*Cordaites laevis*: restoration of branch with spatulate leaves and branches bearing numerous strobili; a large bud is shown at the right.—After GRAND 'EURY (2).

short and obovate, even branching dichotomously, a type suggestive of the leaves of *Ginkgo*.

The recorded anatomy of the leaves has all been obtained from *Cordaites*, and is very characteristic (figs. 200–202). Each of the




conspicuous parallel vascular bundles is invested by a strong sheath which abuts above and below on a hypodermal strand of fibers. These bundle sheaths connect laterally by transverse "bridles"

of thickened cells, which may represent a "transfusion tissue."

In some cases the hypodermal ribs occur only in connection with the bundles; while in other cases they are developed between the bundles. The mesophyll in some leaves is differentiated into palisade and spongy regions, and in others it is very little differentiated.

There is really greater variation in the leaves of *Cordaitales* than is usually appreciated (16), and, as in the case of the anatomy of the stem, they suggest possible connections in various directions, namely, with *Cycadofilicales* on the one hand, and *Coniferales* and *Ginkgoales* on the other.



FIGS. 200-202.—*Cordaites*: transverse sections of leaves; fig. 200, *C. angulostriatus* (?); *r*, ribs of sclerenchyma; *m*, mesophyll; *o*, centrifugal xylem; *i*, centripetal xylem; *x*, protoxylem; *p*, phloem; *b*, bundle sheath; *c*, elongated cells connecting bundles;  $\times 60$ ; fig. 201, *C. rhombinervis*, showing sclerenchyma ribs only in connection with bundles;  $\times 50$ ; fig. 202, *C. lingulatus*, showing well-developed palisade tissue;  $\times 50$ .—After RENAULT (3).

The leaves of *Poroxydon* are of the same general type. They are spirally borne on rather widely separated nodes of a slender stem, and are simple, broad, thick, and petioled, with parallel veins repeatedly dichotomous. The blade is stiffened by hypodermal strands

of fibers on both sides; the large bundles are connected by transverse bridges of thick-walled cells; and the mesophyll is compact. Such a form and structure is entirely unlike anything known among ferns or Cycadofilicales, and certainly approximates that of the leaves of *Cordaites*. SCOTT (8) says that such a leaf organization is comparable to a single leaflet of such a cycad as *Bowenia*.

#### THE ROOT

*Amyelon radicans* is a root of the Coal-measures known to belong to *Cordaites*, and often preserved in remarkable detail (fig. 203). It bears irregularly arranged bunches of lateral roots, which have been examined recently by OSBORN (26). The thick cortex is



FIG. 203.—*Amyelon*, the root of *Cordaites*: *p*, tetrarch primary xylem; *x*, secondary xylem showing growth rings; *ph*, phloem; *d*, periderm;  $\times 9$ .—From photomicrograph of section made by LOMAX.

divisible into two regions, the inner of which contains dark cells that show fungal hyphae. The conclusion is reached that "*Cordaites* was probably a tree inhabiting saline swamps, and having bunches of coralline rootlets on its roots, such as are known to occur in many recent plants growing under similar conditions." As only one case

of mycorrhiza had been reported previously from the Coal-measures, this observation is one of special interest.

## 2. The spore-producing members

### THE STROBILI

The small strobili, not often more than a centimeter in length, are borne laterally upon short, simple or branched, lateral shoots




FIG. 204.—*Cordaites*: portion of stem showing one leaf and four branches, each branch bearing numerous strobili;  $\times \frac{2}{3}$ .—After GRAND 'EURY (2).

(fig. 204). These strobilus-bearing branches suggest inflorescences; and although occurring among the leaves, they do not always seem to be axillary. These structures were recorded under the general name *Antholithus* until GRAND 'EURY found *Antholithus* in connection with the leaf-bearing shoots of *Cordaites*. Since many of the strobili cannot be referred with certainty as yet to the definite species of Cordaitales, the form genus *Cordaianthus* has been used to record most of them. Our knowledge of the internal structure of *Cordaianthus* has

come chiefly from the few sections made by RENAULT (3). Both kinds of strobili are sheathed by bracts, so that it is not always possible to distinguish them externally.

### THE MICROSPORANGIUM

In *Cordaianthus Penjonii* (fig. 205) the staminate strobilus (1 cm. long) consists of a thick axis bearing spirally arranged bracts, among which stamens are inserted. The stamens are either solitary or are grouped near the apex of the axis. Each stamen consists of a more or less elongated stalk bearing at its tip a cluster of three to six erect sporangia (fig. 206). The wall of the sporangium is a single layer



of cells, and the dehiscence is longitudinal. The stalk is traversed by a single vascular strand which sends a branch to the base of each sporangium. There is no evidence that the stamens arise from the axils of bracts, but the two structures seem to replace each other; in fact, the stamen stalk is very little modified from the bract form. In *Cordaianthus Saportanus* the stamens are fewer in number, being restricted to the apical region of the strobilus, and the stalks are shorter.

It is evident that this strobilus is to be interpreted as a mixture of sterile and fertile microsporophylls. If the sterile sporophylls were suppressed, the general condition of the staminate strobilus of *Ginkgo* would be attained, but the sporangia of that form are borne differently. This interpretation implies that the staminate strobilus of Cordaitales is a simple one, and that the stamen stalk is a filament. The suggestion that each stamen is a "flower," and that therefore the stamen stalk is a branch (pedicel), is an attempt to interpret this strobilus by the staminate strobilus of Gnetales or by certain types of angiosperm inflorescence, an attempt which singularly disregards the sequence of evolution.

The terminal and erect microsporangia of Cordaitales were



FIG. 205.—*Cordaianthus Penjonii*: longitudinal section of staminate strobilus, showing microsporangia borne on long stalks; throughout the sporangium region, but especially below it, are numerous sterile bracts;  $\times 10$ .—After RENAULT (3).



regarded as a unique feature among gymnosperms until the terminal and erect microsporangia of Cycadofilicales were discovered. The *Calymmatotheca* type of stamen bears a terminal and erect synangium, in which the sporangia occur in various degrees of "coalescence."

If such sporangia should fail to organize a synangium and should remain separate, such a stamen as that of Cordaitales would be the result.



FIG. 206.—*Cordaianthus Penjonii*: section showing three stamens with their sporangia; the stamen in the middle bears four sporangia, the one farthest to the right having dehiscent;  $\times 23$ .—After RENAULT (3).

#### THE MEGASPORANGIUM

The young ovulate strobilus can scarcely be distinguished from the staminate, the ovules at that stage being completely hidden by the overlapping bracts. RENAULT'S description (3) of *Cordaianthus Williamsonii* will illustrate the structure of the strobilus (fig. 207). Upon a thick conical axis conspicuous bracts are inserted in spiral succession, and in some of their axils there arises a very short dwarf branch which bears some small bractlets and a terminal ovule.

The ovule (fig. 208) has two integuments, the outer one being described as thick and fleshy, the inner one delicate but later becoming hard. The two integuments are free from one another below, but are more or less united above. They may correspond to the outer fleshy and stony layers of the single integument of cycads and *Ginkgo*. There is nothing to indicate the presence of an inner fleshy layer. The nucellus is nearly distinct from the integument, and develops a prominent beak which contains a large pollen chamber. A single vascular strand enters the chalaza and sends out two systems of branches, one into the outer integument, and the other into the peripheral region of the nucellus. The freedom of integument and nucellus, and the occurrence of the inner set of vascular strands in the nucellus, are the striking features of the *Stephanospermum* type of seed, as

described by OLIVER (14), and probably represent a more primitive condition of the ovule than that of the *Lagenostoma* type. As stated under Cycadofilicales, both types probably occurred in both Cycadofilicales and Cordaitales; but as yet only the *Lagenostoma* type is known to belong to the former group, and only the *Stephanospermum* type has been associated with the latter group.

In *Cordaianthus Grand'Euryi* (fig. 209) the bractlets borne by the short ovuliferous shoot are much larger, and a very prominent and resistant nucellar beak projects into the micropyle and forms a passageway to the large pollen chamber. The cells of the lower part of this beak are transversely elongated, narrowing the passageway.

The ovulate strobilus evidently differs from the staminate in being compound; that is, a branch arises from the axis of the strobilus to bear the ovule. This character is distinct from any tendency shown by the strobili of the cycadophytes, and is evidently one that is continued in those groups of Coniferales

(especially Abietineae) in which the "ovuliferous scale" is believed to represent a reduced axillary shoot. RENAULT suggests a more distant resemblance to *Taxus*, in which genus, as well as in *Torreya*, the terminal ovules are borne on short foliage-bearing shoots. In this comparison, however, while the ovuliferous branches are evidently similar, the compact strobilus of Cordaitales is lost in the branching of *Taxus* and *Torreya*.




FIG. 207.—*Cordaianthus Williamsonii*: longitudinal section of strobilus, showing numerous sterile bracts and two ovules;  $\times 10$ . —After RENAULT (3).

When the numerous detached paleozoic seeds were grouped as radiosperms and platysperms (12, 14), it was supposed that the latter, at least, belonged to the Cordaitales, because such as had been definitely referred to the group were of the more or less flattened type. However, since the discovery that certain of the Cycadofilicales, as *Aneimites* and *Pecopteris Pluckenetii*, bore seeds of the platysperm type, it is evident that the reference of any seed to Cycadofilicales or Cordaitales must await the discovery of its actual connection. As a result, many detached seeds, heretofore referred with considerable confidence to Cordaitales, are now in uncertainty; but out of the vast numbers found, many of them must have belonged to this group. GRAND'EURY (17) has called attention to the fact that there are many more seed genera that probably belong to Cordaitales than there are shoot genera (*Cordaites*, etc.) to receive them.




FIG. 208.—*Cordaianthus Williamsonii*: longitudinal section of ovule, showing upper portion of nucellus, lower portion of nucellus free from the integument, cavity which doubtless contained the female gametophyte, outer integument, inner integument free from the outer integument below but more or less applied to it above, bract, and secondary axis bearing ovule;  $\times 35$ .—After RENAULT (3).

Among those that seem most certain are those somewhat flattened seeds with heart-shaped base that have been included by RENAULT in the genus *Cordaicarpus* (*Cardiocarpus* of BRONGNIART). The testa, derived from a single integument, is differentiated into outer fleshy and stony layers. There are two sets of vascular strands: one traversing the outer fleshy layer; the other forming a tracheal plate at the base of the relatively free nucellus, which gives rise to a tracheal mantle in the peripheral region of the nucellus, similar to that in *Stephanospermum*, but not so complete (14). The usual nucellar beak is very prominent and projects into the micropyle. The whole structure agrees so closely with that of the ovules described

above, under *Cordaianthus Williamsonii*, that there can be no reasonable doubt that the seeds belong to Cordaitales. *Cycadinocarpus* of RENAULT is interesting from the fact that the inner set of vascular strands does not enter the nucellus, but is said to traverse the inner layer of the testa, which in this case must be the third or "inner fleshy" layer. This distribution of the vascular strands is the same as in the seeds of Cycadales.

The seeds known as *Rhabdocarpus*, formerly supposed to be forms of *Cordaicarpus* (*Cardiocarpus*) and therefore belonging to *Cordaites*, have been found by GRAND 'EURY (16) associated with leaves believed to be those of *Poroxylon*. If this connection is confirmed, the inclusion of *Poroxylon* among the Cordaitales would seem to have passed the doubtful stage.

Since the investigation of the testa of the seeds of cycads by Miss STOPES (15), in which it was made clear that the testa is differentiated into three layers (outer fleshy, stony, and inner fleshy), the temptation

is to read this structure into the interpretations of the seeds of Cordaitales and Cycadofilicales, and there seems to be enough confirmation of such an interpretation to justify it in some cases. It is conceivable that the inner fleshy layer, which in cycads contains the inner set of vascular strands, might be confused with the peripheral region of the nucellus, provided the testa and nucellus are organically continuous, as in modern seeds. In such cases the inner fleshy layer would be distinct only in the free part of the integument, and since in the testa stage it becomes merely a papery layer, it might not be recognizable




FIG. 209.—*Cordaianthus Grand 'Euryi*: section of beak of nucellus; wedged in the passageway are two large pollen grains, the lower one showing part of the surface of the exine and also the multicellular interior;  $\times 225$ .—After RENAULT (3).



in a fossil. Such confusion of inner fleshy layer and nucellus in many paleozoic seeds, however, in which the testa and nucellus are free, seems impossible. In an ovule of this character, the inner set of vascular strands could not make the very evident connections with the region of the pollen chamber without traversing the nucellus. In such cases, therefore, it is by no means inconceivable that the inner fleshy layer of the testa was not represented.

In whatever character the seeds of Cordaitales differ in structure from modern seeds, these peculiarities are shared by Cycadofilicales; and this association is further emphasized by the entire absence of any trace of an embryo in any of the sectioned paleozoic seeds (p. 46).

### 3. The gametophytes

Pollen grains of the Cordaitales have been found in the sporangia, in the pollen chambers, and in the passageways ("necks") leading to them (figs. 206, 209). The grains are comparatively large, and with a rough outer coat; and they are said to be larger in the pollen chambers than in the sporangia, indicating growth after pollination. The striking feature, however, is the presence of a group of internal cells (fig. 209), which are said to be more numerous after pollination than before. Such a cell plexus has been observed in the pollen grains of Cycadofilicales, and was discussed in that connection (p. 49). It seems to be a safe inference that several, if not all, of these cells were spermatogenous, and that swimming sperms were liberated when the archegonial and pollen chambers had become continuous by the breaking down of the intervening tissue, as in *Ginkgo* and the cycads. SCOTT (18) has called attention to the interesting fact that in 1896 RENAULT (6) suggested this possibility, before the announcement of the discovery of swimming sperms in *Cycas* and *Ginkgo*. No traces of pollen tubes have been observed in any of the paleozoic seeds, although pollen grains have been found in the pollen chamber after it had extended entirely through the nucellus to the megaspore membrane, bringing the pollen grains into direct contact with the female gametophyte. It is very probable that the sperms were discharged from the pollen grains about as from the microspores of modern heterosporous pteridophytes.

In pollen grains found in the pollen chambers of ovules not defi-

nitely referred as yet to either Cordaitales or Cycadofilicales, similar groups of internal cells have been found, as in *Stephanospermum* (p. 50), indicating that the male gametophyte among paleozoic seed plants must have been more primitive in structure, in the amount of either prothallial or spermatogenous tissue or both, than in living seed plants. It is interesting to note, in this connection, that an excess of male prothallial tissue, as compared with the other living gymnosperms, has been found among the podocarps and araucarians.




FIG. 210.—*Cycadinocarpus angustodunensis*: longitudinal section of upper part of ovule; *mi*, micropyle; *int*, integument; *pc*, pollen chamber with pollen grains; *nu*, nucellus; *ar*, archegonia; *pr*, female gametophyte.—After RENAULT (2).

In some of the sections of the seeds of Cordaitales, the mature embryo sac, containing the female gametophyte (endosperm) with its archegonia, has been found, as in a species of *Cycadinocarpus* (fig. 210). In the figure cited it is evident that the endosperm has encroached upon the nucellus almost to the testa, and that it has developed a characteristic endosperm beak which supports the settling nucellar beak, as in *Ginkgo*, in which form HIRASÉ aptly likens the endosperm beak to a "tent pole." Two archegonia are evident in the section, and opened into the archegonial chamber which surrounded the base of the "tent pole" like a moat. This peculiar endosperm beak is one of the several characters that show a close connection between Cordaitales and Ginkgoales.

Perhaps the most important testimony furnished by such sections as the one just described is as to the condition of detached paleozoic seeds. It is evident that when these seeds had formed a heavy testa and had dropped from the parent plant, there had been no such embryo-formation as takes place in modern gymnosperm seeds before shedding. It may be that fertilization had occurred, and that the proembryo had formed within the archegonium; but it is certain that there had been no further development of the embryo. The absence of embryos from paleozoic seeds, therefore, might be due to the fact that they had not formed when the seed was shed; and therefore the change in later times was a longer retention of the seed before shedding, accompanied by a later maturing of the testa; but more probably the seeds sectioned had dropped prematurely (see p. 47 for a fuller discussion).

#### 4. History and distribution

The Cordaitales were contemporaneous with the Cycadofilicales, disappearing from the records in the Devonian, along with the Cycadofilicales, occurring in great profusion during the Carboniferous, and not recognizable beyond the Paleozoic. So far as the historical records go, therefore, the Cordaitales are just as ancient seed plants as are the Cycadofilicales. It is only upon inference from comparative resemblance to ferns that a greater age is assumed for the Cycadofilicales.

The geographical distribution of Cordaitales, also, must have been as extensive as that of Cycadofilicales; and they probably formed extensive forests in connection with the arboreous pteridophytes. Their known distribution during the Carboniferous is only limited by our knowledge of the deposits of that period. They must have displayed a profusion of forms and structures that is meagerly shown by their known remains. It is not unreasonable to suppose that a fuller knowledge of their structure and variations will go far toward settling the problems connected with the origin of the later coniferophytes.

#### 5. Relationship to other gymnosperms

The question of the origin of Cordaitales is a choice between two alternatives. They were either derived from the Cycadofilicales,

or the two groups had a common origin from a still more ancient group of fernlike plants. The historical evidence favors the latter alternative, for the two groups are distinct as far back as the record goes; but it must be remembered that this is negative evidence. On the other hand, although both groups are certainly extremely ancient, their similarities suggest so close a relationship, confirmed by the existence of series of anastomosing forms, that the other alternative is worthy of consideration.

On the whole, the structure of the seed is the most striking character common to Cordaitales and Cycadofilicales. It is no longer possible to distinguish their seeds. The free nucellus and integument that characterized certain seeds of both groups, the distribution of the two sets of vascular strands, the large pollen chamber, the absence of any visible embryo, are all characters that may be regarded as primitive and as indicating a close relationship of the two groups. As an alternative, it may be assumed that these resemblances do not indicate a phylogenetic connection of the groups so much as they do an early stage of seeds in general, and such seeds may have originated independently many times from the original fern stock. This claim can be met only by comparing the other structures of the two groups, to discover whether there is any indication of more progress in one than in the other, progress that would indicate that they are not at the same level of primitiveness.

The organization of strobili represents a distinct advance beyond the condition of Cycadofilicales, and it is the same kind of modification as that suggested in the case of the Bennettitales (p. 87). It consists in the complete differentiation of sporophylls and foliage leaves, the consequent reduction in size of the sporophylls, and their aggregation into a strobilus by shortening the fertile axis. The association of bracts and sporophylls in the strobilus would be natural, some of the bracts (chiefly the outer ones) doubtless representing reduced foliage leaves, and some of them (notably the inner ones) being sterile sporophylls. A notable complication in the ovulate strobilus of Cordaitales is the fact that the primary axis of the strobilus bears only bracts, the ovules appearing on short secondary axes (a compound strobilus).

It is in the vegetative structures that there appears a distinct gradation from Cycadofilicales toward Cordaitales. It has been seen



that the permo-carboniferous *Poroxylon* illustrates what must be regarded as a stage theoretically intermediate between the two groups. The general habit and the leaves are those of Cordaitales in all the essential features. In the vascular cylinder of the stem, the secondary wood is that of Cordaitales, but the primary xylem is mesarch as in *Lyginodendron*. The leaf traces of *Poroxylon*, leaving the central cylinder in pairs and finally becoming exarch in the leaves, are common to both Cycadofilicales (notably in *Medullosa*) and Cordaitales. *Poroxylon* is too recent to serve any phylogenetic purpose except to illustrate an intermediate stage that has persisted. It will be remembered, however, that almost identical forms have been discovered (18) in the Lower Coal-measures of England; and similar forms of still greater age have been recognized. In fact, among the araucarioxylons (presumably the wood of Cordaitales) of the early Carboniferous there occur stems with mesarch primary xylem; and SCOTT (9, 10) has arranged a series of such stems connecting the *Lyginodendron* type with the *Cordaite* type, some of which cannot be referred to either group without the foliage.

In view of the great antiquity of Cordaitales and Cycadofilicales, it is perhaps safer to conclude that the similarities and gradations described above are such as might be expected in two phyla diverging from a common stock and living under the same conditions. Whether this common stock is to be regarded as still more ancient Cycadofilicales or not, is a question that probably never will be answered. In any event, it seems clear that the Cycadofilicales, as we know them, retained more of the features of this ancient stock than did the Cordaitales; and that long after the Cordaitales became distinct, there began to arise from the Cycadofilicales two divergent branches, the Bennettitales and the Cycadales. At about the same time, the great phylum Coniferales probably began to emerge from the Cordaitales, and perhaps also the less conspicuous phylum Ginkgoales.

It will be useful to summarize the important resemblances of Cordaitales to the living groups Cycadales, Coniferales, and Ginkgoales, in order that their significance may be pointed out. This is especially necessary since there is a tendency to use similar characters at random as indicating immediate relationship. For example, the characters common to Cordaitales and Cycadales seem to include those of higher

order than those common to Cordaitales and Coniferales; and yet the latter pair are regarded as much more closely related than the former pair.

The characters in common with the Cycadales are the large pith, the internal structure and mesarch bundles of the leaves, the general structure of ovule and seed, and the swimming sperms. An inspection of these characters shows that they are primitive, and that they may be interpreted as characters which both groups have retained from some common and very distant ancestry. In other words, these characters are just such as might have been retained by divergent lines.

The characters in common with Coniferales are the lofty and branching habit, the character of the vascular cylinder, and especially the structure of the ovulate strobilus. These characters are distinctly not primitive, and suggest at once that the Cordaitales are intermediate between the Coniferales and the more primitive seed plants.

The characters in common with the Ginkgoales are those shared in general by the Coniferales, except the structure of the ovule and seed, and the swimming sperms, which are also cycadean characters. The suggested conclusion is that Cordaitales also connect the Ginkgoales with the more primitive seed plants, and that the reproductive structures of the Cordaitales were retained by the Ginkgoales.

#### LITERATURE CITED

1. WILLIAMSON, W. C., On the structure and affinities of the plants hitherto known as Sternbergiae. *Mem. Manchester Lit. and Phil. Soc.* **14**: 340-358. *pls.* 10. 1851.
2. GRAND'EURY, C., La flore carbonifère du Département de la Loire. *Mém. Acad. Sci.* **24**<sup>1</sup>: pp. 624. *pls.* 38. 1877.
3. RENAULT, B., Structure comparée de quelques tiges de la flore carbonifère. *Nouv. Arch. Mus. Hist. Nat.* **II**. **2**: 213-348. *pls.* 8. 1879.
4. BERTRAND, C. E., et RENAULT, B., Recherches sur les Poroxyloons. *Archiv. Bot. Nord. France* **3**: pp. 147. *figs.* 79. 1886.
5. SOLMS-LAUBACH, H., Fossil botany. English translation. 1891.
6. RENAULT, B., Bassin houiller et Permien d'Autun et d'Épinac. **IV**. Flore fossile. pp. 557. 1896.
7. SCOTT, D. H., On the primary wood of certain araucarioxylons. *Annals of Botany* **13**: 615-619. 1899.
8. ———, Studies in fossil botany. 1900.

9. SCOTT, D. H., Primary structure of certain paleozoic stems. Trans. Roy. Soc. Edinburgh **40**<sup>2</sup>:331-365. pls. 1-6. figs. 5. 1902.
10. ———, The old wood and the new. New Phytologist **1**:25-30. 1902.
11. WORSDELL, W. C., The evolution of the vascular tissue of plants. Bot. Gazette **34**:216-223. figs. 7. 1902.
12. OLIVER, F. W., The ovules of the older gymnosperms. Annals of Botany **17**:451-476. pl. 24. figs. 20. 1903.
13. STOPES, MARIE C., On the leaf structure of *Cordaites*. New Phytologist **2**:91-98. pl. 9. 1903.
14. OLIVER, F. W., On the structure and affinities of *Stephanospermum* Brongniart, a genus of fossil gymnosperm seeds. Trans. Linn. Soc. London Bot. II. **6**:361-400. pls. 41-44. 1904.
15. STOPES, MARIE C., Beiträge zur Kenntniss der Fortpflanzungsorgane der Cycadeen. Flora **93**:435-482. figs. 37. 1904.
16. GRAND'EURY, C., Sur les *Rhabdocarpus*, les graines et l'évolution des Cordaitées. Compt. Rend. Acad. Sci. Paris **140**:995-998. 1905.
17. ———, Sur les graines de *Sphenopteris*, sur l'attribution des *Codonospermum*, et sur l'extrême variété des graines des fougères. Compt. Rend. Acad. Sci. Paris **141**:812-815. 1905.
18. SCOTT, D. H., The early history of seed-bearing plants, as recorded in the carboniferous flora (The Wilde Lecture). Mem. and Proc. Manchester Lit. and Phil. Soc. **49**<sup>3</sup>: pp. 32. pls. 3. 1905.
19. OLIVER, F. W., "The origin of gymnosperms"; a discussion at the Linnean Society. New Phytologist **5**:68-76, 141-148. 1906.
20. SCOTT, D. H., "The origin of gymnosperms"; a discussion at the Linnean Society. New Phytologist **5**:68-76, 141-148. 1906.
21. SEWARD, A. C., "The origin of gymnosperms"; a discussion at the Linnean Society. New Phytologist **5**:68-76, 141-148. 1906.
22. WEISS, F. E., "The origin of gymnosperms"; a discussion at the Linnean Society. New Phytologist **5**:68-76, 141-148. 1906.
23. SCOTT, D. H., The present position of paleozoic botany. Progressus rei botanicae (ed. J. P. LOTSY) **1**<sup>1</sup>:139-217. figs. 37. 1906.
24. ———, The paleontological record. II. Plants. Darwin and modern science, pp. 200-222. Cambridge University Press. 1909.
25. ———, Studies in fossil botany. Second edition. Vol. II. London. 1909.
26. OSBORN, T. G. B., The lateral roots of *Amyelon radicans* Will., and their mycorrhiza. Annals of Botany **23**:603-611. pls. 46, 47. 1909.
27. SCOTT, D. H., and MASLEN, A. J., On *Mesoxylon*, a new genus of Cordaitales (preliminary note). Annals of Botany **24**:236-239. 1910.

## CHAPTER V

### GINKGOALES

*Ginkgo biloba* is the only living representative of a gymnosperm phylum that was well represented during the Mesozoic. It is almost unknown in the wild state, the only reports of its occurrence having come from travelers in the forest regions of western and southwestern China (28). Its extensive cultivation, however, first in China and Japan, and later in Europe and in the United States, has made it very accessible. It was long included among the Taxaceae as an exceptional member, and only since 1897 has it been set apart as representing a group coordinate with Coniferales and Cycadales, and all subsequent morphological investigation has confirmed this position. The appropriate but antedated name *Salisburia adiantifolia* has sometimes been used for the plant, and now and then an additional species or two have been segregated, but the generic name *Ginkgo* must be accepted, and the segregates have had little recognition.

#### 1. The vegetative organs

The tree has the general habit of a conifer, with central shaft and wide-spreading branches (fig. 211), and attains a height of more than 30 m., with a diameter exceeding 1.5 m. The deciduous foliage leaves are very characteristic in form and venation, and are so suggestive of the leaves of *Adiantum* that the common name "maiden-hair tree" seems appropriate. The petiole is long and slender, the blade is broadly wedge-shaped and variously lobed, and the venation is conspicuously dichotomous (fig. 212).

The branches are dimorphic; one kind being long shoots that elongate rapidly and bear scattered leaves; the other being the numerous dwarf shoots that elongate very slowly and bear few leaves in a cluster. The dwarf shoot elongates slightly each year, bearing a terminal group of leaves, and the older portion is covered with leaf scars of previous years. After several years a dwarf shoot may become a long shoot, bearing scattered leaves; and then it may resume the slow growth of the dwarf shoot again; and in some cases it may branch (28).





FIG. 211.—*Ginkgo biloba*: ovulate tree in the botanical garden of the Imperial University at Tokyo, Japan; the first "spermatozoids" discovered in gymnosperms were found by HIRASÉ in material taken from this tree.—From photograph by MIYAKE.

## VASCULAR ANATOMY

The transverse section of the stem of *Ginkgo* shows the general features of Coniferales, namely, a comparatively narrow cortical zone, a thick and compact cylinder of secondary wood developed by a persistent primary cambium (in contrast with Cycadales), and a relatively small pith (in contrast with Cordaitales). In the dwarf shoots, however, the pith is large and the zone of wood comparatively narrow. The primary xylem is endarch, and there is no distinct




FIG. 212.—*Ginkgo biloba*: leaf showing bilobed character and dichotomous venation; slightly enlarged.—After COULTER (54).

mesarch structure except in the bundles of the cotyledons (20) (fig. 213). The leaf trace is double, as in all the more primitive gymnosperms, each of the strands forking at the base of the blade, and the resulting four strands breaking up into the characteristic dichotomous system of veins, which may show now and then slight traces of centripetal wood, and therefore an indistinct mesarch structure.

The vascular anatomy of the seedling has been reviewed by HILL and DE FRAINE (51), whose summary contains the facts that *Ginkgo* differs from the cycads in the rotation of the protoxylem of the cotyledonary traces; that a single vascular strand enters the base of each

cotyledon; that the bundles pass from mesarch to exarch while traversing the cotyledons; that each cotyledonary bundle gives rise to two protoxylem poles of the root; and that there may be an addition of protoxylem elements after the root structure has been organized.

The cycadean type of seedling is described (42) as consisting of four bundles at the base of each cotyledon and a tetrarch root, which generally becomes diarch below. Miss THOMAS (48) has proved




FIG. 213.—*Ginkgo biloba*: transverse section of cotyledon showing mesarch character of vascular bundle; *p*, protoxylem; *x*, metaxylem; *t*, "transfusion tissue";  $\times 150$ .—After SPRECHER (46).

this cycadean type for the *Ginkgo* seedling by showing that the apparently single bundle that enters the cotyledon is really a plexus of four bundles, separating into two double bundles in the petiole, and each of these separating into its two constituent bundles in the blade. It is in the cotyledons that a very distinct mesarch structure is developed (20). The relation of the number of protoxylem poles in the root to the number of cotyledons (12, 39), that is, a diarch root related to two cotyledons and a triarch root to three, is true only in an indirect way. The original root is tetrarch, and is related to the four cotyledonary strands from the transition region, and the diarch condition

observed is a reduction from the tetrarch condition. In the case of three cotyledons, which sometimes occurs in *Ginkgo*, the vascular situation is modified, so that the root is ultimately triarch.

The testimony of the vascular anatomy shows that *Ginkgo* has departed farther from the primitive fern stock in this regard than have the Cycadales and the Cordaitales, only the foliar gaps and the mesarch bundles of the cotyledons remaining to indicate the connection in vascular structure (36).

#### THE LEAF

There is great variation in the size and in the lobing of the leaves of *Ginkgo*. The blades are often deeply cut and with more than two lobes, and the same tree may show every gradation between deeply



FIG. 214.—*Baiera gracilis*: leaf showing bilobed character, but each of the two principal lobes repeatedly dichotomous; regarded as a transition between *Baiera* and *Ginkgo*; natural size.—After RENAULT (9a).

lobed leaves and those with nearly entire margins. The leaves of mesozoic species were much more divided, extreme forms being palmately dissected into numerous very narrow lobes (28) (fig. 214). In the surviving genus *Ginkgo*, the lobed condition is always found in the leaves of seedlings (fig. 215), and usually on the long shoots, leaves from the top of a tree being particularly deeply cleft. The leaves on the dwarf shoots are usually nearly entire, but when the bud of a dwarf shoot develops into a long shoot, the lobed character of



the leaf is suddenly resumed, the contrast between the entire leaves of the dwarf shoot and the lobed leaves of the new long shoot being



FIG. 215.—*Ginkgo biloba*: seedlings showing deeply bilobed leaves; the seed and cotyledons have not yet fallen off.

quite marked (fig. 216). The deep lobing is a juvenile character, and by many would be regarded as an illustration of recapitulation.

During development the blade is bent over at the apex and the margins are strongly inrolled (8). The young leaves develop abundant hairs, especially on the petiole; and the hairs are numerous on the scale leaves, forming a distinct woolly fringe to the petiole (28). The deciduous habit is a very rare one among gymnosperms, being shared with *Ginkgo* only by the coniferous genera *Larix*, *Taxodium*, and *Glyptostrobus*.

In anatomical structure the leaves of *Ginkgo* resemble in general those of Cycadales.

There is an evident but not very thick cuticle; the stomata are mostly restricted to the abaxial surface, the guard cells being somewhat below the level of the epidermis; there is a distinct palisade tissue in the larger leaves, but not in the leaves of the dwarf branches; and between the veins the very loose inner mesophyll cells are elongated parallel with the plane of the leaf surface.

## 2. The spore-producing members

The strobili of *Ginkgo* are not only monosporangiate, but the plants are also dioecious, as in the Cycadales. Neither kind of strobilus is bracteate, as is usual among gymnosperms; and the ovulate strobilus has given rise to much discussion.

## THE MICROSPORANGIUM

The staminate strobili consist of numerous microsporophylls rising in loose catkin-like clusters from the axils of the scale leaves developed at the summit of the dwarf shoot (figs. 216, 217). Comparing this strobilus with the staminate strobilus of Cordaitales, it



FIGS. 216, 217.—*Ginkgo biloba*: fig. 216, branch with dwarf shoots bearing staminate strobili and leaves; about natural size; fig. 217, single staminate strobilus, showing character of individual stamens (a stalk ending in a knob and bearing two pendent sporangia);  $\times 3.5$ .—After COULTER (54).

is evident that if the intermixed sterile sporophylls and bracts of the latter were eliminated, the general structure of the former would be obtained.

The strobili are first evident during the early summer of the year preceding the maturing of the pollen (53), but are hidden in buds that cannot be distinguished from leaf buds. The development of the sporophylls is in acropetal succession, and the older sporangia reach

the mother cell stage before winter (47). Material collected during April (in Ohio) by Miss STARR (53) showed some sporangia in the mother cell stage and others with tetrads.

The mature sporophyll has a rather long stalk, which terminates in a knoblike enlargement, beneath one side of which usually two pendent sporangia are borne. In material grown in the United States there are often three or four sporangia; and SPRECHER (47) cites cases of stamens with as many as seven sporangia. Occasional

abnormalities occur which show even greater variation from the usual form (fig. 218). The more or less expanded knob at the tip of the stalk may be regarded as representing a reduced lamina bearing sporangia pendent from its abaxial surface. The development of this knob has been studied by Miss STARR (53), to discover whether it gives such evidence of abortive sporangia as




FIG. 218.—*Ginkgo biloba*: dwarf shoot bearing normal strobili (d), normal leaves (h), and leaves with microsporangia (g).—After FUJII (17).

had been found in *Torreya* (40). The large mucilage cavities begin to develop like sporangia, and for some time there is a close resemblance to sporogenous tissue, but finally the walls disintegrate and a mucilage cavity is the result (fig. 221). The fact that the stamen of *Ginkgo* sometimes bears more than two sporangia, and that certain fossil forms bear more than two regularly, strengthens the view that the mucilage ducts of the knob have replaced abortive sporogenous tissue. At the same time, it is recognized that the mucilage ducts elsewhere in *Ginkgo*, as in the leaves, pass through the same developmental stages.

Such a stamen suggests the *Crossothea* ("epaulet") type among

Cycadofilicales. The known stamens of Cordaitales are different (p. 172), but it cannot be supposed that the stamens of so great a group were uniform in type.

In fact, in *Antholithus Zeilleri*, which is regarded as the staminate strobilus of *Baiera* (a mesozoic member of Ginkgoales), the sporangium-bearing structures are dichotomously divided, dorsiventral organs, the ultimate divisions of which bore eight sporangia (49). This structure seems to be widely different from the stamen of *Ginkgo*, so much so as to raise the question whether this *Antholithus* belongs to *Baiera*, and hence to the Ginkgoales; but if the sporangia are terminal, the parallel is found in the known stamens of Cordaitales. If the sporangia are abaxial on the ultimate branches, rather than terminal, the reduction to a single branch would represent the stamen of *Ginkgo*. In either



FIGS. 219-221.—*Ginkgo biloba*: fig. 219, young staminate strobilus in September, showing microsporophylls with sporogenous tissue and mucilage ducts;  $\times 20$ ; fig. 220, young sporangium; the four cells in which nuclei are shown have come doubtless from a single archesporial cell; the two inner cells are sporogenous and the two outer tapetal;  $\times 485$ ; fig. 221, a rather late stage in the formation of a mucilage duct in the hump; the sporogenous-like cells are breaking down and the surrounding cells resemble a tapetum;  $\times 485$ .—After Miss STARR (53).



event, the structure emphasizes the interrelationships of Ginkgoales, Cordaitales, and Cycadofilicales.

The development of the microsporangium has been described by Miss STARR (53). Early in July the strobili which are to mature their pollen the following year can be recognized as small papillae in the axils of bracts, and before winter checks the growth the oldest sporangia at the base of the strobilus reach the mother cell stage (fig. 219). Although the earliest stage was not seen, it was evident that a single hypodermal cell divides anticlinally and then periclinal divisions follow, or the order is reversed. The outer cells produce the wall of four to seven layers, and the inner cells a large group of sporogenous cells (fig. 220). The tapetum seems to be formed entirely from the peripheral cells of the sporogenous group. In the mature sporangium the hypodermal layer of cells (outermost wall layer) and the layer beneath it develop thickening bands in the walls, and in the upper part of the sporangium, near the mucilage cavity, the walls of deeper cells are also thickened. *Ginkgo* seems to be the only gymnosperm that develops an endothecium (32), in the sense that the layer or layers of cells that show the structure and function of an endothecium are hypodermal. The longitudinal slits of dehiscence of the two sporangia face one another, and lie at such an angle that the pollen is shed easily (32).

#### THE MEGASPORANGIUM

The ovulate strobili of *Ginkgo* are very much reduced, and are borne in groups at the summit of the dwarf shoot (fig. 222). The individual strobilus consists of a long stalk arising from the axil of a bract and bearing at its apex mostly two ovules, one of which usually aborts, although in favorable seasons it is by no means uncommon to find both ovules fully developed (fig. 223). Occasionally more than two ovules appear, and the indications are that the strobilus of *Ginkgo* has been derived from one bearing several or perhaps many ovules (fig. 224).

About the base of the ovule there is a more or less conspicuous cup or "collar," much more prominent in the young stages of the ovule. This collar has been a prolific source of discussion, and a brief résumé of the views as to its nature and the nature of the strobilus

will serve to illustrate the progress of interpretation, and especially will show the result of attempting to read the structures of a higher group into those of a more primitive one.

In 1869 VAN TIEGHEM (2) interpreted the stalk as a petiole; the two ovules as determined by the two characteristic lobes of the blade; the collar as a reduced aril; and hence the whole structure as a single megasporophyll (carpel). In 1872 STRASBURGER (4) suggested that the stalk is a shoot; that the collar is the rudiment of the first pair of leaves of a secondary shoot; and hence that the whole



FIG. 222.—*Ginkgo biloba*: dwarf shoots with ovulate strobili; the leaves have been cut away from the shoot at the right; the female gametophyte in such ovules is in a very early free nuclear stage;  $\times 1.5$ .—After COULTER (54).

structure is an inflorescence of two flowers in which the carpel is suppressed. In 1879 he modified (6) this view in so far as to conclude that the collar represents an aril. In 1873 EICHLER (5) interpreted the collar as the outer integument of the ovule, which view is not necessarily inconsistent with the preceding views that it stands for an aril; later (10) he called the collar a rudimentary carpel. In 1890 ČELAKOVSKÝ (11) stated that the stalk is an axillary shoot bearing two or more carpels, but that each carpel is represented only by an ovule, which means that the existence of the carpel is only theoretical; later (25) he reaffirmed these views with greater fulness of detail. In 1896 FUJII (17), after a study of abundant Japanese

material, and especially taking into account numerous abnormal cases, came to the conclusion that the stalk is a shoot usually bearing two rudimentary carpels (megasporophylls) which are represented



FIG. 223.—*Ginkgo biloba*: part of a long branch bearing dwarf branches with ovulate strobili.—After COULTER (54).

by the two collars. The abnormal cases may be summed up as follows: ovules on more or less modified foliage leaves; intergrades from normal collars to blades bearing ovules; distinctly stalked ovules; stalks

bearing several ovules and terminating in a scaly bud (fig. 225). In 1900 SEWARD and GOWAN (28) reviewed the whole situation, studied additional abnormalities, and coincided with the conclusions of FUJII. And now SHAW (50), investigating the vascular anatomy of the strobilus, dissents from the current view that the collar is a much reduced megasporophyll. It seems that the bundles of the collar show inverse orientation, and a comparison with *Lagenostoma* suggests that the collar of *Ginkgo* is a vestige of the cupule that invested seeds of the *Lagenostoma* type. This claim for the cupule nature of the collar is most interesting, and if it is the true one, it even more strongly emphasizes the close connection of Ginkgoales and Cycadofilicales.

The evidence at present suggests that the structure under discussion is a strobilus bearing two or more megasporophylls, which are usually reduced to the so-called "collars," but which sometimes resume their original leaflike character. These abnormal ovuliferous leaves are most suggestive of the ovuliferous

leaves of the Cycadofilicales, and hence of the origin of the ovulate strobilus of *Ginkgo*. While the stalk of the strobilus resembles the petiole of a leaf, it is quite different in its structure. A transverse section of a petiole shows the two bundles already mentioned as representing the double leaf trace; while a transverse section of the stalk of a strobilus shows the four bundles which would be expected in a stem bearing two leaves (collars) at its apex (figs. 226, 227). When more than two ovules are borne on one stalk, there are twice as many bundles in the stalk as there are ovules at its apex, just as there should be if each collar were a mega-



FIG. 224.—*Ginkgo biloba*: axis bearing seven ovules, each with a pedicel.—After SPRECHER (47).



sporophyll. The evidence from "abnormalities," which may be interpreted as reversions, together with the testimony of the vascular



FIG. 225.—*Ginkgo biloba*: abnormalities in ovulate structure; *a*, bud; *b*, nearly normal strobilus; *c*, leaf with irregular thickenings; *d*, leaves bearing ovules; *f*, thickening at base of ovule; *g*, longitudinal striation along the fleshy part of the seed.—After FUJII (17).

anatomy, strongly support the view that the stalk is a stem bearing two megasporophylls (collars), each of which bears a single ovule.

The development of the ovule has been investigated by Miss CAROTHERS (46), from material grown in northern Ohio. About the first of April no ovules are visible in the buds on the dwarf shoots,



FIG. 226.—*Ginkgo biloba*: transverse section of leaf, showing two bundles.—After SPRECHER (47).





FIG. 227.—*Ginkgo biloba*: transverse section of the stalk of ovulate strobilus, showing the general structure of a stem.—After SPRECHER (47).

but two weeks later they are 0.25 mm. long, the nucellus being homogeneous and not wholly inclosed by the integument (fig. 228). Not all the buds of the dwarf shoots are fertile, and the strobili in those that are range in number from one to six. In such a bud the sequence of structures from outside inward is as follows: brown bud scales, green scale leaves, foliage leaves, strobili, foliage leaves. About



FIGS. 228-230.—*Ginkgo biloba*: early stages in the development of the ovule; fig. 228, nucellus in April, not yet covered by integument; no archesporium can be distinguished at this stage;  $\times 15$ ; fig. 229, condition May 1;  $\times 12$ ; fig. 230, May 1, megaspore mother cell surrounded by "spongy tissue";  $\times 325$ .—After Miss CAROTHERS (46).

the first of May the ovules are 0.75 mm. long; the prominent nucellar beak has developed, in some cases protruding from the micropyle; a large pollen chamber has been formed, which often contains pollen grains developing tubes; and the sporogenous tissue is in all stages from immature mother cells to complete tetrads. According to HIRASÉ (22), the pollen chamber results from the exclusive growth of the external tissue of the beak, the inner tissue thus becoming ruptured and disorganized.

Usually one mother cell functions, two functioning mother cells

being found in only one ovule out of fifty at this stage. The derivation of the mother cell from a hypodermal archesporial cell could not be traced. It is recognizable in the midst of the so-called "spongy tissue," which may or may not be sporogenous in origin (figs. 229, 230). PAX (13) evidently regarded this tissue as representing a many-celled archesporium; but whatever its morphological nature, its tapetal function is clear. In the mature mother cell there appears the peculiar "kinoplasmic mass" observed in the mother cells of *Taxus*, *Larix*, *Taxodium*, *Thuja*, and certain other genera. The reduced number of chromosomes is eight; and although a linear tetrad is usual, one case of bilateral arrangement was observed, and two cases in which the upper cell of a row of three had divided longitudinally.

The history of the tapetal zone is as follows. During tetrad-formation, this glandular-looking tissue increases in bulk by cell division, encroaching actively upon the surrounding nucellar tissue until the last week of June. The absorbing cells soon become vacuolate and finally multinucleate (fig. 231). The megaspore membrane surrounding the gametophyte now shows the characteristics of its mature condition, although it has not reached its maximum thickness. After June, the tapetal zone in turn begins to be destroyed by the encroachment of the young gametophyte (endosperm), which at this time is still in the free nuclear stage, but the distinct membrane about it has been formed. By the time the centripetal growth of the gametophyte is about one-third of the distance across the embryo sac, all of the tapetal zone has been crushed. It is evident that this zone of cells is one that digests and absorbs, performing the "tapetal function" for the mother cell and the early stages of the gametophyte.





FIG. 231.—*Ginkgo biloba*: multinucleate stage of spongy tissue; bordering upon the spongy tissue at the left is the conspicuous megaspore membrane, and just beyond are three of the free nuclei of the endosperm;  $\times 650$ .—After Miss CAROTHERS (46).



The single thick integument, forming a long and narrow micropylar tube, is at first homogeneous, but by the last of May three distinct layers have become differentiated. The outermost layer is a tissue of large, thin-walled cells with numerous mucilage cavities, and finally becomes the fleshy layer of the mature testa. The middle layer consists of small isodiametric cells, and later forms the stony layer of the testa. The innermost layer consists of large, loosely



FIGS. 232, 233.—*Ginkgo biloba*: diagrams of ovules showing the stony layer (*s*) between the outer (*o*) and inner (*i*) fleshy layers, and the collar (*c*); fig. 232, after the stony layer has become hard, but before the inner fleshy layer has become dry; the inner fleshy layer and the nucellus are shaded with lines; fig. 233, after the inner fleshy layer and nucellus have become dry and papery;  $\times 2$ .

arranged, very thin-walled cells, which in the free portion of the integument are differentiated into two regions: the inner consisting of vertically elongated cells, a tissue restricted to the free portion of the integument; the outer consisting of transversely elongated cells, a tissue that extends the whole length of the ovule just within the stony layer. This inner tissue is at first delicate and watery, but soon becomes crushed and dry, forming in the mature testa a papery layer lining the stone and adherent to it (figs. 232, 233). This general structure of the testa is practically cycadean (p. 128). It has come to

be the habit to refer to these three layers as "outer fleshy," "stony," and "inner fleshy."

At the base of the ovule, two vascular strands enter the inner fleshy layer on opposite sides, through a gap in the stony layer, and continue along the surface of the layer, ending where the integument becomes free. One of the characteristic features of the *Ginkgo* testa is the suppression of one of the two sets of vascular strands characteristic of the more primitive gymnosperms. In this case the outer one, which traverses the outer fleshy layer, has been suppressed.

### 3. The gametophytes

#### THE FEMALE GAMETOPHYTE

The development of the female gametophyte (endosperm) has also been investigated by Miss CAROTHERS (46). As the functioning megaspore enlarges, a large vacuole holds its nucleus near the micropylar end. Since the megaspore, after its nucleus begins to divide, is always vacuolate, the free nuclei are parietal from the beginning. About the middle of May there are 16 to 64 free nuclei, well separated in the very delicate cytoplasmic lining of the thin wall of the embryo sac. Up to this stage (64-nucleate) the free nuclear divisions are simultaneous, but later they become irregular, continuing until the first of July, when there are over 256 nuclei. During this period the ovule and the embryo sac are enlarging, and the megaspore membrane is becoming thicker.

Preliminary to wall-formation, a delicate membrane appears on the outer surface of the protoplast of the embryo sac, which is easily separable from the megaspore membrane, and may be called the endosperm membrane. To this endosperm membrane (not to the megaspore membrane, as has been supposed) the first walls of the endosperm are anchored, being laid down at right angles to it, and leaving the cells open toward the sac cavity (fig. 234). After the first walls are formed, centripetal growth of the endosperm begins, the innermost cells, open toward the center of the sac, always being larger than the outer ones and usually uninucleate, although they are sometimes binucleate and even trinucleate. In the tissue which has reached nearly to the center of the sac binucleate cells are common,

and occasionally a multinucleate cell is observed; but in mature endosperm tissue the cells are uninucleate. Whether this is due to disorganization or fusion of nuclei, or to additional wall-formation, was not determined. Centripetal growth of the endosperm is rapid through July and August, the sac being filled with tissue by the last week of August. In the closure of the tissue at the center of the sac, there is no formation of a common wall, but two distinct abutting walls are formed, so that even in the ripe seed the tissue of the endosperm separates easily at the center by a cleavage plane.




FIG. 234.—*Ginkgo biloba*: walls of endosperm cells in contact with the endosperm membrane, and not extending to the megaspore membrane; June 5;  $\times 650$ .—After Miss CAROTHERS (46).

As the centripetal development proceeds, the whole gametophyte increases in bulk, the inner cells enlarging greatly and occasionally dividing, and those of the peripheral region multiplying. Soon after the appearance of walls and long before the sac is filled with tissue, the endosperm becomes green; and in a few weeks it is the greenest region of the ovule, the spectroscope showing the presence of chlorophyll. The cells are early filled with starch, some of it doubtless formed by the green gametophyte itself. Outside of the gametophyte starch is abundant only in the outer region of the integument. The endosperm in its growth encroaches upon the nucellar

tissues until it destroys not only the previously active tapetal zone, but also most of the undifferentiated nucellar tissue, whose living cells are separated from it by a mass of the dead cells of the tapetal zone. It is probably this zone of crushed cells that has been interpreted as a "tapetum" in certain fossil seeds (p. 37), but whether it was previously active as a tapetum in such cases cannot be determined.

When the endosperm has reached its full development, the endosperm membrane has become much thickened, and the megaspore membrane has become extremely thick and dense. As the endosperm

is entirely free from the megaspore membrane, the latter is pushed outward by the development of tissue about the archegonial chamber, forming a roof over it. The megaspore membrane becomes differentiated into two layers, the inner one being very thin and serving as a base for the transversely placed "rods" of the outer layer, as already noted in the cycads (p. 139). When the endosperm tissue has become closed at the center of the sac, the megaspore membrane has reached a thickness of over  $6\ \mu$ . According to THOMSON (41, 43), the structure of the membrane is very similar to that of the Cycadales, but the inner layer is not so thick. His general conclusion is that *Ginkgo* is farther removed from the fern level in this regard than are the Cycadales, and less so than are the Coniferales, in which the megaspore membrane is variable in thickness and simpler in structure.

The archegonium initials, usually two in number (figs. 242, 243), but occasionally three, appear very early in the history of the gametophyte, the two-celled neck and a considerably enlarged central cell appearing before the tissue lining the embryo sac is equal in depth to the breadth of the central cavity. The development of the archegonium is exactly similar to that in the Cycadales, including the organization of the conspicuous nutritive layer of jacket cells. At the beginning of August (in Japan), when the tube nucleus is passing back into the pollen grain end of the tube, as described by HIRASÉ (22), the endosperm begins to develop a beak between the two archegonia. In about two weeks this beak resembles a small column, with its summit against the settling nucellar beak, "like a tent supported by its center pole." This endosperm beak much enlarges and modifies the archegonial chamber described above. Just before fertilization, early in September (in Japan), the small and ephemeral ventral canal cell is cut off, and the egg is matured (fig. 244). In this respect *Ginkgo* is more primitive than the cycads, in which no wall is formed between the ventral canal nucleus and that of the egg. IKENO (30) reports that in one instance he observed a ventral canal nucleus that had enlarged *pari passu* with the egg nucleus, whose maturation resembles that described under *Pinus Laricio* (p. 266). HIRASÉ states that about twenty weeks elapse between pollination and fertilization.



## THE MALE GAMETOPHYTE

The first account of the male gametophyte of *Ginkgo* is that given by STRASBURGER (15) in 1892. It is of interest to note that HOFMEISTER in 1863 (1) predicted the finding of swimming sperms in the pollen tubes of gymnosperms; and in May 1896, at a meeting of the Botanical Society of Tokyo, HIRASÉ announced (18) the discovery of ciliated sperms, his preliminary paper (19) appearing in October of the same year, and his full paper (22) in 1898. In this connection a detailed study was made of the development of the male gametophyte and of the phenomena connected with fertilization; and it is chiefly from this source that the following account is drawn.


The first division of the microspore is unequal, resulting in cutting off a small lenticular cell, which soon disorganizes and later appears like a cleft in the heavy spore wall. No such ephemeral vegetative cell has been discovered among the Cycadales, but such cells are characteristic of the Abietineae.

A second unequal division occurs, and a second small cell is cut off, which persists, and which is a second vegetative cell. This cell also appears among the Abietineae, but in them it is ephemeral like the first. A single persistent vegetative cell also appears in the Cycadales; so that *Ginkgo* resembles the Abietineae in having two vegetative cells, and the Cycadales in having one persistent cell.

After the two vegetative cells have been cut off, the remaining large cell may be regarded as the antheridium initial, although the ordinary structure of a multicellular antheridium has disappeared. This cell divides equally, the smaller daughter cell, in contact with the persistent vegetative cell, being the generative cell, and the larger cell being the tube cell (fig. 235). The gametophyte is in this four-celled stage (ephemeral vegetative, persistent vegetative, generative, and tube cells) when pollination takes place (fig. 236), during the last of April or early in May (in Japan).

The pollen chamber now begins to enlarge at the expense of the nucellar tissue at the side and beneath, carrying the grains deep into the nucellus. Early in June the chamber has enlarged greatly, forming a large irregular cavity, which extends nearly to the embryo sac. When the grains begin to put out their tubes, the opening to the pollen chamber becomes closed and remains so, the surrounding tissue

becoming brown and forming a resistant beak that long persists as a cap on the sac. The pollen grains, carried well below the beak by the deepening of the chamber, send out their tubes in every direction into the adjacent nucellar tissue, but chiefly away from the embryo



FIGS. 235-240.—*Ginkgo biloba*: the male gametophyte; fig. 235, pollen grain, showing evanescent prothallial cell and persistent prothallial cell; the mitosis in the antheridium initial will form the generative and tube cells; April 24;  $\times 500$ ; fig. 236, pollen at the shedding stage, with prothallial, generative, and tube cells;  $\times 500$ ; fig. 237, part of pollen tube July 10;  $\times 500$ ; fig. 238, the nucleus of the generative cell has divided, the stalk and tube nuclei lying side by side; July 11;  $\times 500$ ; fig. 239, the body cell has divided; blepharoplasts are faintly visible;  $\times 120$ ; fig. 240, the two sperms produced by the body cell; September 11;  $\times 226$ .—After HIRASÉ (16).

sac, and often directly toward the beak. Into these young tubes the tube nuclei pass, and remain there so long as the tube system is developing.

About the beginning of July, the tubes have penetrated the nucellar tissue deeply and have branched freely, the tube nucleus remaining where a tube begins to branch. This extensive system of branching

tubes, as in cycads, seems to function only as a haustorial system. At this stage the generative cell has the appearance of being pushed away from contact with the persistent vegetative cell, on account of the enlargement and development of vacuoles in the latter. The generative cell increases very much in size, its nucleus keeping pace with it; and these relative positions are maintained until just before fertilization, which occurs about ten weeks later. About the middle of July the generative nucleus divides to form the stalk and body nuclei, lying side by side and with no separating wall (figs. 237, 238).




FIG. 241.—*Ginkgo biloba*: upper part of female gametophyte, showing two archegonia, the beaklike process of the endosperm, and the swollen tips of two pollen tubes; September 9;  $\times 24$ .—After HIRASÉ (16).

HIRASÉ says that the non-functioning stalk nucleus is gradually thrust out of the general cytoplasm by the growth of the functioning body nucleus and the organization of the body cell, and functions no further (see fig. 163). At the end of July, the much enlarged body cell is rich in contents, and its nucleus is very large. At this stage the two blepharoplasts appear and assume their polar positions, the

stage persisting for three weeks, that is, until the third week before fertilization.

At the beginning of August the tube nucleus begins to pass back to the pollen grain end of the tube, which it reaches in about two weeks, consorting with the body cell, and later with the sperms, until fertilization. During the return of the tube nucleus, the endosperm beak has developed between the two archegonia as described above, pushing up the megaspore membrane farther, and permitting the grain end of the pollen tube to penetrate to the region of the archegonial chamber, where, freed from pressure, it becomes very turgid (fig. 241).

During the third week before fertilization (about the last of August) the body cell begins to divide, the division occurring in the axial plane of the spore, resulting in two sperm mother cells lying side by side and each containing a blepharoplast (fig. 239). In each mother cell the

blepharoplast becomes bandlike, is attached to the nucleus, and forms the spiral, cilia-bearing band of two and a half coils in connection with the sperms. The details of the structure and behavior of the blepharoplast among Cycadales have been presented (p. 142), and presumably they are approximately the same for the blepharoplast of *Ginkgo*. The mature sperms are ovoid, varying between 80 and 110  $\mu$  in length, and between 50 and 85  $\mu$  in breadth, and are so directed that the two adjacent sperms lie base to base (fig. 240).

It is a little over four months from pollination to the formation of sperms, the time of which varies with the latitude. For example, in Tokyo sperms appear between September 7 and 22, the greatest number occurring September 17 and 18; in Sendai, 200 miles farther north, the optimum date is September 27; in Washington the range of time is from August 25 to September 10, with September 1 to 3 as the optimum period (29).

In 1898 several Japanese students investigated a large number of sperms, correcting a few of the earlier statements and extending the observations. HIRASÉ had described a peculiar "tail," which FUJII (21) and MIYAKE (23) showed to be an appearance that had no connection with the sperm. HIRASÉ had left the impression also that the mother cells were transformed directly into sperms; but FUJII and MIYAKE demonstrated that the sperms are formed within a sperm mother cell, and they observed the cilia vibrating and the sperm shifting its position within the mother cell. The sperms finally break through the wall of the mother cell and escape into the pollen tube, where they were observed "swimming from one end of the tube to the other like a pair of large infusoria." They were observed in active motion for two or three hours, the body readily changing its form under pressure. FUJII (26) observed also a sperm with two spiral bands, its sister sperm being normal; it is probable that the blepharoplast had divided before band-formation.

#### FERTILIZATION

The swollen tip (grain end) of the pollen tube, capped by the old wall of the pollen grain, contains two sperms, the tube nucleus, the persistent vegetative cell, and whatever may remain of the stalk nucleus. At the time of fertilization, the turgid tip of the tube becomes



curved, its apex being directed toward the archegonial chamber, and discharges its contents. The sperms have been observed swimming in the archegonial chamber, from which one of them passes to the egg and enters its cytoplasm. IKENO (30) states that the male nucleus slips from its cytoplasmic and cilia-bearing sheath upon entering the cytoplasm of the egg. At the time of fusion the two nuclei are very unequal, the female nucleus being about ten times larger than the male. The mode of fusion is said to be like that described by IKENO for *Cycas revoluta*; that is, the sperm nucleus gradually penetrates the egg nucleus before losing its own membrane. It has been determined that fertilization occurs while the ovules are still on the tree (30).

#### 4. The embryo

The embryo of *Ginkgo* has long been regarded as peculiar among gymnosperms, chiefly on account of the absence of a conspicuously elongated suspensor, such as occurs in Cycadales and Coniferales. The only suggested resemblance is the embryo of Bennettitales, in which no suspensor has been seen. ARNOLDI (34) recognized a differentiation of the elongating proembryo into three regions: a micropylar haustorial region, a middle suspensor region, and an apical region which gives rise to the embryo proper. This interpretation conforms in general to the three regions found in other gymnosperm embryos.


Another peculiarity of the embryo of *Ginkgo* that has been remarked is the complete filling of the egg with proembryonic tissue, but this peculiarity has held only in comparison with the Coniferales, *Dioon* and perhaps other cycads having the same character.

In 1904 LYON (39) published an account of the embryogeny of *Ginkgo*, and the following description is largely based upon his results as confirmed by our own preparations. The first spindle is very broad and multipolar (30), and a series of simultaneous, free nuclear divisions follows, until the nuclei approximate 256 in number (fig. 245). The nuclei do not become parietally placed by the vacuolation of the cytoplasm, but are distributed more or less uniformly throughout the enlarging egg. At this stage wall-formation occurs, and the egg is filled by a proembryo consisting of undifferentiated tissue (fig. 246).


The cells of the micropylar two-thirds of the proembryo divide very little or not at all, but the cells of the antipodal one-third form a




242




243



244



245



246

FIGS. 242-246.—*Ginkgo biloba*: archegonium and embryogeny; fig. 242, longitudinal section of the neck of the archegonium, showing the two cells;  $\times 160$ ; fig. 243, transverse section of the same;  $\times 160$ ; fig. 244, archegonium shortly before fertilization, showing ventral canal cell (*v*) and egg nucleus (*n*);  $\times 66$ ; fig. 245, free nuclear stage of the proembryo;  $\times 66$ ; fig. 246, later stage, showing that the tissue of the proembryo has resulted from a segmentation of the entire egg;  $\times 66$ .—After STRASBURGER (4).

small-celled meristem which grows vigorously (fig. 247). This growing region invades the endosperm as a broad, blunt cylinder, the micropylar end of the proembryo being forced back through the


neck of the archegonium, many of its cells being crushed. In the axis of the advancing cylinder two growing points are soon established, that of the stem at the end of the axis, and that of the root very close



FIG. 247.—*Ginkgo biloba*: late stage of proembryo; the stem and root will be organized from the small-celled tissue at the apex;  $\times 160$ .—After LYON (39).

to it, the two being separated by very few cells. Later the primordia of the two cotyledons appear in the peripheral region of the cylinder, beginning as crescentic mounds of tissue. From an examination of mature seeds, LYON (39) claims that the proembryo sometimes gives rise to two embryos.

This embryogeny is remarkable for the extensive development and massive growth of the proembryonic tissue, but in kind it resembles



FIGS. 248-251.—*Ginkgo biloba*: later stages in the development of the embryo; fig. 248 shows the upper part of the endosperm and the outline of the embryo;  $\times 10$ ; fig. 249, drawn on a larger scale from the same embryo, shows the differentiation into root and stem;  $\times 40$ ; fig. 250, embryo at about the stage shown in fig. 233;  $\times 15$ ; fig. 251, nearly mature embryo;  $\times 10$ .



that of other gymnosperms, and particularly that of *Dioon edule*, in which there is a temporary segmentation of the entire egg. There is an extensive region of abandoned proembryonic tissue, abandoned in the sense that it does not enter into the structure of the embryo; a suspensor development, which in this case is very massive; and at the tip of the suspensor region the organization of an embryo (figs. 248, 249).

Usually there are two cotyledons, but three are by no means uncommon. In all the Japanese material investigated by LYON two cotyledons were present except in two cases; while 15 per cent of the material from another source showed three cotyledons; and we have noted that material from northern Ohio sometimes shows three cotyledons. The cotyledons are normally equal and entire, springing apart when liberated from the seed. The former accounts of unequal and lobed cotyledons, united at the tip, seem to have been drawn from unusual material. The cotyledons are hypogean, as in the cycads, but they produce stomata, chiefly on the adaxial surface. From this Miss WIGGLESWORTH (38) concludes that the cotyledons are true foliage leaves that have become hypogean.

Polyembryony occurs occasionally, LYON often finding two developing embryos; but one of them usually became centrally placed and the other became abortive; in only one case were two mature embryos seen; in one seed three developing embryos were found. COOK (35) examined 200 seeds (from trees cultivated in Washington), and found four of them containing twin embryos about one-third as long as normal embryos; twenty-four of the seeds contained no embryos.

In germination the plumule is thrust out of the testa by the petiole-like elongation and arching of the bases of the cotyledons, the portions of the cotyledons that remain within the seed enlarging and functioning as haustorial organs, persisting through the first season. The first two or three leaves are small and scalelike, without any development of the characteristic blades (fig. 215). The stem soon stops its rapid elongation for the season and puts forth at the apex a rather close crown of leaves, a large terminal bud being the only prominent one on the plant during the first winter.

### 5. History and distribution

The leaves of *Ginkgo* are so characteristic that they are an unusually trustworthy evidence of the existence of the group during previous periods. Such leaves are found in abundance down to the Coal-measures, and some of them at least must have belonged to Ginkgoales, though some of them may have belonged to other groups. In fact, SEWARD (28) is inclined to think that all of the so-called Ginkgoales of the Paleozoic are Cordaitales. The genus *Whittleseya* from the Lower Carboniferous, distinguished by its short petioles, seems to be connected with *Ginkgo* itself by *Ginkgodium*, a recently described genus from the Lower Oolite of Japan (52).

The most important fossil leaf genus referred to Ginkgoales is the mesozoic *Baiera*, which differs from the leaves of *Ginkgo* in the shortness of the petiole and the repeatedly and deeply dichotomous blades (fig. 214), resulting in narrow, ribbon-like, greatly elongated lobes (14). Such characters are not constant, for even in the existing *Ginkgo* the blade is quite variable (p. 189). Of great interest are the paleozoic leaves referred to *Ginkgo* and *Baiera*, which occur especially in the Permian. In reference to these, the general conclusion seems to be that they cannot be disentangled from the foliage of certain species of Cordaitales and of Cycadofilicales, and perhaps of Filicales. In any event, the evidence is convincing that Ginkgoales were abundant and somewhat diversified during the Mesozoic, their greatest extension occurring during the Jurassic; and it is altogether probable that they existed near the close of the Paleozoic, associated with the Cordaitales and Cycadofilicales. The testimony of the mesozoic leaves is confirmed by the discovery of staminate strobili, ovulate strobili, and seeds. In a staminate strobilus (*Antholithus Zeilleri*) recently described by NATHORST (49) and associated with *Baiera*, the microsporophylls are very different in character from those of *Ginkgo* (p. 193), but this need not exclude the strobilus from Ginkgoales. "On the whole, the sum of fossil evidence is of sufficient weight to prove the great antiquity of the gymnospermous family now represented by the maidenhair tree" (27), a group distinctly foreshadowed in paleozoic vegetation.

Our chief knowledge of the diversity and wide distribution of Ginkgoales during the Mesozoic has come from the investigations of

HEER (7, 9). Jurassic remains of the group have been found in every country, from the arctic regions to the south temperate regions, being abundant in England, throughout Europe, Siberia, China, Japan, North America, and Australia (37). The prominent genera were *Ginkgo* and *Baiera*, the former becoming more abundant in the more recent periods and in the more northern latitudes; the latter including the majority of the older representatives of the group.

## 6. Relationship to other gymnosperms

From the previous account it is evident that the question as to the origin of Ginkgoales is a choice between two alternatives: either they were derived from the Cordaitales, or the two groups became differentiated from a common stock. The historical evidence is all in favor of the former view, and the testimony of the comparative structures of the two groups seems equally convincing. The mesozoic Ginkgoales seem to hold the same relation to the paleozoic Cordaitales that the mesozoic Bennettitales hold to the paleozoic Cycadofilicales. In fact, the connections between the former pair seem closer and more definite than those between the latter pair. Just as the whole cycadophyte phylum retained characters of seed structure and swimming sperms that belonged to the ancient Cycadofilicales, so the Ginkgoales have retained the primitive characters of the Cordaitales. Of course one may imagine a primitive plexus of fernlike seed plants, related in some way to the Botryopterideae, which differentiated at various times into Cycadofilicales, Cordaitales, Ginkgoales, and perhaps other gymnosperm phyla (47), but however true this may be of the contemporaneous Cycadofilicales and Cordaitales, the historical as well as the morphological relation of Ginkgoales to Cordaitales indicates a more immediate connection between these two groups. SCOTT (52) expresses the opinion that *Ginkgo* is "the one surviving member of an ancient stock, derived from the same cycle of affinity as the paleozoic Cordaitae, once the dominant type of gymnosperms."

Among living gymnosperms, *Ginkgo* is to be compared with cycads and conifers. In the structure of the ovule and the seed, and in the details of fertilization, the resemblance is to the cycads; while in habit, stem structure, and vascular anatomy, the resemblance is to conifers. There has recently been a tendency to discover connections

between *Ginkgo* and the Taxaceae (44, 47), in which family *Ginkgo* was placed by the earlier taxonomists as an aberrant member; a connection that will be discussed under Coniferales. The characters in common with the cycads are primitive, shared with Cycadofilicales and Cordaitales; while the characters in common with the conifers are distinctly advanced. At the same time, the foliage and the structure of the strobili are peculiar to *Ginkgo*. This combination of peculiar characters with others belonging to Cycadales and Coniferales justifies the separation of Ginkgoales as a coordinate group; and the nature of the characters justifies the conclusion that Ginkgoales represent a phylum that has retained certain primitive features in common with the cycadophytes, has advanced more in the direction of the Coniferales, and has developed certain peculiarities of its own.

## LITERATURE CITED

1. HOFMEISTER, W., On the germination, development, and fructification of the higher Cryptogamia. English translation. London. 1863.
2. VAN TIEGHEM, PH., Anatomie comparée de la fleur femelle et du fruit des Cycadées, des Conifères, et des Gnetacées. Ann. Sci. Nat. Bot. V. 10:269-304. pls. 13-16. 1869.
3. ———, Recherches sur le symétrie de structure des plantes vasculaires. Ann. Sci. Nat. Bot. V. 13:1-314. pls. 3-8. 1870.
4. STRASBURGER, E., Die Coniferen und die Gnetaceen. 1872.
5. EICHLER, A. W., Sind die Coniferen gymnosperm oder nicht? Flora 56: 241-247, 260-272. 1873.
6. STRASBURGER, E., Die Angiospermen und die Gymnospermen. 1879.
7. HEER, O., Zur Geschichte der *Ginkgo*-artigen Bäume. ENGLER'S Bot. Jahrb. 1:1-13. 1880.
8. FANKHAUSER, J., Entwicklung des Stengels und Blattes von *Ginkgo*. Bern. 1882.
9. HEER, O., Flora fossilis arctica. 1868-1883.
- 9a. RENAULT, Cours de botanique fossile. Paris. 1880-1884.
10. EICHLER, A. W., Coniferae in ENGLER und PRANTL'S Natürlichen Pflanzenfamilien 2<sup>1</sup>:108. 1889.
11. ČELAKOVSKÝ, L., Die Gymnospermen; eine morphologisch-phylogenetische Studie. Abhandl. Königl. Böhm. Gessell. Wiss. VII. 4:1-148. 1890.
12. DANGEARD, P. A., La mode d'union de la tige et de la racine chez les Gymnosperms. Compt. Rend. Acad. Sci. Paris 110:253, 254. 1890.
13. PAX, F., Allgemeine Morphologie der Pflanzen mit besonderer Berücksichtigung der Blütenmorphologie. 1890.
14. SOLMS-LAUBACH, H., Fossil botany. English translation. 1891.



15. STRASBURGER, E., Ueber das Verhalten des Pollens und die Befruchtungsvorgänge bei den Gymnospermen. 1892.
16. HIRASÉ, S., Études sur la fécondation et l'embryogénie du *Ginkgo biloba*. Jour. Coll. Sci. Imp. Univ. Tokyo 8:307-322. pls. 31, 32. 1895.
17. FUJII, K., On the different views hitherto proposed regarding the morphology of the flowers of *Ginkgo biloba*. Bot. Mag. Tokyo 10:115-25, 104-110. pl. 1. 1896.
18. HIRASÉ, S., (Announcement of the spermatozoid of *Ginkgo*). Bot. Mag. Tokyo 10:171, 172. May 1896. (Japanese)
19. ———, (Preliminary report on the spermatozoid of *Ginkgo*). Bot. Mag. Tokyo 10:325-328. Oct. 1896. (Japanese)
20. WORSDELL, W. C., On transfusion tissue; its origin and function in the leaves of gymnospermous plants. Trans. Linn. Soc. Bot. II. 5:301-319. pls. 23-26. 1897.
21. FUJII, K., (Has the spermatozoid of *Ginkgo* a tail or not?) Bot. Mag. Tokyo 12:287-290. 1898. (Japanese)
22. HIRASÉ, S., Études sur la fécondation et l'embryogénie du *Ginkgo biloba*. Jour. Coll. Sci. Imp. Univ. Tokyo 12:103-149. pls. 7-9. 1898.
23. MIYAKE, K., (On the spermatozoid of *Ginkgo*). Bot. Mag. Tokyo 12:33-39. 1898. (Japanese)
24. FUJII, K., (On the morphology of the spermatozoid of *Ginkgo*). Bot. Mag. Tokyo 13:260-266. pl. 7. 1899. (Japanese)
25. ČELAKOVSKÝ, L., Die Vermehrung der Sporangien von *Ginkgo biloba* L. Oesterreich. Bot. Zeitschr. 50:229-237, 276-283, 337-341. 1900.
26. FUJII, K., (Account of a sperm with two spiral bands). Bot. Mag. Tokyo 14:16, 17. Jan. 1900. (Japanese)
27. SCOTT, D. H., Studies in fossil botany. 1900.
28. SEWARD, A. C., and GOWAN, MISS J., The maidenhair tree (*Ginkgo biloba* L.). Annals of Botany 14:109-154. pls. 8-10. 1900.
29. BESSEY, E. A., Notes on the spermatozooids of *Ginkgo*. Science 13:255. 1901.
30. IKENO, S., Contribution à l'étude de la fécondation chez le *Ginkgo biloba*. Ann. Sci. Nat. Bot. VIII. 13:305-318. pls. 2, 3. 1901.
31. COOK, MEL T., Polyembryony in *Ginkgo*. Bot. Gazette 34:64, 65. fig. 1. 1902.
32. GOEBEL, K., Morphologische und biologische Bemerkungen. 13. Ueber die Pollenentleerung bei einigen Gymnospermen. Flora 91:237-263. figs. 19. 1902.
33. MIYAKE, K., The spermatozoid of *Ginkgo*. Jour. Applied Micr. 5:1773-1780. figs. 10. 1902.
34. ARNOLDI, W., Beiträge zur Morphologie der Gymnospermen. VI. Ueber den Bau der Zellkerne im Embryo von *Ginkgo biloba*. VII. Die Embryobildung bei *Ginkgo biloba*. Ann. Inst. Agronomique et Forestière à Nowo-Alexandria 16:1-22. 1903.

35. COOK, MEL T., Polyembryony in *Ginkgo*. Bot. Gazette **36**:142. 1903.
36. JEFFREY, E. C., Comparative anatomy of gymnosperms in COULTER and CHAMBERLAIN's Morphology of angiosperms. New York. 1903.
37. SEWARD, A. C., Floras of the past; their composition and distribution. Rept. British Assoc. Adv. Sci. Section K 1903: pp. 25.
38. WIGGLESWORTH, GRACE, The cotyledons of *Ginkgo biloba* and *Cycas revoluta*. Annals of Botany **17**:789-791. 1903.
39. LYON, HAROLD L., The embryogeny of *Ginkgo*. Minn. Bot. Studies **3**:275-290. pls. 29-43. 1904.
40. COULTER, JOHN M., and LAND, W. J. G., Gametophytes and embryo of *Torreya taxifolia*. Bot. Gazette **39**:161-178. pls. A, 1-3. 1905.
41. THOMSON, R. B., The megaspore membrane of the gymnosperms. Univ. Toronto Studies, Biol. Series no. 4. pp. 64. pls. 5. 1905.
42. THOMAS, ETHEL N., "The origin of gymnosperms"; a discussion at the Linnean Society. New Phytologist **5**:68-76, 141-148. 1906.
43. THOMSON, R. B., "The origin of gymnosperms"; a discussion at the Linnean Society. New Phytologist **5**:68-76, 141-148. 1906.
44. WEISS, F. E., "The origin of gymnosperms"; a discussion at the Linnean Society. New Phytologist **5**:68-76, 141-148. 1906.
45. WETTSTEIN, R. VON, Der Ursprung des Pollenschlauches. Naturw. Rundschau **21**:12. 1906.
46. CAROTHERS, IDA ELEANOR, The development of the ovule and the female gametophyte in *Ginkgo biloba*. Bot. Gazette **43**:116-130. pls. 5, 6. 1907.
47. SPRECHER, ANDREAS, Le *Ginkgo biloba* L. pp. 208. figs. 225. Genève. 1907.
48. THOMAS, ETHEL N., A theory of the double leaf trace founded on seedling structure. New Phytologist **6**:77-91. figs. 4. 1907.
49. NATHORST, A. G., Palaeobotanische Mitteilungen. VI. *Antholithus Zeilleri*, n. sp., mit noch erhaltenen Pollenkörnern aus den rhätischen Ablagerungen Schonens. Handl. Kgl. Svensk. Vetensk.-Akad. **43**:20-24. pls. 2 and 4. 1908.
50. SHAW, F. J. F., A contribution to the anatomy of *Ginkgo biloba*. New Phytologist **7**:85-92. figs. 16-18. 1908.
51. HILL, T. G., and DE FRAINE, E., On the seedling structure of gymnosperms. III. Annals of Botany **23**:433-458. pl. 30. 1909.
52. SCOTT, D. H., Studies in fossil botany. Second edition. Vol. II. London. 1909.
53. STARR, ANNA M., The microsporophylls of *Ginkgo*. Bot. Gazette **49**:51-55. pl. 7. 1910.
54. COULTER, J. M., BARNES, C. R., and COWLES, H. C., A textbook of botany. New York. 1910.

## CHAPTER VI

### CONIFERALES (PINACEAE)

The Coniferales are the representative gymnosperms of the present flora. They comprise 40 recognized genera, and approximately 350 species, constituting more than three-fourths of the present gymnosperm flora. They are characteristic of the temperate regions of both northern and southern hemispheres, presenting a sharp contrast to the Cycadales in their general geographical distribution.

Before discussing the morphology of this great group, it will be necessary to survey the material as it has been organized by taxonomists. Two families are recognized, the *Pinaceae* and the *Taxaceae*. Among the *Pinaceae* distinct strobili are formed, whose overlapping scales protect the ovules, and whose seeds ripen dry; while among the *Taxaceae* distinct ovulate strobili (in the ordinary sense) often are not formed, at least the ovules are frequently freely exposed, and in any event the seeds develop a partially fleshy testa or an aril. Such characters are superficial, but they are accompanied by important morphological differences, so important in fact that the two families must be presented separately.

The *Pinaceae* include 29 of the genera and approximately 245 of the species, so that they are the dominant conifers. Four series of forms are recognized, two of which are doubtless artificial assemblages, but they serve at present to catalogue the material, and may be spoken of as tribes.

The *Abietineae* are spiral forms, and have almost completely distinct bract and ovuliferous scale, winged pollen grains, and needle leaves. They include 9 genera and approximately 129 species, as follows: *Pinus* (75 species, throughout the northern hemisphere, mostly in extra-tropical regions); *Cedrus* (3 species, in Asia and northern Africa); *Larix* (8 species, in North America, Europe, and Asia); *Pseudolarix* (1 species, in eastern China); *Picea* (12 species, in the extra-tropical regions of the northern hemisphere); *Tsuga* (6 species, in North America, Mexico, and Asia); *Pseudotsuga* (2 species, sometimes merged with *Tsuga*, in North America);

*Keteleeria* (2 species, in China); *Abies* (20 species, in North America, Europe, and Asia). It will be seen that this tribe forms the prominent coniferous forest display of the northern hemisphere, and is entirely unrepresented in the southern hemisphere.

The *Taxodineae* are spiral forms, with almost completely coalescent bract and ovuliferous scale, and with wingless pollen grains. They include 8 genera and approximately 13 species, as follows: *Sciadopitys* (1 species, in Japan); *Sequoia* (2 species, in California); *Cunninghamia* (1 species, in China and Japan); *Taiwania* (105, 121) (1 species, in the island of Formosa); *Arthrotaxis* (3 species, in Tasmania and Victoria); *Cryptomeria* (1 species, in northern China and Japan); *Taxodium* (2 species, in North America and Mexico); *Glyptostrobus* (2 species, in China). This assemblage of restricted genera is evidently artificial, and is scattered through North America-eastern Asia, and the Australasian region.

The *Cupressineae* are distinguished from the other tribes of Pinaceae in being cyclic, and the strobili may ripen fleshy (as in *Juniperus*). They include 10 genera and approximately 83 species, as follows: *Actinostrobus* (2 species, in Australasia); *Callitris* (15 species in Australasia); *Widdringtonia* (5 species, in equatorial and south Africa and Madagascar); *Fitzroya* (2 species, in southern Chili and Tasmania); *Thujopsis* (1 species, in Japan); *Libocedrus* (8 species, in California, Chili, New Zealand, New Caledonia, New Guinea, China, and Japan); *Thuja* (4 species, in North America, Japan, China, and central Asia); *Cupressus* (12 species, in North America, Mexico, southeastern Europe, and temperate Asia); *Chamaecyparis* (4 species, in North America and Japan); *Juniperus* (30 species, in the mountains and extra-tropical regions of the whole northern hemisphere). This assemblage also gives evidence of artificiality, and presents some cases of remarkable distribution.

The *Araucarineae* are spiral forms, and have completely coalescent bract and ovuliferous scale (so much so as to suggest a doubt of the double nature of the structure), solitary ovules, and free pendulous pollen sacs. They include 2 genera and approximately 20 species, as follows: *Agathis* (10 species, sometimes reduced to 4, in the Malay Archipelago, Pacific Islands, New Caledonia, and New Zealand); *Araucaria* (10 species, in South America, New Caledonia, Australia,



and the Pacific islands). The group is a very natural one, practically restricted to the southern hemisphere, and very distinct from the other tribes.

It is evident that it is impossible to include so many diverse forms in one continuous account. The tribes will be considered together when the characters justify it; but in many cases they must be treated separately.

### 1. The vegetative organs

The most conspicuous feature of the body of most of the Pinaceae is the central shaft, giving rise to a series of wide-spreading branches (figs. 252-254). In size the Pinaceae range from small shrubs to the largest trees. The "big trees" of California (*Sequoia gigantea*) attain a height of 95 meters, with a diameter of 10 meters; but in diameter the "big tree of Tule" (*Taxodium mucronatum*) in southern Mexico far surpasses even the largest sequoias, for it has reached the surprising diameter of 17 meters (fig. 255). The branches are dimorphic, the two forms being characterized as long shoots and dwarf (or spur) shoots. In some forms both kinds of shoots bear foliage leaves; but in *Pinus* the long shoots bear only scale leaves, while the dwarf shoots bear the only foliage leaves. In *Sciadopitys* the condition of *Pinus* obtains, except that the dwarf shoot is apparently replaced by the peculiar double needle leaf.

In the seedlings a very different behavior of the shoots may be observed. These juvenile forms are usually very transient, but they may be "fixed" by culture, so that the plant assumes a permanent appearance very different from its ordinary adult form. GOEBEL (58) has given an interesting résumé of this subject. For example, in *Pinus* the long shoots of seedlings bear foliage leaves, which may disappear from the long shoots in the second year, as in *P. silvestris*, or may continue for many years. These needle-like primary leaves are of simpler anatomical structure than the subsequent foliage leaves, especially in the matter of provision for controlling transpiration. In the juvenile forms of *Larix* the leaves persist during the winter, and even in adult trees the juvenile characters may appear in first-year shoots from adventitious buds, as we have observed also in *Thuja occidentalis* (fig. 256). It is among the Cupressineae, however, that




FIG. 252.—*Pseudotsuga Douglasii*: two specimens on the Laramie Mountains, Wyoming; the tree on the left is about 40 m. high; between the two large trees and in the middle background is a specimen of *Pinus ponderosa*.—From photograph by LAND.



FIG. 253.—*Sequoia gigantea*: the trunk is 10 m. in diameter.—From photograph in possession of U.S. Geol. Survey.



the greatest amount of work has been done in fixing juvenile forms, such relatively permanent forms being known in cultivation as species of *Retinospora*. While some of the adult forms of Cupressineae, as *Juniperus communis*, retain the habit of spreading needles, others develop conrescent leaves upon their adult shoots, that is, leaves whose adaxial faces have become organically connected with the adjacent stem surface, so that they appear as green scales. In such cases, the juvenile form, with its spreading needle leaves, presents a striking contrast with the adult form (fig. 256). In shoots from stumps or wounds, the juvenile form of leaf has been observed in *Pinus*, *Thuja*, and *Taxodium*, a response quite in harmony with JEFFREY'S interpretation of the appearance of resin ducts as a traumatic response. The juvenile forms of *Sciadopitys*, like those of *Pinus*, produce simple needle leaves upon long shoots, but later, scales appear instead of needles, and in their axils the peculiar double needle leaves are developed.

GOEBEL suggests that the juvenile form probably represents the more primitive form.

It is certainly true that if the adult bodies of many of the forms, not mentioned above, be associated with these juvenile forms, a very consistent body is discovered for Pinaceae (and for Coniferales). It would follow that the replacement of foliage leaves



FIG. 254.—*Arucaria excelsa*: a specimen in the Washington Park (Chicago) conservatory.



by scales on the long shoots of *Pinus* and *Sciadopitys*, the peculiar double leaf of *Sciadopitys*, the deciduous habit of *Larix*, the conrescent leaves of many of the Cupressineae, are all derived characters, from forms with spreading and persistent needle leaves on all the shoots.



FIG. 255.—*Taxodium mucronatum*: the "big tree of Tule"; at the height of 2 m. the trunk is 17 m. in diameter.

The dwarfing of certain forms is also remarkable, and is induced by culture in Japan to produce some extraordinary results. That extreme dwarfing may also be induced in nature has been shown by MACMILLAN (94), who has recorded such cases growing in the crevices of the slate on the coast of Vancouver Island. The dwarfs observed



FIG. 256.—Juvenile leaves: *a-d*, *Thuja occidentalis*; *a*, *b*, seedlings; *c*, *d*, shoots from adventitious buds; *e*, *f*, seedlings of *Phyllocladus rhomboidalis*.

there were *Picea sitchensis*, *Tsuga heterophylla*, and *Thuja gigantea*. In the case of the first species ("Sitka spruce"), the largest tree, 68 years old, was less than 60 cm. high; another, 86 years old, was less than 30 cm. high, with a trunk 1.8 cm. in diameter; a third, 98 years old, was about 30 cm. high, with a trunk 2 cm. in diameter.

#### VASCULAR ANATOMY

The anatomical structure of the stems of conifers, and especially of pines, has long been a favorite subject of study, and perhaps no vascular cylinder is more familiar (fig. 257). The mass of details thus accumulated need not be presented in this connection, for much of it has not been organized for morphological use. During recent years, however, great progress has been made in such an organization, and it should find its place in any presentation of the morphology of Coniferales.

A transverse section of the stem shows a comparatively thin cortex, a thick vascular cylinder built up by a persistent primary cambium, and a small pith. These general features are the same as those of *Ginkgo*, but they are in contrast with the corresponding features of the other groups previously considered. The vascular cylinder is collateral endarch, and all traces of mesarch structure have disappeared from the Pinaceae, so far as investigated, except in the cotyledonary bundles of *Juniperus* and of certain species of *Cupressus* (141), and occasionally in the cotyledons of *Tsuga canadensis*, *Pinus Pinea*, and *P. Gerardiana* (154). In *Juniperus* the mesarch structure is not pronounced, and in the species of *Cupressus* referred to, it is indicated only by one or two centripetal xylem elements. It is to be expected that mesarch structure, at least in the cotyledons, will be discovered in more of the Pinaceae. If the "transfusion tissue," generally present in the leaves of gymnosperms as an auxiliary conducting system, is derived from centripetal xylem, as WORSDELL has suggested (45), the mesarch condition in this stage may be regarded as characteristic of the foliar bundles in general, but it would be a later stage than true mesarch.

One of the most significant facts in connection with the vascular cylinder of Pinaceae is the occurrence of leaf gaps (71). The presence of leaf gaps is a constant feature of the Filicales and Ophioglossales

(Pteropsida) among pteridophytes (p. 9), and with them it is associated with large leaves. The contrast with Lycopsidea (Lycopodiales, etc.), with small leaves and no leaf gaps, is complete. Since the coni-




FIG. 257.—*Pinus Laricio*: a cube from the secondary wood, reconstructed from three camera drawings and showing various features of coniferous wood; in transverse section at the left a few rows of small thick-walled cells of the autumn wood are shown, and at the right the larger thinner-walled cells of the spring wood; *tr*, transverse section; *lr*, longitudinal radial section; *lt*, longitudinal tangential section; *m*, medullary ray; *b*, bordered pit; *s*, simple pit;  $\times 400$ .

fers are characteristically small-leaved forms, they have suggested to some a phylogenetic connection with the Lycopodiales (30, 41, 53); but the presence of leaf gaps associates them with the Filicales, and indicates that they have been derived from large-leaved ancestors. The persistence of leaf gaps when leaves are reduced in size makes



their occurrence a character of the first importance. For example, the leaves of *Thuja occidentalis* are extremely reduced, but the leaf gaps are none the less in evidence; and the same is true of all the numerous conifers examined (77). The conditions, therefore, which resulted in the small leaves of conifers, did not result in obliterating the evidence of their derivation from large-leaved forms. As JEFFREY has stated it (77), the small leaves of conifers are of ecological rather than of phylogenetic interest. This is a good illustration of what he calls cenogenetic and palingenetic characters; the small leaves of Lycopodiales are doubtless palingenetic, but the small leaves of conifers are cenogenetic. An old feature may reappear, therefore, in a recent form, without indicating any phylogenetic continuity. This fact is of great importance, for it compels a decision, in every occurrence of a primitive feature, whether it is really the retention of an ancient character (palingenetic) or the reappearance of an ancient character (cenogenetic). This decision must generally be a matter of opinion, but it is often made probable by its association with other characters.

As has been stated, in the more primitive groups of gymnosperms the so-called double leaf trace occurs, and this is naturally regarded by many as a primitive feature. Among the Pinaceae the double leaf trace is characteristic of the Abietineae, and is not a feature of the Cupressineae at least. Whatever the details may be for the other tribes, if this is a primitive character retained by the older types of gymnosperms, it has begun to disappear among the Pinaceae. From this point of view, one could predicate the presence of the double leaf trace in Araucarineae and its disappearance from Taxodineae. SEWARD (117) has called attention to the fact that the persistence of leaf traces, even in old trunks, is characteristic of araucarians. CHAUVÉAUD (83) has dissented from the view that the double leaf trace is a primitive feature, calling attention to the fact that the trace connected with the cotyledons of *Pinus* and *Abies* is single, and in the course of ontogeny splits into two for the later leaves. He concludes that the double leaf trace is a secondary formation. The cotyledonary vascular strand has been found to be single in all the Pinaceae investigated, except in Araucarineae, and except that occasionally in a species of *Cupressus* (*C. torulosa*) there are found two separate

strands in each cotyledon (141). The solitary strand in each cotyledon of such polycotyledonous forms as CHAUVEAUD observed, however, may hold some relation to the number of cotyledons (p. 297), and so may not contradict the primitive character of the double trace.

A study of the vascular anatomy of seedlings of Pinaceae has developed some interesting facts. It will be remembered that the so-called cycadean type of seedling consists of three or four vascular bundles at the base of each cotyledon, which are connected with three poles of a tetrarch root that generally becomes diarch below (120), a type of seedling that characterizes both Cycadales and Ginkgoales. Among Pinaceae, however, the cotyledonary strands (one for each cotyledon) are connected with the poles of a diarch root, excepting the Araucarineae, which have seedlings of the general cycadean type. On the basis of this character, therefore, the cycads, *Ginkgo*, and the araucarians are in the same general category (with numerous cotyledonary strands). The difference between the cycads and *Ginkgo* on the one hand and the araucarians on the other should be noted. While in the former groups the cotyledonary strands are definitely three, among the araucarians they are usually four to eight (154); while in *A. Bidwillii* they are twelve to sixteen (161). In this last form the protoxylem poles of the root are also quite variable in number (5-7), and their connection with the cotyledonary strands is complex and variable. This pentarch to heptarch root becomes reduced finally to the diarch condition. The contrast of the cycads, *Ginkgo*, and the araucarians with the other Pinaceae, therefore, is that in the latter the cotyledonary strands are single and the primary structure of the root is diarch, while in the former groups the cotyledonary strands are three or more and the primary structure of the root is tetrarch or some higher order, but eventually becomes diarch. The most obvious contrast is with the Cupressineae and certain Taxodineae, which have two cotyledons, each with a single vascular bundle at base; among the other Pinaceae the situation is complicated by polycotyledony (135).

In this connection attention may be called to the fact that in tracing the vascular bundles from the transition region of the seedling (the cotyledonary node) to the root, they become exarch. This persistent exarch character of the primary xylem of all roots was long ago

remarked by VAN TIEGHEM (35), and is taken to mean that the most primitive type of xylem has persisted unchanged in the vascular system of the root.

The spiral vessels of the primary xylem, through various intermediate elements, grade into the characteristic tracheids of the secondary wood. These tracheids are arranged radially and have bordered pits that are usually restricted to the radial walls. The pits occur in a single linear series, except among the Araucarineae, in which they are multiseriate, that is, in two or more alternating series and so crowded that the pits are deformed by mutual pressure. This type of tracheid with multiseriate bordered pits is so characteristic, that when it was discovered entering into the structure of paleozoic woods, they were named *Araucarioxylon*. As has been stated, much of the wood referred to *Araucarioxylon* has been found to belong to Cordaitales, so that it is no longer possible to distinguish the wood of Cordaitales and Araucarineae; but this situation has left the impression that the araucarian type of tracheid is more ancient than the other type (96). Attempts have been made to distinguish the various tribes and even genera of conifers by their tracheids, in the hope of applying the distinctions in the determination of fossil woods, but they have not been successful. BAILEY (153) has recently illustrated this in the case of *Picea*, *Larix*, and *Pseudotsuga*, showing that such characters as wood parenchyma, spiral thickenings, and resin canals, often relied upon in determining the genera of fossil Abietineae, are too sporadic or variable to be used with any certainty.

The structure of the medullary rays has been found to furnish important characters for comparative study. The varying details of this structure are foreign to our purpose; but in general two types of ray are recognized: (1) the linear ray, consisting of a single series of cells in tangential section; and (2) the fusiform ray, which is broad enough to contain a resin canal (96). The medullary rays of the living Abietineae are so complex, with their parenchyma cells, ray tracheids, and elaborate system of resin canals, that they have been used as evidence of a highly specialized and modern group. A recent study of the ray tracheids of *Cunninghamia* by JEFFREY (143), however, has indicated the possibility that the simpler rays may have been derived from more complex ones. The marginal ray

tracheids found occasionally in *Cunninghamia*, JEFFREY has found to be due to wounding, and he infers that this response brings back an ancestral feature, and that the ray of *Cunninghamia* has been derived from a more complex one. Since the ray tracheids described for certain Taxodineae and Cupressineae resemble those induced in *Cunninghamia*, the suggestion is made that this evidence favors the origin of these groups, in which ray tracheids are a vanishing character, from Abietineae, in which ray tracheids are an established character. In a recent study of the origin of ray tracheids by THOMPSON (1970), complete transitions were observed, in the young root, from short tracheids extending between the rays to ray tracheids, both marginal and interspersed; the inference being that ray tracheids originate from tracheary tissue. From a comparison of living and fossil forms, the conclusion is reached that while traumatic ray tracheids are evidently vestigial in *Abies*, their absence is an ancestral feature of the pines. It is evident that the whole subject of the phylogenetic significance of ray tracheids is more suggestive as yet than definite.

The resin canals have become of great service in discussions of the interrelationship of the tribes. In *Pinus*, *Picea*, *Larix*, and *Pseudotsuga* they form an anastomosing system in the secondary wood and cortex of both shoot and root, and also occur in the outer margin of the primary xylem of the root. In *Abies*, *Pseudolarix*, *Cedrus*, and *Tsuga* resin canals do not ordinarily occur in the secondary wood of either shoot or root, and are present in the center of the primary xylem of the root. JEFFREY (90) has discovered that in this latter group resin canals sometimes occur in the wood of the axis of the ovulate strobilus and in the first annual ring of vigorous shoots, and also that they may be induced in the secondary wood by injury. The inference is that resin canals in the secondary wood are a primitive feature of Abietineae; that they persist longest in the reproductive axes, leaves, and first annual rings; and that they may be recalled as a traumatic response. In *Pseudolarix* and *Tsuga* they have disappeared even from the cortex of all organs except the ovulate strobilus and leaves. This reasoning leads to the conclusion that *Pinus* and its associated genera are the most primitive, and that the other genera are derived from the condition of *Pinus* by the disappearance



of resin canals from the secondary wood. The same method of reasoning applied to the resin canals and their appearance as a traumatic response in Taxodineae and Cupressineae results in the conclusion that they have been derived from the Abietineae. This has been done by JEFFREY notably for *Sequoia* (78). This genus was long supposed to be without resin ducts, but they were found in *S. gigantea* in the ovulate strobilus, in the first annual ring of vigorous branches of adult trees, and in leaf traces of very vigorous leaves of adult trees. In *S. sempervirens* resin ducts are absent from all these regions; but in both species resin ducts appear in the wood of both shoot and root as a result of injury. It was inferred that these resin ducts, appearing as a traumatic response, were an ancestral feature of *Sequoia*; and if so, the suggestion of connection with the Abietineae is inevitable.

PENHALLOW (96) has reached a very different conclusion from a study of the resin canals. According to his series, resin cells occur in the more primitive conifers. These cells are successively scattered, zoned, and segregated. Segregated resin cells may give rise to resin cysts, such as occur in *Abies*, *Tsuga*, and *Sequoia*. In *Larix*, *Pseudotsuga*, and *Picea* the continuous system of resin canals shows its derivation from resin cysts by the constricted walls; while in *Pinus* the walls are no longer constricted and are lined by an epithelium. This series leads to the inference that the Abietineae are the most modern of conifers, and *Pinus* the most specialized genus.

The discussion of the interrelationship of tribes is deferred to a later section (p. 308), but the two views outlined above serve not only to emphasize the use that is being made of resin canals, but also the kind of facts in reference to them that are thought to be of service. It is evident that a series may be read in either direction, and that a traumatic response may not necessarily reveal an ancestral character.

The cotyledons have been found to be the last region of the body to lose the primitive features of the vascular bundle. If the mesarch structure has disappeared from all other regions of the body, it may have been retained by the cotyledons, which have been appropriately called the most "conservative" organs. For this reason, it is of interest to note that the resin canals are not found in the cotyledons of the Cupressineae, as witnessed by *Actinostrobus*, *Callitris*, *Libocedrus*, *Thuja*, *Cupressus*, and *Juniperus*; but they occur in the cotyledons

of the Taxodineae, as witnessed by *Sciadopitys*, *Sequoia*, and *Cryptomeria* (141); they are generally present (one or two) in the cotyledons of Abietineae; and there are several in the cotyledons of the Araucarineae (154).

Even tyloses have been used in the recent intensive study of the vascular anatomy of this group. CHRYSLER (140) has found that they are restricted to *Pinus*, in which they occur in the heart of the root and in the first year's growth of the axis of the ovulate strobilus. This restriction was demonstrated by an investigation of the root wood of thirty-two species representing thirteen genera, and of the cone axis of twenty-three species representing eight genera. He finds that, although they occur only in *Pinus*, they may be induced by wounding, and raises the question whether they may be a feature of phylogenetic importance as are the resin canals.

The latest anatomical character applied to the comparative study of the vascular anatomy is obtained from the "bars of Sanio," which are cellulose thickenings in the walls of tracheids and appear as horizontal or more or less semicircular markings, which stand out clearly with proper staining. Miss GERRY (168) has investigated their occurrence and character among the Coniferales, finding them in thirty-five of the living genera, but lacking in the living and mesozoic araucarians. This emphasizes the distinctness of the araucarians from all the other Coniferales.

#### THE LEAF

The distribution of foliage leaves and scales is far from uniform among the Pinaceae. There may be foliage leaves only, as in Araucarineae and most Cupressineae; and in case there are both foliage leaves and scales, the two may occur on the same shoot, as in *Abies*, or on different shoots, as in *Pinus*.

The foliage leaves of Pinaceae are quite variable in form, from small discoid ones closely imbricated and appressed upon the axis ("conrescent"), as in many of the Cupressineae, to the characteristic free needles of the Abietineae, and the broad blades of some of the Araucarineae (*Agathis*) (figs. 256, 258). In general, the phyllotaxy is spiral, but in the Cupressineae it is cyclic. The foliage leaves are very persistent, functioning one to ten years, the basal growth permit-

ting them to increase in size at base with the increase in the diameter of the axis. So far as recorded, the only deciduous forms are *Larix*, *Taxodium*, and *Glyptostrobus*.



FIG. 258.—*Agathis loranthifolia*: a shoot one-half natural size.—Photographed from material furnished by Missouri Botanical Garden.

The well-known structure of the leaf is of an extremely xerophytic type, which the section of a pine needle may illustrate (fig. 259). The epidermis consists of elongated, fiber-like cells, with strongly cutinized walls, the guard cells being deeply sunken. The rigidity of the leaf is due chiefly to the hypodermal layers or masses of elongated sclerenchymatous cells. The mesophyll is uniform throughout, and it is characterized by peculiar platelike "infoldings" of the wall.



FIG. 259.—Transverse section of a pine needle, showing epidermis (in which are deeply sunken stomata) underlaid by several layers of heavy-walled cells (sclerenchyma), the mesophyll with characteristic infolded walls and containing resin ducts, the distinct bundle sheath (endodermis) surrounding the vascular region (stele), and the two parallel vascular bundles (xylem directed toward flat or adaxial face of leaf).

There is a single central bundle region, invested by a very distinct sheath, and traversed by two parallel vascular bundles. The remaining tissue within the sheath is the so-called "transfusion tissue," and consists of two kinds of parenchymatous cells: (1) those without protoplasm and pitted, and (2) those with protoplasm and not pitted. The former cells are thought to represent in function an extension of the tracheid system, passing water from the xylem to the mesophyll; and according to WORSDELL (45) they have been derived from the



centripetal xylem of the ancestral mesarch bundle. The latter cells are said to mediate between the mesophyll and the phloem in the transfer of food. The single vascular bundle as it enters the leaf divides into two strands that run parallel and near together within the common sheath. This is really the double leaf trace characteristic of the more primitive gymnosperms, and separating into its two constituents at the leaf base.

In the case of flat leaves the mesophyll differentiates into the palisade and spongy regions, and in the broader forms the cells of the central mesophyll may be more or less transversely elongated, and the entering vascular bundle breaks up into several more divergent strands.

## 2. The spore-producing members

The strobili of Pinaceae are monosporangiate, the two kinds occurring on the same plant (Abietineae, Taxodineae, and occasionally

in Cupressineae and Araucarineae) or on different plants (the prevailing condition in Cupressineae and Araucarineae). Bisporangiate strobili occur occasionally, having been reported for *Picea excelsa* (9), *Pinus maritima* (58), *Abies* sp., *Pseudotsuga Douglasii* (154), and *Sequoia* (42) (figs. 260-262); and recently a remarkable plant of *Juniperus communis* has been described (97), which bears such strobili almost exclusively. In this last case, the strobilus consists of a few sterile bracts at base, then two or three whorls of staminate sporophylls, and at the tip the ovulate sporophylls; occasionally there is a whorl of sterile bracts between the stamens and the ovules. Such a strobilus is interesting not merely because it is bisporangiate, but also because the relation of the




FIG. 260.—Bisporangiate strobilus of *Pinus maritima*: the three lowest sporophylls on each side of this section bear microsporangia; the next sporophyll above on each side bears a microsporangium and also a rudimentary ovuliferous scale in the axil; above these there is the structure of an ordinary ovulate strobilus; GOEBEL found hundreds of such cones upon one tree.—After GOEBEL (58).

two sets of sporophylls to one another is that found in the strobilus of Bennettitales, in the so-called "flower" of *Welwitschia*, and in the



FIG. 261.—Bisporangiate strobili of *Abies*: the staminate strobilus at the lower right corner is almost normal; all the others have microsporangia both above and below, with ovuliferous scales between.

angiosperm flower. It is to be expected that other cases of bisporangiate strobili will be reported, but they are evidently of very rare occurrence among Pinaceae.




FIG. 262.—Microsporangia from the strobili shown in fig. 261: *A*, normal sporophyll, side view; *B*, slightly modified sporophyll from the summit of a bisporangiate strobilus; *C*, *D*, side and front views of sporophylls from the summit of a bisporangiate strobilus; *E*, *F*, side and front views of sporophylls from the base of a bisporangiate strobilus.

## THE MICROSPORANGIUM

The microsporangiate strobili are never terminal on the primary axis or even upon the larger branches (figs. 263-265). Their relation to the axes, foliage leaves, and scales is variable. Sometimes



FIGS. 263-265.—Strobili of araucarians: fig. 263, *Agathis australis*; staminate (right) and ovulate strobili of same age; fig. 264, *Araucaria imbricata*; two staminate strobili with a vegetative bud between them; fig. 265, *Agathis bornensis*; transverse section of sporophyll and pendent microsporangia.—From photographs by THOMSON.

they appear terminal on small leafy shoots of the last order, and sometimes they occur in the axils of the leaves of stronger shoots. In *Pinus* they replace dwarf shoots in the axils of scales, being usually numerous and forming a cluster beyond which the parent axis continues its growth.

The sporophylls follow the leaf arrangement; for example, they are spiral in the Abietineae, and cyclic in the Cupressineae. They are exceedingly variable in form, nearly every genus having a characteristic microsporophyll. In almost every case there is an evident differentiation into a stalklike base and an expanded terminal region (representing a lamina) bearing the sporangia. In some cases, as in *Widdringtonia* (159, 176) among the Cupressineae, the lamina spreads as a peltate expansion, the several sporangia arising from the stalk and girdling it. In other cases, as in the Araucarineae, the lamina is represented by a knoblike enlargement, beneath one side of which the free sporangia hang, suggesting the stamen of *Ginkgo*, and also the *Crossotheca* ("epaulet") type among the Cycadofilicales (fig. 265). There is every gradation between this more or less peltate type and the bladelike expansion of the sporangium-bearing region in the plane of the stalk. The bladelike tip shows all degrees of development, from conspicuous (as in *Cedrus* and *Cunninghamia*) to much reduced (as in *Pinus*), and with its abaxial sporangia suggests the most primitive type of sporophyll, namely that of the Filicales, which was continued among the Cycadofilicales. So far as known, no living conifer has the type of stamen known to belong to some of the Cordaitales, namely a stamen with terminal and erect sporangia; but doubtless these two other types also belong to that great paleozoic group.

The number of sporangia is quite variable, being always two among the Abietineae, two to five (perhaps more) among the Taxodineae, two to six among the Cupressineae, and five to eight or more among the Araucarineae. It is to be remembered that these numbers apply only to living representatives of these tribes, and that they doubtless varied much more widely among their predecessors.

The development of the microsporangium is of the usual eusporangiate type, that is, the archesporium is a hypodermal layer of cells, varying in number, which divides periclinally to form the primary wall layer (outside) and the primary sporogenous layer (inside). The primary wall layer, by successive periclinal divisions, produces several wall layers (usually four or five in the Abietineae, three in *Taxodium*, and two or three in the Cupressineae), the innermost one of which forms a part of the conspicuous tapetum, and the outermost one sometimes developing as an endothecial layer (76). While in general



the mature sporangium wall, after the breaking-down of the inner layers, consists of two layers (epidermis and endothecium), in *Widdringtonia* (159) the mature wall of the small sporangium becomes one-layered, all the true wall layers within the epidermis disappearing. The primary sporogenous layer, by successive divisions, produces a mass of sporogenous cells, which finally reach the mother cell stage, at which time the tapetum forms a complete investment of glandular and sometimes binucleate cells.


In most of the recorded cases, the microsporangium passes the winter approximately in the mother cell stage (figs. 266-269). This is certainly true for *Cupressus Lawsoniana* (48), *Pinus silvestris* (126), *Larix europea* (74), *Taxodium* (76), and *Juniperus communis* (173). In her study of *Pinus*, however, Miss FERGUSON (87) states that in most species, while the sporogenous tissue is well developed before winter, the mother cell stage is not reached until the following spring; while in *P. Strobilus* even the sporogenous tissue is not well developed until May. In *Cryptomeria japonica* (in California) LAWSON (93) found that the staminate cones appear early in October, the reduction divisions occur during the first week of November, and the microspores are rounded off by December. In *Juniperus virginiana* in the vicinity of Chicago, the pollen mother cell divides before development is checked by the cold weather. Observations have not been recorded for tropical species, but we have seen the Mexican *Pinus patula* (?) shedding pollen in September, which would indicate that the pollen had been matured without any resting period.

These discrepancies show a wide seasonal variation in the development of the sporogenous tissue. Even in the cases first cited there is evident a certain amount of variation in seasonal range and rate of development. For example, in *Pinus Laricio* and *Larix europea* the mother cell stage is reached usually in October; while in *Taxodium* the staminate cones do not begin to develop until September or October, but they are in the mother cell stage at the arrival of winter (January or earlier in the southeastern United States); in both cases the mother cell stage is the winter stage, and the reduction divisions take place during the following spring (March to May), but in an early winter *Pinus Laricio* may not reach the mother cell stage, and a few sporogenous mitoses will then precede the mother cell stage the next spring.


In the case of *Pinus Laricio* (in Chicago), about the first of May the mother cells are found in various stages of division, the sporangium usually having passed the winter in the mother cell stage or in a late stage of the sporogenous tissue. The divisions do not appear



266



267



268



269

FIGS. 266-269.—Winter condition of microsporangia: fig. 266, *Pinus Laricio* on October 1; fig. 267, the same on January 3; fig. 268, the same on April 4, showing synapsis; while fig. 267 is probably in the mother cell stage, it is certain that sporogenous divisions sometimes occur in the spring; fig. 269, *Taxus canadensis* on October 1, showing mother cell stage.—After CHAMBERLAIN (48).

to be simultaneous as among angiosperms, for in the same sporangium some mother cells are preparing for the first division, others contain completed tetrads, and others represent every stage between (fig. 301). In the same sporangium, also, the division may be simultaneous or

successive, although the former seems to be the prevailing method; and the tetrad may be tetrahedral or bilateral. The wings of the spores begin to develop while they are within the mother cell (fig. 304). While winged pollen grains are a feature of Abietineae, it is interesting to note that in *Pseudotsuga* (156) wings do not develop, so that winged and wingless pollen grains are found in the two tribes characterized by their wings (Abietineae and Podocarpaceae).

GOEBEL (70) has called attention to the fact that the dehiscence of the microsporangia of gymnosperms is definitely related to their form and position, and favors the distribution of the spores. For example, the nearly related genera *Picea* and *Abies* differ in the dehiscence of their sporangia, the former being longitudinal and the latter transverse. The suggested explanation is that the upright strobilus of *Picea* requires a longitudinal dehiscence for a thorough discharge of spores; while a transverse dehiscence is more effective in discharging spores from the drooping strobilus of *Abies*. The Cupressineae were considered to be outside the range of the problem because their small and rather globular sporangia are not definitely oriented as in the other tribes.

#### THE MEGASPORANGIUM

The ovulate strobilus of Pinaceae has given rise to more discussion than any structure among gymnosperms. The great body of literature dealing with this subject has been traversed and outlined by WORSDELL (62), to whose account we are much indebted for the following statement. The early discussions, which arose from the attempt to interpret an abietineous cone in terms of an angiospermous flower, have chiefly a historic interest. To decide whether such a cone is a flower or an inflorescence does not seem important to the modern morphologist, for if it holds any relation to these things it is that of an ancestral structure which as yet has become neither flower nor inflorescence. The question of chief interest is whether the ovulate strobilus of Pinaceae is to be regarded as simple or compound; that is, whether the ovules are borne by axes of the first or second order.

Among the Abietineae the ovuliferous structures (from below upward) consist of a small bract, a very much larger ovuliferous scale (usually becoming woody) coalescent with the bract at the very

base, and two inverted basal ovules (figs. 270, 271). Among the Taxodineae and Cupressineae there is a single bract or scale structure with two distinct apices (dorso-ventral) at the free and enlarged end and bearing one (*Juniperus*) to many (*Cupressus*) ovules. In *Juniperus* this structure becomes fleshy in the organization of the so-called "berry." Among the Araucarineae there is a prominent bract, a ligule-like ovuliferous scale (present in *Araucaria*, wanting in *Agathis*), and a single imbedded ovule some distance above the base (figs. 272, 273). The discussion has centered about the nature of the ovuliferous scale, and a brief outline of the development of the subject will be of interest.

Before 1827, in which year ROBERT BROWN announced gymnospermy (1), the ovule was regarded as a pistil, and the related parts were variously interpreted. BROWN's conclusion as to a naked ovule was derived from a comparison of the so-called "ovule" (nucellus) of




FIG. 270.—*Pinus Laricio*: diagram of ovule and associated structures; *b*, bract; *s*, ovuliferous scale; *v*, vascular bundles; *m*, micropyle; *i*, integument; *p*, pollen grains; *c*, cavity in apex of nucellus; *n*, nucellus; *g*, embryo sac.

cycads and conifers with the ovule of angiosperms. His corollary was that the ovuliferous scale is an open carpel, but his statement that this so-called carpel is a leaf in the axil of a bract met strong opposition.

In 1839 SCHLEIDEN called attention (2) to the fact that BROWN's "folium in axilla folii" is a morphological impossibility, and that the ovuliferous scale must be a flattened axis in the form of a placenta, the axial nature of placentas in general being one of SCHLEIDEN's peculiar views. This view of the branch nature of the ovuliferous scale was concurred in later by BAILLON, DICKSON, STRASBURGER, and MASTERS, but without regarding the axis as a placenta.

In 1842 A. BRAUN (3) first advanced the theory that the ovuliferous scale represents the first two leaves of an axillary shoot, which are



fused by their adaxial (posterior) margins. His illustrative material consisted of a cone of *Larix*, in which the ovuliferous scale was replaced by a short branch bearing two leaves transversely placed (that is, their margins adaxial and abaxial with reference to the main axis), the bract developing as a foliage leaf. This view was accepted later by CASPARY, PARLATORE, OERSTED, VON MOHL, STENZEL, ENGLEMAN, WILLKOMM, and ČELAKOVSKÝ.



FIG. 271.—Ovulate structures of various Abietineae: 1, *Abies pectinata*, ovulate strobilus; 2, dorsal view of its bract and ovuliferous scale; 3, ventral view of same; 4, longitudinal section of same; 5, a winged seed; 6, longitudinal section of seed; 7, *Pinus silvestris*, ventral view of ovuliferous scale; 8, *Larix europaea*, ovuliferous scale and bract with bristle; 9, longitudinal section of same.—After KERNER (41a).

It is of interest to note that as late as 1860 BAILLON announced (7) his opposition to the claim of gymnospermy, a position which he maintained persistently, basing it upon the first really careful researches in the organogeny of the structures under discussion. He sustained SCHLEIDEN's view that the ovuliferous scale is an axis, but regarded it as an axillary shoot rather than a placenta.

In 1860 DICKSON recorded (9) some cones of *Picea excelsa* in which the lower bracts were replaced by stamens, while the upper bracts

bore axillary ovuliferous scales as in the normal cone. He concluded that stamens are to be homologized with the bracts of the ovuliferous cone, and that the ovuliferous scales are axes of the next higher order. Similar cones have been reported by SHAW (42) from *Sequoia*, and by GOEBEL (58) from *Pinus*. For some, such illustrations settle the sporophyll character of the bract in both cones, and to them the bract of the ovulate cone is a carpel.

In 1860, also, CASPARY (8) confirmed BRAUN'S conclusion, citing specimens in which branches occurred in the axils of the bracts, and bore the two halves of the ovuliferous scale as lateral appendages.

In 1864 PARLATORE recorded (12)

a cone of *Pinus Pinaster* (*P. Lemoniana*) in which an ordinary dwarf shoot with its two needle leaves sprang from the axil of every alternate bract, replacing the ovuliferous scale. His conclusions naturally accorded with those of BRAUN.



FIG. 272.—*Arancaria excelsa*: ovulate cone from a tree in the plaza at Jalapa, Mexico; one-half natural size.

In 1864, also, OERSTED described (11) some remarkable cones, in which the lowest bracts had the form of foliage leaves; in the axils of the next higher bracts were several scales as on a suppressed axis, the two outermost being the largest and opposite; higher up the bracts became gradually smaller and the axillary scales less numerous, but the two outermost scales gradually increased in size and became connate by their adaxial (posterior) margins, while rudimentary ovules appeared at their base; and in the uppermost part of the cone the bract was reduced to its ordinary size, and the ovuliferous scales had fused into a single large broad structure dentate or bifid at apex.



FIG. 273.—*Araucaria excelsa*: longitudinal section of bract (*b*) and scale (*s*) from cone shown in fig. 272; natural size.

One of the simplest explanations of these problematical structures was that proposed by SACHS (14) in 1868, and afterward more fully elaborated by EICHLER (19). They claimed that the bract

is a carpel, and the ovuliferous scale a ligular outgrowth from its face, calling attention to a similar condition in the leaves of *Isoetes* and *Selaginella*. Such a ligular placenta does not appear among the Taxodineae and Cupressineae, and in these cases the bract is evidently an open carpel.

In 1869 VAN TIEGHEM presented his conclusions (16) based upon anatomical structure, a new point of view. He states that the bundles of the bract and of the ovuliferous scale leave the main axis each in its own sheath, and therefore represent independent systems of bundles and independent members; that the upper bundle divides to form an arc (in transverse section) of bundles with inverse orientation, the arc arrangement showing that the axillary structure is a leaf and not a branch; and that the inverse orientation shows that the leaf belongs upon the suppressed branch opposite the bract. His conclusion was that the ovuliferous scale is the first and only leaf of an axillary branch.

In 1871 VON MOHL further strengthened BRAUN'S position by the publication (17) of his studies of the peculiar "double leaf" of *Sciadopitys*. He showed that this leaf represents the first two leaves

of an axillary shoot, which stand transversely, and which become coalescent by their adaxial (posterior) edges, the vascular bundles thus necessarily showing inverse orientation. As this normal behavior of the leaves of *Sciadopitys* exactly parallels what was claimed by BRAUN for the ovuliferous scale, the results of VON MOHL are almost in the nature of a demonstration.

In 1876 STENZEL described (21) striking abnormalities in cones of *Picea excelsa*. In one cone leafy axes occurred in the axils of the bracts, the first two leaves resembling ovuliferous scales more than ordinary foliage leaves in texture. In other cones the abnormalities recorded by DICKSON (9) were observed. In still other cones he found the two parts of the ovuliferous scale in all stages of coalescence. All of his material confirmed BRAUN's view that the ovuliferous scale is made up of the first two leaves of an axillary shoot, which stand transversely, and are connate by their adaxial edges. In reviewing STENZEL's paper, ENGLEMANN reported (20) similar abnormalities in cones of *Picea Englemannii* and *Tsuga canadensis*.

In 1879 ČELAKOVSKÝ began publishing upon the subject, and has constructed a theory (24, 26, 32, 47) intended to unify the puzzling diversities of structure. He regards the ovuliferous scale as the representative of an axillary shoot, but formed directly rather than as an axis with two distinct lateral leaves, which is a statement of the ontogeny rather than of the phylogeny. In this scale he sees the modified and blended outer integuments of the two ovules. There is, therefore, no true carpel present; it is represented by a single ovule, which is borne by a branch of the second order. In brief, from the standpoint of phylogeny, this is the reduction of a leafy, ovuliferous branch to its ovules. The foliar origin of the outer integument is the thesis of ČELAKOVSKÝ, and this really brings one around again to the foliar nature of the ovuliferous scale and BRAUN's theory. A related view is that of KUBART (103), who from a study of *Juniperus* concludes that the ovuliferous scale is an aril.

In 1892 BESSEY published (67) the view that the staminate and ovulate cones are strictly homologous, and that the ovuliferous scale is a chalazal development of the ovules. "The sporophyll enlarges or remains small just as the chalazal development of the ovule into a scale is more or less pronounced."



The ovuliferous scale of Pinaceae, therefore, has been regarded successively an open carpel, a placenta, a flattened axillary shoot, the first two leaves of an axillary shoot, the first and only leaf of an axillary shoot, a ligule, fused outer integuments, and a chalazal outgrowth. To select among these views is more difficult than important. The testimony would seem to favor BRAUN'S general view, and this would relate the megasporangia properly to the abaxial surface of their sporophylls, the relation held by the microsporangia. Moreover, it was evidently the situation in the ovulate strobilus of some of the Cordaitales at least, and the historical connection of Pinaceae and Cordaitales is fairly clear. Amid all the possible details of views, the really important fact is reasonably substantiated that the scale and its ovules, in Abietineae at least, in some way represent a modified axillary shoot, corresponding to the characteristic dwarf shoot of the group; and therefore, that the strobilus is a compound one, as among the Cordaitales and Gnetales.

Among Taxodineae and Cupressineae bract and scale form a single structure; but the two distinct and dorso-ventral apices, and the two sets of vascular strands with opposing orientation (the xylem of the one facing the xylem of the other), make the inference reasonable that the same structures are represented as occur among the Abietineae.

Investigators claim that the case of the Araucarineae is very different (figs. 272, 273). In *Araucaria* a superficial examination seems to show a fused bract and ovuliferous scale, as in the Cupressineae, but those who have investigated the structure say that there is no such evidence of its double nature. Even if the ligule of *Araucaria* be accepted as a vestige of the ovuliferous scale, there is no ligule in *Agathis*. It seems to be a needless forcing of the situation to regard the ovuliferous bracts of Araucarineae other than they seem, that is, simple sporophylls (117), some of which are ligulate. In a recent study of the vascular anatomy of the ovuliferous structure of conifers, THOMSON (164) has found definite evidence that the araucarian ovulate strobilus consists of simple megasporophylls. In the vascular supply bundle for sporangia (including microsporangia) there is developed an inverse orientation. Among the other tribes of Pinaceae there are two such orientations, indicating a different condition; while in the megasporophylls of podocarps there is the single inverse orien-

tation. The conclusion seems evident that the ovuliferous structure of araucarians and of podocarps is of the same nature, and that it is a simple megasporophyll. That in so large and ancient a group as the Pinaceae both simple and compound ovulate strobili should be represented, would not be strange. In fact this difference between the Araucarineae and the other three tribes only emphasizes other differences that indicate the long separation of the Araucarineae from the other Pinaceae.

The scales or bracts, whatever may be their morphological character, bear a variable number of ovules. Among the Abietineae the number is definitely two, and the ovules are inverted; but in the other tribes of Pinaceae the number is variable. Among the Taxodineae the numbers range from two in *Taxodium* to seven to nine in *Sciadopitys* (arranged in a transverse row), and the ovules are all erect except in *Cunninghamia*, *Sciadopitys*, and sometimes *Arthrotaxis*. Among the Cupressineae the ovules are all erect, and range in number from one or two in *Juniperus* and *Actinostrobus* to indefinite and often numerous in *Cupressus* and *Callitris*. Among the Araucarineae the solitary (sometimes two in *Agathis*) ovule is inverted.

One of the remarkable features of the development of the ovule of Pinaceae is the long period that often elapses between the first appearance of the ovulate strobilus and the maturing and shedding of the seed (fig. 274). The schedule for *Pinus Laricio* growing in Chicago is as follows. The strobilus begins to develop in the late fall and winter; in the spring the integument and nucellus of the young ovule are distinct, but there is no evident differentiation of sporogenous tissue; in May the mother cell is recognizable by its great increase in size (the stage found in the youngest evident cones); in October the endosperm is found as a parietal layer of free nuclei, in which condition the second winter is passed; in the following spring the endosperm begins to develop rapidly; and in June the archegonia are ready for fertilization, which takes place about the first of July, at least twenty-one months after the first organization of the ovule; in the following year the seed is shed, three winters being included between the primordium of the ovulate strobilus and the shedding of its seed. It is recognized that this schedule is an unusually long one, and how far it applies among Pinaceae is unknown. In



FIG. 274.—*Pinus Laricio*: branch from top of thrifty tree, June 1; the four small strobili at the top are in the stage shown in fig. 280; in the strobili next below, which are a year older, the archegonium initials are distinguishable (fig. 289); the strobili next below, another year older, have shed their seeds; to the right is a cluster of staminate strobili just ready to shed pollen.

*Taxodium* (76) the ovulate strobili also begin in the early fall (in southeastern United States), grow during the winter, the mother cell is indistinct in March or April, and fertilization occurs in June, but the seed matures before the end of the year. These two schedules probably represent the extremes among Pinaceae, at least one winter and not more than three elapsing between the primordium of the strobilus and the shedding of the seed. So far as the investigations include a record of time, the mother cells are evident and dividing during the spring, from the first of March in California to the last of May in England.

The integument and nucellus are free from one another only in the region of the sterile cap of the latter. In the early stages of the ovule they appear almost entirely free, but the later growth of the ovule is chiefly in the chalazal region, so that the free portion of the two regions appears only at the tip of the mature ovule. An unusual freedom of nucellus and integument is reported for the Araucarineae (107), but complete freedom at the maturity of the ovule is recognized as a primitive feature characterizing certain paleozoic seeds, some of which doubtless belong to the Cordaitales. Cases of two separate nucelli within a common integument have been reported for *Thuja* (86).

In general the integument forms a more or less elongated but indefinite micropyle, but LAWSON has described (156) a remarkable organization of the micropylar tube in *Pseudotsuga Douglasii*. A stricture of the integument midway between the apex of the nucellus and the mouth of the micropyle results in two micropylar chambers. The rim of the outer chamber is folded inward, and on the inner surface of the infolded portion numerous hairlike processes are developed. It is in this outer stigmatic chamber that the pollen grains lodge and germinate, the pollen tubes passing through the inner micropylar chamber to reach the apex of the nucellus. In *Widdringtonia* (159) the micropylar tube is remarkably long and slender, and since the integument is bilaterally winged, the ovule bears a remarkable resemblance to that of *Welwitschia*.

The integument differentiates into the three layers characteristic of all the groups previously considered; but the outer fleshy layer does not deserve its name, for it is represented only by a thin layer



of cells that disappear with the maturing of the testa. The middle or stony layer in this case is the conspicuous one, the seed being said to "ripen dry"; while the inner fleshy layer is most largely and distinctly developed, as usual, in the free portion of the integument (fig. 275).





FIG. 275.—*Pinus Laricio*: longitudinal section of ovule; *o*, outer fleshy layer of integument; *i*, inner fleshy layer; *s*, stony layer; *p*, pollen tubes; *n*, free portion of nucellus; *g*, gametophyte; *a*, archegonia.

The vascular supply of the seed has been modified by this change in the structure of the testa. Both inner and outer sets of vascular strands have disappeared, the vascular connections ending in a more or less extensive tracheal plate at the base of the ovule.

The development of the sporogenous tissue has seldom been traced. In *Larix* STRASBURGER (25) has demonstrated a hypodermal archesporial cell, which divides periclinally into an outer primary wall cell ("tapetal cell") and an inner primary sporogenous cell (figs. 276-279). The wall cell begins an extensive series of divisions, accompanied by divisions of the overlying epidermal cells, so that soon there is a large mass of sterile nucellar tissue capping the sporogenous cell. Presumably this description applies in a general way to the formation of the nucellar cap in all the forms, but in

most cases the hypodermal cells are not distinguishable from the others, and the succession of divisions cannot be followed with any certainty. In *Sciadopitys* LAWSON (175) describes the differentiation of a "pollen cushion" at the tip of the nucellus, consisting of a loose tissue of large thin-walled cells that receives the pollen grains. In general, the first clear evidence of sporogenous tissue is the appearance of one or more deep-lying mother cells, recognized first by their increasing size. It is probable that if there is a primary sporogenous cell formed as described above, it does not divide to produce sporogenous tissue,

but is the mother cell, as in angiosperms. It seems more probable that in most cases mother cells are "picked out" directly from an undifferentiated mass of cells. In *Widdringtonia* (159) there is a remarkable early differentiation of the nucellus into peripheral and central regions, suggesting to SAXTON that the central group of cells may be sporogenous; in fact, in a later paper (176) he speaks



FIGS. 276-279.—*Larix europaea*: fig. 276, longitudinal section of young ovule, showing megaspore mother cell and tapetal cells, and at the left the beginning of the integument (March 1); fig. 277, the mother cell has divided; fig. 278, the row of megaspores, the innermost of which is functioning; fig. 279, the beginning of free nuclear division within the functioning megaspore; all  $\times 150$ .—After STRASBURGER (25).

of "64 megaspore mother cells." In any event, only one of them was observed to function as a mother cell; although in the very similar *Callitris* two endosperm-filled sacs were observed lying in contact.

The number of distinct mother cells is variable. For example, in *Pinus* and *Larix*, and probably in all the Abietineae, the mother cell is usually solitary. Among the Taxodineae the mother cells are

solitary in *Taxodium* (76), three or four in *Cryptomeria* (93), and five or six in *Sequoia* (92); and among the Cupressineae, *Thuja* (86) occasionally has two or three mother cells, and *Libocedrus* (131) one to three. That the number of mother cells may be quite variable is shown by the case of *Cunninghamia*, in which one observer (64) reported several mother cells developing embryo sacs, and another




FIG. 280.—*Pinus Laricio*: longitudinal section of an ovule on June 1, with megaspore mother cell in the center, surrounded by a region of more or less modified cells; nucleus of mother cell in prophase of reduction division;  $\times 500$ .

(147, 180) reported a solitary mother cell. The season for the recognition and functioning of mother cells has been mentioned, ranging throughout all the spring months for different latitudes, but there is no clear evidence whether in any case the megasporangium passes the winter in the mother cell stage, as is often true of the microsporangium.

A well-marked feature of the Pinaceae is the development of a more or less extensive zone of nutritive cells about the enlarging

mother cell, which persists into the early stages of endosperm-formation (fig. 280). This conspicuous zone has been taken to represent sporogenous tissue; but the most usual mistake is to interpret it as endosperm tissue, overlooking the comparatively inconspicuous embryo sac, a mistake first made by HOFMEISTER (10) and later corrected by STRASBURGER (25). In the more recent literature of the subject it has been referred to as the "spongy tissue."

This differentiated region has been studied in considerable detail in *Pinus* (87) and *Taxodium* (76), but it appears to be a general feature of Pinaceae, as distinct from Taxineae. In its later development it becomes differentiated into three zones: (1) a tapetal zone, consisting of large, glandular cells, that are evidently digestive and are very active during early endosperm-formation; (2) a tabular zone, consisting of flattened and finally disorganized cells; (3) a starch zone, consisting of cells rich in starch. This elaborate nutritive mechanism persists until the endosperm tissue invades the surrounding nucellar tissue. This region may not always be so complex as in *Pinus*, but the tapetal cells are always evident.


The megaspore mother cell, deeply placed in the nucellar tissue, initiates the two reduction divisions, and a linear tetrad is formed (fig. 281). Sometimes the micropylar daughter cell of the first division does not divide, so that there appears a row of three cells, as in *Larix* (25), *Pseudotsuga* (156), *Taxodium* (76, 86), and *Juniperus* (132), but the row of four cells has been observed in a sufficient number of cases to indicate that the full number of divisions is usual. In *Sciadopitys*, according to LAWSON (175), the division of the mother cell nucleus is not accompanied by wall-formation, but walls appear in connection with the subsequent divisions of the two daughter nuclei; so that the tetrad comprises three cells, the middle one of which is binucleate. The



FIG. 281.—*Pinus Laricio*: a linear tetrad of four megaspores derived from the megaspore mother cell; the innermost megaspore enlarging and the others beginning to disintegrate;  $\times 666$ .



tetrad is not always linear, COKER having reported (85, 86) that in *Thuja*, so far as he has observed, it is always tetrahedral. In case there are several mother cells, they may all form tetrads. In *Sequoia sempervirens* (92) the five or six mother cells form tetrads, and ten or twelve megaspores begin to germinate, only two or three continuing beyond the first division, and finally one becoming dominant (figs. 282, 283). The sterile megaspores in this species are quite prominent,



FIGS. 282, 283.—*Sequoia sempervirens*: fig. 282, longitudinal section of ovule, showing six megaspore mother cells; pollen tubes are growing down between nucellus and integument; March 12, 1902;  $\times 83$ ; fig. 283, longitudinal section of nucellus, showing eight germinating megaspores, each containing two nuclei; April 25, 1902;  $\times 116$ .—After LAWSON (92).

being clustered about the upper third or fourth of the remarkably elongated functional megaspore (42). In *Cryptomeria japonica* (93) there are four tetrads formed, and the centrally placed megaspore of the group of twelve to sixteen functions. In *Libocedrus decurrens* (131) one to three tetrads appear, from which a single functioning megaspore is selected; and in *Pinus silvestris* (361, 166) and *Callitris* two embryo sacs have been observed. It may be inferred that two or more mother cells and tetrads may occur in any of the Pinaceae, but thus far they seem to be especially characteristic of the Taxodineae and the Cupressineae.

The chromosome numbers among gymnosperms seem to be prevailing 12 and 24, and the Pinaceae, so far as observed, conform to this, counts having been made in *Pinus* (38, 40, 46, 51), *Larix* (59), *Thuja* (72), *Taxodium* (76), *Araucaria* (104), and *Callitris* (159). In *Sequoia sempervirens* LAWSON (92) obtained counts of 16 and 32 in the endosperm and first spindle of the embryo; and the same observer (93), without definite counting, has reported 9 or 10 as the approximate haploid number in *Cryptomeria*, and 8 and 16 as the numbers in *Sciadopitys* (175); while in *Widdringtonia* SAXTON (159) has definitely counted 6 and 12.

### 3. The gametophytes

#### THE FEMALE GAMETOPHYTE

The development of the female gametophyte (endosperm) and of the archegonia of Pinaceae has long been known in outline for a few forms, through the early investigations of HOFMEISTER (10, 13) and STRASBURGER (15, 18, 22, 25, 31). The later investigations have filled in the outlines and have included a much wider range of forms. In general, the sequence of events is approximately uniform in all the Pinaceae observed, but differences in detail have been discovered whose significance and range are at present uncertain. It should be remembered that the megaspore begins to germinate early in the history of the ovule, that when its membrane becomes the boundary of the embryo sac there is still much of the nucellar tissue to be developed, and that the membrane continues to grow along with the growing endosperm.

The division of the megaspore nucleus is followed by a series of simultaneous nuclear divisions, until a large number of free nuclei have been produced. Early in this series of divisions the embryo sac, with its increasing capacity, begins to become vacuolate, and the large central vacuole restricts the free nuclei to the layer of cytoplasm lining the wall (fig. 284). In this parietal position free nuclear division continues. The number of free nuclei produced before wall-formation is probably very indefinite. The case of *Taxus* (52), with its eight successive divisions resulting in 256 free nuclei, has been applied with too much assurance to Pinaceae. It may be that this number is a very common one among Pinaceae, but Miss FERGUSON

(87) estimated that in cases of *Pinus* under her observation 2,000 free nuclei were produced before wall-formation. This would mean approximately eleven successive divisions, but there is no reason to

suppose that the regularity of the early divisions is continued by the later ones. This period of free nuclear division may be spoken of as the first stage of endosperm development.

The second stage of development is that of wall-formation, during which walls appear among the free and usually equally distributed nuclei, and a parietal layer of cells is formed, which are open toward the center of the sac. The third stage is that of centripetal growth, the parietal tissue growing toward the center of the sac from every direction, until the sac becomes filled up with tissue. In this centripetal growth the innermost cells are always open toward the center, and may become quite elongated. When the center has been reached by the abutting cells, end walls are formed by each open cell and the tissue is continuous throughout the sac. It will be noted





FIG. 284.—*Pinus Strobilus*: longitudinal section of ovule, May 26, 1898; gametophyte in the free nuclear condition, and surrounding it is a jacket of spongy tissue mostly two cells thick;  $\times 62$ .—After Miss FERGUSON (87).

that this outline is in general that which was given for Cycadales and Ginkgoales.

The details of the centripetal growth have been found to vary widely, but this growth has been studied in a close series in very few forms, so that no general conclusions are possible as yet. The case of *Sequoia sempervirens* was first described by ARNOLDI (49) and later by LAWSON (92). Free nuclear division occurs in the two

extremities of the sac, so that when wall-formation occurs three distinct parietal regions are apparent (upper, middle, and lower), the ends of the sac becoming filled with compact tissue while the middle region is hardly beyond the stage of free nuclei. In filling up the center of the sac with tissue, the belated middle region grows centripetally, its inner cells being open toward the center of the sac, as



FIGS. 285-288.—*Cryptomeria japonica*: development of the endosperm; fig. 285, longitudinal section of upper portion of endosperm showing multinucleate condition and also that the walls are incomplete; May 26, 1902;  $\times 235$ ; fig. 286, telophase of the mitosis which is to result in the formation of a binucleate cell like those shown in fig. 288; May 29, 1903;  $\times 1,000$ ; fig. 287, a later stage in the same mitosis, the two daughter nuclei completely inclosed by the kinoplasmic fibrils;  $\times 1,000$ ; fig. 288, portion of the endosperm soon after free cell-formation; the membrane formed by the kinoplasmic fibrils has inclosed both daughter nuclei; the free cells crowded together resemble a tissue; May 29, 1903;  $\times 320$ .—After LAWSON (93).

usual. The details of this centripetal growth, as given by ARNOLDI, are that when the centripetally growing walls have reached the center and the end walls have been formed, the result is a series of radially elongated cells, which he calls "alveoli." In these cells nuclear division with wall-formation occurs, so that each alveolus becomes divided into several cells. In investigating *Sequoia gigantea*, the same investigator (64) discovered that the endosperm development is uniform, and with no such regional differences and cell-formation by alveoli as are exhibited by its fellow species. LAWSON's account



(92) of the first wall-formation in *Sequoia sempervirens* is probably true for the first walls of endosperm in general. At the last division of the free nuclei (in this case at the two extremities of the sac), adjacent nuclei remain connected by the spindle fibers, which increase in number, and upon them cell plates are formed.

The details of endosperm-formation in *Cryptomeria*, however, seem to be the most peculiar (93). The sac is filled with tissue by centripetal growth as usual, but the formation of the permanent endosperm is the remarkable feature. The "primary" endosperm cells, that is, those open toward the center of the sac, elongate centripetally and by free nuclear division become multinucleate (fig. 285). There is then a stage when "hundreds" of these nuclei divide about simultaneously, with no formation of a cell plate; but the kinoplasmic fibrils extending between each pair of daughter nuclei increase in number and curve outward on all sides, until both nuclei are completely surrounded by a sheath of fibrils, which fuse to form an investing membrane. This method of free cell-formation goes on throughout the whole endosperm except in the region of the archegonium initials; the cells become crowded, thus resembling ordinary tissue composed of binucleate cells; and after this nuclear division accompanied by wall plates proceeds in the usual way (figs. 285-288).

In considering these cases of *Sequoia* and *Cryptomeria*, the secondary formation of cells by centripetally growing primary ones ("alveoli" of ARNOLDI) is common to both, whether the details of secondary cell-formation are the same or not. There is also suggested the possibility of a permanent secondary tissue which replaces the primary tissue, the development of the latter usually having closed previous investigations in this direction. Random reports of endosperm cells that are uninucleate, or binucleate, or multinucleate may find their explanation in stages of the development of permanent endosperm tissue.

More recently LAWSON (156) has studied *Pseudotsuga*, and finds that in that form also free nuclear division occurs in the primary endosperm cells before cross-walls appear to form the uninucleate cells of the permanent tissue. SAXTON (159, 176) has observed the same free nuclear division in the primary endosperm cells of *Widdringtonia*, but in this case the cells usually become only binucleate (occa-

sionally multinucleate), and this binucleate or multinucleate condition persists in the permanent tissue, as if the last stage of other forms were omitted in *Widdringtonia*.

The development of the archegonium follows the same course as that described for Cycadales and Ginkgoales. The archegonium initials, selected usually from the superficial micropylar cells of the endosperm, become recognizable by their size at various stages in the development of the endosperm tissue. In some cases they are differentiated almost as soon as wall-formation has occurred in the micropylar region; in other cases they are not evident until the endosperm tissue has reached an advanced stage of growth; and between these two extremes there is every intergrade. There is evident among Pinaceae, and notably among Coniferales in general, a tendency to develop archegonia earlier and earlier in the ontogeny of the gametophyte, a tendency that expresses itself somewhat irregularly but none the less clearly, and that reaches its extreme expression in the appearance of archegonium initials immediately after the free nuclear stage of the gametophyte (as in *Torreya*). The significance of this tendency may be appreciated when it is remembered that among Gnetales it has resulted in the differentiation of eggs during the free nuclear stage of the gametophyte, and therefore in the elimination of archegonia. This tendency will be discussed more fully later, in connection with a general consideration of evolutionary tendencies among gymnosperms.

An initial cell, recognizable usually in May or June, enlarges considerably and then divides by a periclinal wall into the primary neck cell (outer) and the central cell (inner) (figs. 289, 290). The primary neck cell divides by an anticlinal wall, and this division may be followed by others, the number of cells in the archegonium necks of Pinaceae being very variable. The adjacent cells of the endosperm grow faster than the neck cells, so that the neck opens in the bottom of a funnel-shaped depression, known as the archegonial chamber.

The central cell begins a remarkable increase in size, and about it a definite nutritive jacket of endosperm cells becomes differentiated, which may be referred to as the archegonial jacket or tapetum, and which must not be confused with the nucellar tapetum that invests

the mother cell and its successors (fig. 291). The cells of this jacket, which invests not only the central cell but also the succeeding egg, develop the usual features of tapetal cells, with densely staining cytoplasm and large nuclei; but their special feature is the conspicuous thickening and pitting of the walls bounding the central cell (and egg). At first it was supposed that through these pits the jacket cells emptied their contents into the enlarging central cell and egg



FIGS. 289-292.—*Pinus Laricio*: development of the archegonium; fig. 289, archegonium initial, May 28; fig. 290, neck and central cells, June 2; fig. 291, central cell just before cutting off ventral canal cell, June 18; fig. 292, cutting off ventral canal cell, June 21;  $\times 104$ .

(28), including the bodily transfer of their nuclei. In this way the central cell and egg were thought to be packed with food, their cytoplasm being filled with large and deeply staining masses (more prominent in the egg) which were regarded as the nuclei contributed by the jacket cells. Even after STRASBURGER had shown that these deeply staining masses are not nuclear in nature, but that the best organized are the so-called "proteid vacuoles," ARNOLDI (55) described the behavior of the migrating nuclei, reporting them to become amoeboid in the jacket cells, to squeeze through the pits, and to regain their form in the central cell and egg. Nuclei were also

said to pass from the next outer layer into the cells of the jacket, and the jacket cells were often seen emptied of all their contents. These details of observation have been mentioned chiefly to illustrate the dangers of such interpretations when the sections are more than one layer of cells in thickness. Migrating nuclei squeezing through walls can often be seen by examining several superimposed layers of cells. It is now known (117) that these large pits of the archeogonial jacket cells, in early stages, are closed by a membrane, which is perforated only by *Plasmodesmen*, so that under these conditions the bodily transfer of nuclei or any solid material is impossible. Just what the situation is in later stages is uncertain.


The central cell enlarges and receives food material for two or three weeks, its nucleus retaining the apical position, when it divides about simultaneously with the division of the body cell in the pollen tube (76, 157), to form the very small ventral canal cell and the very large egg (figs. 292-297). The ventral canal cell disorganizes and disappears with more or less rapidity; while the egg nucleus begins immediately a very rapid and a very great enlargement. It moves toward the center of the egg, and attains a size that seems out of all proportion to its original bulk and to the time involved. During maturation of the egg the characteristic changes occur in the nucleus which were described in connection with the egg of Cycadales.

The notable feature in connection with the development of this archeogonium, as contrasted with that of pteridophytes, is the complete elimination of the neck canal cells. The general tendency among pteridophytes is to reduce the number of these cells, and among Filicales the reduction has reached the stage of a single uninucleate cell; but among gymnosperms even this has disappeared, and there is no trace of neck canal cells.


The behavior and character of the nucleus of the ventral canal cell, which is sister to the egg, has attracted attention. Usually its disorganization is very prompt, often beginning before it returns to the resting stage; and afterward its disorganized remains may be seen in various stages, even to the early stages of embryo-formation. The nuclei of the ventral canal cell and of the egg are at first exactly similar, apparently differing only in the quantity of cytoplasm involved in each case, and suggest that the ventral canal cell is an abortive




egg (46). This view is confirmed by cases in *Pinus* in which the ventral canal cell is very much larger than usual, and its nucleus has reached the size of the egg nucleus and has passed through the same




293




294



297



295



296

FIGS. 293-297.—*Pinus Laricio*: formation of ventral canal cell; fig. 293, typical division, the ventral canal nucleus beginning to disorganize and the egg nucleus beginning to enlarge;  $\times 500$ ; fig. 294, disorganizing ventral canal cell;  $\times 500$ ; fig. 295, an unusually large spindle in cutting off ventral canal cell, the two nuclei being the same size and showing the same developmental changes;  $\times 500$ ; fig. 296, a large ventral canal cell formed in this way;  $\times 500$ ; fig. 297, the wall separating the ventral canal cell from the egg has broken down, leaving both nuclei free in the cytoplasm of the egg; *nv*, nucleus of ventral canal cell; *no*, nucleus of egg;  $\times 100$ .—After CHAMBERLAIN (51).

maturation changes (51, 126). A similar case was reported for *Ginkgo* by IKENO. Such a nucleus appears to be ready for fertilization. In *Abies balsamea* (79a) the ventral canal nucleus usually enlarges somewhat and persists until fertilization. There are also cases in which the wall separating such a ventral nucleus from the egg has been observed to disappear, leaving two similar nuclei free in the cytoplasm of the egg (51); and such equal nuclei have been observed in contact (fig. 298), as if fusing (23, 44). It seems reasonable to infer that the ventral canal cell is an abortive egg, which is occasionally organized as an egg, and which in that condition may be fertilized (72), or may fuse with the egg nucleus. The ventral nucleus has also been observed to divide (after the fertilization of the egg), either by amitosis (76) or mitosis (72).

The account of the archegonium given above applies in general outline to all the Pinaceae, but there are differences among the tribes that must be considered.

Among the Abietineae the number of archegonia ranges from one to seven, with two to five as the usual range, the smallest among Pinaceae. The number of neck cells may be said to average about eight, arranged in two tiers, with four cells in each tier; but there




FIG. 298—*Pinus Laricio*: conjugation of two nuclei which were described as male (*m*) and female (*f*), but which are doubtless the nuclei of the egg and ventral canal cell, as in fig. 297; both nuclei are in an early spirem stage; it is interesting to note that the first record of fertilization in gymnosperms (*Picea*, reported by STRASBURGER 22) was very probably a case of this kind;  $\times 500$ .—After COULTER (44).



may be only one tier or more than two tiers, more than four cells in each tier are known to occur, in some cases there are only two cells in a tier, and in *Tsuga canadensis* (37, 60) the neck is frequently two-celled, but often consists of three or four cells. It should be kept in mind that a two-celled neck is a feature of Cycadales and Ginkgoales, and for that reason it has been assumed to be the primitive type of neck. So far as we have observed, however, there is no typical number for neck cells, the two-celled neck occurring indiscriminately among Pinaceae, the number of cells developing apparently holding no definite relation to phylogenetic connections. A notable feature of the Abietineae is the formation of a true ventral canal cell, a distinct wall plate cutting it off from the egg. This is true only of the Abietineae among conifers; and if the elimination of the separating wall plate, resulting in the ventral canal cell being represented only by its nucleus, is an evidence of a further stage in the reduction of the axial row, the Abietineae are the most primitive conifers in this character. Even among them, as mentioned above, occasionally the wall sometimes disappears, leaving the ventral nucleus free.

Among the Taxodineae the number of archegonia ranges from four to sixty (4-6 in *Sciadopitys*, 8-15 in *Cryptomeria*, 10-35 in *Taxodium*, 60 in *Sequoia sempervirens*), which is the largest range among Pinaceae. The number of neck cells ranges from two to eight (*Sequoia* 2 and occasionally 4, *Taxodium* 2-6 or more, *Cryptomeria* usually 4, *Sciadopitys* 4-8), forming a single tier. The neck cells of *Sciadopitys* are peculiar in being vertically elongated. In *Sequoia sempervirens* LAWSON reports (92) that the very numerous archegonium initials are differentiated deep in the endosperm of the micropylar region, and that the necks are pushed to the periphery of the endosperm by the elongating central cells, being directed toward the nearest pollen tubes, which have taken their positions before the archegonia were formed (92). It is in *Cunninghamia* (147, 180) that the archegonium initials appear very early in the ontogeny of the gametophyte. A significant feature in connection with the archegonia of this tribe is their grouping, in some genera, into what may be called an archegonium complex. This means that the archegonia are grouped in contact, invested by a common archegonial jacket, and with a common archegonial chamber. Since

this is a feature of the Cupressineae, its occurrence among the Taxodineae has tempted various investigators to use it as a reason for transferring certain genera of that tribe to the Taxodineae. The two tribes are confessedly artificial, but such a character is not a safe one, for the grouping of archegonia is often indefinite and variable. This complex has been found in *Sequoia* (50, 64), *Taxodium* (76), *Cryptomeria* (93), and *Cunninghamia* (147, 180), but it does not occur in *Sciadopitys* (175). Both species of *Sequoia* show an interesting transition between separate archegonia and an archegonial complex, the numerous archegonia occurring singly or in groups. In the three other genera observed there is sometimes a layer of endosperm cells between adjacent archegonia; and in *Cunninghamia* (147, 180) the group of archegonia (15 in the preparation figured by MIYAKE) surrounds a central mass of endosperm tissue. Among gymnosperms there seems to be a sequence in the distribution of archegonia, the most primitive situation being numerous scattered archegonia, followed by fewer archegonia derived from superficial cells of the micropylar region, and then by their organization into a complex. In none of the Taxodineae has a ventral canal cell been discovered, but in all of them a ventral nucleus is cut off, which is sometimes very ephemeral.

Among the Cupressineae the number of archegonia ranges from five to about one hundred, the number in *Thuja* (72) averaging six, in *Juniperus communis* (173) ranging from four to ten in a single complex, in *Libocedrus* (131) ranging from six to twenty-four in the complex, and in *Widdringtonia* (159, 176) ranging from thirty to one hundred. The neck cells appear to be always in a single tier, and vary in number between two and eight, the number for *Juniperus* (132) and *Widdringtonia* (176) being usually four, and *Thuja* (72) ranging from two to six. In *Thuja* the neck cells begin to disorganize as soon as they are formed, and are almost completely absorbed by the enlarging central cell (figs. 299, 300). In the whole tribe the archegonial complex is a feature, being compactly organized, with a distinct and common jacket and a common chamber. No ventral canal cell is formed, but the ventral nucleus is always cut off, as among the Taxodineae. The case of *Widdringtonia* (159, 176) deserves special mention, and it seems to be duplicated in *Callitris*. Before





FIGS. 299, 300.—*Thuja occidentalis*: archegonium complex; fig. 299, longitudinal section of upper portion of endosperm with three of the elongated archegonium initials;  $\times 450$ ; fig. 300, later stage with necks breaking down; the nuclei of the central cells have not yet divided to form the ventral canal nucleus and the egg nucleus; the pollen tube, with its body cell and stalk and tube nuclei, has almost reached the archegonium complex;  $\times 540$ .—After LAND (72).

the archegonium initials are recognizable, the solitary pollen tube has passed down the surface of the endosperm just within the megaspore membrane, until it lies in contact with the upper third or even the upper half of the elongated gametophyte, bearing in its tip the body cell. This position seems to determine the selection of archegonium initials, which begin to appear in groups beneath the surface, the groups being in the upper half of the gametophyte but not at its micropylar extremity. There is hardly a trace of a jacket layer, and no distinct complex. A very ephemeral ventral nucleus is cut off. The whole situation is more suggestive of *Sequoia* and the araucarians than of any other known forms.

Among the Araucarineae sufficient work has not been done to justify a general statement, but so far as known (117) the archegonia are numerous and scattered irregularly, as in *Sequoia*, and some of them are deep-seated, as in the same genus.

As the endosperm grows, the megaspore membrane grows also and thickens, finally differentiating into two layers, the outer one being completely suberized and the inner one containing cellulose. THOMSON (108) has made a comparative study of this membrane and finds it thickest and most completely developed among the Coniferales in the Abietineae; less developed by the Taxodineae and Cupressineae, among which it may be quite poorly developed, as in *Libocedrus* (131); while among the Araucarineae the suberized outer layer is wanting. He concludes that the condition of this membrane may be used as a test of the relative age of the gymnosperm groups, which when applied among Coniferales makes Abietineae the most ancient and Taxineae the most recent, in the latter tribe the megaspore membrane not appreciably developing.

Ordinarily the endosperm invades the tissue of the nucellus uniformly, but among the Araucarineae (121) this invasion may be irregular, resulting in an endosperm with a more or less dissected contour. This is the so-called "ruminated" endosperm, which of course is a misnomer, since it is the endosperm that is "ruminating" the nucellus. This unusual character among gymnosperms is also strongly developed by *Torreya*, in which connection it will be considered more in detail.

## THE MALE GAMETOPHYTE

The male gametophyte of Pinaceae has long been known in a general way, but the present knowledge of the functions of the cells dates from BELAJEFF's work in 1891 on *Juniperus* (33), and STRASBURGER's work in 1892 on a wider range of forms, notably *Larix* and *Cupressus* (38). Every year since has increased the number of forms observed, until now a fairly complete knowledge of the principal features of the male gametophyte is available. The onto-





FIG. 301.—*Pinus Laricio*: part of microsporangium showing mitosis in pollen mother cells, May 3;  $\times 500$ .

geny is comparatively uniform, so that a single account will include a general outline for all forms. For this purpose, the development of the male gametophyte of *Pinus Laricio* will be used.

About May 9 (in Chicago) the nucleus of the microspore of *P. Laricio* enlarges for the first division (fig. 305), a spindle is formed rapidly (fig. 306), and an equal division follows. Before the cell plate is organized, the nucleus nearer to the wall of the spore begins to disorganize, and the other begins to enlarge (fig. 307). In this way a lenticular and disorganizing cell is cut off against the spore wall (fig. 308). A second division follows immediately, the spindle being observed about May 25 (fig. 309). This division is a repetition

of the first in details, and the two lenticular cells disorganize rapidly (fig. 310), become flattened against the spore wall, and very soon



FIGS. 302-313.—*Pinus Laricio*: a series from the formation of tetrads to the development of the pollen tube; *p*, prothallial cells; *s*, stalk cell; *b*, body cell; *t*, tube nucleus; figs. 302, 303, May 3; fig. 304, May 10; figs. 305-308, May 20; figs. 309-311, May 25; fig. 312, June 15; fig. 313, May 1, nearly a year after the stage shown in fig. 312; the exine (*e*) is shaded with short radial lines, and the intine (*i*) with longitudinal lines;  $\times 600$ .



appear merely as two thin and darkly staining disks, which are overgrown rapidly by the intine. These two evanescent cells represent the only vestige of the vegetative tissue of the male gametophyte, and hence are called vegetative (sometimes prothallial) cells. It will be recalled that only one such cell appears among the cycads, and that it persists; while in *Ginkgo* two appear, the first disorganizing while the second one persists.

The third (large) cell, which is sister to the second evanescent vegetative cell, is an antheridial cell in the sense that it gives rise to the series of cells that represent the antheridium in function, but




FIG. 314.—*Pinus Strobilus*: microspore with nucleus in prophase of first division; the broad dotted portion of the wall was described as a third coat; June 7, 1898;  $\times 810$ .—After Miss FERGUSON (87).

not at all in structure. The division of this cell follows immediately, giving rise to the generative cell (cut off against the evanescent vegetative cells) and the tube cell (the larger portion of the antheridial cell, containing the tube nucleus). This conspicuous tube nucleus was regarded as the generative nucleus until 1891, when BELAJEFF (33) discovered its true function. The exine and intine are differentiated quite early, and both are thickest at the prothallial end of the spore (figs. 305–312). Miss FERGUSON (87) described a third coat, but it was evidently only the thicker intine of the basal region of the spore (fig. 314).

No further division takes place until the following spring, a period of about eleven months, and in this condition pollination occurs. As the pollen is being shed, a drop of mucilaginous substance secreted by the upper part of the nucellus appears at the apex of the ovule,

and the pollen, caught in this pollination drop, is conveyed to the nucellus (fig. 315). The pollen tube begins to grow into the nucellus as soon as the spore is deposited, and continues to develop until it is checked by cold weather. The next spring the tube begins to renew its penetration of the nucellus during April, about a year after the pollen mother cell entered upon the reduction divisions, the large tube nucleus enters the tube, and at the same time the generative cell divides into the stalk cell (toward the vegetative cells) and the body cell (toward the free cavity of the spore) (fig. 313). The stalk cell is sterile (persistently so among gymnosperms), and may represent the stalk cell of an antheridium, while the body cell may be the true primary spermatogenous cell. The pollen tube branches as it traverses the nucellus, not so extensively as do the tubes of cycads and of *Ginkgo*, but sufficiently to indicate its primitive haustorial function. After its second start, the pollen tube consumes about two months in traversing the nucellus, reaching the archegonium about the first of July.




FIG. 315.—*Cephalotaxus Fortunei*: pollination drops at the tips of the numerous ovules;  $\times 3.33$ .—After TISON (171).

The body cell rounds off, and becoming freed from the stalk cell passes into the tube. The separation of the body cell from the stalk cell frees the nucleus of the latter, and it also passes into the tube, where the nucleus of the body cell divides, forming two nuclei which do not become separated by a wall. The body cell, with its two nuclei, then passes down the tube, and when it has reached the tip, the four nuclei may be found grouped together, usually with the stalk and tube nuclei in advance. At this stage the contour of the body cell may be quite distinct (fig. 316), or rather indefinite (fig. 317), or its cytoplasm may have become so mingled with that of the pollen tube that the nuclei lie in a common mass of cytoplasm (fig. 318).

The division of the body cell occurs just before fertilization, about two months after the division of the generative cell into stalk and body

cells. The latter then divides and forms two equal male cells (as in *Taxodium*), or only two nuclei not separated by a wall (as in *Pinus*). It is this division which among cycads and in *Ginkgo* results in two sperm mother cells, which later produce and discharge two ciliated sperms. It is this contrast in spermatogenesis that must be



FIGS. 316-318.—Tips of pollen tubes containing the male nuclei: *m*, male nuclei; *n*, nuclei of tube and stalk cells; *s*, starch; fig. 316, *Pinus Strobus*; June 14, 1898; the body cell maintains its outline and the two male nuclei are unequal;  $\times 236$ ; after Miss FERGUSON (87); fig. 317, *Pinus Laricio*; the outline of the body cell is indistinct and the two male nuclei are equal;  $\times 500$ ; after COULTER (44); fig. 318, *Pinus Laricio*; somewhat later stage than that shown in fig. 317; the cytoplasm of the body cell has become continuous with that of the tube; the male nuclei are equal, and above them, but not shown, are the stalk and tube nuclei;  $\times 500$ ; after CHAMBERLAIN (51).


regarded as the most important contrast between Coniferales and the groups previously considered. In Coniferales a cell generation has been eliminated, and whether the daughter cells of the body cell (in forms like *Taxodium*) are called sperm mother cells or sperms makes very little difference. They are formed as are the sperm mother cells of the preceding groups, but they do not produce sperms; on the other hand, they function as sperms, but have no cilia. These non-ciliated cells, produced like mother cells and functioning like

sperms, are called for convenience simply *male cells*. The disappearance of the wall between the two male cells, leaving the male nuclei free in the cytoplasm of the body cell, represents a further stage in the reduction of the male element. The significant fact is the abandonment of the swimming sperm by Coniferales, and when one recalls the surprising persistence of swimming sperms in connection with the land habit, their final disappearance marks an epoch in the history of land plants. With the abandonment of swimming sperms, blepharoplasts in the body cell have disappeared, and the pollen tubes are utilized as sperm carriers.

The appearance of two evanescent vegetative (prothallial) cells is a feature only of the Abietineae, and even among them there is some fluctuation, the spores of *Picea excelsa* having been observed (114) to produce one to three such cells. Among Taxodineae and Cupressineae no such cells occur, the vegetative tissue of the male gametophyte having been eliminated completely. In these tribes, therefore, the first division of the pollen grain produces the generative and tube cells. The ephemeral nature of the prothallial cells in Abietineae suggested for a time that they had escaped observation in the two other tribes, but the evidence is now too complete to warrant any such assumption. Among Taxodineae the absence of prothallial cells is known for *Sciadopitys* (175), *Cunninghamia* (147, 180), *Sequoia* (64, 92), *Cryptomeria* (85, 93), and *Taxodium* (76); and among the Cupressineae it is known for *Callitris* (85), *Widdringtonia* (159), *Libocedrus* (131), *Thuja* (72, 86), *Cupressus* (85), *Chamaecyparis* (85), and *Juniperus* (85). Since this list includes twelve genera of the eighteen included in the two tribes, there is no reason to expect that vegetative cells will be found in the remaining genera. In this feature, therefore, the Abietineae are in a more primitive condition than are the two other tribes.

Among Araucarineae, however, there is still another prothallial situation (figs. 319-321). Two lens-shaped vegetative cells are cut off, as among Abietineae, but they are not ephemeral. LOPRIORE describes them (104) in *Araucaria Bidwillii* as giving rise to a tissue of about fifteen cells, whose walls presently disappear, freeing the nuclei, which then continue division, until twenty to forty-four (most frequently thirty-six) free nuclei were observed, no divisions occurring






FIGS. 319-321.—*Araucaria Bidwillii*: fig. 319, portion of the prothallial end of the pollen grain, showing two prothallial cells, each of which has divided, giving rise to numerous cells; the next division of the nucleus beyond the prothallial complex will give rise to the generative cell and tube nucleus;  $\times 666$ ; fig. 320, later stage, transverse section, showing body cell in the center surrounded by nuclei which have been set free by the breaking down of the walls of the prothallial cells;  $\times 666$ ; fig. 321, pollen tube with numerous nuclei; on so small a scale the male nuclei and prothallial nuclei could hardly be distinguished;  $\times 54$ .—After LOPRIORE (104).

after the pollen tube begins to develop. THOMSON (107) has also observed many supernumerary nuclei in the pollen tubes of *Araucaria*, as many as thirty being counted. It adds to the interest of this situation when it is known that the same condition exists among the Podocarpaceae (Taxaceae), although the prothallial tissue is not so extensive in that tribe. If the two-celled prothallial tissue of Abietineae indicates a more primitive condition than no prothallial tissue, as noted above, is the many-celled prothallial tissue of Araucarineae (and of Podocarpaceae) still more primitive? The only escape from an affirmative answer is to prove that the tissue formed by the two original vegetative cells is to be explained physiologically rather than phylogenetically; in other words, that it is ceno-genetic and not palingenetic (p. 230).

Another variation of general importance is that observed in the relative size of the two male cells produced by the body cell, and also in the completeness of their organization as cells. Among Taxodineae

(figs. 322-327) and Cupressineae (figs. 328-331) usually two equal male cells are produced, and both cells may function and have been observed (72, 173) to function, since fertilization occurs in an arche-



FIGS. 322-327.—Pollen tube structures of Taxodineae: fig. 322, *Taxodium distichum*; the two male cells with stalk and tube nuclei in advance;  $\times 540$ ; after COKER (76); figs. 323-325, *Cunninghamia sinensis*, fig. 323 showing the pollen grain with generative cell (no prothallial cells) and tube cell, fig. 324 the body cell with stalk and tube nuclei in advance, and fig. 325 the two male cells;  $\times 430$ ; after MIYAKE (147); figs. 326, 327, *Cryptomeria japonica*, fig. 326 showing the body cell with stalk and tube nuclei in advance, and fig. 327 the two male cells;  $\times 666$ ; after LAWSON (93).

gonial complex. Among the Abietineae, however, only one of the two male cells produced by a body cell can function, and this fact seems



FIGS. 328-331.—Pollen tube structures of Cupressineae: figs. 328, 329, *Thuja occidentalis*, fig. 328 showing the body cell with stalk and tube nuclei in advance, and fig. 329 the two male cells;  $\times 560$ ; after LAND (72); fig. 330, *Cupressus Goveniana*, end of pollen tube with complex of male cells, the stalk and tube nuclei in advance;  $\times 350$ ; after JUEL (91); fig. 331, *Libocedrus decurrens*, the two male cells; after LAWSON (131).

to be related to the tendency to eliminate one of the male cells. In *Tsuga canadensis* (60) one male cell becomes larger than the other.

In *Pinus* (65, 87) no wall is formed at the division of the body cell, the two male nuclei being free in the general cytoplasm, and one of them, according to Miss FERGUSON (87), soon becoming much larger than the other; a condition also observed in *Pseudotsuga* (156). In *Picea excelsa* (79) a cell plate appears on the spindle of the dividing body cell and at once disappears, leaving the two male nuclei free in the general cytoplasm. Just how far this tendency to eliminate one of the male cells has gone among the Abietineae remains to be discovered. An interesting test of this view has recently been supplied by LAWSON (175) in his study of *Sciadopitys*. The other genera of Taxodineae investigated have the archegonial complex and equal male cells; while *Sciadopitys* has no archegonial complex and unequal male cells. It is possible to mistake inequality of cells and of nuclei in preparations, so that unusual care will be needed in accumulating these facts, but the tendency is evident enough. In *Cupressus Goveniana* a remarkable situation has been reported (91), the body cell being said to give rise to a cell complex of four to twenty cells, eight or ten cells being the most frequent number (fig. 339). In *Juniperus communis* the body cell has been observed (173) occasionally to produce three or four male cells, but only two of them were considered capable of functioning. The only other cases known among gymnosperms, in which the body cell gives rise to more than two cells, are *Microcycas*, in which the body cell regularly produces sixteen or more sperms; and *Ceratozamia*, in which four sperms are formed occasionally (p. 147). The multiplication of male cells in such a form as *Cupressus*, with its large archegonial complex, might be expected, but at present no conclusions are safe in reference to these rare occurrences.

The condition of the male gametophyte at the time of pollination is of interest. The records are apt to be misleading if no consideration is given to the fact that some tribes have prothallial cells and others do not. So far as observed, the prevailing condition at shedding is the stage following the formation of the generative and tube cells. This means after one nuclear division among Taxodineae and Cupressineae, and after three divisions among Abietineae, but it is the same stage in the ontogeny of the gametophyte. Pollination at an earlier stage has been reported for *Cupressus* (86) and *Juniperus*



(86, 132, 157), that is, the uninucleate spore is shed; but in both these genera the division to form generative and tube nuclei occurs on the nucellus, before tube-formation. Pollination at a later stage has been reported for *Picea excelsa* (79), in which the next division has occurred, the generative cell having produced the stalk and body cells. In *Widdringtonia* (159, 176) the divisions are remarkably delayed. The spore is shed in the uninucleate condition, and since there are no prothallial cells there has been no division. Unlike *Cupressus* and *Juniperus*, however, whose pollen grains are shed in the same condition, the nucleus does not divide until after tube-formation, the generative and tube nuclei being observed only in the tubes. The single pollen tube penetrates the megaspore membrane and passes down inside of it for one-third to one-half the length of the gametophyte, and only after entering within the membrane does the generative cell divide. When the tube has reached the limit of its growth, its tip may contain only the large body cell, the stalk and tube nuclei having a tendency to disappear. Two of the numerous archegonia are fertilized by the two male cells.

The period that elapses between pollination and fertilization, which covers the activity of the pollen tube and the life of its contents, falls into two categories. One of them includes cases in which pollination occurs one season and fertilization the next. As has been mentioned (p. 275), this is true of *Pinus Laricio*, in which pollination occurs in June and fertilization about July first of the following year. It is also true of *Juniperus communis* (132, 157, 173), which has about the same period; and in both cases the generative cell does not divide until the second season. In *Sciadopitys*, however, LAWSON (175) reports that the generative cell divides during the first season into the body cell and a free stalk nucleus, and that the division of the body cell and fertilization do not occur until the second season. In *Widdringtonia*, also, SAXTON (176) reports that fourteen or fifteen months elapse between pollination and fertilization. In many other forms approximately the same periods have been observed. These long periods may escape recognition unless there is familiarity with the condition of adjacent structures and especially of the female gametophyte, for two similar pollen tubes may belong to two different seasons.

The other category includes the cases in which pollination and fertilization occur during the same season. The records of these cases show considerable variation in the time of pollination, but remarkable uniformity in the time of fertilization, which falls in general between the middle of June and the middle of July. The period of pollen tube activity varies approximately as follows: *Sequoia* (92) and *Cryptomeria* (93) about fifteen weeks; *Cunninghamia* (147, 180) about twelve weeks; *Pseudotsuga* (156) about eight weeks; *Tsuga* (60) about six weeks; *Thuja* (72) and *Picea* (79) about four weeks. This perhaps fairly expresses the range of variation within a season, which allows for pollination from early in January to early in June. It is evident that this feature holds no relation to tribes, either in reference to periods of one season or of two seasons; or in reference to the longer and shorter periods of the single season; nor does the time of pollination seem to affect the time of fertilization.

The course of the pollen tube is various. Sometimes it is very direct through the nucellus to the archegonia, as in *Cryptomeria* (93), and probably in all forms with short periods; sometimes it is devious and branching, especially in forms with long periods; and in *Sequoia* (92) the tubes penetrate between integument and nucellus, as well as directly to the nucellus. In *Widdringtonia* (159) the solitary pollen tube, after piercing the megaspore membrane, passes down the surface of the endosperm for one-third to one-half its length, and fertilizes the deep-seated and laterally placed archegonia (p. 271). In *Pseudotsuga* (156) the pollen grains germinate in the outer micropylar chamber (p. 253), and the numerous tubes pass in a tangle through the inner chamber on their way to the apex of the nucellus, which disintegrates in advance of the approaching tubes, so that there is little or no resistance to their passage. In this case it is an interesting fact that the body cell divides before the tip of the pollen tube reaches the nucellus. Among the Araucarineae THOMSON (107, 121) has made the interesting observation that the pollen grains are lodged on the ligule in *Araucaria* and on the bract nearer the micropyle in *Agathis*, and in this position send out their tubes, which grow along the surface of the ligule or bract for some distance before entering the micropyle.

Certain unusual occurrences in the course of spermatogenesis have been observed, which may be mentioned. COKER (86) observed

a number of cases in *Larix europea* in which there is only one division in the spore mother cells, resulting in two daughter cells that function as microspores in the production of male gametophytes. This condition finds its parallel in the development of certain female gametophytes among angiosperms in which the second or both of the reduction divisions occur as the first divisions of the ordinary gametophyte, which in such a case is really formed by two or four megaspores. This case of *Larix* suggests that the second reduction division occurs in connection with the first division of the so-called microspore, and that two spores enter into the formation of the gametophyte. The same observer has also reported (86) that the generative cell is often free in the cytoplasm of the tube cell in *Cupressus*. In *Cunninghamia* MIYAKE (147, 180) observed that in the division of the generative cell no wall is formed, and the bulk of the cytoplasm is organized in connection with the body nucleus, the stalk nucleus lying free in the cytoplasm of the tube; and the same observation has been made by NICHOLS (173) in *Juniperus communis*, and by LAWSON (175) in *Sciadopitys*. This reduction is like that described by HIRASÉ for *Ginkgo* (p. 208), and may possibly presage the final elimination of the stalk cell.

#### FERTILIZATION

The tip of the pollen tube having reached the megaspore membrane either penetrates it directly or flattens out upon it in a footlike expansion, sending out a small branch to pierce the membrane. The body cell divides about simultaneously with the central cell, so that the egg and the male cell are produced a very short time before their fusion; in *Juniperus communis* this period has been observed (173) to be approximately three days. In the case of isolated archegonia (*Abietineae*), the tube reaches the neck of the archegonium, crushes the neck cells, and comes into contact with the egg; in the case of an archegonial complex, the tube usually discharges its contents into the common archegonial chamber.


In addition to the two male cells, the tube contains the stalk and tube nuclei, and in general all four bodies are discharged into the cytoplasm of the egg, or into the chamber of an archegonial complex. In the latter case, two eggs are usually fertilized from a single pollen

tube, as in *Thuja* (72), *Taxodium* (76), *Sequoia* (92), *Cryptomeria* (93), *Libocedrus* (131), and *Juniperus* (173). The non-functioning male cell and the stalk and tube nuclei, which are carried into the peripheral region of the cytoplasm of the egg, gradually disintegrate there, but sometimes the male cell and the tube nucleus have been observed to divide amitotically, as in *Pinus* (66, 87). In the case of an archegonial complex, stalk and tube nuclei disintegrate in the chamber. A peculiar discharge of male cells is described by LAWSON (92) for *Sequoia sempervirens*, the male nuclei invested by very little cytoplasm passing out of the tube and leaving behind the enucleated male cells, which retain their form in the tube.

In general, the functioning male nucleus slips out of its cytoplasm in the peripheral region of the egg, and passes to the egg nucleus, increasing somewhat in size. This behavior has been observed in *Pinus*, *Thuja* (72), *Cryptomeria* (93), *Juniperus* (95), and *Libocedrus* (131). In *Taxodium* COKER (76) observed the complete male cell pass to the egg nucleus and infold it, the starch of the male cytoplasm being seen distributed uniformly about the fusion nucleus, and even accompanying it to the base of the egg. The same phenomenon has been observed recently by NICHOLS (173) in the fertilization of *Juniperus communis*.

In fusion, the male nucleus presses inward the limiting membrane of the female nucleus, and the two remain distinct for some time (fig. 332). Evidence is accumulating that there is no fusion of the male and female chromatic substance, the two chromatic groups being distinct in *Larix* (54), *Pinus* (51, 87) (figs. 332-337), *Tsuga* (60), *Juniperus* (132, 173), and *Cunninghamia* (180) (figs. 338-340). In *Pinus* the chromatin is in the resting stage as the pairing nuclei come into contact; but as the sperm nucleus begins to penetrate, both nuclei form distinct spirems, each of which breaks up into 12 chromosomes, the two groups remaining recognizable until the nuclear plate stage. As the 24 chromosomes become oriented in the nuclear plate, the two groups can no longer be distinguished, and it is impossible to determine whether any given chromosome was contributed by the sperm or by the egg. The chromosomes now split longitudinally and 24 go to each pole, where the two daughter nuclei pass into the resting condition. Consequently, there is no fusion of chromatin





FIGS. 332-337.—Fertilization in *Pinus*: fig. 332, *P. silvestris*, the sperm nucleus entering the egg nucleus, June 19;  $\times 135$ ; after BLACKMAN (46); fig. 333, *P. Laricio*, the chromatin of the sperm and egg nuclei in the spirem stage within the limits of the egg nucleus;  $\times 500$ ; after CHAMBERLAIN (51); figs. 334-337, *P. Strobus*; fig. 334, a somewhat later stage than that shown in fig. 333; fig. 335, the spirems of the egg and sperm nuclei after segmentation; fig. 336, the two spirems after segmentation; the two halves of the spindle seem to indicate the paternal and maternal parts of the mitotic figure; fig. 337, longitudinal section, showing the orientation of chromosomes at the nuclear plate, the egg and sperm chromosomes no longer distinguishable;  $\times 315$ ; after Miss FERGUSON (87).

during fertilization in the various species of pines which have been studied. In *Tsuga* it is stated that the two sets of chromosomes are associated, but remain distinct in the equatorial region of the first spindle. In *Juniperus*, while there are slight differences in details, the essential features are quite similar. Whether this independence



FIGS. 338-340.—Fertilization in *Juniperus communis*: fig. 338, chromatin of sperm and egg nuclei in late prophase within the limits of the egg nucleus; fig. 339, later stage in which the egg and sperm chromosomes are no longer distinguishable; fig. 340, first division of fertilized egg;  $\times 520$ .—After NORÉN (132).

of male and female chromatin continues into succeeding cell generations or not is a most important question. In his investigation of *Sequoia sempervirens*, however, LAWSON (92) concluded that in fusion the two chromatic masses form a common network, in which the male and female constituents become indistinguishable.

#### 4. The embryo

The development of the embryo, as in the preceding groups, includes two general stages: (1) the development of the proembryo, which is the preliminary tissue developed in the base of the egg; and (2) the growth of the suspensor into the endosperm and the development of the embryo proper at its tip. Among Pinaceae the proembryo is a much less extensive tissue than among Cycadales and Ginkgoales, being a few cells at the base of the egg, the bulk of the egg functioning

as a food reservoir. Since there seems to be a general tendency among gymnosperms to reduce the proembryonic stage of the embryo, the Pinaceae may be regarded as a more advanced group in reference to this character than the preceding ones.

#### THE PROEMBRYO


The development of the proembryo of *Pinus Laricio* may be taken as an illustration (figs. 341-349). The fusion nucleus retains its central position in the egg, and organizes the largest spindle of the free nuclear series. It is worthy of note that this first spindle is almost always oblique (fig. 341). The two daughter nuclei are very small



FIG. 341.—*Pinus Laricio*: first division of the nucleus of the fertilized egg; the entire mitotic figure is intranuclear; the two daughter nuclei resulting from this division are the first two nuclei of the sporophytic generation;  $\times 500$ .—After CHAMBERLAIN (51).

at first, but increase rapidly in size, and then divide simultaneously. The resulting four free nuclei, after increase in size, pass to the base of the egg, where they become arranged in a single plane (figs. 343, 344). There follows a simultaneous transverse division, which results in two tiers of nuclei, with four nuclei in a tier (figs. 344-346). With this division the first transverse walls appear in connection with the spindles, and almost at the same time vertical walls are formed in each tier on secondary transverse fiber connections established between the nuclei (129) (figs. 350-352). This appearance of walls at the eight-nucleate stage of the proembryo is a remarkably constant feature of the Pinaceae. The older accounts of


*Pinus* introduce vertical walls at the four-nucleate stage, but it is now discovered that a meshwork of fibrils was interpreted as a wall (fig. 350). It must be understood that the first walls do not appear after eight free nuclei are organized, but in connection with the organization of the eight-nucleate stage. The lower tier of four cells is completely walled, but the upper tier is open above, so that the nuclei are freely exposed to the general cytoplasm of the egg.




FIGS. 342-349.—*Pinus Laricio*: early stages in the development of the sporophyte; the term proembryo applies to all the stages except that shown in the last figure; fig. 342, the chromatin of the egg and sperm nuclei within the limits of the egg nucleus, shown on a larger scale in fig. 333; fig. 343, first four nuclei of proembryo, also numerous proteid vacuoles (*p*, pollen tube; *n*, cavities caused by inrush of contents of pollen tube, or according to Miss FERGUSON they are receptive vacuoles); fig. 344, the four nuclei (two shown) dividing at base of egg; fig. 345, eight-celled stage; fig. 346, somewhat later stage; fig. 347, last division of proembryo; fig. 348, the complete proembryo, with four tiers of cells, four cells in a tier; *r*, rosette tier; *s*, suspensor tier; fig. 349, suspensor tier beginning to elongate; figs. 342-344, from material collected June 25; figs. 345-348, July 2;  $\times 104$ .




The next division may occur in either tier, but usually in the upper (open) one, resulting in three tiers of cells, two of which are inclosed by walls. Still another division, usually in the lowest tier (fig. 347), results in four tiers, and with this division the proembryo is com-



350



351




352

FIGS. 350-352.—*Pinus Laricio*: three stages in the formation of the proembryo; fig. 350, four nuclei (two shown) at base of fertilized egg, showing the fibers which had been mistaken for a wall;  $\times 225$ ; fig. 351, division of the nuclei shown in previous figure, indicating that no wall is formed at the four-nucleate stage;  $\times 355$ ; fig. 352, late telophase of the mitosis the anaphase of which is shown in the previous figure; the transverse walls are nearly complete and the vertical walls, formed on the radiating fibers which are already becoming conspicuous in fig. 351, are developing;  $\times 350$ .—After Miss KILDAHL (129).

plete (fig. 348). It consists, therefore, of twelve walled cells and four open ones, arranged in four uniform tiers of four cells each. The functions of the tiers are definitely distributed; the lowest forming the embryo proper, the tier next above elongating to form the suspensor, and the third walled tier constituting the so-called "rosette,"

which is the plate or group of proembryonic cells remaining within the egg and mediating between the food supply of the egg and the suspensor. The size and generally active appearance of the four uppermost nuclei, exposed to the cytoplasm of the egg, indicate that they must remain functional for some time.

This account of the proembryo of *Pinus* probably applies equally well to all the Abietineae, although the account is not full for any other genera except *Picea* (79) and *Pseudotsuga* (156). The other



FIGS. 353-355.—Proembryo of Taxodineae: fig. 353, *Taxodium distichum*, sixteen-celled embryo in three tiers, six cells in rosette, six in suspensor, and four below;  $\times 280$ ; after COKER (76); fig. 354, somewhat later stage of same;  $\times 375$ ; after ARNOLDI (64); fig. 355, *Cunninghamia sinensis*, proembryo of three tiers of cells;  $\times 145$ ; after MIYAKE (147).

tribes have received the chief attention recently, and deserve some separate mention.

Among the Taxodineae, the proembryo of *Cryptomeria* (64, 93), *Taxodium* (64, 76), *Sciadopitys* (64, 175), *Sequoia* (92), and *Cunninghamia* (147, 180) have been investigated (figs. 353-355). In all of them, with the exception of *Sequoia*, wall-formation occurs at the appearance of the eight-nucleate stage, but there is considerable variation in the passage of free nuclei to the base of the egg, even in the same form. For example, in *Cryptomeria* one observer (64) reports that the fusion nucleus passes to the bottom of the egg, while another observer (93)

reports that four free nuclei (in one case six) pass to the bottom. There is agreement that the fusion nucleus of *Taxodium* passes to




FIG. 356.—*Sequoia sempervirens*: first division of the fertilized egg, showing a wall forming between the two daughter nuclei;  $\times 500$ .—After LAWSON (92).

the bottom of the egg before division; while in *Cunninghamia* this position is taken at the two-nucleate stage, and in *Sciadopitys* at the four-nucleate stage (as in *Pinus*). The indications are that this movement occurs at any time before wall-formation, but most frequently after two divisions.

In general, also, the completed proembryo consists of three tiers of cells instead of the four observed in *Pinus*, the "rosette" tier not being present. The tiers may not contain the same number of cells, as the proembryo of *Taxodium* will illustrate. Preceding wall-formation the eight nuclei are arranged in two tiers, the upper containing six cells, the lower two. There is only one division of tiers after wall-formation, which divides the upper tier into the suspensor cells and the open cells; at the

same time, the two basal cells divide by vertical walls to a tier of four cells. The completed proembryo, therefore, consists of six open cells, six suspensor cells, and four embryo cells.

The case of *Sequoia sempervirens* (92) is very peculiar among Pinaceae. There is no free nuclear division at all, a wall being formed at the first division, which results in two cells nearly filling the egg (fig. 356). Succeeding divisions result in a linear row of five large cells, the lowest forming the embryo, and the next upper one elongating to form the suspensor. The elimination of the free nuclear stage and the complete occupation of the egg by a few embryonal cells are facts difficult to relate at present.



FIG. 357.—*Sciadopitys verticillata*: secondary suspensors.—After ARNOLDI (64).

The case of *Sciadopitys* (64, 175) presents an interesting variation, but it is not so fundamental a difference as that shown by *Sequoia*. The four tiers of the proembryo, as in *Pinus*, consist of open cell, rosette, suspensor, and embryo tiers, but the last is represented by




FIGS. 358-360.—*Thuja occidentalis*: proembryo and early embryo; fig. 358, mitoses giving rise to eight nuclei; the first walls appear in connection with this mitosis; *v*, ventral canal nucleus; fig. 359, later stage, after the organization of tiers; fig. 360, continued elongation of the suspensor;  $\times 425$ .—After LAND (72).

a loose group of cells, which LAWSON (175) says become about sixteen in number. The terminal cells of this group form the embryo, those just above form a secondary suspensor, and there are still some loose cells between the two suspensor regions (fig. 357).

Among the Cupressineae the proembryos of *Thuja* (72) (figs. 358-360), *Juniperus* (95, 132) (figs. 361-363), and *Libocedrus* (131) have been investigated. In all of them wall-formation occurs



at the eight-nucleate stage; but in *Thuja* and *Libocedrus* the nuclei pass to the bottom of the egg after the first division, and in *Juniperus* the fusion nucleus takes this position before dividing. Whether this indicates a general situation among the Cupressineae or not remains to be seen. As among the Taxodineae, the proembryo consists of three tiers of cells, the uppermost one being open above, but its nuclei



FIGS. 361-363.—*Juniperus communis*: proembryo and early embryo; fig. 361, suspensor beginning to elongate;  $\times 430$ ; fig. 362, about the same stage; the large nucleus at the top is "presumably the ventral canal nucleus";  $\times 405$ ; fig. 363, continued elongation of suspensor;  $\times 230$ .—After NORÉN.

soon disintegrate in *Thuja*. The four cells of the embryo tier in *Thuja* are not in one plane, having a tetrahedral arrangement. In *Widdringtonia* and *Callitris* (159, 176) the details of proembryo-formation have not been observed, but the completed proembryo completely fills the egg with a tissue of eight or more cells, resembling in general the proembryo of *Sequoia*. SAXTON states (176), furthermore, that walls appear in the proembryo of *Widdringtonia* before the eight-nucleate stage, which probably means that they appear during

the transition from the four-nucleate to the eight-nucleate stage, as in most Pinaceae. Only one of the cells of the proembryo develops the embryo, and the one next above forms the long suspensor, while the other proembryonal cells soon disappear.

In these three tribes of Pinaceae, therefore, the proembryo consists of twelve to sixteen cells, arranged in three (Taxodineae and Cupressineae) or four (Abietineae) tiers, the fewer cells belonging to the Cupressineae; a statement that must exclude *Sequoia*, *Widdringtonia*, and *Callitris*. Unfortunately, the proembryo of none of the Araucarineae has been investigated.

#### THE SUSPENSOR AND EMBRYO

The suspensor cells elongate enormously, thrusting the embryo cells into the endosperm, and usually becoming very long and tortuous (figs. 364, 365). In such cases as *Pinus*, in which there is a suspensor cell for each of the four embryo cells, four separate embryos may begin to develop, which is the usual method, or all four cells may form a single embryo. Even in such cases as *Taxodium*, in which there is inequality in the number of suspensor and embryo cells, the former may or may not separate from each other, resulting in one or more embryos. Of course in such a case as *Thuja*, in which the embryo cells are not in one plane, and one of them is terminal, a single embryo is formed. Even a single embryo cell may give rise to two embryos, if the first division is vertical and the two daughter cells become organically dissociated. The indifference of these cells in reference to embryo-formation is very marked, an embryo being formed by a group of proembryonic cells (the "embryo tier"), by any member of this group, or even by its daughter cell.

In many of the Pinaceae "embryonal tubes," haustorial in function, are developed from the basal cells of the embryo, and are found investing the end of the suspensor and the base of the embryo, sometimes being exceedingly numerous and conspicuous (figs. 365, 366).

There is no definite sequence in the early divisions of embryo-formation. Transverse or vertical walls may occur at any division, although in the case of an embryo developing from a single cell the first two or three divisions are generally transverse. The organization of the great body regions has not been investigated, so that between



FIGS. 364, 365.—*Pinus Laricio*: two embryos with long suspensors; in fig. 365 three young embryonal tubes may be seen between the embryo proper and the end of the suspensor.

the earliest divisions and the beginning of the vascular system of the seedling there is a hiatus in our knowledge.

The only information in reference to the embryo of the Araucariaceae is an early account of *Araucaria brasiliana* by STRASBURGER (25) (figs. 367, 368). The stem tip is not terminal, but is covered by a small group or layer of cells which is soon thrown off, and seems for a time to serve as an organ of penetration or protection. This terminal group of cells shifts the usual functions of the tiers of the proembryo, the lowest tier developing this embryo cap, the middle tier producing the embryo, the tier next above (ordinarily the rosette) forming the suspensor. It is an interesting fact that this same feature is found also in the embryo of *Cephalotaxus Fortunei* (25) (figs. 369, 370).

The origin of the testa is but little known in detail, but the region of its development may be seen in fig. 275. Next to the endosperm is a dry, membranous layer derived from fleshy tissue; outside this is the hard layer, which in the upper region, at least, comes from the middle layer of the integument; the outermost layer, dry and incomplete, comes from fleshy tissue (fig. 371).

The number of cotyledons among Pinaceae, involving as it does the origin of polycotyledony, is an interesting and important topic. The Bennettitales, Cycadales, and Ginkgoales have given the impression that the primitive number of cotyledons is two, but this still remains an open question. Among the Pinaceae the number varies from two to fifteen, and the fluctuations hold no relation to the tribes, except that the higher numbers are characteristic of the Abietineae, in which the recorded range is three to fifteen. Among the Taxodineae the range is two to six, two cotyledons appearing quite uniformly in *Sciadopitys*, *Cunninghamia*, *Sequoia sempervirens*, and *Arthrotaxis*; two or three in *Cryptomeria*; and three to six in *Sequoia*





FIG. 366.—*Taxodium distichum*; apparently three embryos in a group uniting to form a single embryo; the embryonal tubes are conspicuous;  $\times 180$ .—After COKER (76).



*gigantea*. Among the Cupressineae the range is two to five, two being usual in *Thuja*, *Callitris*, *Widdringtonia*, and *Actinostrobus*; two or three in *Libocedrus*; and the whole range of two to five in the various species of *Juniperus* and *Cupressus*. Among the Araucarineae, *Agathis* has two cotyledons, and *Araucaria* two to four. These numbers will doubtless vary upon wider acquaintance with the forms, but they serve to illustrate that the fluctuations occur not only between tribes, but also within tribes and genera, and even species.




FIGS. 367, 368.—*Araucaria brasiliensis*: a proembryo filling the entire egg; only the shaded cells belong to the embryo proper, the wedge-shaped mass of cells below being the embryo cap; fig. 368, later stage, showing the wedge-shaped mass of cells being thrust aside;  $\times 153$ .—After STRASBURGER (25).

The explanation of this variation is difficult, but there seem to be two alternatives: either the polycotyledonous condition is derived from the splitting of two ancestral cotyledons (141, 154), or the dicotyledonous condition is derived from the fusion of more numerous cotyledons. In other words, it is a question whether polycotyledony is primitive or derived.

The argument for the derivation of polycotyledony from dicotyledony has been developed by HILL and DE FRAINE (141, 154). This belief dates from ADANSON and JUSSIEU, and was supported by

DUCHARTRE (5) and DANGEARD (36), the former calling attention to the inconstancy in the number of the cotyledons of polycotyledonous forms, and to the lack of any direct relation between these numbers and the connecting vascular strands. SACHS (27) and MASTERS (34) opposed this view, and so opinion has long been divided. HILL and DE FRAINE find that among the Taxaceae and many Cupressineae the cotyledons are definitely two, each (except in podocarps) with a single vascular strand, and the root is diarch from the first. Among the Abietineae, in which there are three to many cotyledons, the vascular strand is single and the primary root structure is diarch, triarch, tetrarch, etc., the number of protoxylem poles bearing no obvious relation to the number of cotyledons, and variations occurring in the same plant. This lack of relationship between the number of cotyledonary strands and of root poles was noted by CHAUVEAUD (68), who found in *Pinus maritima* such combinations as five cotyledons and a pentarch root, seven cotyledons and a tetrarch root, etc., the cotyledons in general being more numerous than the root poles. The argument further appeals to the occurrence of partially split cotyledons (*Cupressus torulosa*, *Abies sibirica*, *Pinus montana gallica*, *Araucaria Cunninghamia*), and to the fact that the cotyledons are often obviously in groups. Cases of transition are also cited, in which the strands are more or less divided, and this is accompanied by division of the cotyledon. As an illustration of this, three entire cotyledons were found in *Pinus contorta Murrayana*, one of which was much larger than the others and contained two separate strands, the conclusion being that one cotyledon had split into two and the other had remained entire. In the case of the higher numbers of cotyledons,



FIGS. 369, 370.—*Cephalotaxus Fortunei*: fig. 369, proembryo still within the egg; fig. 370, later stage showing the elongated suspensor (s);  $\times 63$ .—After STRASBURGER (25).

the origin by splitting becomes difficult to explain, and it is believed that in some cases the number may be increased by the coming in of extra primordia, probably displaced from the first stem node to the cotyledonary node. The occurrence of more or less complete cotyledonary tubes was also found to be quite general, twenty species being cited.




FIG. 371.—*Pinus Laricio*: diagram of longitudinal section of seed; the three layers of the seed coat are not separated from each other as shown in the diagram, but are tightly appressed, and the outer may be quite incomplete; *n*, remains of nucellus; *i*, remains of inner fleshy layer; *s*, hard layer; *o*, remains of the outer fleshy layer.

On the other hand, it must be remembered that these same facts may be used also as an evidence that the dicotyledonous condition has arisen from the fusion of more numerous cotyledons. It is evident that the question is at present an open one, but it must be remembered that probably our oldest group of Coniferales, older even than the Cycadales and Bennettitales with which we are acquainted, is the extreme illustration of polycotyledony, while the youngest of the Coniferales are dicotyledonous or nearly so.

It has long been expected that parthenogenesis would be found to occur among the Pinaceae, and recently SAXTON has reported (158) that *Pinus Pinaster* ("cluster pine"), growing at Cape Town, is parthenogenetic, the nucleus of the egg dividing, and the divisions continuing to all stages of the proembryo, when there was no trace of pollen tubes in the nucellar cap, or tubes containing no nuclei were only part way through the nucellus. The series was close enough, and the comparison with stages in the normal embryo complete enough, to make the conclusion reasonably safe.

HAYDON (126) has made an interesting comparison between the theoretical and actual output of an ovulate strobilus of *Pinus silvestris*. It seems that such a strobilus might produce theoretically about 1,500 proembryos, which means that number of successfully fertilized

eggs; but that actually it produces 10 to 20 good embryos in as many seeds.

### 5. Distribution

The geographic distribution of Coniferales as a whole is in striking contrast with that of Cycadales, the former belonging to the temperate regions of both northern and southern hemispheres, and the latter belonging to the tropics and subtropics. The Pinaceae are massed chiefly in the northern hemisphere, and there is no crossing of the tropical belt by any genus except *Libocedrus*, which extends far into temperate South America by way of the Andes, and reaches Australia through the East Indian region. The main facts of distribution may be stated in connection with the tribes.

The Abietineae, including more than half the species of Pinaceae, are almost exclusively northern; the dominant genera, distributed throughout the temperate regions of the northern hemisphere, being *Pinus*, *Abies*, *Picea*, and *Larix*, genera which include 115 of the 129 species of Abietineae. China contains two endemic genera (*Pseudolarix* and *Keteleeria*) and North America one (*Pseudotsuga*); while *Tsuga* is North American and Asiatic, and *Cedrus* is Asiatic and North African. Both structure and distribution indicate a very natural group, which forms the chief gymnospermous forest display of the northern hemisphere.

The Taxodineae are a remarkable group geographically, for all the genera, eight in number, are narrowly restricted in range, and three of them are monotypic. If the tribe is at all natural, the distribution indicates a former wide extension, represented now by thirteen species in eight widely scattered and endemic genera. Four genera (*Sciadopitys*, *Cunninghamia*, *Taiwania*, and *Glyptostrobus*) occur only in the China-Japan region; two genera (*Sequoia* and *Taxodium*) are found in restricted areas of North America; while the remaining genus (*Arthrotaxis*) belongs to the southern hemisphere (Tasmania and Victoria). This distribution seems unnatural for a natural tribe, especially when contrasted with the distribution of Abietineae.

The Cupressineae are almost as remarkable in their distribution as the Taxodineae. Two genera, including more than half the species, range widely through the northern hemisphere, *Juniperus* belonging to the whole north temperate region, and *Cupressus* occurring in



North America (including Mexico), southeastern Europe, and temperate Asia. *Thuja* and *Chamaecyparis* belong to North America and the China-Japan region, the former extending into central Asia; and *Thujopsis* is endemic in Japan. Four genera belong to the southern hemisphere, *Actinostrobus* and *Callitris* being restricted to the Australasian region, *Widdringtonia* occurring in equatorial and southern Africa, and *Fitzroya* with one species in southern Chili and the other in Tasmania. *Libocedrus* girdles the Pacific, being the only genus represented in both the northern and southern hemispheres, the general outline of its range being California, Chili, New Zealand, Australia, China, and Japan.

The Araucarineae are exclusively southern, *Agathis* belonging to the Malay Archipelago and the Pacific islands to New Zealand, and *Araucaria* occurring not only in the Australasian region but also in South America. This tribe is as characteristic of the southern hemisphere as are the Abietineae of the northern hemisphere.

By far the greatest display of Pinaceae in genera and species is that which borders the Pacific Ocean, the chief areas being western North America, the Australasian region, and the China-Japan region; and throughout the whole of this vast border region *Libocedrus* is represented.

The China-Japan region is notable for its eight endemic genera, six of which are monotypic (*Pseudolarix*, *Sciadopitys*, *Cunninghamia*, *Taiwania*, *Cryptomeria*, and *Thujopsis*), and the remaining two are each represented by two species (*Keteleeria* and *Glyptostrobus*). That such an assemblage of the genera of Pinaceae should have been preserved in this region after they had become extinct elsewhere is remarkable. The wealth of the coniferous flora of this region may be appreciated when it is understood that 87 species and 23 genera of Coniferales have been recorded from China (113, 146), 42 of the species being endemic; while in Japan 48 species are recorded, 15 of which are endemic.

Four of the genera of Pinaceae (*Arthrotaxis*, *Actinostrobus*, *Callitris*, and *Agathis*) are endemic in the Australasian region; and three (*Pseudotsuga*, *Sequoia*, and *Taxodium*) in North America.

These general facts of modern distribution can only be understood in connection with the more ancient distribution of genera and tribes,

but the history of the Pinaceae is not in a condition as yet to supply such definite information.

## 6. History

The Coniferales are certainly very ancient, for remains of undoubted conifers occur from the later Paleozoic (Permian) on, and the total amount of material is enormous. Efforts have been made to determine the material upon the basis of anatomical structure, and the literature of paleobotany is full of names suggestive of affinities with modern genera, but the results have been disappointing. Beautifully preserved coniferous wood is common in Mesozoic deposits, but no means have been found to determine, without peradventure, even the tribes to which it belongs. Even the strong superficial resemblances of leaf-bearing twigs and cones cannot be relied upon to determine affinities. For example, HOLLICK and JEFFREY (155) have found that cretaceous coniferous remains referred with considerable confidence to Cupressineae, Podocarpineae, and *Sequoia* really belong to Araucarineae.

It would be a matter of very great interest if the affinities of the permian conifers could be determined, for it would go far toward determining the genetic relationships of the modern tribes. Recently new methods have been introduced, in connection with the study of mesozoic material, which promise to bring much nearer the knowledge of affinities, and with it some knowledge of the evolution of this most important group of gymnosperms.

In 1900 SCOTT concluded (61) that there was no sure evidence of Abietineae below the Cretaceous. In the Wealden (lowest Cretaceous) there are dwarf shoots bearing fascicles of needle leaves, which are so characteristic of *Pinus* as to leave no doubt that forms allied at least to that genus existed; and at the same horizon abietineous wood occurs. Later ZEILLER and FLICHE (82, 88) reported the discovery of pine cones in the Jurassic of France. The discovery was interesting not only because it brought to light the oldest known pines, but also because the cones represented the two main series of existing pines (*Strobus* and *Pinaster*), and therefore the pines were already well differentiated in the Jurassic. Recently NATHORST (148) announced the discovery of numerous winged pollen grains

from the Triassic of Sweden, and concluded that pines flourished at that time. These discoveries carry the Abietineae, represented by *Pinus* and allied forms, through the Mesozoic, in a position to be connected with paleozoic gymnosperms. It must be recognized that cones and even winged pollen grains may not be sure evidence of Abietineae during the early Mesozoic, but they must be regarded as at least probable evidence.

The more detailed connection of living Abietineae with the paleozoic Cordaitales has been made by JEFFREY (142) in his investigations of the gymnosperm remains from the Cretaceous of Staten Island (N.Y.), partly in connection with CHRYSLER (112) and HOLLICK (155). The investigations involved the development of a special technic in the treatment of fragments obtained from clay pits. The wood of these pines of the Middle Cretaceous, known as *Pityoxylon*, differs from that of living pines in the absence of marginal ray tracheids, highly resinous rays, and an association of certain features of hard and soft pines. It is inferred that these characters are ancestral for *Pinus* since they persist in the cones of existing species (112). It was in connection with an investigation of the structure of the leaves of cretaceous pines, however, that the most interesting connection was made, for it resulted in the recognition of what is regarded as the direct ancestor of *Pinus*, which received the generic name *Prepinus* (142). This interesting form had deciduous dwarf shoots bearing numerous spirally arranged leaves, whose structure is most suggestive. There are paired resin canals continuous to the very base, well-marked centripetal xylem, and about the vascular bundles a complicated double sheath of transfusion tissue resembling that found in the leaves of some Cordaitales. Many of the true pines of the Cretaceous were found to have this sheath, but not the centripetal xylem; and JEFFREY regards the tissue adjacent to the protoxylem in the leaves of existing pines as a relic of the inner transfusion sheath rather than of centripetal xylem (p. 10). In this way a connection is established between living pines and paleozoic Cordaitales through cretaceous pines and *Prepinus*. If this connection is trustworthy, the Abietineae are as old as any tribe of the Pinaceae can be, and *Pinus* is the oldest genus.

If *Sequoia* be excluded from the Taxodineae, there is no evidence

of the existence of that tribe before the end of the Cretaceous. Until recently, the oldest claim made for *Sequoia* was its occurrence in the Wealden (lowest Cretaceous) of Portugal; but ZEILLER and FLICHE (82, 88) have announced cones of *Sequoia* from the Jurassic of France, which represent both the *S. gigantea* and the *S. sempervirens* types, and therefore the genus was already differentiated in the Mesozoic. Much doubt has been thrown upon these determinations by increasing knowledge in reference to the extensive araucarian flora of the Mesozoic, for cretaceous forms referred to *Sequoia* have proved to be araucarian. Of still greater uncertainty is *Voltzia* of the Upper Permian and Triassic (61), which has been referred to the Taxodineae on the evidence of certain vegetative and cone characters, the cone scales being said to be two-lobed as in *Cryptomeria*. With the triassic *Voltzia* and the jurassic *Sequoia* in a state of uncertainty, the only safe conclusion is that Taxodineae are not older than the Cretaceous and that the most certain remains are those of the Tertiary.

The same statement may be made for Cupressineae, for although *Cupressus*-like twigs and cones have been described from the Jurassic, there is no reliable evidence of the tribe earlier than the Upper Cretaceous.

It is clear, therefore, that the Abietineae are much older than the Taxodineae and Cupressineae, and this historical relation favors the view that these two tribes have come from abietineous stock.

The Araucarineae are rival claimants with the Abietineae for antiquity, and the question as to the relationship of these two tribes is of great interest. It is now known that there existed an extensive araucarian flora during the Mesozoic, and that this was probably the dominant type of Coniferales at that time. Araucarians ranged from Greenland to Patagonia in one hemisphere, and from Spitzbergen to Cape Colony in the other, but apparently became almost extinct at the opening of the Tertiary, and are now restricted to South America and the Australasian region, having disappeared from North America, Europe, Africa, and practically all of Asia (118, 137): In our own country the Atlantic coastal plain evidently supported during the Mesozoic an abundant araucarian vegetation, and from the cretaceous clay pits of Staten Island alone, HOLLICK and JEFFREY have described recently (155) nine new genera and recognized seven



others; and SINNØTT (162) has added another new genus from Massachusetts. It was in connection with these studies that the general character of this flora was outlined. One of the important results was the discovery that coniferous remains which had been referred to *Sequoia*, Cupressineae, and Podocarpineae, on account of strong superficial resemblances, are really araucarians.

Two types of wood structure have been described (155), which seem to represent a phylogenetic connection of the living araucarians with some very ancient type. The anatomical characters of existing araucarians are summarized as follows: tracheids with radial bordered pits alternating or flattened by mutual contact; resin canals not formed as a traumatic response; medullary rays pitted only in contact with tracheids; and leaves not on dwarf shoots. One of the mesozoic types, including several genera whose wood has been named *Brachyoxylon*, differs in that there is an association of araucarian and abietineous pitting, the former being restricted to the ends of tracheids, and also in that resin canals are formed in response to injury, as in Abietineae. The other type is represented by the genus *Araucariopitys* (127), whose tracheids show the same association of araucarian and abietineous pitting, and in which traumatic resin canals are often present, but whose medullary rays have pits not only on the lateral walls but also on the other walls, as in Abietineae, and whose leaves are probably on dwarf shoots, as in *Pinus*. There are thus three types of araucarians, which show intergrading characters from the existing type through the two mesozoic types toward the Abietineae. These intergrading characters, if they have the value that has been assumed for them, seem to connect in some way the Araucarineae and the Abietineae, and this connection must have been a very old one.

An abundant and world-wide araucarian flora during the Jurassic and Cretaceous would at least suggest the existence of the tribe in much earlier times, but the evidence from actual remains is not convincing. The permian genus *Walchia*, whose leafy twigs are common, some of them bearing cones, has been referred to the Araucarineae. The habit is like that of some of the living araucarians; casts of the pith (*Tylodendron*) agree closely with *Araucaria*, the wood is of the *Araucarioxylon* type, and the small scaly cones suggest the same connection. Even with all this agreement, however, the case is not

proved, and the strongest evidence for such ancient araucarians is the abundance of mesozoic araucarians. The impression that the Araucarineae are the oldest of the Coniferales seems to have arisen, therefore, from the abundance of the *Araucarioxylon* type of wood in the Paleozoic; but since it is found that this paleozoic wood probably all belongs to Cordaitales (p. 165), the evidences of paleozoic araucarians look very scanty. SCOTT (160) has expressed the judgment that "the direct paleontological evidence, apart from theoretical considerations, is favorable to the opinion that the Araucarineae have the longest fossil history, probably overlapping that of the typically paleozoic order Cordaiteae."

The general conclusion in regard to the antiquity of the four tribes of Pinaceae, therefore, is that the Abietineae and the Araucarineae are much the oldest, both being certainly represented throughout the Mesozoic, and probably in the Permian, with no sure evidence as to which of the two is the older. The Taxodineae and Cupressineae are probably not older than the Cretaceous, and are recognized with certainty chiefly from the Tertiary.

Recently Miss STOPES and FUJII (169) have uncovered the first glimpse of a cretaceous flora of northern Japan, the well-preserved material permitting sections. The most common plant was a gymnosperm, whose vegetative structures were named *Yezonia*. Constantly associated with its remains there were strobili, named *Yezostrobus*, and strongly suspected of belonging to it, but not found in actual organic connection. The small concrescent leaves suggest the Cupressineae, but they are in a close spiral and differ in structure from those of any other gymnosperms, having a number of vascular bundles and broad bands of transfusion tissue. Its strobili, if *Yezostrobus* belongs to it, were composed of scales bearing single seeds in the middle, whose massive integument was cycadean (three-layered, and with vascular strands in the outer and inner fleshy layers), but whose nucellus was free to the base (fig. 45). This combination of characters has induced the authors to suggest the establishment of a new family of Coniferales, to be known as the Yezoniaceae. There is thus evidence of an abundant cretaceous gymnosperm flora in a region which has preserved a remarkable series of "endemic" genera of gymnosperms, and whose fossil flora may add very materially to

their number. It is very probable, according to JEFFREY, that *Yezonia* is the same as *Brachyphyllum*, the commonest conifer (araucarian) of the later Mesozoic in the Atlantic coastal region of the United States. Whatever the peculiar anatomy of the leaves of *Yezonia* may suggest as to relationships, the structure of the seed, with its completely free nucellus, suggests either a remarkably persistent retention of an ancient character, or an abandonment of the idea that such a character is necessarily ancient. Moreover, in these detached seeds no embryos were found, adding force to the suggestion, made in connection with paleozoic seeds, that the absence of embryos is not a paleozoic character, but a character of seeds prematurely detached.

### 7. Interrelationship of the tribes

All the evidence of morphology, vascular anatomy, and history favors the belief that the Taxodineae and Cupressineae have been derived from the much more primitive stock of the Abietineae; and these two branches may be assumed to have arisen during the Mesozoic.

The discussion of relationship, however, has really to do with the Abietineae and Araucarineae, and to this discussion history can contribute nothing decisive. The apparent anatomical connection of these two tribes, suggesting genetic relationship, has been mentioned, and JEFFREY has concluded that the Araucarineae have been derived from the primitive stock of the Abietineae. The general outline of the argument is as follows. That abietineous wood with resin canals only as a result of injury (as in *Cedrus*, *Abies*, *Tsuga*, *Pseudolarix*) is less ancient than that in which resin canals are a normal feature (as in *Pinus*), is shown by the greater geological age of the latter; and this is indicated further by such a *Pinus*-like form as *Prepinus*, which, in addition to its resin canals, has foliar vascular bundles identical with those of Cordaitales. The inference is that a resin canal produced by wounding is a "reversionary character." These wound reactions occur in both of the fossil araucarian types of wood known as *Brachyoxylon* and *Araucariopitys*, but not in living araucarians; and since these two types show also a combination of araucarian and abietineous pitting, both in the secondary wood and

in the medullary rays (p. 306), the movement of evolution seems to have been from the Abietineae toward the Araucarineae. It would follow that the modern araucarians have come from ancestors (like *Araucarioxylon*) allied to the Abietineae through such intermediate forms, as *Brachyphyllum* and its allies (with *Brachyoxylon* wood). It is evident that these cretaceous types could not have made the actual connection with Abietineae, but they may represent the structure of much more ancient forms that did.

One objection to the abietineous origin of araucarians is that the latter were a dominant type during the Mesozoic, while the Abietineae seem to have been scantily represented. At present it is an assumption that the Abietineae were poorly represented, and so far as there is any proof to the contrary, *Pinus* may have been represented by as many species during the Cretaceous as now. At the same time it must be remembered that these resemblances and the historical record would be satisfied by the independent origin of the two tribes from such a common ancestry as the Cordaitales. Therefore, so far as the present evidence goes, it is satisfied with two alternatives: either the Araucarineae were derived from the Abietineae at a very early period, or the two tribes arose independently and about the same time from the same ancestral stock.

### 8. Relationship to other gymnosperms

The question of the origin of the Pinaceae was involved in the discussion of the interrelationship of the tribes. There seems no reason to doubt that the primitive stock came from the Cordaitales, either an abietineous stock alone, which gave rise to the other tribes, or such a stock accompanied by a separate araucarian phylum. It must be remembered that Cordaitales include a range of forms much more extensive than the Cordaitineae (Cordaiteae), forms which show intergrading characters between Cordaitineae and Cycadofilicales. It is from such a plexus that Coniferales as a whole may be claimed to have been derived. To present the data which favor this connection with the Cordaitales would be to rehearse the facts of structure and of history that have been presented in connection with the two groups. With Cycadofilicales and Cordaitales in mind as the dominant paleozoic groups of gymnosperms, the latter as clearly



leads to the habit and structure of Coniferales, as the former does to that of Cycadales. The habit of the body, the thick vascular cylinder, the entire leaves, the structure of the ovulate strobilus, are all conspicuous features of Cordaitales that are carried forward by the Coniferales, and are in strong contrast with the features of the cycadophytes. Apparently the most important change observed in the Coniferales is the abandonment of the swimming sperm with its associated pollen chamber. It must be remembered, however, that the record of this change is obtained by contrasting living conifers with paleozoic Cordaitales, and that there is really no evidence as to when it occurred or in what group.

There are two views as to the origin of Pinaceae which differ from the one expressed above, and which deserve mention.

In his investigation of the secondary wood of Coniferales, PENHALLOW (96, 133) has reached the conclusion that the Pinaceae have come from the Taxaceae (that is, a primitive taxad stock), which in turn are a phylogenetic branch from the Cordaitales. So far as the Cordaitan origin of conifers is concerned, this view agrees with the preceding one; but as to the primitive conifers, the two views are directly contradictory; and the latter view seems to be contradicted also by history, especially as the phylogenetic succession proposed is Taxodineae, Cupressineae, and Abietineae, with *Pinus* as the most modern genus. The conclusions are based upon the assumption that greater complexity of structure necessarily indicates a more modern form. It must be kept in mind, in connection with all these views, that the tribes as represented in our present flora are not thought of as ancestral forms, but that they represent the ends of successive branches that have arisen from a common coniferous stock. This investigator concludes also that the Araucarineae had an independent and direct origin from the Cordaitales, which is one of the alternatives mentioned above.

The other view referred to is that of SEWARD (105, 117, 118), who has argued for the origin of Araucarineae from Lycopodiales. This is an older view (SACHS, EICHLER, POTONIÉ) that had passed out of notice in connection with recent work. SEWARD urges that the primitive character of araucarians is shown by (1) the gradual transition from ordinary foliage leaves to sporophylls (also often green);

(2) the uniform and simple character of the secondary wood, composed almost entirely of tracheids with multiseriate bordered pits; (3) the persistence of leaf traces, even in old trunks; (4) the simple sporophylls (each the homologue of a foliage leaf) in contrast with the double structure that characterizes the ovulate cones of the other Pinaceae; and (5) the very numerous and irregularly scattered archegonia, which are found in no other Pinaceae except *Sequoia*. Admitting the force of all these characters in proving the primitive character of any group possessing them, they merely emphasize the fact that the araucarians are very distinct from the other Pinaceae, and must have been distinct for a very long time. Of course this claim is only preliminary to the attempt to establish a phylogenetic connection with the Lycopodiales, through some such form as *Lepidocarpon*. The objections to this connection are numerous, and perhaps the most fundamental one is the presence in araucarians of foliar gaps and of wood indistinguishable from that of Cordaitales (116). The gradual transition from foliage leaves to sporophylls finds a parallel among the Cycadofilicales; and the cited characters of the archegonia are repeated in *Sequoia* and *Widdringtonia*. SEWARD and FORD (105, 118) have been so impressed by the isolation of Araucarineae among gymnosperms that they have proposed a group *Araucariales*, coordinate with Coniferales, Cycadales, etc.

SCOTT (160) has summed up the evidence in favor of the cordaitean origin of the araucarians, as against their lycopodinean origin, in effect as follows: (1) the stem structure, especially that of the wood, is cordaitean, and is unknown among lycopods; (2) the roots are essentially of cordaitean type (true of conifers in general), and show none of the peculiarities of the roots of lycopods; (3) the leaves (with their numerous parallel bundles) agree with those of Cordaitales, and not with those of Lycopodiales (with a single foliar bundle); (4) the staminate strobili and sporangia are cordaitean, and differ absolutely from those of lycopods. The ovulate strobilus seems to be the only support of the view that araucarians have been derived from lycopods.

The relation of the Pinaceae to the other living groups of gymnosperms may be inferred from the previous statements, and needs only a brief mention. The only connection with Cycadales is through the Cycadofilicales, and that is both very ancient and very problematical,

involving as it does the question of the relationship of Cordaitales and Cycadofilicales. It is evident, therefore, that Cycadales and Coniferales are as far apart as the history of gymnosperms could make them. The connection of Pinaceae and Ginkgoales is much closer, for it is evidently made through their common ancestral group, the Cordaitales. These two groups, therefore, have many characters in common, but have carried forward differences that have made them distinctly divergent, and they are now as far apart as two groups with an immediate common ancestry can be. The relation of Pinaceae to Taxaceae is obscure, but the combined testimony of history and of structure suggests that the latter have been derived from the former. A fuller discussion of this is deferred until the Taxaceae are presented. The relation of Pinaceae to Gnetales is still more obscure, but a phylogenetic connection seems evident through *Ephedra*, which will be considered later.<sup>1</sup>

<sup>1</sup> The literature cited for Pinaceae will be found under the general list for Coniferales, at the end of the next chapter.

## CHAPTER VII

### CONIFERALES (TAXACEAE)

The Taxaceae were defined superficially (p. 220) as conifers in which usually distinct ovulate strobili (in the ordinary sense) are not formed, the ovules often being exposed freely, and in which the seeds develop a partially fleshy testa or an aril. These very general characters are accompanied by such peculiarities in the morphology that the family is presented separately from the Pinaceae. The Taxaceae include 11 genera and approximately 105 species, two tribes being recognized.

The *Podocarpineae* (podocarps) are superficially recognized by their winged pollen grains, and are characteristic of the southern hemisphere. They include 6 genera and approximately 86 species, as follows: *Podocarpus* (60 species, throughout the southern hemisphere: West Indies and South America, tropical and southern Africa, Australasia to Japan), *Dacrydium* (16 species, Australasia to the East Indies), *Microcachrys* (1 species, in Tasmania), *Pherosphaera* (2 species, in Australia and Tasmania), *Saxegothaea* (1 species, in the Andes of Chili), and *Phyllocladus* (6 species, in New Zealand, Tasmania, and the East Indies). The dominant genus is *Podocarpus*, which holds the same conspicuous place among the conifers of the southern hemisphere that *Pinus* holds among the northern conifers. This great genus is also the only one of the podocarps represented in the northern hemisphere, extending into Japan from the East Indies (fig. 372). *Phyllocladus* is often regarded as representing a third tribe, intermediate between the other two, but its morphological characters clearly associate it with Podocarpineae (145, 174).

The *Taxineae* (taxads) have wingless pollen grains, and are found chiefly in the northern hemisphere. They include 5 genera and approximately 19 species, as follows: *Taxus* (7 species, throughout the temperate and subtropical regions of the northern hemisphere; also in tropical Asia and the mountains of Mexico), *Torreya* (4 species, in the United States, Japan, and China), *Cephalotaxus* (6 species, in eastern Asia), *Acmopyle* (1 species, in New Caledonia),





FIG. 372.—*Podocarpus dacrydioides* in a remnant of a forest of *Taxaceae* near Invercargill, New Zealand.—From photograph by J. CROSBY SMITH.

and *Polypodiopsis* (1 species, in New Caledonia). The New Caledonian representation is so small, and the affinities of *Polypodiopsis* are so uncertain, that the tribe may be regarded as northern in its distribution, in contrast with the southern distribution of the podocarps. The difficulty of estimating the number of species may be illustrated by *Taxus*, at least 75 species of which have been described, 7 of which are recognized by BENTHAM and HOOKER; and these have been reduced to a single species by PILGER (81).

The Taxaceae and Pinaceae have so many features in common that in the following account, to avoid needless repetition, attention will be called chiefly to the differences.

### 1. The vegetative organs

The general habit of the body of Taxaceae resembles that of Pinaceae. In some forms, also, the branches are dimorphic, the dwarf shoots of *Phyllocladus* being transformed into the characteristic phylloclads (fig. 373). The phylloclads are in the axils of small scalelike leaves, which are at first green, but later become true scales, and are really developed by the primordia of foliage leaves; while in the juvenile forms the first leaves are flat green needles, which are successively replaced by shorter and shorter ones until the adult form is reached, and the phylloclads themselves only gradually acquire their peculiar character (fig. 256, e, f). It seems evident that this peculiar form has been derived from forms with ordinary spreading needles and axillary dwarf shoots.

### VASCULAR ANATOMY

The structure of the stem is the same as that of Pinaceae, the vascular cylinder being collateral endarch. Among the taxads, however, the traces of ancient structure in the form of mesarch bundles are of more general occurrence than in any other tribe of conifers. Pronounced mesarch bundles occur in the cotyledonary strands of *Cephalotaxus* (45, 110, 141), and less obviously in those of *Taxus* (110, 141) and *Torreya* (75); while one species of *Cephalotaxus* is reported to have a mesarch stem cylinder. Among the podocarps mesarch bundles occur in the phylloclads of *Phyllocladus* (115), and there are apparently traces of centripetal xylem in the axis of

the staminate cone of *Saxegothaea* (150). It is probable that mesarch bundles will be found to be a common feature of the cotyledons of all



FIG. 373.—*Phyllocladus rhomboidalis*: portion of a small branch showing leaves (l), from the axils of which come the phylloclads (p); natural size.

Taxaceae, and that they will prove to be of common occurrence in the peripheral parts of the shoot. However this may be, the number of cases reported already are sufficient to contrast the Taxaceae with the

Pinaceae in this feature, which is barely represented in the latter family in *Juniperus* and *Cupressus*, and in the cone scales of *Araucaria*.

The leaf trace is single, even the cotyledons being supplied by a single vascular strand, except those of *Podocarpus*, in which there are two entirely separate strands. In this feature *Podocarpus* (and perhaps other podocarps) differs from the taxads and most of the Pinaceae. In this case the two cotyledonary strands together form one pole of the primary diarch root (141).

The tracheids of the secondary wood are in general of the abietineous type, the bordered pits being uniseriate; but in *Saxegothaea* (150) the pits are flattened horizontally and occasionally tend to form two ranks, and in *Dacrydium* the pits are two-ranked and alternate. How far these araucarian tendencies will be found to prevail among the podocarps remains to be seen.

The medullary rays are simple as compared with those of Pinaceae, especially the Abietineae. In *Saxegothaea*, for example, they are one cell wide and rarely more than three cells deep. Resin canals are not present at all in taxads; they do not occur in the secondary wood of podocarps, so far as recorded, although they are found in the cortex; and they are said to be wanting in the cotyledons of all the Taxaceae. Further observation of the family for this feature, especially in connection with experimental work, will probably relate it in this regard much more definitely to the Pinaceae.

#### THE LEAF

The foliage leaves of Taxaceae are in general spirally arranged (opposite and decussate in *Microcachrys*), and are as variable as are those of Pinaceae. Among the taxads the free, bladelike needles prevail; while among the podocarps there is every gradation from the very small and closely overlapping and even concrescent leaves of certain species of *Dacrydium* and of *Microcachrys*, to the large and broad leaves of some species of *Podocarpus* (fig. 374). In *Phyllocladus* there are no foliage leaves, their function being performed by the phylloclads, and leaves being represented only by scales (fig. 373).

The anatomical structure of the leaf is in general that of the leaves of corresponding form among the Pinaceae (p. 237).





FIG. 374.—*Podocarpus Purdieana*: from a photograph of a herbarium specimen; two-thirds natural size.

## 2. The spore-producing members

The strobili of Taxaceae are monosporangiate, and in the main the plants are dioecious, *Saxegothaea*, some species of *Podocarpus*, and perhaps occasionally *Phyllocladus* being monoecious. The interesting observation has been made (149) that in a specimen of *Saxegothaea* growing in a greenhouse at Uppsala, some of the branches are mostly staminate and others mostly ovulate. No bisporangiate strobili have been reported, except a single case of *Phyllocladus alpina* (115), in which an ovule was found at the base of a staminate strobilus. Although the statement is current that usually strobili are not formed among the Taxaceae, this refers to the ovulate strobili, for the microsporophylls are as definitely organized into simple strobili as are those of Pinaceae. Even in the case of the ovulate strobili, the statement must be taken with a good deal of allowance, for such strobili do occur, as in *Microcachrys* and *Saxegothaea*, but not always in the same conspicuous way as among the Pinaceae.

### THE MICROSPORANGIUM

The staminate strobili are borne on short stalks in the axils of foliage leaves (scales in *Phyllocladus*), usually appearing upon young shoots of the same season (fig. 375). The relations of leaves and strobili are such that if the axis of the shoot were shortened, becoming a dwarf shoot, it would be transformed into a compound strobilus; as it is, the staminiferous shoot often resembles a raceme (150). The strobili are generally solitary in the axils, but they may occur in pairs or in threes, as in *Podocarpus* (139) and *Saxegothaea* (150); and in *Phyllocladus* they are borne in clusters of two to eight at the tips of the lateral branches. In the monoecious *Saxegothaea* the ovulate strobilus is terminal on the short branch in the axils of whose leaves the staminate strobili are borne. The size and form of the strobili are variable, ranging from 2 to 20 mm. in length, and in form from linear to nearly spherical. The strobili consist externally of a variable number of overlapping sterile bracts, which sometimes completely envelop the tip, as in *Torreya* (101), and sometimes form an involucre-like cluster at the base of the strobilus, as in *Saxegothaea* (150).

The sterile bracts (sporophylls) are replaced above by a more or less indefinite number of stamens. Among the taxads, disregarding

the rather doubtful New Caledonian genera *Acmopyle* and *Poly-podiopsis*, the stamens are of the peltate type; that is, the stalk is



FIG. 375.—*Microcachrys tetragona*: branch with staminate strobili;  $\times 2.25$ .—After THOMSON (151).

capped by a peltate expansion, from beneath which the sporangia are pendent. In *Taxus* the sporangia are four to seven in number, completely surrounding the stalk; in *Torreya* seven sporangia begin to develop, but only the four abaxial ones mature, so that the stamen

appears one-sided with its pendent abaxial sporangia; while in *Cephalotaxus* the sporangia range from four to two in number. The site of the three abortive sporangia in *Torreya* is occupied at maturity by a large adaxial resin cavity, and in some cases six or seven mature sporangia occur (98); whether there is such evidence of abortive sporangia in *Cephalotaxus* has not been determined. This type of stamen is very suggestive of that of the araucarians; and is represented among the Cycadofilicales by the so-called *Crossotheca* or "epaulet" type. Among the podocarps the stamens in general resemble those of the Abietineae, two sporangia being borne on the abaxial face of a bractlike sporophyll (sometimes pendent?), whose sterile tip is variously developed, from an inconspicuous point to a relatively broad expansion.

The details of the development of the microsporangium have not been followed, but at maturity the wall is three to five layers of cells thick, the one or two innermost layers forming a somewhat inconspicuous and short-lived tapetum. In *Torreya taxifolia* each sporangium begins as a single hypodermal archesporial cell, which divides to form the primary wall cell and the primary sporogenous cell. In the case of the three abortive adaxial sporangia, their primary sporogenous cells do not divide, but at this stage begin to break down, along with the intervening sterile cells, and form the large resin cavity.

The records of the winter condition of the microsporangia are too meager to form the basis of a general statement, but *Taxus canadensis* in Chicago (51) and *Torreya* in England (98) pass the winter in the mother cell stage. In *Torreya taxifolia* in Florida (101), the staminate strobili begin to be visible in June, the primordia of the stamens begin to appear in August, the primary sporogenous cells are recognizable early in September, the spores are in the shedding condition in April, and fertilization occurs in August, making a period of fifteen months from the first appearance of the staminate strobilus to fertilization. It seems safe to conclude that this species also passes the winter in the mother cell stage.

#### THE MEGASPORANGIUM

The ovulate strobilus is often so much reduced among the Taxaceae as to lose the ordinary appearance of a strobilus; but in *Saxegothaea*



(150) it is made up of spirally arranged and imbricated bracts that form an ovoid cone, and in *Microcachrys* a definite strobilus is formed by the sporophylls, which occur in decussating cycles of four and thus give the appearance of a spiral arrangement. The case of *Torreya*



FIG. 376.—*Torreya taxifolia*: ovulate branch, April 7, 1904; natural size.—After COULTER and LAND (101).

*taxifolia* (101) may illustrate the general situation. In this form the strobili are borne in the axils of the lower leaves of short young shoots, usually a pair of them on a short axillary branch. In most cases there is only a single pair of strobili on a strobiliferous shoot, but frequently there are two pairs, and rarely three on the same shoot. Therefore, near the base of these shoots two to six strobili may occur, the upper pairs never maturing and usually only one of the lowest pair producing the large plumlike seed (fig. 376). A strobilus consists of four enveloping bracts and a single, terminal, erect ovule, resembling a simple ovulate flower with a perianth of four bracts; but these are evidently the sterile bracts of a much reduced strobilus. The relation of the strobili to the young shoot is exactly comparable

to the arrangement of the staminate strobili, the difference being that more of the latter mature and the stamens are numerous. In this sense, the whole ovuliferous shoot may be regarded as corresponding to the compound ovulate strobilus of the Abietineae.

A general feature of Taxaceae, illustrated by *Torreya*, is the

occurrence of very simple strobili, containing usually one ovule, and borne in the axils of leaves of young shoots (fig. 377). Among the taxads and in *Phyllocladus* the solitary (two in *Cephalotaxus*) ovule is erect, while among the rest of the podocarps it is inverted. *Podocarpus* has received its name from the fact that the ovule is stipitate, usually arising conspicuously above the bracts (fig. 378).

In *Saxegothaea* (152) the solitary and more or less inverted ovule is borne on the ovuliferous scale near the base of the adaxial face. The ovulate cone of this genus, as stated above, is terminal on the short branch in the axils of whose leaves the staminate strobili occur. Its peduncle is at first short and is clothed with bracts that envelop the strobilus, but later it elongates, rises above the bracts, and becomes relatively long and slender. The resemblance of this habit to that described for *Podocarpus* is evident, although the elongating structure is not the same in the two cases. In both *Saxegothaea* and *Microcachrys* there is the same intergrading of bracts into sporophylls above and foliage leaves below that characterizes the araucarians.

In *Phyllocladus* (144) the strobili are borne at the edge of the phylloclads near the base, occurring singly or in pairs, and consisting of six or eight thick bracts, each with an axillary erect ovule. This position is understood when it is remembered that the phylloclad is a transformed dwarf shoot.

It is difficult, and perhaps unprofitable, to compare this strobilus situation with that of the Pinaceae; but the two families exhibit the same general features in the position of the ovules, and differ in the compactness of the strobiliferous region. It is in this feature that *Saxegothaea* so impressed LINDLEY, who established the genus, that he regarded it as a transition form between Taxaceae and Pinaceae.




FIG. 377.—*Torreya taxifolia*: ovulate strobilus showing enveloping bracts; *n*, nucellus; *ii*, inner integument; *oi*, outer integument; *r*, resin cavity; April 7, 1904;  $\times 24$ .—After COULTER and LAND (101).

In a study of the ovuliferous bracts of *Saxegothaea* and *Microcachrys*, THOMSON (164) has discovered an inverse orientation of the vascular bundle supplying the ovule, a feature which has been used to prove the double nature of the ovuliferous structure in Pina-

ceae. The same inversion, however, occurs in the supply bundle for the microsporangium, which is evidently borne upon a simple sporophyll. Among the Abietineae, Taxodineae, and Cupressineae, however, there is a double inversion in the ovuliferous structure, one related to the sporangial supply, and the other presumably related to the modified dwarf shoot; while among the Araucarineae only the sporangial inversion occurs. The conclusion is that among the Taxaceae and Araucarineae the ovuliferous structure is a simple megasporophyll; while among the Abietineae, Taxodineae, and Cupressineae it is a double structure.




FIG. 378.—Ovulate structures of various conifers: 1, *Agathis australis*, ovuliferous scale from inner side (M, winged seed); 2, longitudinal section of 1; 3, *Araucaria excelsa*, longitudinal section of scale, etc., also showing the outgrowth (i) above the seed; 4, *Cunninghamia sinensis*, ovuliferous scale, showing three ovules (M), and an outgrowth (i); 5, *Microcachrys tetragona*, longitudinal section of ovuliferous scale, also showing the arillus (a) and the outgrowth (i); 6, *Cryptomeria japonica*, longitudinal section of part of the strobilus; 7, 8, *Cupressus Lawsoniana*, showing a young cone (7) and a later stage (8); 9, *Podocarpus macrophylla*, longitudinal section, showing ovulate structures and aril (ar).—From ENGLER and PRANTL'S *Nat. Pflanzenfam.*

The developmental periods of the ovules of the Taxaceae have not been obtained in so many cases as among Pinaceae. In *Torreya taxifolia* (101) the ovulate strobilus is first apparent late in July (in Florida), the mother cells appear during the autumn or early winter and are in synapsis the next April, fertilization occurs during

the summer, the proembryo is formed during the autumn and passes the winter, the embryo is completed during the next season, and the seed is mature in the autumn. This involves two full years, from the appearance of ovules to the maturity of the seed. *Taxus* (100) and *Cephalotaxus* (124) have approximately the same period, and the first winter is passed in the mother cell stage. While the total period in each of these three genera, which really constitute the taxads, is approximately the same, its distribution among the various events is strikingly different. In *Torreya* fertilization occurs four months after pollination, and the seed is mature fourteen months later; in *Cephalotaxus* fertilization occurs fourteen months after pollination, and the seed is mature four months later; while in *Taxus* fertilization follows pollination in two months. The only information concerning the podocarps, as yet, is that in *Phyllocladus* (174) about a month intervenes between pollination and fertilization.

The current statements in reference to the integument among Taxaceae are confusing, because of the appearance of a second or outer integument, which arises considerably later than the inner one, and which has been variously called outer integument, aril, and epimatium. In *Torreya* (101) the outer integument develops the thick fleshy covering of the seed, which gives it a plumlike appearance; the inner integument differentiates into two layers, the outer of which is the stony layer, and the inner consists of several layers of thin-walled cells, distinctly differentiated only where the integument is free from the nucellus. It is natural to see in these three layers the outer fleshy, stony, and inner fleshy layers characteristic of the testa in cycads, *Ginkgo*, and the older gymnosperms; and to conclude that the two integuments have arisen from a single one, by delaying the development of the region that becomes the outer fleshy layer. These facts and the inference seem to hold good also in the case of *Taxus*, the only difference being that the outer fleshy layer ("aril" in this case) remains distinct from the inner one. In the case of *Phyllocladus* (144), however, a different inference seems necessary; for the inner integument differentiates into all three layers, the difference being that the outer fleshy layer is represented by only two layers of cells, which are finally sloughed off. The outer integument arises late and



grows very rapidly, soon inclosing the ovule, but the latter finally grows above it, and at last it is only a light leathery sheath about the base of the ovule extending half way to its tip. From this it would appear that the outer integument or "aril" is a new structure, having arisen in addition to all the old ones, and is not merely a dissociated outer fleshy layer. That this new structure should frequently take the character of this layer is not strange, for it holds the same general relation to the seed; and among the podocarps the tendency to develop the fleshy character extends far beyond the integuments. In *Podocarpus* it involves the bract on the stipe; while in *Saxegothaea* (150) the scales of the strobilus enlarge and fuse into a globular fleshy mass, much as in *Juniperus*. In the development of the stony layer, the transformation of tissue begins at the apex of the integument and gradually extends downward until it completely surrounds the structures within.

In *Torreya* the integuments are entirely free from the nucellus at first, even after the mother cells are in synapsis. After that time intercalary growth begins in the chalazal region and continues until into the next season. As a consequence, in the mature seed the free region of integument and nucellus is at the very tip, and is not more than one-twentieth the total length of the seed. The same condition exists in *Taxus*, and perhaps in most of the genera; while in *Phyllocladus* the nucellus and integuments remain entirely free. The vascular connections of the ovule in *Torreya* and in *Phyllocladus*, *Microcachrys*, and *Saxegothaea* only are known, and the three latter genera are probably representative of Taxaceae in general. In *Torreya*, near the limit of the outer fleshy layer, there are two conspicuous and opposite vascular strands; while in *Phyllocladus*, *Microcachrys*, and *Saxegothaea* the vascular system ends at the base of the ovule. It is to be expected that the distribution of the vascular strands should depend upon the presence and position of a fleshy region in connection with the seed. The seed of *Torreya* is regarded by OLIVER (80) as the most archaic of living conifers in its vascular anatomy. In addition to the two vascular strands in the outer fleshy layer (outer integument), the vascular plate at the base of the nucellus sends out branches into the nucellus, which connect with a peculiar mucilaginous layer that may represent the tracheal mantle of some of the paleozoic

seeds (p. 43). All the other conifers have lost all traces of their nucellar vascular systems.

In *Saxegothaea* (149, 150, 152) there is a remarkable extension of the tip of the nucellus, which protrudes beyond the micropyle into an irregular, flaring apex, which is said to become covered by a sticky secretion and to act as a stigma, continuing to grow for about two months after pollination (fig. 379). This character appears, in less degree, in *Araucaria*.




FIG. 379.—*Saxegothaea conspicua*: longitudinal section of ovule, showing the stigma-like extension of the nucellus;  $\times 50$ .—After NORÉN (149).

The development of the sporogenous tissue has been traced by STRASBURGER (100) in *Taxus*, and it is presumably the same in the other Taxaceae. The archesporium is a hypodermal plate, which divides periclinally as usual. The outer cells, in connection with the overlying epidermal cells, produce the large mass of sterile tissue that caps the nucellus. Each primary sporogenous cell (mother cell) is the innermost cell of a long row, and the number of mother cells is approximately the same as the number of archesporial cells (fig. 380). In most genera, apparently, these rows are not dis-

tinct enough to follow, and the enlarging mother cell is the first evidence of its existence. The number of mother cells varies as among the Pinaceae, but the only recorded cases of more than one mother cell are *Taxus*, in which there are one to five, and *Podocarpus*, in which there are occasionally two. In *Taxus* the occasional appearance of more than one developing embryo sac has been known ever since HOFMEISTER's investigations.




FIG. 380.—*Taxus baccata*: three megaspore mother cells, each at the end of a row of cells derived from a primary tapetal cell;  $\times 375$ .—After STRASBURGER (100).

An important fact in connection with the megasporangium of taxads is the general absence of any tapetal zone about the megaspore and embryo sac, so characteristic a feature of the Pinaceae. Among podocarps, however, "spongy tissue" occurs in *Phyllocladus* (174), *Podocarpus* (69), *Dacrydium* (174), and *Saxegothaea*, which indicates that it is of general occurrence in the tribe. The general lack of differentiation of any glandular cells in taxads may be regarded either as a primitive character or a degradation.

The deep-seated megaspore mother cell usually forms a linear tetrad, the innermost megaspore functioning. As in Pinaceae, the second division may not occur in the upper daughter cell of the mother cell, resulting in the row of three cells originally reported for *Taxus*, and also in *Phyllocladus* (174); but complete tetrad-formation has now been observed in a sufficient number of cases to establish it as the usual condition. Even the linear arrangement of the tetrad is occasionally departed from, as has been observed in *Taxus* (100). There are exceptions as to the functioning megaspore of a tetrad; while the innermost one usually functions, any one may function, and two contiguous ones have been observed to begin

growth in *Taxus* (100). When the mother cells are more than one, several of them may begin to function. This functioning of more than one mother cell may not reach the synapsis stage, as observed in *Taxus* (100), or it may proceed until the gametophytes are well formed, as has been reported in one case of *Podocarpus coriacea* (cultivated in Jamaica), in which two gametophytes were observed in one ovule (69), and in one of them there were tracheids. If the presence of tracheids in female gametophytes means sporophytic tissue, as has been shown among ferns, this is a case of incipient apogamy.

The number of chromosomes in Taxaceae has been determined for very few forms. In *Podocarpus* (139) the numbers are 12 and 24, conforming to the numbers among the Pinaceae, so far as observed; but among the taxads they have been found to be 8 and 16 in *Taxus* (100) and *Torreya* (99). Whether this is a feature of the taxads, in contrast with the podocarps and Pinaceae, is a question that remains to be answered.

### 3. The gametophytes

#### THE FEMALE GAMETOPHYTE

The development of the female gametophyte follows the general course described for the Pinaceae (p. 259), with free nuclear division, parietal wall-formation, and centripetal growth until the embryo sac is full of tissue (fig. 381). The vacuolation of the sac depends upon the rate of its growth; but in general it occurs so that the free nuclei become parietally placed from the 2-nucleate to the 32-nucleate stage. Actual counts of the number of free nuclei before wall-formation have been made for *Taxus* (52) and *Torreya* (101), and found to be 256, representing eight successive divisions. Probably this represents the usual number of free nuclear divisions among conifers, although it must be expected that great variation and irregularity may occur. The behavior of the nuclei in the endosperm-formation of *Taxus* has been studied in detail by STRASBURGER (100), and no fusions or unusual conditions were discovered, as have been described for some of the Pinaceae. An idea of the amount of endosperm growth may be obtained from measurements made in *Torreya taxifolia* (101). At fertilization the endosperm consists of 400–800 cells and measures 20 by 30  $\mu$ ; while in the mature seed it measures 14 by 20 mm.



The archegonium initials become recognizable at various stages in the development of the gametophyte. In *Taxus* and *Torreya* they appear as soon as the sac is full of tissue; in fact, any earlier differentiation would occur in the stage of free nuclei and would result in the selection of eggs and the elimination of archegonia. This tendency to differentiate the female sexual organ earlier and earlier

in the history of the gametophyte has been referred to under Pinaceae (p. 263); and in this feature *Taxus* and *Torreya* stand in an extreme position. In *Cephalotaxus* (124), on the other hand, the archegonium initials do not appear until the endosperm is well developed; and in *Podocarpus* the gametophyte is two-thirds to three-fourths its full size when fertilization occurs. In some cases, therefore, the principal growth of the endosperm takes place after fertilization, and in other cases before fertilization.



FIG. 381.—*Taxus baccata*: eight-nucleate stage of female gametophyte;  $\times 375$ .—After STRASBURGER(100).

The development of the archegonium is exactly as described for the Pinaceae (p. 263), and no archegonial complex is formed, each archegonium having its separate chamber and jacket (in case there is one). In *Phyllocladus* occasionally two archegonia occur in a common jacket (174). The archegonial jacket, investing the central cell and later the egg, is not developed so constantly or so conspicuously as among the Pinaceae. In *Phyllocladus* (144) it is conspicuous, consisting of a layer of cells with large nuclei or several nuclei; in *Cephalotaxus* (124) it is less conspicuous, frequently being interrupted by ordinary cells; while in *Torreya* (101) it is not evident until after fertilization and is then weakly organized. The condition of this jacket among Taxaceae is not known well enough to justify a general statement, but among the taxads, at least, it gives the impression of a vanishing structure, which finds its parallel in the disappearance of the

jacket of the mother cell and early embryo sac ("spongy tissue") in the same group. The conspicuous archegonial jacket of *Phyllocladus* suggests that this structure may be as fully developed among podocarps as among Pinaceae. A peculiar situation is developed in *Phyllocladus* (174) in the relation of the neck cells to the jacket cells. It had been observed (144) that the top of the archegonium is its widest part, the whole outline being roughly funnel-shaped, resulting in leaving the neck cells apparently detached. This is found to be due to the rapid centrifugal growth of the adjacent tissues at the upper end of the endosperm, but the neck cells remain anchored to the jacket cells by a membrane.

In all the Taxaceae observed no ventral canal cell is formed, but a ventral nucleus is cut off by the central cell, which is more or less ephemeral. Attention has been called to the fact (p. 268) that this is a stage toward the elimination of the ventral canal cell, and it has been reached by all the conifers except the Abietineae and possibly the Araucarineae. The Taxaceae in which a ventral nucleus has been definitely observed are *Taxus*, *Cephalotaxus* (124, 130), *Phyllocladus* (174), *Podocarpus* (69), and a somewhat doubtful case in *Torreya* (99). The case of *Torreya californica* was an inference from a spindle seen twice in the central cell, and it is not always easy to distinguish a central cell from an egg. In *Torreya taxifolia* (101) the series seemed to be close enough to detect a ventral nucleus if one was formed, but no trace was found, the nucleus of the central cell appearing like an egg nucleus from the very beginning. It is very unsafe to infer the absence of a ventral nucleus from a single investigation, but it is so very ephemeral in some cases that it may have disappeared entirely in other forms. So far as any general conclusion is safe, it may be said that among the Taxaceae the central cell does not cut off a ventral canal cell, but that a ventral nucleus appears which is sometimes very ephemeral, and that in some cases even the nucleus may not be formed. In *Cephalotaxus drupacea* (130) the ventral nucleus is so ephemeral that it degenerates before fertilization; while in *Podocarpus* (69) it has been observed to divide amitotically after fertilization.


Among the Podocarpineae the number of archegonia ranges from one to eleven, being one to four in *Phyllocladus alpina* (144), and

seven to eleven in *Podocarpus coriacea* (69). This is a meager record, but it probably expresses the variability and range in number. There are four neck cells in *Phyllocladus* (174); but in the *Podocarpus* investigated the number varies from two to twenty-five, the most common condition being three tiers of cells with four cells in each tier. This extreme variability seems to hold some relation to the arrival of the pollen tube, which permits an almost indefinite growth of the neck or does not allow it to extend beyond the two-celled stage.

Among the Taxineae the number of archegonia has the same range (one to eleven), being one (in one case two) in *Torreya taxifolia* (101), two to four (usually three) in *Torreya californica* (99), two to five (usually three) in *Cephalotaxus Fortunei* (124), four in *Cephalotaxus drupacea* (130), and five to eleven in *Taxus*. The number of neck cells varies from two to six, always in one plane: two in *Torreya taxifolia*, two or three in *Cephalotaxus drupacea*, two to five in *Cephalotaxus Fortunei*, and four to six in *Torreya californica*. Such ranges in the number of archegonia and in the number of neck cells, even within a genus, indicate that such numbers have very little significance.

The comparative development of the megaspore membrane in Coniferales was referred to under Pinaceae (p. 271). The Taxineae are peculiar in being the only tribe in which this membrane is really a negligible feature, developing none of the structure observed in the other tribes. If THOMSON'S conclusions (108) are true, this indicates that, so far as this feature is concerned, the taxads are the most recent of the conifers. Among the Podocarpaceae, at least as evidenced by *Phyllocladus* (174), *Dacrydium* (174), *Microcachrys* (164), and *Saxegothaea*, there is a megaspore membrane of the usual two-layered type.

*Torreya* furnishes a conspicuous illustration of a seed with "ruminated endosperm" (figs. 382, 383). In a smaller degree this feature appears in the seed of *Phyllocladus* (especially in its early stages) and of the araucarians; but its extreme expression is exhibited by *Torreya*. In the study of *Torreya taxifolia* (101) an opportunity was given to investigate this so-called "rumination." In ordinary seeds the endosperm invades the surrounding tissue more or less uniformly, in the case of most gymnosperms obliterating most of the



382



383

FIGS. 382, 383.—*Torreya taxifolia*: ovules showing "ruminating" endosperm; fig. 382, longitudinal section of mature seed showing embryo, endosperm, and seed coats;  $\times 3$ ; fig. 383, transverse section showing endosperm with storage region in the center, seed coats, stored food in the perisperm, and resin ducts in the outer portion;  $\times 3$ .—After COULTER and LAND (101).



perisperm. In *Torreya*, on the other hand, the invasion by the endosperm is irregular in the extreme. It is in the season after the proembryo has formed that the active invasion of the perisperm begins. The extension of the endosperm into the tip of the nucellus above the sac proceeds in the usual way, obliterating all of it except a few peripheral layers of cells. This uniform invasion seems to be due to the fact that in this apical region (the original nucellus) the perisperm is not growing actively if at all. Below this small region at the tip, however, the perisperm is very active and evidently resists disintegration much more at certain points than at others. As a consequence, it becomes eroded by the irregularly advancing endosperm, and is left in the condition of a much dissected coast line. To the casual observer this results in an appearance suggesting that the endosperm is being invaded by plates of perisperm, but this is no more true than that the promontories of a dissected coast line are advancing into the sea. The suggestion of an invading perisperm is further strengthened by the fact that within the perisperm bordering the endosperm a dark brown and finally black band of cells is developed, due to abundant food storage, but this really recedes as the endosperm advances.

A transverse section of the mature seed of *Torreya* always shows a definite and deep constriction of the endosperm in the center, exactly opposite the two opposed vascular strands that run up on each side of the seed through the inner part of the outer integument (fig. 383). This constriction is the transverse section of two opposite and deep longitudinal furrows in the endosperm, and it means that in this longitudinal plane the endosperm encounters the greatest resistance in invading the perisperm. This most resistant perisperm certainly seems to hold a very definite topographical relation to the principal vascular strands, and this relation may explain the resistance.

That endosperm is the aggressive tissue at every point, even at the region of most resistant perisperm, is evident for several reasons. In no case are the peripheral cells of the the endosperm broken down; and in no case does there fail to appear one or two layers of disorganized cells of the perisperm in contact with the endosperm. In every case, also, the peripheral cells of the endosperm appear active and very vigorous, and their different appearance in regions of more

or less active encroachment is striking. In regions of active invasion the endosperm cells are radially elongated, and many of them are binucleate; while in regions of less active invasion the cells are more nearly isodiametric and rarely binucleate.

Another proof that endosperm is the encroaching tissue may be obtained from comparative measurements. At the time of fertilization the gametophyte usually measures 20 by 30  $\mu$ . In the mature seed the ordinary length of the gametophyte is 20 mm., the greatest width being 14 mm., and the least (at the deep constriction opposite the vascular strands) 1.5 mm. At this most resistant region of the perisperm, therefore, where it is hard to escape the conviction that the perisperm plate has cut the endosperm nearly in two, the endosperm has increased its diameter against the perisperm seventy-five times. The best reason, however, for concluding that the endosperm is the invading tissue in this case is that this is always the behavior of endosperm; and it is singular that the old explanation of "rumination" was ever suggested.


#### THE MALE GAMETOPHYTE

The male gametophytes of podocarps and of taxads are in such sharp contrast that the two tribes must be considered separately.

Among the Taxineae the gametophyte of *Taxus* naturally received early attention, and its principal features have been known since the pioneer work of BELAJEFF (33) and STRASBURGER (38). At that time it was not appreciated that the vegetative (prothallial) cells had been eliminated, much less that this elimination was a feature of all the taxads.

The development of the gametophyte of *Torreya taxifolia* (101) will serve as an illustration and for comparison. The first division of the microspore results in the generative and tube cells, separated from one another by a very delicate wall or membrane. In this binucleate condition (fig. 384) the pollen grains are shed (late in March to early in April in Florida). Pollen tubes penetrate the nucellar cap at once, and occupy it for about four months. The generative cell divides early in the history of the tube, which contains almost from the first the large body cell and the stalk and tube nuclei (fig. 385). Shortly before fertilization (about the middle of August), the body

cell divides into two distinct and unequal male cells, the cytoplasm of the body cell being divided unequally (fig. 386). The behavior



384



385

FIGS. 384, 385.—*Torreya taxifolia*: fig. 384, tip of nucellus with pollen chamber (disintegrated tip of nucellus) containing a two-celled microspore, the smaller cell being the generative cell and the larger the tube cell; *pc*, pollen chamber;  $\times 220$ ; fig. 385, end of pollen tube in contact with embryo sac, which is in free nuclear stage; in the tube the stalk and tube nuclei are in advance of the body cell;  $\times 460$ .—After COULTER and LAND (101).

of the tubes is interesting and suggestive. They may advance rapidly, reaching the female gametophyte at an early free nuclear stage (16–64 nuclei), or they may advance very slowly. The course may be very direct, resulting in a straight cleft through the tip of the nucellus, or it may be extremely devious. In one case observed the tube advanced directly half-way through the tip of the nucellus; then proceeded spirally downward and outward to the peripheral cells of the nucellus, several of which it destroyed; then turned abruptly inward, penetrated the nucellus at the level of the archegonium, crossed the top of the endosperm, and discharged into the archegonium on the opposite side. In another case a wandering tube penetrated the inner integument before turning back into the nucellus. Very frequently the tube pushes into the

embryo sac at the free nuclear stage, making a deep invagination (often to the middle of the sac), and from this pocket it turns back




FIG. 386.—*Torreya taxifolia*: median longitudinal section of female gametophyte, showing egg with large nucleus (*o*), the remains of a neck cell (*nc*), and antipodal haustorial cells (*hr*); also the tip of a pollen tube in contact with the egg, showing stalk nucleus (*stn*), tube nucleus (*tn*), and the two unequal male cells (*m*<sup>1</sup> and *m*<sup>2</sup>); the upward growth of the endosperm cells forms a sheath around the pollen tube; August 12, 1904;  $\times 460$ .—After COULTER and LAND (101).



into the nucellus. *Torreya californica* is said to differ in that male cells are not formed, but the two male nuclei are invested by the general cytoplasm of the body cell, and with no inequality (99).

In *Taxus* the microspore is shed in the uninucleate stage, the division into generative and tube cells occurring while the spore is resting on the tip of the nucellus, and the pollen tubes are in the nucellus only about two months before fertilization; otherwise the events are exactly as in *Torreya*, including the formation of two very unequal male cells (fig. 387). In *Cephalotaxus* the first division of




FIG. 387.—*Taxus baccata*: tip of a pollen tube with the two unequal male cells; the stalk and tube nuclei in advance;  $\times 200$ .—After BELAJEFF (33).

the microspore (to generative and tube cells) occurs before shedding, as in *Torreya*. Pollination occurs from January to March (varying with the species and the latitude), but no further division occurs until the following spring, when the generative cell divides, and the body cell and stalk and tube nuclei are found in the pollen tube; in fact, the tube does not penetrate the nucellus for nine to twelve months after pollination (124, 130). The two accounts of *Cephalotaxus* differ as to the character of the male cells, which are said to be unequal in *C. Fortunei* (124), and in *C. drupacea* (130) to be represented by two male nuclei, without wall-formation (fig. 388). The inequality of the cells in the former species is not so great as in *Torreya* and *Taxus*; and since inequality is chiefly that of the cytoplasm rather than of the nuclei, the absence of wall-formation in the latter species might result in no appearance of inequality. In both cases the tube reaches the female gametophyte quickly (in about ten days in *C. drupacea*); and in *C. Fortunei* it reaches the archegonium neck before the chamber is formed, so that the endosperm grows up about the tip of the tube and may bury the archegonia.

The features of the male gametophyte of Taxineae, therefore, are the absence of vegetative (prothallial) cells, a feature shared with

Taxodineae and Cupressineae among Pinaceae; and the unequal male cells, possibly related to the fact that the archegonia are not organized into a complex, a feature found among Abietineae. The exceptional condition in *Cephalotaxus* is that the inequality of the male cells is not so marked, and may disappear entirely through lack of wall-formation.

The male gametophyte of the Podocarpaceae has attracted so much attention that every genus (except *Pherosphaera*) has now been investigated, and the peculiar condition of the vegetative (prothallial) tissue is found to belong to all of them (figs. 389-396). It appears that this feature of the podocarps was first described and figured in 1896 by THIBOUT (43) for *Podocarpus polystachya*.

The first peculiarity of the tribe is that the pollen grains are winged, except in *Saxegothaea* (149, 150),

a character that has suggested a connection with Abietineae, the only other tribe of conifers with winged pollen grains. The situation in *Microcachrys* (151, 163), however, taken in connection with the wingless spores of *Saxegothaea*, suggests that wings may have arisen quite independently in this tribe. In *Microcachrys* the wings are not so definite in development or in number as in *Podocarpus* and *Dacrydium*, in which two well-developed wings occur. THOMSON (163), examining sixty-four pollen grains, found fifty with three wings, nine with four, two with five, and three with six. In every case the wings are comparatively small, variable in size, and late in development. Three wings are also found in




FIG. 388.—*Cephalotaxus drupacea*: the two sperm nuclei within the body cell; the stalk nucleus (smaller) and tube nucleus are in advance; May 23, 1904.—After LAWSON (130).

certain species of *Podocarpus* (*P. dactydioides* and *P. ferruginea*). In this feature, therefore, *Microcachrys* seems to be a transition form

between *Podocarpus* and *Dacrydium* on the one hand, and *Saxegothaea* on the other.

In the development of the prothallial tissue, two cells are successively cut off, as among the Abietineae, but the peculiarity of the podocarps is that these cells usually divide, resulting in extreme cases in a tissue of eight cells. A further peculiarity of this tissue is that the walls break down and the nuclei become free, passing into the pollen tube with the body cell and stalk and tube nuclei (fig. 391). It must be understood that these supernumerary cells are not formed as are the two original cells, that is, in the series of divisions from microspore to male cells, but represent a secondary and variable product of the two primary cells. The variability may be indicated as follows.


In *Phyllocladus* (144) the two prothallial cells usually do not divide, and the first one begins to disorganize as soon as it is formed (occasionally persisting more or less), but the second one persists (fig. 392), and occasionally divides (174). This is exactly the behavior of the prothallial tissue of



FIGS. 389-391.—Male gametophyte of *Dacrydium*: s, stalk cell; b, body cell; t, tube nucleus; fig. 389, *D. Bidwillii*, just after the division into stalk and body cells; the two prothallial cells have not divided; fig. 390, *D. cupressinum*, later stage; both prothallial cells have divided; fig. 391, *D. laxifolium*, showing the body cell and tube nucleus, and the nuclei of the stalk cell and of four prothallial cells; X960.—After Miss YOUNG (136).

(174). This is exactly the behavior of the prothallial tissue of

*Ginkgo*, but in *Phyllocladus* the nucleus (or nuclei) becomes free. As a consequence, the spores on the tip of the nucellus are found to contain three or four nuclei, one or two of which are vegetative, and the body cell. In *Dacrydium* (136) the generative cell is cut



FIGS. 392-396.—Pollen grains of several podocarps:—stalk, body, and prothallial cells evident; fig. 392, *Phyllocladus alpina*, showing an evanescent and a persistent prothallial cell, also stalk, body, and tube cells;  $\times 950$ ; after Miss YOUNG (174); fig. 393, pollen grain of *Microcachrys tetragona* at the shedding stage; after THOMSON (163); figs. 394, 395, *Saxegothaea conspicua*; fig. 394, the two prothallial cells, the generative cell, and the tube cell are in a line;  $\times 700$ ; after NORÉN (149); fig. 395, later stage, showing body cell, and nuclei of tube, stalk, and three prothallial cells; also several large starch grains;  $\times 700$ ; after NORÉN (149); fig. 396, *Podocarpus totarra Hallii*; the usual condition of pollen grain at the shedding stage, containing tube nucleus, stalk and body cells, and eight prothallial cells (only four shown) derived from the two primary prothallial cells; after BURLINGAME (139).

off immediately after the two prothallial cells; and then it and the second prothallial cell divide. In some cases (*D. Bidwillii*) usually only the second prothallial cell divides, but in others (*D. laxifolium* and *D. cupressinum*) both prothallial cells divide. The result is that at pollination the spore contains three or four free vegetative nuclei, in addition to the body cell and the stalk and tube nuclei



(figs. 389-391). In *Microcachrys* (151, 163) the situation in *Dacrydium* is repeated, three (more frequent) or four prothallial cells appearing, depending upon the division of one or both of the two primary cells (fig. 393); and the prothallial tissue of *Saxegothaea* (149) is exactly the same (figs. 394, 395). In these three




FIG. 397.—*Phyllocladus alpina*: the two unequal male cells, with the stalk and tube nuclei and one prothallial nucleus in advance; the archegonium shows a four-celled neck and a definite jacket; the egg is ready for fertilization;  $\times 440$ .—After Miss YOUNG (174).

genera, the second prothallial cell always divides and the first also may divide, and at pollination three or four free vegetative nuclei are found in the grain. *Podocarpus* is much more variable (69, 128, 139), the number of prothallial cells and free nuclei varying from one to eight (fig. 396). Only one prothallial cell may be cut off, and it may not divide; but usually there are two primary cells, the second of which always divides and both of which may, and in both cases there may be still another division. Therefore, there

may be one, three, four, six, or eight prothallial cells, and subsequently the same number of free vegetative nuclei that swarm into the pollen tube.

This behavior of the male prothallial tissue among the podocarps is not only constant and striking, but it is the same in kind as that observed among the araucarians (p. 277), the only difference being that the vegetative cells and free nuclei in the latter group reach a

much higher number than among the podocarps. The suggestion of a genetic connection between these two tribes will be considered later.

The course of spermatogenesis in the podocarps, from the division of the generative cell just before fertilization, presents no unusual features. In *Dacrydium* (136) it was observed that the generative




FIG. 398.—*Phyllocladus alpina*: apex of nucellus broken down by numerous pollen tubes; the top of the endosperm also somewhat disorganized; each archegonium is surrounded by a definite jacket;  $\times 180$ .—After Miss KILDAHL (144).

cell divides anticleinally, the stalk and body cells being side by side and for some time indistinguishable. Presently one of them enlarges, rounds off, and becomes free, while the nucleus of the other becomes free by the disappearance of its wall or membrane. In the two genera in which the male cells have been observed, the two extremes of variation are represented. In *Phyllocladus* (174) the body cell divides to form two unequal male cells, only one of which functions (fig. 397);

while in *Podocarpus* (69) only the nucleus of the body cell is said to divide and all of the cytoplasm to be organized in connection with one of the male nuclei as a male cell, leaving the other male nucleus thrust out at its periphery.

In *Saxegothaea* (149) pollen falls not only on the extruded and broadly flaring tip of the nucellus, but sometimes also in the depression around the ovule, and in this position pollen tubes develop and grow over the tissues to the micropyle. It will be remembered that this growth of pollen tubes to the micropyle from some distance outside is one of the features of the araucarians (p. 283).

#### FERTILIZATION

Among the Taxaceae the tip of the pollen tube discharges all of



FIG. 399.—*Torreya taxifolia*: fertilization; the male nucleus is in contact with the egg nucleus; the cytoplasm of the male cell is closely applied to the egg nucleus; the functionless male cell and stalk and tube nuclei are in the upper part of the egg; August 12, 1904;  $\times 460$ .—After COULTER and LAND (101).

its free contents into the cytoplasm of the egg, in the peripheral region of which there may be found both male cells or nuclei, the stalk and tube nuclei, and such prothallial nuclei as may be in the tube. All of these gradually disappear except the functioning male cell or nucleus, although sometimes they may still be distinguished in the early stages of the proembryo.

In *Cephalotaxus Fortunei* the non-functioning male nucleus has been observed (55) to divide amitotically, producing as many as six nuclei. In *Phyllocladus* (174) the male cells are

discharged outside the archegonium and pass between the separated neck cells.

In *Torreya californica* (99), *Torreya taxifolia* (101), *Cephalo-*

*taxus Fortunei* (124), and *Phyllocladus* (144) the functioning male cell, with its complete investment of cytoplasm, has been observed to come in contact with the egg nucleus (figs. 399, 400). In this position, the male cytoplasm spreads from its own nucleus and invests the egg nucleus, and this investment is very evident in the fusion nucleus, and may persist in *Torreya taxifolia* as a distinct cytoplasmic sheath even about the four free nuclei at wall-formation. This sheath is recognizable on account of its abundant supply of food material, and is doubtless of service in the nutrition of the fusion nucleus. In *Cephalotaxus drupacea* (130), in which male cells are not formed, the two free male nuclei do not escape from the membrane of the body cell until at the time of discharge.

An interesting consequence of the early appearance and fertilization of the eggs of *Torreya taxifolia* may be mentioned. At this time the endosperm tissue has not grown, and in its subsequent development it grows about the tip of the pollen tube, incloses the fertilized egg, and forms quite a beak above the embryo.

Critical observations of fertilization among the conifers are not numerous enough to form the basis of a general conclusion, but the evidence thus far indicates that the behavior of the male cytoplasm, in investing the fusion nucleus as a nutritive zone, is a feature of the Taxaceae; while among the Pinaceae the male nucleus slips from its cytoplasmic sheath in the periphery of the egg cytoplasm (with *Taxodium* and *Juniperus* as exceptions). Subsequent investigation may show that both methods belong indiscriminately to both families.




FIG. 400.—*Phyllocladus alpina*: fertilization; both male cells are shown, the one at the right is functional, and the one at the left is disorganizing;  $\times 440$ .—After Miss YOUNG (174).



#### 4. The embryo


The two general stages in the development of the embryo of Pinaceae are repeated among Taxaceae, but there is more variation in the character of the proembryo, and it more commonly fills the whole egg. The fact that among Pinaceae the proembryo usually occupies only a relatively small part of the basal region of the egg is not due to the small number of cells, for these may be just as numerous as among the Taxaceae, but is due to the large size of the egg at fertilization. The proembryo of Taxaceae also differs in the lack of uniformity of its tiers, the embryo-forming tier usually being represented by a single cell, while the suspensor and "rosette" tiers may be represented by a considerable number of cells; a fact that is probably due to the size and configuration of the egg.

##### THE PROEMBRYO

The development of the proembryo of *Torreya taxifolia* (101) may be used as an illustration. The division of the fusion nucleus is followed immediately by a second division, and the four large free nuclei almost fill the small egg (fig. 401). As a consequence, there is no such movement of nuclei toward the base as occurs in larger eggs. At this four-nucleate stage wall-formation occurs in the usual way by connecting fibers, the four walled cells completely filling the egg. Division of these cells continues until a proembryo of about twelve cells is produced, arranged more or less definitely in three tiers, as follows: five or six in the "rosette" tier, five or six in the suspensor tier, and one in the embryo-forming tier (fig. 402). Later divisions may result in a proembryo of eighteen cells. It is this twelve to eighteen-celled proembryo that persists, without further change, until the following spring. The relatively small egg, the very large nuclei, and the early appearance of walls are probably accountable for the tissue-filled egg. This account agrees with that given for *Torreya californica* (99).

In *Cephalotaxus* fertilization occurs later in the history of the gametophyte and the eggs are larger. In the two species investigated, *C. Fortunei* (124) and *C. drupacea* (130), four free nuclei are formed and then assume the basal position, in which nuclear division continues

until eight or sixteen free nuclei are produced, when wall-formation occurs, the completed proembryo consisting of sixteen or thirty-two cells. These cells form fairly definite tiers above, but become more or less irregularly arranged below. Four regions or tiers may be recognized, at least so far as their functions are concerned: open tier (open above), suspensor tier, embryo-forming region, and region of the "penetrating cap," which last is a peculiar feature of the genus (figs. 369, 370). In *Taxus* there are also sixteen free nuclei before wall-formation.



FIGS. 401, 402.—*Torreya taxifolia*: fig. 401, four-nucleate stage of proembryo; August 12, 1904;  $\times 460$ ; fig. 402, proembryo showing the three tiers of cells; the entire egg is segmented; the proembryo passes the winter in this stage; August 27, 1904;  $\times 460$ .—After COULTER and LAND (101).

Among the podocarps *Podocarpus* (69) and *Phyllocladus* (144) have been investigated. In the former genus the fusion nucleus assumes the basal position, and sixteen free nuclei appear before wall-formation. The three tiers of the completed proembryo are made up as follows: fourteen cells in the open tier, fourteen in the suspensor tier, and one binucleate cell in the embryo-forming tier. In *Phyllocladus* there are eight free nuclei before wall-formation.

Among the Pinaceae, with the possible exception of the araucarians, wall-formation in connection with the mitosis which gives rise to the eight-nucleate stage of the proembryo is a remarkably uniform

feature. Among the Taxaceae, however, there is wall-formation in connection with the mitosis which produces the four-nucleate stage (*Torreya*), the sixteen-nucleate stage (*Phyllocladus* and sometimes *Cephalotaxus*), and the thirty-two nucleate stage (*Taxus*, *Cephalotaxus*, and *Podocarpus*). A large number of free nuclei before wall-formation is a feature of the proembryos of Cycadales and Ginkgoales, and therefore it has been regarded as a primitive character. In general, this is probably true, but that it cannot be applied within a range of one or two divisions is evident from the fact that the extreme limits of free nuclei among conifers (two and sixteen) are found in *Torreya* and *Taxus*, two of the most closely allied genera.

#### THE SUSPENSOR AND EMBRYO

Suspensor-formation as observed in *Torreya taxifolia* (101) is probably true in general of all the genera of Taxaceae (fig. 403). Among Pinaceae the elongation characteristic of suspensor-formation so often appears to be definitely restricted to a single tier of proembryonic cells that it has produced the impression that the suspensor is necessarily an organ of definite origin. The elongation may involve every tier of the proembryo, and the suspensor is the total product of this elongation. In *Torreya* elongation begins in the uppermost tier ("rosette") of the proembryo, which is probably always the case when this tier is closed, and extends gradually downward, tier after tier, until it includes the proximal region of the meristematic cylinder produced by the embryo-forming cell. In this case, therefore, every tier of the proembryo "contributes" to the suspensor. The same phenomenon was observed in *Thuja* (72), among the Pinaceae.

Usually a single embryo is developed at the end of the suspensor, but in *Podocarpus* the constituent cells of the suspensor have been observed (69) to separate, resulting in the formation of several embryos from a single egg. Secondary embryos have been observed in *Cephalotaxus* (130) also to bud from the group of embryo-forming cells; and in *Torreya* such embryos have been seen (101) to bud from the suspensor region during the second season. In *Cephalotaxus* (124, 130) a series of long haustorial "embryonal tubes" develop early from the proximal cells of the embryo.

The single embryo-forming cell of *Torreya* (101) develops a cylin-

drical mass of meristematic cells, and this cylinder invades the endosperm, its basal cells contributing to the suspensor. Later, growing points are organized, the root tip being deep in the cylinder, and the two concave cotyledons completely surrounding the stem tip. The peculiarity of the embryo-formation in *Cephalotaxus* (25, 124, 130) has been mentioned, in which the terminal cells of the proembryo form a persistent cap for the embryo during its advance through the endosperm. That this same feature appears in *Araucaria brasiliana* (25) is a matter of interest (figs. 367, 368).

So far as known, all of the Taxaceae are dicotyledonous. This has been regarded as a primitive feature, because Bennettitales, Cycadales, and Ginkgoales are dicotyledonous; but the relation of polycotyledony to dicotyledony may lead to a different conclusion (see p. 298).

*Podocarpus Makoyi* has been found (73) to be viviparous, the embryo continuing its development and the hypocotyl passing out of the micropyle while the seed is attached to the parent plant. It is probable that other species of Taxaceae will be found to show the same habit, as it is not uncommon in other groups of gymnosperms.




FIG. 403.—*Torreya taxifolia*: proembryo showing elongation of suspensor cells; April 7, 1904;  $\times 460$ .—After COULTER and LAND (101).

## 5. History and distribution

The Taxaceae have not been recognized farther back than the Cretaceous, and so far as this negative evidence can be relied upon the family is comparatively a modern one among gymnosperms, certainly much younger than the Abietineae and the Araucarineae. It is possible that older Taxaceae existed, and that they have not been recognized among coniferous remains; but until they are recognized, the failure to find them earlier than the Cretaceous must be considered in any discussion of phylogeny.



In the present geographic distribution of Taxaceae, the two tribes are in contrast, the podocarps belonging almost exclusively to the southern hemisphere, and the taxads as exclusively to the northern. This associates the former tribe geographically with the araucarians, and the latter with the three other tribes of Pinaceae.

Among Podocarpineae the genus *Podocarpus* is the only one that ranges through a hemisphere, and is the only one represented in the northern hemisphere by its extension into Japan. Both *Dacrydium* and *Phyllocladus* belong to the Australasian region, but extend northward into the East Indies; while *Microcachrys* and *Pherosphaera* are restricted to Australasia (chiefly Tasmania), and *Saxegothaea* to the southern Andes. The tribe as a whole is distinctly Australasian.

Among Taxineae the genus *Taxus* is the only one represented throughout the northern hemisphere, extending southward into tropical Asia and the mountains of Mexico. The other genera are much restricted, *Cephalotaxus* being found only in Eastern Asia, *Acmopyle* and *Polypodiopsis* being restricted to New Caledonia, and *Torreya* being represented by four scattered species in Florida, California, Japan, and China. The general northern complexion of the group is evident, and the only endemic genus, excluding the two doubtful New Caledonian genera, is *Cephalotaxus*, all of whose six species occur only in eastern Asia.

## 6. Relationship to other gymnosperms

The opinions that have been expressed in reference to the relationships of the Taxaceae are so diverse that it is evident that the family presents a peculiarly difficult combination of resemblances. They have been called the oldest living conifers (133) and the most recent; they have been connected with *Ginkgo* through *Cephalotaxus* (124, 134), and with Cordaitales on account of the structure of the ovuliferous shoot of *Taxus* (134); and the podocarps have been related to the araucarians through *Dacrydium* and *Saxegothaea* (150).

In the absence of any history of the family, only the testimony of reproductive morphology and of vascular anatomy is available. In reviewing this testimony, it seems impossible to regard the family as a natural one, in the sense that all of its members belong to the same immediate stock. The tracheids of *Dacrydium* and *Saxe-*

*gothaea*, the ovulate cones of *Microcachrys* and *Saxegothaea*, the solitary ovule, and above all the peculiar male prothallial tissue of all the genera suggest that the Podocarpineae are allied to the Araucarineae, a suggestion that the common and peculiar geographical distribution of the two tribes reinforces. This may mean only a common immediate ancestry; but the well-known age and wide mesozoic distribution of the araucarians, when taken in connection with the lack of evidence of podocarps before the Cretaceous, makes the conclusion reasonable that the Podocarpineae of today are a southern offshoot from the mesozoic Araucarineae; and they do not contradict any more ancient connection that the araucarians may have had with the Abietineae.

A recent conclusion as to relationships, suggested by TISON (165), deserves mention. It is based upon a study of the vascular anatomy of *Saxegothaea conspicua*, especially that of the ovulate strobilus. From the behavior and distribution of the two systems of bundles found in the megasporophyll, one serving the sporophyll and the other the ovule, it is concluded that *Saxegothaea* is more nearly related to the araucarians than to the podocarps, but that through *Microcachrys* it is connected with the latter so definitely that the araucarians, *Saxegothaea*, and the podocarps should constitute a single group comprising the three members indicated as subgroups. This conclusion depends upon the view that the structure of the ovulate cone, especially its vascular structure, is the paramount feature in determining relationship.

A recent study by Miss GERRY (168) has thrown doubt upon the association of the podocarps with the araucarians. She has discovered that the "bars of Sanio" (p. 235), apparently a serviceable character in the determination of coniferous woods, are present in all the Coniferales except the araucarians. This character dissociates the podocarps from the araucarians, and allies them more nearly with the Abietineae. Just how much this should outweigh the other characters which suggest an araucarian alliance is a matter of individual judgment, but it is clear that it must be taken into consideration.

The Taxineae present greater difficulties, for their resemblances are not so definite, and their combination of so-called primitive and

advanced characters is more perplexing. This is indicated by SCOTT's statement (160) that if any one of the tribes of conifers could be regarded as distinct in origin, it would be the taxads. It seems impossible to interpret the resemblances to *Ginkgo* as meaning anything more than the retention of common characters derived from a common ancestor, presumably in this case the Cordaitales. At the same time, it would seem impossible to connect the Taxineae, which have no history earlier than the Cretaceous, directly with the paleozoic Cordaitales. The only mesozoic stock they suggest is that from which the modern Abietineae, Taxodineae, and Cupressineae have come; and they differ from Abietineae in some of the important morphological features shown by Taxodineae and Cupressineae. The geographical association also enforces this suggestion, and the conclusion seems reasonable that the living Taxineae represent a phylum which was derived early from the abietineous stock, and which has retained cordaitan features that have disappeared among existing Abietineae, Taxodineae, and Cupressineae. The greatest objection to this connection lies in the structure of the ovulate strobilus, but the condition in Taxineae, as contrasted with that of the three tribes of Pinaceae, is one of those differences in degree rather than in kind (see p. 322) which mark ancient separation at a time when both groups bore more resemblance to their common ancestral stock.

The position of *Phyllocladus* among Taxaceae has given rise to such diversity of opinion that a summary of the evidence may be useful. The three alternatives are (1) to include it with Taxineae, (2) to include it with Podocarpineae, or (3) to constitute for it an intermediate tribe. The taxad resemblances are (1) structure of ovule, (2) symmetrical arillus, (3) ovulate strobilus, (4) mesarch bundles, (5) markings of tracheids. The podocarp resemblances are (1) male gametophyte, (2) structure of stamen, (3) winged pollen grains, (4) megaspore membrane, (5) "spongy tissue." The taxad features are, on the whole, more superficial and variable; and the podocarp features are more fundamental, so fundamental, in fact, that an intermediate tribe seems unjustifiable. It seems evident that the testimony is strongly in favor of including *Phyllocladus* in Podocarpineae (174).

LIST OF GENERA OF CONIFERALES, WITH APPROXIMATE  
NUMBER OF SPECIES

## A. PINACEAE

I. *Abietineae*

1. <i>Pinus</i> .....	75	6. <i>Tsuga</i> .....	6
2. <i>Cedrus</i> .....	3	7. <i>Pseudotsuga</i> .....	2
3. <i>Larix</i> .....	8	8. <i>Keteleeria</i> .....	2
4. <i>Pseudolarix</i> .....	1	9. <i>Abies</i> .....	20
5. <i>Picea</i> .....	12		

II. *Taxodineae*

10. <i>Sciadopitys</i> .....	1	14. <i>Arthrotaxis</i> .....	3
11. <i>Sequoia</i> .....	2	15. <i>Cryptomeria</i> .....	1
12. <i>Cunninghamia</i> .....	1	16. <i>Taxodium</i> .....	2
13. <i>Taiwania</i> .....	1	17. <i>Glyptostrobus</i> .....	2

III. *Cupressineae*

18. <i>Actinostrobus</i> .....	2	23. <i>Libocedrus</i> .....	8
19. <i>Callitris</i> .....	15	24. <i>Thuja</i> .....	4
20. <i>Widdringtonia</i> .....	5	25. <i>Cupressus</i> .....	12
21. <i>Fitzroya</i> .....	2	26. <i>Chamaecyparis</i> .....	4
22. <i>Thujopsis</i> .....	1	27. <i>Juniperus</i> .....	30

IV. *Araucarineae*

28. <i>Agathis</i> .....	10	29. <i>Araucaria</i> .....	10
--------------------------	----	----------------------------	----

## B. TAXACEAE

I. *Podocarpineae*

30. <i>Podocarpus</i> .....	60	33. <i>Pherosphaera</i> .....	2
31. <i>Dacrydium</i> .....	16	34. <i>Saxegothaea</i> .....	1
32. <i>Microcachrys</i> .....	1	35. <i>Phyllocladus</i> .....	6

II. *Taxineae*

36. <i>Taxus</i> .....	7	39. <i>Acmopyle</i> .....	1
37. <i>Torreya</i> .....	4	40. <i>Polypodiopsis</i> .....	1
38. <i>Cephalotaxus</i> .....	6		

## LITERATURE CITED

1. BROWN, ROBERT, Character and description of *Kingia*, a new genus of plants found on the S.W. coast of New Holland, with observations on the structure of its unimpregnated ovulum and the female flower in Cycadeae and Coniferae. 1827. Included also in BROWN'S Miscellaneous botanical works 1:1866.
2. SCHLEIDEN, M. J., Sur la signification morphologique du placentaire. Ann. Sci. Nat. Bot. II. 12:373-376. 1839.



3. BRAUN, A., Vortrag auf dem Congrès scientifique de France, 10th session (Strassburg), pp. 171, 172. 1842 (communicated in BRAUN's *Leben von C. METTENIUS*, p. 335. Berlin. 1882).
4. VON MOHL, HUGO, Ueber die männlichen Blüthen der Coniferen. *Verm. Bot. Schriften*, pp. 45-61. 1845. (Published as a dissertation, 1837.)
5. DUCHARTRE, P. E., Mémoire sur les embryons qui ont été décrits comme polycotylés. *Ann. Sci. Nat. Bot. III.* 10:207-237. *pls.* 7-10. 1848.
6. HOFMEISTER, W., Embryobildung der Phanerogamen. *Jahrb. Wiss. Bot.* 1:82-188. *pls.* 7-10. 1858.
7. BAILLON, H., Recherches organogéniques sur la fleur femelle des Conifères. *Ann. Sci. Nat. Bot. IV.* 14:186-199. *pls.* 12, 13. 1860.
8. CASPARY, R., De Abietinearum floris feminei structura morphologica. *Ann. Sci. Nat. Bot. IV.* 14:200-209. 1860.
9. DICKSON, A., Observations on some bisexual cones occurring in the spruce fir (*Abies excelsa*). *Trans. Edinburgh Bot. Soc.* 6:418-422. 1860.
10. HOFMEISTER, W., Vergleichende Untersuchungen, etc. English translation. 1863.
11. OERSTED, A. S., Bidrag til Naaletroeernes Morphologi. *Vidensk. Meddel. Nat. Foren. Copenhagen.* 1864.
12. PARLATORE, F., Studi organografici sui fiori e sui frutti delle Conifere. *Opuscula botanica.* 1864.
13. HOFMEISTER, W., Lehre der Pflanzenzelle. 1867.
14. SACHS, J., Lehrbuch. 1868.
15. STRASBURGER, E., Die Befruchtung bei den Coniferen. 1869.
16. VAN TIEGHEM, PH., Anatomie comparée de la fleur femelle et du fruit des Cycadées, des Conifères, et des Gnetacées. *Ann. Sci. Nat. Bot. V.* 10:269-304. *pls.* 13-16. 1869.
17. VON MOHL, HUGO, Morphologische Betrachtung der Blätter von *Sciadopitys*. *Bot. Zeit.* 29:17-23. 1871.
18. STRASBURGER, E., Die Coniferen und Gnetaceen. 1872.
19. EICHLER, A. W., Sind die Coniferen gymnosperm oder nicht? *Flora* 54: 241-247, 260-272. 1873; and later papers.
20. ENGELMANN, G., Morphology of the carpellary scales of Coniferae. *Amer. Jour. Sci. III.* 12:469, 470. 1876.
21. STENZEL, G., Beobachtungen an durchwachsenen Fichtenzapfen. Ein Beitrag zur Morphologie der Nadelhölzer. *Nov. Act. Nat. Cur.* 38:289-350. *pls.* 12-15. 1876.
22. STRASBURGER, E., Die Befruchtung und Zelltheilung. *Jen. Zeitsch.* 2:435-536. *pls.* 27-35. 1877.
23. ———, Befruchtung und Zelltheilung. 1878.
24. ČELAKOVSKÝ, L., Zur Gymnospermie der Coniferen. *Flora* 62:257-264, 272-283. 1879.
25. STRASBURGER, E., Die Angiospermen und die Gymnospermen. 1879.

26. ČELAKOVSKÝ, L., Zur Kritik der Ansichten von der Fruchtschuppe der Abietineen. Abhandl. Königl. Böhm. Gesell. Wiss. VI. 11: 1882.
27. SACHS, J., Textbook of botany. Second English edition. 1882.
28. GOROSCHANKIN, J., Zur Kenntniss der Corpuscula bei den Gymnospermen. Bot. Zeit. 41: 825-831. pl. 7A. 1883; Ueber den Befruchtung-Process bei *Pinus Pumilio*. 1883.
29. DEBARY, A., Comparative anatomy of the vegetative organs of the phanerogams and ferns. English translation. 1884.
30. RENAULT, B., Cours de botanique fossile. Paris. 1880-1884.
31. STRASBURGER, E., Neue Untersuchungen, etc. 1884.
32. ČELAKOVSKÝ, L., Die Gymnospermen: eine morphologisch-phylogenetische Studie. Abhandl. Königl. Böhm. Gesell. Wiss. VII. 4: 1-148. 1890.
33. BELAJEFF, W., Zur Lehre von dem Pollenschlauche der Gymnospermen. Ber. Deutsch. Bot. Gesell. 9: 280-286. pl. 18. 1891.
34. MASTERS, M. T., Comparative morphology, anatomy, and life history of the Coniferae. Jour. Linn. Soc. London Bot. 27: 226-332. figs. 29. 1891.
35. VAN TIEGHEM, PH., Traité de botanique. Paris. 1891.
36. DANGEARD, P. A., Recherches sur les plantules des Conifères. La Botaniste 3: 126-204. pls. 13-17. 1892.
- 36a. FARMER, J. B., On the occurrence of two prothallia in the embryo sac of *Pinus*. Annals of Botany 6: 213, 214. fig. 5. 1892.
37. MOTTIER, D. M., On the archegonium and apical growth of the stem in *Tsuga canadensis* and *Pinus silvestris*. Bot. Gazette 17: 141-143. pl. 8. 1892.
38. STRASBURGER, E., Ueber das Verhalten des Pollens und die Befruchtungsvorgänge bei den Gymnospermen. Hist. Beitr. 4: 1-158. pls. 1-3. 1892.
39. BELAJEFF, W., Zur Lehre von dem Pollenschlauche der Gymnospermen (Zweite Mittheilung). Ber. Deutsch. Bot. Gesell. 11: 196-201. pl. 12. 1893.
40. DIXON, H. N., Fertilization of *Pinus silvestris*. Annals of Botany 8: 21-34. pls. 3-5. 1894.
41. CAMPBELL, D. H., Mosses and ferns. New York. 1895.
- 41a. KERNER VON MARILAUN, Das Pflanzenleben. Leipzig and Vienna. 1896.
42. SHAW, W. R., Contribution to the life history of *Sequoia*. Bot. Gazette 21: 332-339. pl. 24. 1896.
43. THIBOUT, E., Recherches sur l'appareil mâle des gymnospermes. pp. 265. pls. 16. Lille. 1896.
44. COULTER, JOHN M., Notes on the fertilization and embryogeny of conifers. Bot. Gazette 23: 40-43. pl. 6. 1897.
45. WORSDELL, W. C., On transfusion tissue; its origin and function in the leaves of gymnospermous plants. Trans. Linn. Soc. London Bot. II. 5: 301-319. pls. 23-26. 1897.
46. BLACKMAN, V. H., On the cytological features of fertilization and related phenomena in *Pinus silvestris* L. Phil. Trans. Roy. Soc. B 190: 395-426. pls. 12-14. 1898.

47. ČELAKOVSKÝ, L., Nachtrag zu meiner Schrift über die Gymnospermen. ENGLER'S Bot. Jahrb. **24**:202-231. 1898.
48. CHAMBERLAIN, C. J., Winter characters of certain sporangia. Bot. Gazette **25**:125-128. *pls. 11*. 1898.
49. ARNOLDI, W., Beiträge zur Morphologie einiger Gymnospermen. I. Die Entwicklung des Endosperms bei *Sequoia sempervirens*. Bull. Soc. Imp. Nat. Moscou 1899: pp. 13. *pls. 7, 8*.
50. ———, Beiträge zur Morphologie und Entwicklungsgeschichte einiger Gymnospermen. II. Ueber die Corpuscula und Pollenschlauche bei *Sequoia sempervirens*. Bull. Soc. Imp. Nat. Moscou 1899: pp. 8. *pls. 10, 11*.
51. CHAMBERLAIN, C. J., Oogenesis in *Pinus Laricio*. Bot. Gazette **27**:268-280. *pls. 4-6*. 1899.
52. JÄGER, L., Beiträge zur Kenntniss der Endospermbildung und zur Embryologie von *Taxus baccata*. Flora **86**:241-288. *pls. 15-19*. 1899.
53. POTONIÉ, H., Lehrbuch der Pflanzenpalaeontologie. Berlin. 1899.
54. WOYCICKI, Z., (On fertilization in Coniferae). pp. 57. *pls. 2*. 1899. (Russian)
55. ARNOLDI, W., Beiträge zur Morphologie der Gymnospermen. III. Embryogenie von *Cephalotaxus Fortunei*. Flora **87**:46-63. *pls. 1-3*. 1900.
56. ———, Beiträge zur Morphologie der Gymnospermen. IV. Was sind die "Keimblaschen" oder "Hofmeister's-Körperchen" in der Eizelle der Abietineen? Flora **87**:194-204. *pls. 6, 7*. 1900.
57. COKER, W. C., Observations on the gametophyte and embryo of *Taxodium distichum*. Johns Hopkins Univ. Circ. **19**:45, 46. 1900.
58. GOEBEL, K., Organography of plants. English translation. pp. 153-155. 1900.
59. JUEL, H. O., Beiträge zur Kenntniss der Tetradenbildung. Jahrb. Wiss. Bot. **35**:626-659. *pls. 15, 16*. 1900.
60. MURRILL, W. A., The development of the archegonium and fertilization in the hemlock spruce (*Tsuga canadensis*). Annals of Botany **14**:583-607. *pls. 31, 32*. 1900.
61. SCOTT, D. H., Studies in fossil botany. London. 1900.
62. WORSDELL, W. C., The structure of the female "flower" in Coniferae. Annals of Botany **14**:39-82. 1900.
63. ———, The vascular structure of the ovule of *Cephalotaxus*. Annals of Botany **14**:317, 318. 1900.
64. ARNOLDI, W., Beiträge zur Morphologie einiger Gymnospermen. V. Weitere Untersuchungen der Embryogenie in der Familie der Sequoiaceen. Bull. Soc. Imp. Nat. Moscou 1910: pp. 28. *pls. 2*.
65. FERGUSON, MARGARET C., The development of the pollen tube and the division of the generative nucleus in certain species of pines. Annals of Botany **15**:193-223. *pls. 12-14*. 1901.

66. FERGUSON, MARGARET C., The development of the egg and fertilization in *Pinus Strobus*. *Annals of Botany* **15**:435-479. *pls.* 23-25. 1901.
67. BESSEY, CHARLES E., The morphology of the pine cone. *Bot. Gazette* **33**: 157-159. *pl.* 8. 1902.
68. CHAUVEAUD, G., Passage de la disposition primitive à la disposition secondaire dans les cotylédons du Pin maritime. *Extr. Bull. Mus. Hist. Nat. Paris*. 1902.
69. COKER, W. C., Notes on the gametophytes and embryo of *Podocarpus*. *Bot. Gazette* **33**:89-107. *pls.* 5-7. 1902.
70. GOEBEL, K., Morphologische und biologische Bemerkungen. 13. Ueber die Pollenentleerung bei einiger Gymnospermen. *Flora* **91**:237-263. *figs.* 19. 1902.
71. JEFFREY, E. C., The structure and development of the stem in the Pteridophyta and Gymnosperms. *Phil. Trans. Roy. Soc. London B* **195**:119-146. *pls.* 6. 1902.
72. LAND, W. J. G., A morphological study of *Thuja*. *Bot. Gazette* **34**:249-259. *pls.* 6-8. 1902.
73. LLOYD, FRANCIS E., Vivipary in *Podocarpus*. *Torreya* **2**:113-117. *figs.* 3. 1902.
74. ALLEN, C. E., The early stages of spindle formation in the pollen mother cells of *Larix*. *Annals of Botany* **17**:218-312. *pls.* 14, 15. 1903.
75. CHICK, EDITH, The seedling of *Torreya myristica*. *New Phytologist* **2**:83-91. *pls.* 7, 8. 1903.
76. COKER, W. C., On the gametophytes and embryo of *Taxodium*. *Bot. Gazette* **36**:1-27, 114-140. *pls.* 1-11. 1903.
77. JEFFREY, E. C., Comparative anatomy of gymnosperms, in COULTER and CHAMBERLAIN'S *Morphology of angiosperms*. New York. 1903.
78. ———, The comparative anatomy of the Coniferales. I. The genus *Sequoia*. *Mem. Boston Soc. Nat. Hist.* **5**:441-459. *pls.* 68-71. 1903.
79. MIYAKE, K., On the development of the sexual organs and fertilization in *Picea excelsa*. *Annals of Botany* **17**:351-372. *pls.* 16, 17. 1903.
- 79a. ———, Contribution to the fertilization and embryogeny of *Abies balsamea*. *Beih. Bot. Centralbl.* **14**:134-144. *pls.* 6-8. 1903.
80. OLIVER, F. W., The ovules of the older gymnosperms. *Annals of Botany* **17**:451-476. *pl.* 24. *figs.* 20. 1903.
81. PILGER, R., Taxaceae in ENGLER'S *Das Pflanzenreich*. 1903.
82. ZEILLER, R., et FLICHE, P., Découverte de strobiles de *Sequoia* et de Pin dans le Portlandien des environs de Boulogne-sur-Mer. *Compt. Rend. Acad. Sci. Paris* **137**:1020-1022. 1903.
83. CHAUVEAUD, G., Le liber précurseur dans le sapin pinsapo. *Ann. Sci. Nat. Bot.* **VIII**. **19**:321-333. 1904.
84. ———, Origine secondaire du double faisceau foliaire chez les sapins (*Abies*) et les pins (*Pinus*). *Ann. Sci. Nat. Bot.* **VIII**. **19**:335-348. 1904.



85. COKER, W. C., On the spores of certain Coniferae. *Science N.S.* **19**:424. 1904.
86. ———, On the spores of certain Coniferae. *Bot. Gazette* **38**:206-213. *figs.* 24. 1904.
87. FERGUSON, MARGARET C., Contributions to the life history of *Pinus*, with special reference to sporogenesis, the development of the gametophytes, and fertilization. *Proc. Wash. Acad. Sci.* **6**:1-202. *pls.* 1-24. 1904.
88. FLICHE, P., et ZEILLER, R., Note sur un florule portlandienne des environs de Boulogne-sur-Mer. *Bull. Soc. Geol. France IV.* **4**:787-812. 1904.
89. JEFFREY, E. C., A fossil *Sequoia* from the Sierra Nevada. *Bot. Gazette* **38**:321-332. *pls.* 18, 19. 1904.
90. ———, The comparative anatomy of the Coniferales. II. The Abietineae. *Mem. Boston Soc. Nat. Hist.* **6**:1-37. *pls.* 1-7. 1904.
91. JUEL, H. O., Ueber den Pollenschlauch von *Cupressus*. *Flora* **93**:56-62. *pl.* 3. 1904.
92. LAWSON, A. A., The gametophyte, archegonia, fertilization, and embryo of *Sequoia sempervirens*. *Annals of Botany* **18**:1-28. *pls.* 1-4. 1904.
93. ———, The gametophyte, fertilization, and embryo of *Crytomeria japonica*. *Annals of Botany* **18**:417-444. *pls.* 27-30. 1904.
94. MACMILLAN, CONWAY, Note on some British Columbian dwarf trees. *Bot. Gazette* **38**:379-381. *figs.* 3. 1904.
95. NORÉN, C. O., Ueber Befruchtung bei *Juniperus communis*. Vorläufige Mitteilung. *Arkiv. Bot. Svensk. Vetensk.-Akad.* **3**: pp. 11. 1904.
96. PENHALLOW, D. P., The anatomy of the North American Coniferales, together with certain exotic species from Japan and Australia. *Amer. Nat.* **38**:243-273, 331-359, 523-554, 691-723. 1904.
97. RENNER, OTTO, Ueber Zwitterblüthen bei *Juniperus communis*. *Flora* **93**:297-300. *figs.* 3. 1904.
98. ROBERTSON, AGNES, Spore formation in *Torreya californica*. *New Phytologist* **3**:133-148. *pls.* 3, 4. 1904.
99. ———, Studies in the morphology of *Torreya californica*. II. The sexual organs and fertilization. *New Phytologist* **3**:205-216. *pls.* 7-9. 1904.
100. STRASBURGER, E., Anlage des Embryosackes und Prothalliumbildung bei der Eibe nebst anschliessenden Erörterungen. *Festschrift zum siebzigsten Geburtstage von ERNST HAECKEL*. pp. 18. *pls.* 2. Jena. 1904.
101. COULTER, JOHN M., and LAND, W. J. G., Gametophytes and embryo of *Torreya taxifolia*. *Bot. Gazette* **39**:161-178. *pls.* A, 1-3. 1905.
102. GOTHAN, W., Zur Anatomie lebender und fossiler Gymnospermenhölzer. *Abhandl. Preuss. Geol. Landesanstalt. Neue Folge. Heft* 44. 1905.
103. KUBART, BRUNO, Die weibliche Blüthe von *Juniperus communis* L. *Sitzungsber. Kais. Akad. Wiss. Wien* **114**: pp. 29. *pls.* 2. 1905.

104. LOPRIORE, G., Ueber die Vielkörnigkeit der Pollenkörner von *Araucaria Bidwillii*. Vorläufige Mitteilung. Ber. Deutsch. Bot. Gesell. **23**:335-346. *pl.* 15. 1905.
105. SEWARD, A. C., and FORD, SIBILLE O., The Araucarieae, recent and extinct. Abstract read before Roy. Soc. London, December 1905.
106. SLUDSKY, N., Ueber die Entwicklungsgeschichte des *Juniperus communis*. Vorläufige Mitteilung. Ber. Deutsch. Bot. Gesell. **23**:212-216. *pl.* 6. 1905.
107. THOMSON, R. B., Preliminary note on the Araucarineae. Science N.S. **22**:88. 1905.
108. ———, The megaspore membrane of the gymnosperms. Univ. Toronto Biol. Series no. 4. pp. 64. *pls.* 5. 1905.
109. HAYATA, B., *Taiwania*, a new genus of conifers. Jour. Linn. Soc. Bot. **32**:330-332. *pl.* 16. 1906.
110. HILL, T. G., and DE FRAINE, E., On the seedling structure of gymnosperms. Annals of Botany **20**:471-473. 1906.
111. HOLLICK, A., and JEFFREY, E. C., Affinities of certain cretaceous plant remains commonly referred to the genera *Dammara* and *Brachyphyllum*. Amer. Nat. **40**:189-215. *pls.* 1-5. 1906.
112. JEFFREY, E. C., and CHRYSLER, M. A., On cretaceous Pityoxyla. Bot. Gazette **42**:1-15. *pls.* 1, 2. 1906.
113. MASTERS, MAXWELL T., On the conifers of China. Jour. Linn. Soc. London Bot. **37**:410-424. 1906.
114. POLLOCK, JAMES B., Variations in the pollen grain of *Picea excelsa*. Amer. Nat. **49**:253-286. *pl.* 1. 1906.
115. ROBERTSON, AGNES, Some points in the morphology of *Phyllocladus alpina* Hook. Annals of Botany **20**:259-265. *pls.* 17, 18. 1906.
116. SCOTT, D. H., "The origin of gymnosperms"; a discussion at the Linnean Society. New Phytologist **5**:68-76, 141-148. 1906.
117. SEWARD, A. C., "The origin of gymnosperms"; a discussion at the Linnean Society. New Phytologist **5**:68-76, 141-148. 1906.
118. SEWARD, A. C., and FORD, SIBILLE O., The Araucarieae, recent and extinct. Phil. Trans. Roy. Soc. London B **198**:305-411. *pls.* 23, 24. *figs.* 28. 1906.
119. STOPES, MARIE C., and FUJII, K., The nutritive relations of the surrounding tissues to the archegonia in gymnosperms. Beih. Bot. Centralbl. **20**:1-24. *pl.* 1. 1906.
120. THOMAS, ETHEL N., "The origin of gymnosperms"; a discussion at the Linnean Society. New Phytologist **5**:68-76, 141-148. 1906.
121. THOMSON, R. B., "The origin of gymnosperms"; a discussion at the Linnean Society. New Phytologist **5**:68-76, 141-148. 1906.
122. WEISS, F. E., "The origin of gymnosperms"; a discussion at the Linnean Society. New Phytologist **5**:68-76, 141-148. 1906.
123. WORSDELL, W. C., "The origin of gymnosperms"; a discussion at the Linnean Society. New Phytologist **5**:68-76, 141-148. 1906.

124. COKER, W. C., Fertilization and embryogeny in *Cephalotaxus Fortunei*. Bot. Gazette **43**:1-10. *pl. 1. figs. 5.* 1907.
125. HAYATA, B., On *Taiwania* and its affinity to other genera. Bot. Mag. Tokyo **21**:21-27. *pl. 1.* 1907.
126. HAYDON, WALTER T., The seed production of *Pinus sylvestris*. Proc. and Trans. Liverpool Biol. Soc. **22**:1-32. *figs. 16.* 1907.
127. JEFFREY, E. C., *Araucariopityx*, a new genus of araucarians. Bot. Gazette **44**:435-444. *pls. 27-30.* 1907.
128. JEFFREY, E. C., and CHRYSLER, M. A., The microgametophyte of the Podocarpaceae. Amer. Nat. **41**:355-364. *figs. 5.* 1907.
129. KILDAHL, N. JOHANNA, Development of the walls in the proembryo of *Pinus Laricio*. Bot. Gazette **44**:102-107. *pls. 8, 9.* 1907.
130. LAWSON, A. A., The gametophytes, fertilization, and embryo of *Cephalotaxus drupacea*. Annals of Botany **21**:1-23. *pls. 1-4.* 1907.
131. ———, The gametophytes and embryo of the Cupressineae, with special reference to *Libocedrus decurrens*. Annals of Botany **21**:281-301. *pls. 24-26.* 1907.
132. NORÉN, C. O., Zur Entwicklungsgeschichte des *Juniperus communis*. Uppsala Universitets Årsskrift **1907**: pp. 64. *pls. 4.*
133. PENHALLOW, D. P., A manual of the North American gymnosperms, exclusive of the Cycadales but together with certain exotic species. Boston. 1907.
134. ROBERTSON, AGNES, The Taxoideae; a phylogenetic study. New Phytologist **6**:92-102. *pl. 1.* 1907.
135. THOMAS, ETHEL N., A theory of the double leaf trace founded on seedling structure. New Phytologist **6**:77-91. *figs. 4.* 1907.
136. YOUNG, MARY S., The male gametophyte of *Dacrydium*. Bot. Gazette **44**:189-196. *pl. 19.* 1907.
137. BERRY, EDWARD W., Some araucarian remains from the Atlantic coastal plain. Bull. Torr. Bot. Club **35**:249-260. *pls. 11-16.* 1908.
138. ———, A mid-cretaceous species of *Torreya*. Amer. Jour. Sci. **25**:382-386. 1908.
139. BURLINGAME, L. L., The staminate cone and male gametophyte of *Podocarpus*. Bot. Gazette **46**:161-178. *pls. 8, 9. figs. 9.* 1908.
140. CHRYSLER, M. A., Tyloses in tracheids of conifers. New Phytologist **7**:198-204. *pl. 5.* 1908.
141. HILL, T. G., and DE FRAINE, E., On the seedling structure of gymnosperms. I. Annals of Botany **22**:689-712. *pl. 35. figs. 8.* 1908.
142. JEFFREY, E. C., On the structure of the leaf in cretaceous pines. Annals of Botany **22**:207-220. *pls. 13, 14.* 1908.
143. ———, Traumatic ray tracheids in *Cunninghamia sinensis*. Annals of Botany **22**:593-602. *pl. 31.* 1908.
144. KILDAHL, N. JOHANNA, The morphology of *Phyllocladus alpinus*. Bot. Gazette **46**:339-348. *pls. 20-22.* 1908.

145. KILDAHL, N. JOHANNA, Affinities of *Phyllocladus*. Bot. Gazette **46**:464, 465. 1908.
146. MASTERS, MAXWELL T., On the distribution of the species of conifers in the several districts of China, and on the occurrence of the same species in neighboring countries. Jour. Linn. Soc. London Bot. **38**:198-205. 1908.
147. MIYAKE, K., The development of the gametophytes and embryogeny of *Cunninghamia* (preliminary note). Bot. Mag. Tokyo **22**:45-50. *figs.* 14. 1908.
148. NATHORST, A. G., Palaeobotanische Mitteilungen. III. *Lycostrobus Scottii*, eine grosse Sporophyllähre aus den rätischen Ablagerungen Schonens. Handl. Kgl. Svensk. Vetensk.-Akad. **43**:1-12. *pls.* 1, 2. 1908.
149. NORÉN, C. O., Zur Kenntnis der Entwicklung von *Saxegothaea conspicua* Lindl. Svensk. Bot. Tidsskr. **2**:101-122. *pls.* 7-9. 1908.
150. STILES, W., The anatomy of *Saxegothaea conspicua* Lindl. New Phytologist **7**:209-222. *figs.* 28-34. 1908.
151. THOMSON, R. B., Note on the pollen of *Microcachrys*. Bot. Gazette **46**:465, 466. 1908.
152. TISON, A., Le nucelle stigmatifère et la pollination chez le *Saxegothaea conspicua*. Compt. Rend. Acad. Sci. Paris **147**:137-139. 1908.
153. BAILEY, IRVING W., The structure of the wood in the Pineae. Bot. Gazette **48**:47-55. *pl.* 5. 1909.
154. HILL, T. G., and DE FRAINE, E., On the seedling structure of gymnosperms. II. Annals of Botany **23**:189-227. *pl.* 15. *figs.* 11. 1909.
155. HOLLICK, ARTHUR, and JEFFREY, E. C., Studies of cretaceous coniferous remains from Kreischerville, New York. Mem. N.Y. Bot. Garden **3**:1-138. *pls.* 1-29. 1909.
156. LAWSON, A. A., The gametophytes and embryo of *Pseudotsuga Douglasii*. Annals of Botany **23**:163-180. *pls.* 12-14. 1909.
157. OTTLEY, ALICE M., The development of the gametophytes and fertilization in *Juniperus communis* and *Juniperus virginiana*. Bot. Gazette **48**:31-46. *pls.* 1-4. 1909.
158. SAXTON, W. T., Parthenogenesis in *Pinus Pinaster*. Bot. Gazette **47**:406-409. *figs.* 7. 1909.
159. ———, Preliminary account of the development of the ovule, gametophytes, and embryo of *Widdringtonia cupressoides* Endl. Bot. Gazette **48**:161-178. *pl.* 11. *figs.* 3. 1909.
160. SCOTT, D. H., Studies in fossil botany. Second edition. Vol. II. London. 1909.
161. SHAW, F. J. F., The seedling structure of *Araucaria Bidwillii*. Annals of Botany **23**:321-334. *pl.* 21. *figs.* 6. 1909.
162. SINNOTT, E. A. W., *Paracedroxylon*, a new type of araucarian wood. Rhodora **11**:165-173. *pls.* 80, 81. 1909.



163. THOMSON, R. B., On the pollen of *Microcachrys tetragona*. Bot. Gazette 47:26-29. pls. 1, 2. 1909.
164. ———, The megasporophyll of *Saxegothaea* and *Microcachrys*. Bot. Gazette 47:345-354. pls. 21-25. 1909.
165. TISON, A., Sur le *Saxegothaea* Lindl. Mém. Soc. Linn. Normandie 23:139-160. pls. 9, 10. 1909.
166. BARTHOLOMEW, MARY, Abnormal prothalli of *Pinus sylvestris*. Notes Roy. Bot. Gard. Edinburgh 4:253-255. pl. 49. 1909.
167. SAXTON, W. T., Development of the embryo in *Pinus Pinaster* Soland., with some notes on the life history of the species in Cape Colony. S. African Jour. Sci. 6:52-59. pl. 2. 1909.
168. GERRY, ELOISE, The distribution of the "bars of Sanio" in the Coniferales. Annals of Botany 24:119-124. pl. 13. 1910.
169. STOPES, MARIE C., and FUJII, K., Studies on the structure and affinities of cretaceous plants. Phil. Trans. Roy. Soc. London B 201:1-90. pls. 1-9. 1910. Abstract in Annals of Botany 24:231, 232. 1910.
170. THOMPSON, W. P., On the origin of ray tracheids in the Coniferae. Bot. Gazette 50:101-116. figs. 6. 1910.
171. TISON, A., Remarques sur les gouttelettes collectrices des ovules des Conifères. Mém. Soc. Linn. Normandie 24:51-66. pls. 3, 4. 1910 (?).
172. COULTER, J. M., BARNES, C. R., and COWLES, H. C., A textbook of botany. New York. 1910.
173. NICHOLS, GEORGE E., A morphological study of *Juniperus communis* var. *depressa*. Beih. Bot. Centralbl. 25:201-241. pls. 8-17. figs. 4. 1910.
174. YOUNG, MARY S., The morphology of the Podocarpaceae. Bot. Gazette 50:81-100. pls. 4-6. 1910.
175. LAWSON, A. A., The gametophytes and embryo of *Sciadopitys verticillata*. Annals of Botany 24:403-421. pls. 29-31. 1910.
176. SAXTON, W. T., Contributions to the life history of *Widdringtonia cupressoides*. Bot. Gazette 50:30-48. pls. 1-3. 1910.
177. ———, Contributions to the life history of *Callitris*. Annals of Botany 24:July 1910.
178. BROOKS, F. T., and STILES, W., The structure of *Podocarpus spinulosa* (Smith) R. Br. Annals of Botany 24:305-318. pl. 21. 1910.
179. SAXTON, W. T., Notes on the anatomy of *Widdringtonia* and *Callitris*. S. African Jour. Sci. 7:282-286. figs. 11. 1910.
180. MIYAKE, K., The development of the gametophytes and embryogeny in *Cunninghamia sinensis*. Beih. Bot. Centralbl. 27:1-25. pls. 1-5. figs. 2. 1910.
181. VIERHAPPER, F., Entwurf eines neuen Systemes der Coniferen. Abhandl. K. K. Zool.-Bot. Gesell. Wien 5:1-56. 1910.

## CHAPTER VIII

### GNETALES

This group includes three genera which differ remarkably in habit and geographical distribution. Their great diversity and scattered distribution suggest the existence of older and more widely distributed forms, but no such history has been discovered. They are notable among gymnosperms for the presence of certain angiospermous features, and for this reason they have been regarded often as a transition group between gymnosperms and angiosperms. The two most important resemblances to angiosperms are the occurrence of true vessels in the secondary wood, and the elimination of archegonia in *Welwitschia*<sup>1</sup> and *Gnetum*. The presence of a "perianth" has also been cited as an angiospermous character, but it is not to be distinguished from the bracts associated with ovules and stamens in other gymnosperms, as in *Torreya*.

The common characters that hold these three genera together in a single group are the compound strobili (both staminate and ovulate) resembling inflorescences in which the simple and axillary strobili resemble flowers, the conspicuous micropylar tube, the opposite leaves, the dicotyledonous embryo, the true vessels, and the absence of resin canals. No one of these characters is peculiar to Gnetales among gymnosperms, excepting the true vessels and the compound staminate strobilus; but the combination of characters makes the group very distinct.

The genera are *Ephedra*, with about thirty species growing in the arid regions about the Mediterranean, and in tropical to temperate Asia, North America, and South America; the monotypic *Welwitschia* (*Tumboa*), in an extremely arid and restricted region of western South Africa; and *Gnetum*, with about fifteen species growing in the tropical forests of America, Asia, and Africa.

The earlier knowledge of the group was included in the accounts published by HOOKER (1), EICHLER (2), STRASBURGER (3, 5), and

<sup>1</sup> The Brussels Congress (May 1910) included *Welwitschia* among the genera *conservanda*; therefore the name is used in this volume instead of the older *Tumboa*.

BECCARI (4). Since that time there has been some fruitful investigation, but the comparative inaccessibility of the material has made the investigations less numerous and complete than the importance of the group would justify.

### 1. The vegetative organs


The species of *Ephedra* are low straggling shrubs, with long-jointed and fluted green stems, and opposite scalelike leaves connate in a two-toothed sheath. True foliage leaves are generally lacking, and the whole habit is suggestive of a shrubby *Equisetum* (fig. 404).



FIG. 404.—*Ephedra* sp., growing near Tucson, Arizona.—From photograph by D. T. MACDOUGAL.

*Welwitschia* is a plant of remarkable habit (figs. 405-407). The very tough body has the shape of a gigantic radish, which rises little above the surface of the ground, and whose crown is sometimes 3.5 to 4.5 meters in circumference. The broad top is more or less concave and somewhat two-lobed, and from the deep horizontal groove

which separates the crown (shortened stem) from the rest of the body (tap root) two enormously long parallel-veined leaves arise, which



FIGS. 405-407.—*Welwitschia mirabilis*: fig. 405, two views of the youngest specimen sent by WELWITSCH to HOOKER, showing the leaves in an entire condition; figs. 406, 407, side and top views of an older specimen, showing laceration of the end of the leaf; all one-half natural size.—After HOOKER (1).

extend upon the ground sometimes for 3 to 3.5 meters, and become split into numerous ribbons (fig. 408). The single pair of opposite



leaves succeeds the cotyledons (fig. 455), and is the only pair of foliage leaves produced, growing continuously at the base, where they are protected by the groove. These leaves last through the lifetime of the plant, which is said to reach more than one hundred years.



FIG. 408.—*Welwitschia mirabilis*: in the foreground are two plants with lacerated leaves; in the background are seven more plants.—From a photograph by H. SCHENCK.

The species of *Gnetum* are either small trees or woody climbers, being among the lianas of tropical forests (fig. 409). The leaves are leathery in texture, and are very suggestive of those of dicotyledons, the well-developed opposite leaves being lanceolate to ovate in outline and pinnately net-veined.

#### VASCULAR ANATOMY

So far as known, all traces of mesarch structure are lacking among the Gnetales, although it is altogether probable that it may be found in some peripheral members. However this may be, in this feature, as well as in others, the Gnetales seem farther removed from the ferns than any other group of gymnosperms, the only suggestion of connection being the foliar gaps.

In *Ephedra* there is a persistent primary cambium, but not much




FIG. 409.—*Gnetum ovalifolium*: climbing on *Cocos nucifera*.—After G. KARSTEN  
(11).

secondary wood-formation, so that the vascular cylinder does not become thick. The tracheary vessels are found in the inner region of the cylinder, and consist of broad vessels associated with ordinary gymnospermous tracheids. They are interrupted by oblique walls, and have bordered pits as well as simple pits, suggesting an intermediate condition between the characteristic gymnospermous tracheids and the true vessels. A peculiar anatomical feature of the genus is the diaphragm-like plate of cells which occurs at the base of each internode, rendering the stem easily separable at the nodes. The stomata occur upon the fluted stem in rows, and are sunken in urn-shaped depressions formed by mounds of cuticle.

In *Welwitschia* the vascular system of the stem is in a very confusing condition on account of the shortened axis. At the junction of the crown (the excessively shortened stem) and the huge tap root there is a broad plate of collateral bundles, made up of two plates in contact. The vessels of the upper plate connect with the leaves and the strobili, and those of the lower plate with the system of vessels in the tap root. The primary cambium is short-lived, and irregular series of bundles suggest the existence of successive cortical cambiums, but the testimony is too vague to use in any general conclusion. It is reported that tracheids with bordered pits are entirely lacking, being replaced by simple pitted and spiral vessels, which suggests a further stage of advance in this feature than that exhibited by *Ephedra*. In connection with the vascular bundles there is a conspicuous development of fibrous sclerenchyma. A remarkable anatomical feature of the genus is the occurrence of the so-called "spicular cells," which are found in large numbers and are scattered throughout all the organs (figs. 410-412). They are very large cells, fusiform or branched, straight or variously curved, with greatly thickened walls, and often so closely packed and interlaced that they make the tissues extremely hard and tough. In the outer layers of the walls, and especially on the surface of the longer spicular cells, crystals of calcium oxalate are very conspicuous.

In *Gnetum* the primary cambium is also short-lived, and successive cortical cambiums produce concentric series of vascular bundles. This common feature of *Gnetum* and *Welwitschia* and its occurrence among the Cycadales is a fact of interest rather than of present sig-

nificance. In *Gnetum*, as in *Ephedra*, the secondary wood contains true vessels associated with gymnospermous tracheids. [ ]

The vascular anatomy of the group needs a wider range of investigation than has been given to it, and this has been partially supplied by a recent investigation by HILL and DE FRAINE (28). The traces entering the base of each cotyledon are two in *Ephedra*, four (in two pairs) in *Welwitschia*, and four or five in *Gnetum*. The strands of the hypocotyl are inserted on the cotyledonary strands, and are four in *Ephedra*, eight or less in *Welwitschia* (quickly reduced to four), and a variable number (about 12-15) in *Gnetum*. The transition to root structure occurs in the lower region of the hypocotyl, and in all cases the primary root is diarch.


On the whole, the meager data available suggest a group farther removed from ferns

than other groups of gymnosperms, and one that has developed more or less completely the true vessels characteristic of angiosperms.

#### THE LEAF

The opposite leaves of *Ephedra*, reduced to a two-toothed and scaly sheath, certainly suggest ancestors with true foliage leaves, and occasionally such leaves are developed now.

The single pair of long-lived parallel-veined leaves of *Welwitschia* are remarkable. The stomata are in rows and deeply sunken, and



FIGS. 410-412.—*Welwitschia mirabilis*: spicular cells from the perianth of the staminate flower; fig. 410, a branching cell, the branching represented in one plane; fig. 411, a simple cell; fig. 412, the cut end of a long cell, with lumen almost closed and the surface covered by crystals of calcium oxalate;  $\times 225$ .



the mesophyll sheaths a conspicuous, central, nearly colorless tissue which constitutes a water reservoir. This colorless middle tissue is

traversed by the very numerous and strong parallel bundles, which are connected by transverse branches. These branches sometimes end freely in the mesophyll, or send out branchlets that end blindly. It follows that while the parallel course of the principal veins is monocotyledonous, the blind ending of some of the veinlets is dicotyledonous.

The leaves of *Gnetum* seem to differ in no essential feature from those of dicotyledons with leathery texture, being pinnately and reticulately veined, so that the plant, except when in fruit, might be mistaken for a dicotyledon (fig. 413).

This assemblage of leaves is more puzzling than suggestive, and if the genera are really of common ancestry, it implies a history

and a range of forms that remain to be discovered.



FIG. 413.—*Gnetum Gnemon*: from a photograph of a plant at the University of Chicago.

## 2. The spore-producing members

The strobili of Gnetales are compound, each strobilus being a catkin-like cluster of simple axillary strobili, which resemble flowers, especially since their bracts are arranged like a perianth. While

compound ovulate strobili occur among Cordaitales and Coniferales, compound staminate strobili are restricted to Gnetales. If the strobiliferous shoot of *Torreya taxifolia*, with its simple axillary strobili, were compacted into a strobilus, the condition among Gnetales would be attained. To avoid confusion we will call these simple axillary strobili of Gnetales flowers, to distinguish them from the compound strobilus which they make up. It must be remembered, however, that they are flowers only in the sense that the simple strobili of *Taxus* and *Torreya* are flowers. The whole group is prevailingly dioecious.

#### THE MICROSPORANGIUM

In *Ephedra* the flowers are monosporangiate and generally dioecious, arising from the axils of broad imbricate bracts, which in decussating pairs form a short, membranaceous strobilus (fig. 414). These strobili occur in pairs at the nodes, one arising from the axil of each of the opposite and minute scalelike leaves. Occasionally an ovulate flower replaces a staminate one (18), so that the strobilus, but not the flower, becomes bisporangiate.

The staminate flower consists of two more or less connate scales ("perianth") investing a projecting axis that bears two or more sporangia. This stamen, which is evidently an axial structure, may remain simple, in which case it bears two sporangia; or it may branch somewhat above and bear several sporangia. The period of development is remarkably short, the staminate strobilus of *E. trifurca* first becoming evident in December (in New Mexico), the mother cells in February, the reduction divisions in March, and pollination in April. A "resting period" of one month for the mother cell is a remarkably short one for a gymnosperm. The anthers mature in acropetal succession in the strobilus, and the only account of the development of the microsporangium of Gnetales is that of LAND for *Ephedra trifurca* (18). In the organogeny of the flower the stamen appears first, and the "perianth" later, but before there is any differentiation of an archesporium. Apparently the archesporium is a single hypodermal cell (in transverse section), dividing periclinally as usual. The primary wall layer divides periclinally, but there are no further periclinal divisions, so that there is only a single layer

between the epidermis and the tapetum. There are three or four successive divisions from the primary sporogenous cell to the mother cells, the tapetal cells enlarging about them and the wall cells becoming





FIG. 414.—*Ephedra antisiphilitica*: 1, staminate branches; 2, ovulate branches; 3, sterile branches; 4, staminate strobilus; 5, ovulate strobilus; 6, longitudinal section of seed; 7, bracts of the ovulate strobilus.—After WATSON (2a).

flattened. There is not always the same stage of division in a sporangium, in some cases every stage from synapsis to completed tetrads being seen in passing from the upper part of a sporangium to the lower. In this division the 12 chromosomes are very evident.

In *Welwitschia* the flowers are functionally monosporangiate and dioecious, but the staminate flowers are structurally bisporangiate (figs. 415, 416). They are borne in the axils of broad and closely overlapping bracts, whose decussating pairs form a conifer-like strobilus (figs. 417, 418). These strobili are produced upon branching axes which arise from the crown above the foliage leaves, or rarely beneath them. PEARSON (20), from a field study of *Welwitschia*, states that it is probably partially if not wholly pollinated by insects, a statement which finds additional confirmation in the fact that just below the anthers there are glandular protuberances which, in sections, may be interpreted as nectaries (fig. 415, *t*).

The staminate flower consists of two decussate pairs of free bracts, within which there is a whorl of six (rarely five or four) monadelphous stamens, each of which bears a terminal peltate group of three sporangia arranged in an approximately circular syngonium. In the center there is a single sterile ovule whose projecting micropylar tube is spirally coiled and ends in a broad flaring expansion (figs. 415, 416). It is very evident that the immediate ancestors of *Welwitschia* had bisporangiate flowers, a feature completely eliminated from most of the gymnosperms, if they ever possessed it. The only other gymnosperms that possess it are the Bennettitales, and they are



FIGS. 415, 416.—*Welwitschia mirabilis*: fig. 415, longitudinal section of the flower; *p*, bracts of perianth; *s*, trilocular anther; *t*, protuberance on the inner face of the stamen tube; *i*, inner integument, ending above in the expanded "stigma"; *n*, nucellus of sterile ovule; *b*, bract from the axil of which the flower arises;  $\times 30$ ; fig. 416, diagram of transverse section of the flower at the level of *s* in the preceding figure; +, axis of cone.



too far removed from *Welwitschia* in other characters to suggest any immediate connection. It would be easier to imagine a bisporangiate offshoot from the Coniferales.



FIGS. 417, 418.—*Welwitschia mirabilis*: ovulate and staminate strobili; fig. 417, branch with numerous ovulate strobili; one-half natural size; fig. 418, branch with staminate strobili; natural size.—After HOOKER (1).

In *Gnetum* the flowers are monosporangiate and mostly dioecious, and are numerous in the axils of connate bracts, which form a series of contiguous but not overlapping cups (closer together in the stami-




FIG 419.—*Gnietum Gneumon*: various phases of the life history; A, ovulate strobilus; B, strobilus upon which only one seed has matured; C, longitudinal section of a young ovulate strobilus,  $\times 24$ ; D, later stage, showing ovules and paraphysal hairs (*h*),  $\times 45$ ; E, longitudinal section of an immature ovulate flower, showing “perianth” (*p*), inner integument (*i*), rudimentary outer integument (*r*), and nucellus (*n*); F, nucellus showing three mother cells; G, longitudinal section of a mature ovulate flower, showing the “perianth” (*p*), outer integument (*o*), and inner integument (*i*),  $\times 33$ ; H, embryo sac with free nuclei in a parietal layer, and showing the beginning of the constriction which results in the antipodal and micropylar chambers; I, cell-formation in the “antipodal chamber,” another sac which is being pushed aside is shown at the right above,  $\times 50$ ; J, upper portion of sac soon after fertilization, showing a pollen tube with its nucleus (*t*), oospores (*f*), and unfertilized eggs,  $\times 340$ ; K, embryo sac, showing the suspensor-like development of the oospore (*g*) advancing toward the “antipodal endosperm,”  $\times 50$ .—All from LOTSY (15) excepting F, which is after STRASBURGER (10).

nate than in the ovulate strobilus) and a slender cylindrical strobilus (figs. 419-422). The strobili are axillary or terminal, solitary or fascicled or even paniculate. The staminate flower resembles that of *Ephedra*, consisting of two coherent bracts investing a short axis

that bears at its tip two sporangia. In the staminate strobilus of *Gnetum* also, as in *Ephedra*, ovulate flowers are frequently present.

It is tempting to see in these flowers (simple strobili) the essential features of the angiospermous flower, and to relate the strobilus to the catkin-like inflorescences of angiosperms. While the parts may hold the same general relations, these situations may have arisen in many regions of the gymnosperms, and none of them may have involved the history of the angiosperms.




FIGS. 420-422.—*Gnetum Gnemon*: ovulate strobili; fig. 420, young strobilus with six cuplike whorls, the ovules projecting beyond the dense tufts of hairs; fig. 421, a later stage, with three ovules much larger than the rest; two ovules in the second whorl show very well the projecting tip of the inner integument; fig. 422, transverse view of the stage shown in the previous figure.

#### THE MEGASPORANGIUM

In all the genera of Gnetales the ovulate flower consists of a single ovule invested more or less closely by a pair of bracts that are more or less connate in *Ephedra*, and completely so in *Welwitschia* and *Gnetum*. In fact, so complete is the coalescence and so close is the investment in *Gnetum* that this envelope has been regarded as an integument. In every case there are two integuments, appearing in basipetal succession, the inner one forming the micropylar tube. The elongated and projecting micropylar tube is a feature of the Gnetales, being neither spirally coiled nor expanded at the tip in *Welwitschia*, as in

FIG. 423.—*Ephedra trifurca*: longitudinal section of ovule, showing nucellus with deep pollen chamber (*p*), inner (*i*) and outer (*o*) integuments, and female gametophyte with reproductive, storage (*s*), and haustorial (*h*) regions;  $\times 48$ .—After LAND (18).





the sterile ovule of the staminate flower, and with a lacerate tip whose lobes spread during pollination in *Gnetum*. The three genera differ so much in the details of the structure and development of the megasporangium that they must be considered separately.

In *Ephedra trifurca* (LAND 18, 23) the inner integument is free from the nucellus for more than half its length, and the two integuments are free from one another except at the base, and are multiple in origin (fig. 423). The inner integument, never more than two cells thick, appears first in two distinct parts, but the later development is zonal, so that when this integument elongates rapidly just before pollination and protrudes through the apex of the flower, the exposed tip is wide open and is slit a short distance down one side. It also contains two rudimentary vascular bundles, and there is every evidence that it consists of two fused members. The outer integument, which becomes several cells thick and later hard, appears first in four distinct parts, and contains as many rudimentary vascular bundles. Such a multiple origin of integuments was described in connection with the paleozoic *Physostoma* (p. 35), one of the Cycadofilicales.

Although the single hypodermal archesporial cell was not observed, its existence was evident from the subsequent stages, a parietal cell being cut off, which together with the overlying epidermal cells produces a large amount of sterile tissue above the mother cell. About the time that archegonium initials appear, the tip of the nucellus begins to be disorganized, and this disorganization gradually proceeds downward, until when the ventral nucleus is cut off there is a broad circular opening, narrowing below, from the tip of the nucellus to the endosperm (fig. 423, *p*). This is the deepest pollen chamber known among gymnosperms, for it permits the pollen grains to rest upon the necks of the archegonia. The pollen chamber is finally closed by a plug formed by the endosperm cells, preventing the escape of the embryo into the chamber. The development of the megasporangium of *Ephedra campylopoda*, as described by STRASBURGER (3), is essentially the same, except that the archesporium is said to consist of a group of hypodermal cells.

In fruit the bracts of the strobilus become much modified in *Ephedra*, becoming red and succulent, or much enlarged and chaffy, and

the "perianth" persists and becomes lignified. In *E. trifurca* only six months elapse between the first appearance of the ovulate strobilus and the germination of the seed.

The development of the megasporangium of *Welwitschia* is unknown, except that a group of mother cells is present beneath long rows of parietal cells, the inference being that a hypodermal archesporium of several cells is differentiated. No pollen chamber is developed in the nucellar cap, but it becomes riddled by the descending pollen tubes and the ascending prothallial tubes (fig. 424). In fruit the enlarged bracts of the strobilus become bright scarlet, and the seed is winged by the expanded perianth.

The three envelopes investing the nucellus of *Gnetum* have given rise to much discussion, especially as they are said to arise in acropetal succession (4, 15). BECCARI (4) regarded the outermost one as a perianth; STRASBURGER (10) and ČELAKOVSKÝ considered them all as integuments, the delicate middle one being only an outer layer of the inner integument; while LOTSY (15) recognized only the innermost one as an integument. Usually only ovulate flowers are found in ovulate strobili (fig. 425), but occasionally staminate flowers appear. There are two kinds of ovulate flowers (10): those of the ovulate strobili, as described above; and those found with considerable regularity in the staminate strobili. The latter differ in having only two envelopes, the middle one of the complete flower being absent (fig. 426). These incomplete flowers usually do not function, but sometimes they develop





FIG. 424.—*Welwitschia mirabilis*: upper part of nucellus, with ascending prothallial tubes; *t*, prothallial tubes; *s*, sterile cells of fertile region of prothallium; *n*, nucellus; *m*, megaspore membrane;  $\times 140$ .—After PEARSON (20).

far enough to contain embryo sacs (fig. 427). In the rare cases when they function, the three envelopes are said to develop (15), but, as shown in the preceding figure, only two envelopes may appear in ovules which have enlarged considerably. KARSTEN (9,



FIGS. 425-427.—*Gnetum Gnemon*: longitudinal sections, showing bract with cluster of flowers in the axil; fig. 425, ovule in ovulate strobilus with two integuments and perianth; beneath the ovule is a dense tuft of hairs, so compact that they sometimes appear like a tissue; fig. 426, sterile ovule in staminate strobilus, showing only two envelopes (inner integument and perianth); the oldest stamens are at the top, and in longitudinal radial section usually show only one sporangium (as in the third stamen from the top); fig. 427, section from staminate strobilus, in which the ovule has developed to the free nuclear stage of the endosperm; all  $\times 23$ .

11, 12) has found that the middle envelope always appears in a rudimentary condition during the development of the incomplete ovulate flowers, but gradually disappears.


This confusion of interpretation has been cleared up (25) by a

study of the ovule and seed in comparison with those of other gymnosperms. The outermost envelope is undoubtedly the so-called perianth of Gnetales, very closely investing the ovule, with its own vascular supply, and appearing before the integuments. This last fact gave rise to the impression that the three envelopes appear in acropetal succession. The seed becomes slightly stalked in this perianth, and the two integuments appear in basipetal succession. The inner one extends above to form the long micropylar tube, and at the maturity of the seed it completely invests the nucellus (at this time replaced by the endosperm) as a papery layer. The outer integument becomes differentiated into an outer fleshy layer and an inner stony layer, the latter completely investing the seed, the former being chiefly developed in the region of the nucellar beak. Two sets of vascular strands are present, the outer set traversing the fleshy layer of the outer integument, the inner set traversing the inner integument.

In Cycadophytes, Ginkgoales, and Coniferales a single integument becomes differentiated into a testa of three layers: outer fleshy, stony, and inner fleshy. In *Gnetum* the same three layers are present, but the inner fleshy one becomes differentiated in ontogeny as a separate integument. In all cases this innermost layer finally forms a papery lining of the stony layer. Among the Pinaceae the outer fleshy layer is represented in the integument, but it does not develop into the pulpy investment that characterizes the Cycadales, Ginkgoales, and Taxaceae. The variation in the distribution of the vascular strands among these layers should be summarized. Among the more primitive Cycadofilicales and Cordaitales, in which the nucellus is relatively free from the integument, the outer set of strands traverses the outer fleshy layer (or integument) and the inner set traverses the peripheral tissue of the nucellus. In other Cycadofilicales and Cordaitales, however, and in Cycadales, in which the nucellus and integument are free only in the region of the nucellar beak, the inner set of vascular strands traverses the inner fleshy layer; and this is the condition of *Gnetum*, except that this layer has become differentiated as an inner integument. In Ginkgoales the outer set of strands (belonging to the outer fleshy layer) is suppressed; in Taxaceae the inner set (belonging to the inner fleshy layer) is suppressed; and in Pinaceae both are suppressed.



The development of the sporogenous tissue in the ovule of *Gnetum* has been described by STRASBURGER (3) for *Gnetum Gnemon*. The archesporium consists of a group of hypodermal cells which cut off wall cells by periclinal divisions, and the wall cells, together with the overlying epidermis, give rise to the usual thick mass of sterile tissue above the sporogenous region (fig. 419, *F*). Before pollination the



FIGS. 428, 429.—*Gnetum Gnemon*: fig. 428, diagram of longitudinal section of ovule, showing position of embryo sac and the "pavement tissue" beneath;  $\times 54$ ; fig. 429, the embryo sac and pavement tissue more highly magnified;  $\times 300$ .—After COULTER (25).

cells at the tip of the nucellus become disorganized, resulting in an indefinite and shallow pollen chamber. The several primary sporogenous cells are said to divide in the formation of mother cells, but this would be a very unusual occurrence for a gymnosperm.

A remarkable differentiation of nutritive tissue occurs in the chalazal region of the ovule of *Gnetum Gnemon* (25) during the early stages of the embryo sac. At the eight-nucleate stage of the sac it is

invested by the loose and undifferentiated tissue of the nucellus. A little later, the cells at the chalazal end of the sac become strikingly differentiated, becoming more and more compactly arranged, gradually obliterating the intercellular spaces, and taking on the appearance of glandular cells (figs. 428, 429). This compact "pavement tissue" gradually extends deeper into the chalaza, and spreads laterally below, becoming fan-shaped in longitudinal section, but with so definite a contour that it was mistaken by LOTSY (15) for a compact antipodal tissue within the embryo sac (fig. 419, *D*). After the fertilization stage has been reached within the sac, this pavement tissue begins to lose its glandular appearance, and later it is destroyed entirely by the growing endosperm.

A year later, the endosperm has destroyed all of the nucellar tissue except a very small amount at the tip. In destroying the nucellar beak, the central region of the endosperm ad-

vances into the beak and then spreads laterally (fig. 430). In the meantime the peripheral region advances more slowly toward the beak, and as a consequence a ring of nucellar tissue is pinched between two growing masses of endosperm.

The division of the megaspore mother cell has been observed only in *Ephedra* (3, 14, 18), in which a linear tetrad is produced. Apparently the outer daughter cell of the mother cell frequently does not divide, for the earlier accounts describe a row of "three megasporos." A close series shows (18) that in the same species this outer cell may divide completely, may divide incompletely, or may not divide at




FIG. 430.—*Gnetum Gnetum*: tip of seed; small amount of tissue of nucellar beak not destroyed by endosperm; differentiation of central and peripheral regions of endosperm, the former having advanced into the center of the nucellar beak and spread laterally, resulting in crushing the nucellar tissue against the encroaching peripheral region of endosperm; sections of two suspensors shown;  $\times 40$ .—After COULTER (25).

all. In no case does it divide until the inner daughter cell has completed its division (fig. 431). This situation is so general that a row of three cells occupying the position of a tetrad hardly deserves attention. The chromosomes have been counted in *Ephedra* (18, 23) and in *Gnetum* (25), and in both the numbers are 12 and 24, conform-



FIGS. 431, 432.—*Ephedra trifurca*: fig. 431, row of four megaspores, the lowest beginning to enlarge; fig. 432, simultaneous free nuclear division to form the 64-nucleate stage of the female gametophyte;  $\times 500$ .—After LAND (18).

ing to the remarkably uniform condition of gymnosperms in this regard; although JACCARD (14) reports 8 and 16 for *Ephedra helvetica*. If several tetrads are produced in a single ovule, several megaspores may begin to function, and in the case of *Gnetum* several contiguous embryo sacs with free nuclei may be formed.

### 3. The gametophytes

#### THE FEMALE GAMETOPHYTE

The development of the female gametophyte is so strikingly different in the three genera that they must be described separately.

The course of development in *Ephedra* was first outlined by STRASBURGER (3), and it conforms to that described for conifers, with free nuclear division, vacuolation accompanied by parietal placing, for-


mation of parietal tissue, and centripetal growth until the sac is full of tissue. The details have been given by LAND for *Ephedra trijurca* (18). At the division of the megaspore nucleus, the two daughter nuclei assume polar positions in the sac on account of the development of a vacuole between them, which in fact surrounds the equatorial region of the spindle like a ring. These two nuclei divide simultaneously, and the four resulting nuclei assume equidistant positions at the periphery of the sac. Successive simultaneous divisions follow rapidly (fig. 432), until approximately 256 free nuclei are formed, free nuclear division extending through a period of about twenty days.

With the appearance of the walls the endosperm is differentiated into distinct micropylar and antipodal regions, the former consisting of very loosely arranged cells with extremely delicate walls, and the latter of more compact cells. As the very rapid growth proceeds, the antipodal tissue becomes differentiated into storage and haustorial regions (fig. 423). The storage region comprises the greater bulk of the endosperm and is full of starch and other foods. In the center of it a column of thin-walled cells, richer in food than the others, extends from the haustorial region to the base of the archegonia, marking the path along which the embryo is to be thrust by the elongating suspensor. The haustorial region consists of the one or two outermost layers of endosperm cells at the antipodal end. The loosely arranged cells of the micropylar region, with their delicate and sometimes belated walls, are of interest in connection with the same region in *Welwitschia*, described below.

About April (in New Mexico) the archegonium initials begin to be differentiated, two being the usual number, although one or three sometimes occur. After the primary neck cell is cut off, it divides at once periclinally, and other periclinal divisions follow before anticlinal walls are formed which divide the cell of each tier into four cells. Eight such tiers of neck cells have been observed, and later divisions may result in six or eight cells in a tier. The appearance of regular tiers may be lost by the irregular planes of the later divisions, and the neck may resemble ordinary tissue (figs. 433-435). The minimum number of neck cells is probably thirty-two, but there may be many more. In any event, the archegonium neck of *Ephedra* is the



longest one known among gymnosperms, and it is associated with the deepest pollen chamber. It follows that although the pollen grains



FIGS. 433-435.—*Ephedra trifurca*: development of the archegonium; fig. 433, the neck (*n*) and central cell;  $\times 500$ ; fig. 434, three tiers of cells in the neck, the central cell not yet divided;  $\times 500$ ; fig. 435, later stage, in which the neck can scarcely be distinguished from the surrounding cells; the central cell (*c*) still undivided;  $\times 112$ .—After LAND (18).

rest upon the neck of the archegonium, there remains much tissue for the tubes to penetrate.

A zone of jacket cells (tapetum) is organized about the central cell, the cells being at first isodiametric, but with the elongation of the central cell they become much elongated and their walls become so thin as to be seen with difficulty. At the time of fertilization the walls separating the jacket cells from the egg break down altogether, and the contents of these cells are mingled with those of the egg. Miss BERRIDGE and Miss SANDAY (22) have reported a remarkable behavior of the jacket cells of *Ephedra distachya*, claiming that the nuclei of the broken-down jacket cells escape into the egg, fuse in pairs, and produce proembryos. Such behavior was never observed in thousands of ovules of *E. trijurca* (23), but occasionally jacket cells were found resembling the isolated proembryonic cells in appearance but never in function.

The ventral nucleus of *Ephedra trijurca* (18) is cut off during the first two weeks of April (in New Mexico), and there is no trace of a wall separating it from the egg. It remains in the upper part of the archegonium and becomes conspicuously enlarged.

The earlier account of the female gametophyte of *Welwitschia* was very perplexing, and although it is now found to have been inaccurate and even misleading, it suggested an unusual situation, which has been cleared up to some extent by PEARSON (27). The endosperm begins as usual with free nuclear division, and an embryo sac with approximately 1,024 free nuclei was observed, representing ten successive divisions rather than the usual eight. Attention has been called to the fact, however, that in *Pinus* there may be as many as eleven such divisions, and that the number may well vary widely among gymnosperms (see p. 259). These nuclei are distributed through the sac, so that when cleavage of the cytoplasm by walls occurs the embryo sac is divided into multinucleate cells. Those in the micropylar region contain fewer nuclei than do the others, and these nuclei become the nuclei of free eggs. The cells of the lower three-fourths of the endosperm contain many nuclei, which are said to fuse and thus produce a uninucleate tissue, and this primary endosperm tissue continues to grow both before and after fertilization. The multinucleate cells of the micropylar region, which were formerly mistaken for archegonium initials, send out tubes into the overlying nucellar tissue, into which the free nuclei pass, and these prothallial tubes

meet the pollen tubes in the lower half of the nucellar cap. It is evident that archegonia are eliminated, and that this is associated with the fact that the sexual nuclei are differentiated before a uninucleate tissue is formed. An earlier differentiation is possible only in the free nuclear stage of the endosperm, before there is any wall-formation; and this condition has been reached by *Gnetum*. The details of the formation of the permanent endosperm tissue of *Welwitschia* need critical study, but the general outline of the situation is clear.

The embryo sac of *Gnetum* has long been noteworthy for its suggestion of that of angiosperms. Several species have been investigated by KARSTEN (9, 11, 12), and *Gnetum Gnemon* has been described by LOTSY (15). The embryo sac of the last species has been regarded as illustrating a female gametophyte intermediate in structure between the tissue-filled sacs of *Ephedra* and *Welwitschia* on the one hand, and the sacs of the other species of *Gnetum*, which contain only free nuclei at the time of fertilization. The antipodal end of the embryo sac was described as being filled with a compact endosperm tissue before fertilization, while the micropylar end contained free nuclei. Later investigation (25) has shown that the tissue referred to is a nutritive tissue developed in the chalaza in contact with the antipodal end of the sac, and that all the species of *Gnetum*, so far as known, have embryo sacs containing only free nuclei at the time of fertilization, as described by KARSTEN.

The endosperm of *Gnetum* begins with free nuclear division, and eight nuclei have been observed (25) grouped near the center of the sac before vacuolation. Later the vacuolation of the sac results in the imbedding of the nuclei in a thin parietal layer of cytoplasm surrounding a large central vacuole. The number of free nuclei has not been determined, but presumably it is quite indefinite. It is in this stage that fertilization occurs, for the free nuclei are potential egg nuclei, although a group near the antipodal end of the sac may be as distinctly vegetative as are the antipodal cells of angiosperms. After fertilization, walls appear among the endosperm nuclei and a tissue is formed, which finally invades and destroys all of the nucellar tissue (p. 383). Under such circumstances the formation of archegonia is impossible, free eggs being organized at the free nuclear stage

of the endosperm. There can be no question that the embryo sac of *Gnetum* is strongly suggestive of that of angiosperms, in which the egg is also organized in the free nuclear stage of the gametophyte; but there is nothing in *Gnetum* to suggest the remarkable fusion of polar nuclei so characteristic of the angiospermous sac. It is at least a case of remarkable parallel development.

In all of the Gnetales the megaspore membrane is very thin, and according to THOMSON (21) this confirms the evidence from other structures that the group is relatively modern among gymnosperms.


#### THE MALE GAMETOPHYTE

The development of the male gametophyte of Gnetales was unknown, except for occasional glimpses, until the investigation of *Ephedra trifurca* by LAND (18), and it still remains the only complete account.

A short time after the rounding off of the spore, its nucleus divides, forming the first prothallial (vegetative) cell. This cell is pressed closely against the wall of the spore by the enlargement of its sister cell, from which it is separated by a wall, the only wall that appears in the spore (figs. 436-441). A second division gives rise to the second prothallial cell and the antheridium initial, which are not separated from one another by a wall. The second prothallial cell and its nucleus become flattened also by the pressure of the growing antheridium initial, whose nucleus enlarges very much, and upon division produces the generative and tube nuclei. The generative nucleus becomes surrounded by a zone of cytoplasm differentiated from the general cytoplasm, the result being a free naked cell (fig. 439). The general cytoplasm still invests the second prothallial and tube nuclei, with no evident boundary between them. The nucleus of the generative cell divides, giving rise to the stalk and body nuclei, which remain invested by the cytoplasm of the generative cell, the body nucleus soon becoming much larger than the other. It is in this condition that pollination occurs (during the first two weeks of April), the spore containing five conspicuous nuclei (two prothallial, stalk, body, and tube) (fig. 441). The short period of this species has been referred to (p. 371), only two months elapsing between the first appearance of the primordia of the sporangia and the five-nucleate grain, which is shed about two weeks later.



After reaching the deep pollen chamber, the exine of the spore is sloughed off and the intine with its contents is completely freed. The two prothallial cells soon disappear, and the nucleus of the body cell divides to form two equal male nuclei. The tube nucleus moves around the cavity of the grain and comes to rest against the wall, and soon after the pollen tube is put out from this point of contact




FIGS. 436-441.—*Ephedra trifurca*: germination of the microspore; *p*, first prothallial cell; *pr<sub>1</sub>* and *pr<sub>2</sub>*, first and second prothallial cells; *ai*, nucleus of antheridium initial; *tn*, tube nucleus; *g*, generative cell; *bn*, nucleus of body cell; *sn*, nucleus of stalk cell;  $\times 1,500$ .—After LAND (18).

(figs. 442, 443). As previously stated, the greater number of pollen grains rest upon the necks of the archegonia, and fertilization is possible within ten hours, as shown by experiment. The tube forces its way between the neck cells, rarely destroying them in its passage.

In *Ephedra distachya* (22) the two male nuclei lying in the general cytoplasm of the body cell are said to be unequal. The equality or inequality of such cells should be based upon an estimate of their

volume, rather than upon optical sections, which frequently appear to show an inequality that does not exist.

The male gametophyte of *Welwitschia* is known only from a few figures by STRASBURGER (10), which show a prothallial cell and the division resulting in the generative and tube nuclei; supplemented by the statement of PEARSON (27) that the nucleus of the body cell divides to form two male nuclei. These glimpses agree with the corresponding stages in *Ephedra*, except the presence of a single prothallial cell, which may or may not have been accompanied by another one. Our only knowledge of the male gametophyte of *Gnetum* is from the statement and figures of LOTSY (15) from *Gnetum Gnemon*, showing the tube nucleus and two male cells of the ordinary type in the tip of the pollen tube just before fertilization.



FIGS. 442, 443.—*Ephedra trifurca*: fig. 442, pollen grain just before the formation of the tube; the nucleus of the body cell is dividing to form the two male nuclei;  $\times 500$ ; fig. 443, the pollen tube;  $m_1$  and  $m_2$ , the male nuclei;  $s$ , nucleus of stalk cell;  $t$ , tube nucleus;  $\times 500$ .—After LAND (23).

#### FERTILIZATION

The fertilization of *Ephedra trifurca* has been observed by LAND (23) and, as has been stated, it may occur within ten hours after pollination. The pollen tube forces its way between the neck cells of the archegonium and discharges all its contents into the cytoplasm of the much elongated egg. While the sperm and egg nuclei are fusing in the upper part of the egg, there may be seen in the overlying cytoplasm the ventral, second male, stalk, and tube nuclei. A dense and darkly staining mass of cytoplasm surrounds the fusion nucleus and extends downward through the long egg (fig. 444). This differentiated mass of cytoplasm appears first in spherical form in the upper third of the central cell, and does not disappear until the proembryonic cells are formed. In *Ephedra distachya* it is reported (22) that the




FIG. 444.—*Ephedra trifurca*: fertilization; *pt*, pollen tube; *v*, ventral nucleus; *m*<sub>1</sub>, *o*, fusing nuclei; *m*<sub>2</sub>, second male nucleus;  $\times 215$ .—After LAND (23).

functioning male nucleus slips out of its cytoplasmic sheath in the periphery of the egg, and probably this is true of the species of *Ephedra* in general.

In *Welwitschia* the pollen tubes and prothallial tubes come in contact in the nucellar cap. How the transfer of male cells or nuclei is effected has not been observed, but several eggs are fertilized in each ovule, and PEARSON says (26) that the cytoplasm of the fusion nucleus is mainly that of the male cell, which would practically repeat the behavior observed in the sexual fusion of the Taxaceae and *Taxodium*.

In *Gnetum* (15) one or more pollen tubes enter the embryo sac, and their tips are observed among the free nuclei (fig. 419, *J*). The tip of the tube becomes distended and discharges its contents (usually four nuclei), both male cells being free in the sac and functioning. Approximately as many eggs are fertilized as there are male cells discharged into the sac, that is, twice as many as there are entering pollen tubes. About the fusion nucleus a dense layer of cytoplasm appears and soon a cell membrane is formed. The discharge of male cells into an embryo sac

containing free nuclei or cells, and the functioning of both cells discharged by a tube suggest the so-called "double fertilization" characteristics of angiosperms. The peculiarity of the angiosperm situation, however, is not that two male cells fuse with two eggs, but that one of them enters into a triple fusion which results in the so-called endosperm tissue.

#### 4. The embryo

The development of the embryo of Gnetales differs widely from that of other gymnosperms; and the three genera differ so much among themselves that a separate account must be given for each.

In 1872 STRASBURGER (3) described the remarkable embryo-formation of *Ephedra altissima*, outlining a general situation which has proved to characterize all the species investigated (fig. 445). The principal features are as follows: free nuclear division up to eight nuclei; the organization of two to eight independent cells; the independent functioning of each proembryonal cell in the formation of a suspensor and an embryo. The free nuclear division up to eight nuclei repeats the early stage of the proembryo of most conifers; but the difference appears in the separate organization and functioning of the eight cells, resulting in a proembryo of eight independent cells rather than one consisting of a tissue of eight cells. Each functioning proembryonal cell elongates to form a suspensor-like tube, which emerges from the egg, penetrates the endosperm, and cuts off at its free tip an embryo-forming cell. This is quite like the embryogeny of conifers, except that several suspensors emerge from the egg in various directions, rather than a single one emerging from the base of the egg. It must be remembered, however, that among conifers the constituent cells of a suspensor may separate, and an embryo be formed at the tip of each one. This is exactly the case of *Ephedra*, for its proembryonal cells act independently in embryo-formation.

Fuller details of the embryogeny of *Ephedra* have been given by LAND for *Ephedra trifurca* (23). The behavior of the jacket cells and of the non-functioning male nucleus, during the development of the proembryo, is worthy of mention. Soon after fertilization, the extremely thin walls of the jacket cells disappear, and the contents of these cells become mingled with those of the egg. Shortly



before the walls disappear the jacket cells become binucleate, the nuclei dividing mitotically and amitotically. Mitotic divisions may occur simultaneously in every cell of both layers of the jacket, or every division may be amitotic, or both kinds of division may occur in the same jacket. Amitotic divisions occurring at the upper end of the archegonium might pass easily for fusions. In some jacket cells the





FIG. 445.—*Ephedra*: A, young ovule; B, upper part of female gametophyte after fertilization, showing the free cells of the proembryo within the two eggs;  $\times 64$ ; C, suspensors developing from the free cells, passing from the egg into the endosperm, and each bearing at the tip an embryonal cell;  $\times 64$ ; D–F, later stages in the development of the embryo;  $\times 154$ ; A, *E. campylopoda*; B–F, *E. altissima*.—After STRASBURGER (3).

nucleus enlarges and becomes surrounded by delicate cytoplasmic radiations such as appear in connection with the unfertilized egg, suggesting the possibility of apogamy, but an investigation of thousands of ovules failed to discover any evidence that these egglike jacket nuclei ever function in the production of embryos. It is evident that Miss BERRIDGE and Miss SANDAY (22) discovered the same situation in *Ephedra distachya*, although they interpreted it differ-

ently. To them the freed nuclei of the jacket cells appeared to fuse in pairs and to form the functioning proembryonal cells; in other cases the jacket cells of either layer were thought to function directly



FIGS. 446, 447.—*Ephedra trifurca*: the proembryo; fig. 446, upper end of egg, showing a group of spindles derived from the second male cell; just below are numerous small cells which have come from jacket cells that have wandered into the egg, or from the division of non-functioning proembryonal cells, or from both; farther down are two functioning proembryonal cells; fig. 447, three of five functioning proembryonal cells; jacket nuclei in the egg cytoplasm; free masses of cytoplasm; also masses of cytoplasm remaining after the proembryonal cells have been carved out;  $\times 500$ .—After LAND (23).


as proembryonal cells, in which case there had been migration of nuclei from adjacent jacket cells and nuclear fusion.

The non-functioning male cell enlarges and occupies the extreme upper part of the egg, a space previously filled by the adjacent jacket

cells. As it disorganizes, an irregular group of spindles first appears, and then a number of minute cells (fig. 446). This ephemeral group of cells is produced probably by division of the non-functioning male nucleus, or it may be the joint product of the chromatin of this nucleus and of some of the jacket nuclei. In any event, its appearance in connection with the "second male nucleus" has suggested that it may be the physiological equivalent of the endosperm of angiosperms.

The formation of the embryo of *Ephedra trifurca* occurs as follows (23). The fusion nucleus gives rise to eight free nuclei, more or less unequal in size, and three to five of the largest enter into the organization of walled cells that can produce embryos (fig. 446). The free nuclei are usually irregularly distributed through the egg, or they may form a row through the middle. The proembryonal cells are isolated from the surrounding cytoplasm by the development of cleavage cracks, which finally carve out a more or less irregular sheath of cytoplasm for each nucleus (figs. 447, 448). In general the lower cells are successful in producing embryos, but sometimes only the upper (micropylar) ones are successful. Each functioning proembryonal cell rounds out, and its nucleus divides. The two daughter nuclei are at first equal, but one soon becomes noticeably larger than the other. As a result of vacuolation the two nuclei become placed on one side of the cell (if it is one of the upper cells), or on the bottom of the cell (if it is the lowest one in the egg). Two papillae are put out by the wall adjacent to the two nuclei, but the papilla related to the larger nucleus elongates rapidly to form the suspensor and the other one disappears (fig. 449). In one case four nuclei were seen in a proembryonal cell. The suspensor develops directly toward the antipodal region if the proembryonal cell is the lowest one, but it advances outward and then downward if it is developed by one of the upper cells. The larger nucleus passes nearly to the end of the tube, and a cleavage plate, beginning at the wall, cuts it off in a terminal embryo-forming cell (figs. 450, 451). The other nucleus now enters the suspensor and functions as its nucleus, remaining at the lower end until it disintegrates. The suspensor elongates rapidly, thrusting the embryo-forming cell deep into the endosperm and remaining turgid until the secondary suspensor appears, when it collapses. The longest suspensor observed measured 3.1 mm. in length.

The embryo cell divides transversely, and this is followed by a succession of divisions in various planes until an ovoid mass of cells



FIGS. 448-453.—*Ephedra trifurca*: development of embryo; fig. 448, one of the proembryos before the formation of the suspensor tube;  $\times 500$ ; fig. 449, proembryo with two free nuclei (*s*, of suspensor; *e*, of embryo) and a suspensor tube (*t*);  $\times 500$ ; fig. 450, a later stage, showing suspensor (*s*) and embryo (*e*);  $\times 500$ ; fig. 451, character of the wall, nearly complete, which separates the suspensor and embryo;  $\times 1,900$ ; fig. 452, division of embryo initial cell; *s*, suspensor;  $\times 500$ ; fig. 453, later stage of embryo and secondary suspensor;  $\times 250$ .—After LAND (23).

is produced (figs. 452, 453). The basal cells of this group elongate successively, forming a multicellular secondary suspensor, which



merges insensibly into the root cap. There are thus three stages of suspensor-formation: the first elongation in connection with the nucleus which later becomes the nucleus of the embryo cell; the second and chief elongation in connection with the smaller nucleus of the proembryonal cell; and the formation of a secondary, multicellular suspensor by the basal cells of the embryo.

Although several embryos may begin to develop in a single ovule, only one of them reaches maturity.

In *Ephedra trifurca* the occurrence of vivipary is evident, at least in some cases, numerous seedlings being observed to have emerged from the seeds while the strobili were still attached to the stem. In any event, the period of rest for the embryo must be very short, and favorable conditions for growth may eliminate it entirely. The whole period from the first appearance of the ovulate strobili to the "germination" of the seed is approximately six months.



FIG. 454.—*Welwitschia mirabilis*: a young embryo consisting of a pyramidal group of cells, the basal ones giving rise to embryonal tubes.—After STRASBURGER (3).

In *Welwitschia* the fertilized egg, within the prothallial tube, behaves as does the proembryonal cell of *Ephedra*. As described by PEARSON (27), it elongates toward the top of the endosperm, and the first nuclear division is followed by a cleavage wall which cuts off a terminal embryo cell. The general statement has been that in *Welwitschia* and *Gnetum* there is no free nuclear division in the first stages of embryo-formation, but that the first division of the fusion

nucleus is accompanied by wall-formation, as in the angiosperms. This statement must be revised, for in *Welwitschia* the fusion nucleus produces two free nuclei, which are later separated by a wall that holds no relation to the spindle of the fusion nucleus. The suspensor cell of *Welwitschia* elongates extremely, becoming much coiled and persistent, and the embryo cell produces a pyramidal group of cells (about

thirty-two at the time of observation), the basal ones of which develop numerous embryonal tubes that surround the lower part of the suspensor, while the terminal ones (a plate of eight cells) develop the embryo (fig. 454). The embryonal tubes are produced from the same region that develops as a secondary suspensor in *Ephedra*, but their function is not the same. In germination the young seedling of *Welwitschia* (BOWER 6, 7) shows a well-developed root, a very long hypocotyl, and two small cotyledons; and between the root tip and the hypocotyl there is developed a very conspicuous footlike ("spade-like," 28) process that remains in the seed as a haustorial organ. At a later stage the cotyledons become more conspicuous, and the single pair of persistent leaves appears associated with them (fig. 455).




FIG. 455.—*Welwitschia mirabilis*: a young seedling, showing the cotyledons and the pair of persistent leaves; the bilobed crown is evident just above the insertion of the cotyledons; natural size. —From photograph by H. SCHENCK.

The embryo-formation of *Gnetum* is a repetition of that of *Welwitschia*, at least in general outline. LOTSY's account (15) for *Gnetum Gnemon* describes the extensive suspensor-like elongation of the fertilized egg, the penetration of the endosperm in various directions, the occasional branching of the tube, and the cutting-off of the embryo cell, but does not follow the nuclear divisions.

A recent investigation (25) of the same species has added some interesting details. When the endosperm is fully developed, having replaced the nucellus completely during the second season, its pe-

ripheral region contains a tangle of long, tortuous, and branching suspensors, which are difficult to trace. During the formation of the suspensor by the fertilized egg, free nuclear division takes place,



FIGS. 456-458.—*Gnetaum Gnemon*: development of embryo; fig. 456, a proembryo showing the branching, suspensor-like elongation of the egg, with free nuclei and cleavage walls; also the embryonal cell containing a nucleus and numerous starch grains; sections of other suspensors shown, and also a small portion of the undestroyed tip of the nucellus;  $\times 40$ ; fig. 457, beginning of embryo-formation by the embryonal cell, showing free nuclei and the beginning of a cleavage wall; a cleavage wall in the suspensor is also shown;  $\times 250$ ; fig. 458, an embryo reconstructed from several sections, showing free nuclei, cleavage walls, and the beginning of uninucleate cells;  $\times 140$ .—After COULTER (25).

resulting in a few nuclei (four in some cases) distributed along the suspensor (fig. 456). Usually between these nuclei transverse walls are formed by the development of cleavage plates from the wall of the suspensor. A cell at the tip of the suspensor is cut off in the same

way, and contains one of the free nuclei, with which numerous starch grains are associated. In this terminal embryo cell free nuclear division continues, accompanied by cleavage walls, until a multicellular embryo is formed (figs. 457, 458). The formation of cleavage walls appears to continue until uninucleate cells are produced.

As in the case of *Welwitschia*, it had been supposed that in the embryo-formation of *Gnetum* the preliminary stage of free nuclear division, common to other gymnosperms, had been eliminated, and that the first nuclear division was accompanied by wall-formation, as in angiosperms. In *Gnetum Gnemon*, however, free nuclear division not only characterizes the proembryo, but also the early stages of the embryo. In comparing *Gnetum* with *Ephedra* it will be seen that the number of free nuclei formed by the egg in each case is approximately the same, the difference being that in *Ephedra* several suspensors are formed by independent proembryonal cells, while in *Gnetum* a single suspensor is formed by the fertilized egg.

The later stages of the embryo of *Gnetum Gnemon* have been described by BOWER (8), the basal cells of the embryo group producing embryonal tubes, as in *Welwitschia*; and the young seedling showing the same endospermic foot (rodlike) attached between the long hypocotyl (bearing two small cotyledons) and the root. HILL (26) has studied the germination of these species, and reports that the hypocotyl soon escapes from the seed coats, leaving behind a foot or sucker in close connection with the storage tissue. The cotyledons are at first small, but later enlarge somewhat and do photosynthetic work; and the rodlike foot in the center of the endosperm contains vascular tissue. This foot, reported for *Gnetum* and *Welwitschia*, needs investigation, for there is no such structure in *Ephedra*, the only genus of the Gnetales whose germination we have seen. In that genus the germination is as in *Pinus*, the cotyledons being pulled out of the testa and spreading, and there is left no structure imbedded in the endosperm. Whether this sucker-like outgrowth from the cotyledonary node of *Gnetum* and *Welwitschia* is to be regarded as a "foot," with all the morphological connections that that term implies, or merely a special "peg" such as appears in certain dicotyledons, is a question to be decided only by one's point of view.



Lotsy has described (17) the occurrence of parthenogenesis in *Gnetum Ula*. When the embryo sac was full of loose tissue, no pollen tubes were found, but many of the loose cells behaved like fertilized eggs in sending out tubes.

### 5. History and distribution

At present Gnetales are unknown as fossils, but they give evidence of a considerable history (24). Their great dissimilarity in habit, structure, and habitat, associated with their widely scattered distribution, indicates a relatively large group of ancestors of somewhat general distribution. Even if this should prove to be the case, the group is doubtless a modern one among gymnosperms.

The present geographic distribution of Gnetales has been indicated already (p. 363). *Ephedra* is distinctly a genus of arid regions, its species ranging throughout the dry borders of the Mediterranean and extending eastward into the Caspian region of Asia, and in similar habitats in both North and South America. The species of *Gnetum*, on the contrary, belong to the tropical forests of both hemispheres; while *Welwitschia* is isolated from its congeners in a desert waste of western South Africa. The facts of this distribution can be stated, but their meaning is entirely obscure.

### 6. Relationships

The origin of Gnetales is very obscure, and in the absence of history any statement in reference to it must be regarded as a guess. It is clear that *Ephedra* is more closely related to the other gymnosperms than are *Welwitschia* and *Gnetum*; and that if it is to be connected with them at all, it is most reasonably connected with the Coniferales. This general connection is so uncertain that any attempt to select for it a particular family or tribe of conifers is peculiarly unprofitable. It must be understood that the connection referred to may mean only the parallel development of the two groups.

It is equally clear, whatever may be the connections of *Ephedra* with other gymnosperms, that it cannot be separated from *Welwitschia* and *Gnetum*. These two genera have many things in common with *Ephedra*, but they have more things in common with one another, and have advanced much farther in the development of angiospermous

features. It is not worth while to arrange the three genera in a series, for this would only involve the impossible determination as to whether *Welwitschia* or *Gnetum* is the more advanced in some selected direction. Certainly they can hold no such serial relation to one another, for they must represent divergent lines from some general common stock. So far as the features of the embryo sac can determine advancement, as measured by the angiosperms, *Gnetum* is more advanced than any other gymnosperm. All that is necessary, however, is to recognize the facts that the group as a whole, while clearly related to other gymnosperms, is remarkable for its angiospermous features, and that *Welwitschia* and *Gnetum* are farther removed from the other gymnosperms in this regard than is *Ephedra*.

The most interesting question in connection with the relationships of Gnetales is their possible relationship to angiosperms. It was natural at first to regard them as the immediate progenitors of angiosperms, for their structures seemed to point irresistibly to that conclusion. When transition groups were in vogue, there was no better illustration of one than the Gnetales. But those who are now claiming a phylogenetic connection between Gnetales and angiosperms do not claim it in the sense that the former is a transition group. To many it seems very improbable that there is any connection between the two groups, except one so distant that it does not fall within the claim of connection. After a critical cytological investigation of the female gametophyte and of fertilization in *Gnetum*, STRASBURGER has concluded (19) that it is impossible to derive the angiospermous embryo sac from that of *Gnetum*, and that such resemblances as do exist are illustrations of phylogenetic parallels.

ARBER and PARKIN (24) have applied their strobilus theory of angiospermous descent to an interpretation of the origin of Gnetales, and the result may be regarded as combining the two views mentioned above. This theory was referred to in connection with the Bennettitales (p. 74). These authors do not regard the Gnetales as a very modern group, in spite of the fact that they are unknown as fossils. It is claimed that the three survivors of this ancient group have "proanthostrobili" (an "anthostrobilus" is an axis bearing both microsporophylls and megasporophylls, with the latter above the former; and a "proanthostrobilus" is one in which the ovules are gymno-

spermous), a fact apparent in the staminate "flower" of *Welwitschia*, and made true for all other flowers of Gnetales by inferring the suppression of one set of sporangia. The conspicuous illustration of a proanthostrobilus among gymnosperms is of course found among the Bennettitales. Based upon this strobilus situation, the Gnetales are regarded as a phylum of gymnosperms having a common ancestry with angiosperms, the two phyla in many particulars following parallel lines of development. It hardly seems necessary to name hypothetical groups, but these common bisporangiate ancestors have been called "hemiangiosperms." Thus the Gnetales have not given rise to the angiosperms; and yet the resemblances of the two are satisfied by the parallel development of two lines from a common ancestry. The gymnosperm connection naturally involves the Bennettitales, and all those groups whose monosporangiate condition may be the result of the suppression of one set of sporangia. It is recognized that in the evolution of strobili among gymnosperms there were probably two distinct tendencies: a monosporangiate strobilus (Cycadales, Cordaitales, Ginkgoales, Coniferales), and a bisporangiate strobilus with the anthostrobilus arrangement of sporophylls (Bennettitales, Gnetales, and leading to angiosperms).

#### LITERATURE CITED

1. HOOKER, J. D., On *Welwitschia*, a new genus of Gnetaceae. Trans. Linn. Soc. London **24**: 1-48. pls. 1-4. 1863.
2. EICHLER, A. W., Ueber *Welwitschia mirabilis*, etc. Flora **47**: 459-464, 473-479, 489-496, 508-510, 513-520. 1863.
- 2a. WATSON, SERENO, Botany of King's Exp. 1871.
3. STRASBURGER, E., Die Coniferen und die Gnetaceen. 1872.
4. BECCARI, O., Della organogenia dei fiori feminei del *Gnetum Gnemon* L. Nuovo Giorn. Bot. Ital. **7**: 91-99. 1877.
5. STRASBURGER, E., Die Angiospermen und die Gymnospermen. 1879.
6. BOWER, F. O., On the germination and histology of the seedlings of *Welwitschia mirabilis*. Quart. Jour. Micr. Sci. **21**: 15-30. pls. 3, 4. 1881.
7. ———, On the further development of *Welwitschia mirabilis*. Quart. Jour. Micr. Sci. **21**: 571-594. pls. 22, 23. 1881.
8. ———, The germination and embryology of *Gnetum Gnemon*. Quart. Jour. Micr. Sci. **22**: 278-298. pl. 25. 1882.
9. KARSTEN, G., Beiträge zur Entwicklungsgeschichte der Gattung *Gnetum* Bot. Zeit. **50**: 205-215, 221-231, 237-246. pls. 5, 6. 1892.

10. STRASBURGER, E., Ueber das Verhalten des Pollens und die Befruchtungsvorgänge bei den Gymnospermen. *Hist. Beitr.* **4**:1-158. *pls.* 1-3. 1892.
11. KARSTEN, G., Untersuchungen über die Gattung *Gnetum*. *Ann. Jard. Bot. Buitenzorg* **11**:195-218. *pls.* 17-19. 1893.
12. ———, Zur Entwicklungsgeschichte der Gattung *Gnetum*. COHN's Beitr. *Biol. Pflanz.* **6**:337-382. *pls.* 8-11. 1893.
13. JACCARD, P., Le développement du pollen de l'*Ephedra helvetica*. *Archiv. Sci. Phys. et Nat.* **III**. **30**:280-282. 1893; rev. in *Bot. Centralbl. Beih.* **4**:230. 1894.
14. ———, Recherches embryologiques sur l'*Ephedra helvetica*. *Bull. Soc. Vaudoise Sci. Nat.* **30**: *pls.* 10. 1894; rev. in *Bot. Centralbl.* **61**:111-113. 1895.
15. LOTSY, J. P., Contributions to the life history of the genus *Gnetum*. *Ann. Jard. Bot. Buitenzorg* **II**. **1**:46-114. *pls.* 2-11. 1899.
16. LIGNIER, O., La fleur des Gnétacées est-elle intermédiaire entre celle des gymnospermes et celle des angiospermes? *Bull. Soc. Linn. Normandie* **V**. **7**:55-71. 1903.
17. LOTSY, J. P., Parthenogenesis bei *Gnetum Ula* Brongn. *Flora* **92**:397-404. *pls.* 9, 10. 1903.
18. LAND, W. J. G., Spermatogenesis and oogenesis in *Ephedra trifurca*. *Bot. Gazette* **38**:1-18. *pls.* 1-4. 1904.
19. STRASBURGER, E., Anlage des Embryosacks und Prothalliumbildung bei der Eibe nebst anschliessenden Erörterungen. *Festschr. siebenzigsten Geburtstage von ERNST HAECKEL*. pp. 18. *pls.* 2. Jena. 1904.
20. PEARSON, H. H. W., Some observations on *Welwitschia mirabilis* Hooker. *Phil. Trans. Roy. Soc. London B* **198**:265-304. *pls.* 18-22. 1906.
21. THOMSON, R. B., "The origin of gymnosperms"; a discussion at the Linnean Society. *New Phytologist* **5**:68-76, 141-148. 1906.
22. BERRIDGE, ETHEL M., and SANDAY, ELIZABETH, Oogenesis and embryogeny in *Ephedra distachya*. *New Phytologist* **6**:128-134, 167-174. *pls.* 3, 4. 1907.
23. LAND, W. J. G., Fertilization and embryogeny in *Ephedra trifurca*. *Bot. Gazette* **44**:273-292. *pls.* 20-22. 1907.
24. ARBER, E. A. NEWELL, and PARKIN, JOHN, Studies in the evolution of the angiosperms: the relationship of the angiosperms to the Gnetales. *Annals of Botany* **22**:489-515. 1908.
25. COULTER, JOHN M., The embryo sac and embryo of *Gnetum Gnemon*. *Bot. Gazette* **46**:43-49. *pl.* 7. 1908.
26. HILL, T. G., The germination of *Gnetum Gnemon* L. *Jour. Roy. Hort. Soc.* **34**:1, 2. 1908.
27. PEARSON, H. H. W., Further observations on *Welwitschia*. *Phil. Trans. Roy. Soc. London B* **200**:331-402. *pls.* 22-30. 1909.
28. HILL, T. G., and DE FRAINE, E., On the seedling structure of gymnosperms. IV. Gnetales. *Annals of Botany* **24**:319-333. *pls.* 22, 23. 1910.



## CHAPTER IX

### EVOLUTIONARY TENDENCIES AMONG GYMNOSPERMS

The gymnosperms have been presented group by group, but they should be viewed also as a whole. It would be possible to summarize the facts in reference to each structure, but this not only would involve needless repetition, but also would fail to distinguish between the facts that are significant and those that are relatively insignificant. There is no better way in which to develop a clear picture of a great group than to select those facts of structure that enter into its general evolutionary history. This has nothing to do with differences among species, or even among genera, which may be left to the taxonomist; but it deals with those general tendencies to change structures which can be noted in passing from the most ancient gymnosperms to the most recent.

While the discovery of these tendencies aids in reaching conclusions in reference to the phylogenetic connections of the groups of gymnosperms, it must be remembered that the tendencies are facts and the phylogenetic conclusions are very uncertain inferences. Moreover, a general tendency expresses itself throughout a great group, and has to do with the transition from ancient to modern forms, rather than with the breaking up of the group into several phylogenetic lines. Failure to remember this fact has been responsible for much sterile inference as to relationships, similar stages in some general tendency being assumed to mean immediate genetic connection. The organism is a plexus of structures, and must be considered in its totality when relationships are being considered. Among the general tendencies leading to the origin of seed plants, that which resulted in heterospory must be regarded as of paramount importance; and yet it is clear that heterospory arose several times, and probably many times, independently, as the natural result of a general tendency among pteridophytes. To put into the same genetic group all heterosporous pteridophytes would be regarded now as a morphological absurdity; and yet there have been repeated sugges-


tions of relationship, especially among conifers, on the basis of certain features of the female gametophyte, for example, features which represent a stage in a general change that may occur in a number of independent lines.

In passing from the ancient to the modern gymnosperms, it becomes evident that groups differ as to the rapidity with which they respond to a general tendency to change, and it is this difference that helps to constitute groups. A modern group, for example, may associate a number of ancient features with others that are recent; or all of the ancient features may have been changed. This has been called the "lagging behind" of certain structures, but this should not imply that they are held back and will come forward later; it simply means that for some reason they have not responded to the general tendency among gymnosperms to change in a certain direction. The retention of an old structure must not be confused with the reappearance of an old structure. For example, it seems clear that the most ancient gymnosperms were large-leaved forms, from which the small-leaved conifers were derived; and yet small-leaved pteridophytes may have been more ancient than large-leaved ones. If this be true, the appearance of small leaves among conifers is the reappearance of an ancient feature, and not its retention. To prove the retention of an ancient feature demands the establishment of its phylogenetic continuity.

#### PHYLOGENY

Before sketching the general evolutionary tendencies among gymnosperms, it will be of service to outline what seems to be a reasonable conclusion as to the phylogenetic connections of their groups. This statement and those that follow will be all the more clear if freed from the details upon which they are based and also from citations. Those who know the facts and the investigators do not need their recital; and those who do not know them would only be confused by their recital. In connection with the following statement, the accompanying diagrams (figs. 459-461) will assist in indicating the historical connections of the groups, and also to some extent the relative periods of time involved.

The paleozoic groups Cycadofilicales and Cordaitales represent the historical background of gymnosperms. They are of equal age,



460

FIGS. 459, 460.—Diagrams indicating the historical connections of the gymnosperm groups and the relative periods of time involved: fig. 459, a sector of the earth, showing to scale the thickness of the superficial deposits (shaded) from which fossil records have been obtained; fig. 460, the suggested historical connections of the gymnosperm groups, all contained within the shaded region of fig. 459.—Prepared by SISTER HELEN ANGELA.

so far as the records are available, and are so connected by intergrading (or rather anastomosing) forms that their relationship seems




FIG. 461.—A more detailed diagrammatic presentation of the connections suggested in fig. 460.—Prepared by SISTER HELEN ANGELA.

evident. The Cycadofilicales are so fernlike in every feature except their seeds, that their derivation from some ancient fern stock



(called provisionally *Primofilices*) is as certain as phylogenetic connections can be. The origin of the *Cordaitales*, therefore, presents two alternatives: either they arose independently from the same ancient fern stock, or they were differentiated from the *Cycadofilicales* very early. To choose between these alternatives is not very important, but the latter one seems to be the more reasonable, because the *Cordaitales* (as we know them) are much more removed from the ferns than are the *Cycadofilicales*. If this conclusion be accepted, it follows that gymnosperms began with *Cycadofilicales* more ancient than any yet known; that *Cordaitales* branched off from *Cycadofilicales* earlier than our present records; and that the two groups constituted the extensive gymnosperm flora of the Carboniferous.

This paleozoic display of gymnosperms was succeeded by a mesozoic display, in which at least four groups are recognized. From the *Cycadofilicales* there arose the mesozoic *Bennettitales* and the *Cycadales*; and from the *Cordaitales* the mesozoic *Ginkgoales* and *Coniferales* were derived. The *Bennettitales* have been traced almost to the Paleozoic, and their structure, as well as the habit of some of the earlier forms, makes their connection with *Cycadofilicales* appear convincing. The relation of the *Bennettitales* to the *Cycadales* is not so clear; either the two groups were differentiated from a common stock that arose from the *Cycadofilicales* and continued into the Mesozoic, or the *Cycadales* were differentiated early from the *Bennettitales*. The records indicate that the *Cycadales* are much younger than the *Bennettitales*, and were much more scantily represented during the Mesozoic; and therefore the latter alternative seems to be the more reasonable. In any event, the only question at issue is whether the gymnosperm stock which came from the *Cycadofilicales* into the Mesozoic is to be called *Bennettitales* or a *Bennettitales-Cycadales* plexus (a "common stock"); and it is altogether probable that this stock has already been assigned to the *Bennettitales* in the description of cycadophyte forms from the Triassic and Jurassic. In the gymnosperm flora of today, therefore, the *Cycadales*, although relatively a modern group, are the nearest representatives of the paleozoic *Cycadofilicales*.

The *Ginkgoales* and *Coniferales* have both been traced into late and independent paleozoic connection with the *Cordaitales*, and were

well displayed during the Mesozoic. The Ginkgoales, while widely distributed during the Mesozoic, apparently were never a large group; and this group has continued as a single line into the present flora, and has retained certain features of the Cordaitales which the Coniferales have lost. The Coniferales, on the other hand, began that extensive differentiation during the Mesozoic which has resulted in six recognized tribes in our present flora. Among these tribes the earliest to be recognized are the Abietineae and the Araucarineae, and their very early separation is so evident as to raise the question whether they may not be independent in origin. In any event, the other tribes recognized in our present flora were of later origin; the Taxodineae and the Cupressineae, and possibly the Taxineae, arising from the mesozoic Abietineae; and the Podocarpineae possibly arising from the mesozoic Araucarineae.

The connections of the Gnetales are altogether obscure, and every opinion as to their origin must be regarded as very tentative. Although they have not been discovered as fossils, the great amount of differentiation they show and their widely scattered geographical distribution indicate a considerable history. Evidence seems to be accumulating that they may have been derived from the Cupressineae, or at least that they are closely related to that tribe in origin.

#### VASCULAR ANATOMY

The central cylinder of the Cycadofilicales, like that of ferns, was protostelic, siphonostelic, or polystelic. Whatever may be the genetic connection of these types of cylinder, the siphonostele is the type that was carried forward in the evolution of gymnosperms. This siphonostele was made up of collateral mesarch bundles, developed secondary wood composed of tracheids, and the bundles of all its peripheral connections were concentric or at least mesarch.

Among the gymnosperms the universal tendency was to eliminate the centripetal xylem, a tendency carried forward from the ferns, until the collateral mesarch bundles of the central cylinder became collateral endarch; and more gradually the bundles of the peripheral regions became collateral mesarch and finally collateral endarch. So early was this accomplished for the central cylinder that a collateral endarch cylinder is a feature of gymnosperms in general.

From what has been said as to the variable rate of change among the members of a great group, it would be expected that mesarch and concentric bundles might be found in peripheral parts of certain species or genera whose allies had completely eliminated centripetal xylem, or might occur occasionally in any species or genus. It is an interesting fact that centripetal xylem appears to linger longest in the cotyledons; and the number of gymnosperms in which it is known to occur in this organ, regularly or occasionally, is increasing rapidly.

In the development of secondary wood, the general tendency among gymnosperms is to increase it in amount, so that a thick vascular cylinder is built up by the primary cambium. This tendency is apparent among the Cordaitales, but it reaches its most conspicuous result in the Coniferales and Ginkgoales. This changed also the general topography of the stem, both pith and cortex being much reduced in relative amount. The Bennettitales and Cycadales responded feebly if at all to this tendency, one of their features being the retention of the general stem structure of the Cycadofilicales. In these groups the primary cambium is either short-lived or functions very slowly, and in some forms secondary cambium produces cortical bundles; but the formation of secondary wood never prevents the formation of a large pith and an extensive cortex. It is in these groups also that the concentric and mesarch bundles are most common in the peripheral members, being found somewhere in all forms; while among the Coniferales the centripetal xylem has been almost completely eliminated. In vascular anatomy, therefore, the Cycadales have retained more ancient features than any other living group.

The vascular condition among Gnetales can hardly be spoken of in connection with general tendencies; but the appearance of true vessels associated with the tracheids of the secondary wood is too important to omit. In any event, these true vessels of the secondary wood suggest that in the evolution of the vascular cylinder the original tracheids of the secondary wood are finally and gradually replaced by true vessels.

#### THE LEAF

The leaves of gymnosperms may be used to illustrate a structure that exhibits no general evolutionary tendency, but responds more or

less directly to the conditions of living. The most ancient gymnosperms possessed ample, fernlike leaves, and under appropriate conditions this type of leaf persisted, as in the tropical cycads of today. The conifers, however, have developed a very different type of leaf, one that was well under way among the Cordaitales, and which reaches an extreme expression in small and rigid needles or concrescent scales. This cannot be regarded as the result of a general tendency among gymnosperms, quite unrelated to conditions of living, such as is shown by the persistent progressive changes of other structures. The leaf is too variable a structure, and too closely related in its work to external conditions to permit such an explanation of its changes.

It would be interesting to know the conditions in which needles and concrescent disks were established; but in the absence of any such knowledge, the sharply contrasted geographical distribution of Cycadales and Coniferales may suggest that the conditions of change were associated with the evolution of the land areas and of the climate of the temperate regions.

#### THE STROBILUS

The Cycadofilicales are the only gymnosperms without strobili. Although the sporophylls differ more or less from the fernlike foliage leaves or their branches, they are not aggregated into a strobilus distinct from the rest of the shoot. The organization of a strobilus by the shortening of the sporophyll-bearing shoot is a conspicuous feature of gymnosperms, and it must have been derived from the condition observed among the Cycadofilicales.

The Cordaitales were the first gymnosperms to produce strobili, and this is one of their conspicuous contrasts with Cycadofilicales. The record of the structure of their strobili is meager, but it shows several tendencies in strobilus-formation. Of primary importance is the fact that the strobili are monosporangiate, and this monosporangiate character prevails throughout the Ginkgoales and Coniferales. Among the Gnetales, a group probably related to the general coniferophyte phylum, bisporangiate strobili occur in *Welwitschia*. If this connection be accepted, therefore, these bisporangiate strobili have been derived from monosporangiate strobili. It is not necessary to associate in one genetic connection all of the bisporangiate gymno-



sperms, for that condition doubtless appeared independently several times, just as the monosporangiate strobilus is known to have appeared at least twice in distinct phyla (coniferophytes and cycadophytes).

Another fact in reference to the strobili of Cordaitales, which must stand for the most ancient gymnosperm strobili, is that they included both simple and compound strobili. The staminate strobilus was simple, that is, its sporophylls were borne directly upon the axis of the strobilus; and this type of staminate strobilus persisted throughout the Ginkgoales and Coniferales. Among the Gnetales the staminate strobilus is compound, the individual simple strobili being borne on axes of the second order in the axils of sterile bracts which make up the general strobilus. There is an evident relationship between the compact compound staminate strobilus, such as occurs in *Ephedra* and in *Welwitschia*, and the short foliage branch bearing axillary simple staminate strobili, as in *Torreya*. Even in *Gnetum* the compound staminate strobilus is a loose one; and among the taxads there is a tendency to compact the staminate strobiliferous branch. The conclusion is that the staminate strobilus is quite persistently simple, but that in the more modern members of the phylum it tends to become compound, a condition accomplished by compacting a short strobiliferous shoot.

The ovulate strobilus of Cordaitales was compound, at least in the very few specimens sectioned; that is, the ovules were borne on short secondary and bractlet-bearing axes that arose in the axils of the sterile and overlapping bracts that constituted the strobilus. This compound ovulate strobilus is a distinctive feature of the Coniferophytes, prevailing among the Pinaceae and characterizing the Gnetales. That simple ovulate strobili may have been derived from it is quite possible. For example, in *Torreya* the ovulate strobili are simple and are axillary on short leafy branches, just such a branch as could have arisen through the elongation of the axis of a compound ovulate strobilus, so that the sterile bracts could be replaced by foliage leaves. It may be said that the change may have taken place in the other direction, and that the short leafy strobiliferous branch was compacted into a compound ovulate strobilus; but it must be remembered that the Cordaitales with their compound ovulate strobili are very old, and that the Taxineae with their leafy strobiliferous branches

are relatively very recent. Of course it may be discovered that the Cordaitales included also forms with simple strobili on leafy shoots. This possibility is further emphasized by the fact that the ovulate strobili of the Araucarineae, and of their allies the Podocarpaceae, are simple. The former tribe is a very old one, and its connection with the Cordaitales is either direct or nearly so, so that it is altogether probable that such ovulate strobili occurred in that group. The connection of the Taxineae with the Cordaitales, however, appears to be so remote, and their relation to groups with compound ovulate strobili seems to be so much more immediate, that it is more reasonable to suppose that their ovulate strobiliferous branches have arisen from compound strobili in the way described above.

Long after the Cordaitales had established their simple staminate and compound ovulate strobili, strobili appeared in the cycadophyte phylum, being found in Bennettitales and Cycadales; and even in the living *Cycas* the loose ovulate strobilus retains the evidence of its origin from the separated sporophylls of Cycadofilicales. The cycadophyte strobilus has always been simple, and this may be related to the more compact habit of body, with its lack of free branching. The most remarkable feature of the early strobili of this phylum, however, is their bisporangiate character, the two sets of sporophylls holding the same relation to one another that is held by the stamens and carpels of angiosperms; and this marks the Bennettitales as a unique group among gymnosperms. The monosporangiate tendency, however, which characterizes the coniferophytes, is shown by the Cycadales among cycadophytes, and it was either established directly, or it arose from an early differentiation of the bisporangiate strobilus of the Bennettitales. The evidence of history favors the latter view, but the probabilities of the situation favor the former. In any event, both monosporangiate and bisporangiate strobili were established among cycadophytes.

#### THE STAMEN

Among gymnosperms the stamen may be regarded as a very conservative structure, retaining throughout most of the phyla its fernlike characteristics. Its form perhaps became almost as much differentiated among the Cycadofilicales as it ever became among gymno-

sperms. In this primitive group, in addition to microsporophylls resembling fernlike leaves with abaxial synangia, there appeared others that have been spoken of as the *Crossothea* ("epaulet") and the *Calymmatothea* ("cupule") types, and in all probability still others will be discovered. All of these types were continued among the coniferophytes, with varying details of minor importance. Among some of the Gnetales either the sporophyll has become very reduced, or it has become suppressed, so that the microsporangia are cauline; but even in *Welwitschia* the old terminal synangium is evident.

Among the cycadophytes, on the other hand, only what may be regarded as the most ancient type of microsporophyll has been retained, that is, the fern type with abaxial sporangia (often synangia). Among the Bennettitales, there is so little departure from the old type that its microsporophylls resemble pinnate fern leaves with abaxial synangia; and even among the Cycadales the more or less leaflike microsporophylls show the same character. If there is any tendency in the stamens of this phylum worth noting, it is the tendency shown among the cycads to reduce the sterile apex of the sporophyll to a more compact peltate expansion.

The microsporangium of gymnosperms is a very consistent structure, originating from the hypodermal layer of cells, and developing a wall of several layers, the innermost one of which is differentiated as the tapetum. The only general tendencies to be observed are the gradual replacement of synangia by separate sporangia, and the more rapid elimination of all evidences of an annulus (in the general sense). It is noteworthy that in both these particulars the cycadophytes, with their much more recent connection with the Cycadofilicales, are far behind the coniferophytes.

#### THE OVULE

The origin of the ovule of gymnosperms remains in obscurity. While the stamen and its sporangia repeat the corresponding structures of ferns, the ovules of Cycadofilicales and of Cordaitales are so well organized, even in the modern sense, that their connection with the sporangia or synangia of ferns is entirely a matter of inference. This means a tremendous gap between the somewhat hypothetical Primo-filices, on the one hand, and the Cycadofilicales and Cordaitales,

as we know them, on the other hand; a gap which there seems to be small probability of filling up with intermediate forms. In this presentation the only thing possible is to take the ovules of the paleozoic forms as representing the oldest known ovules, and to note the general changes that have occurred since.

To select the most primitive type of ovule from among the paleozoic forms that have been investigated is impossible, unless it is assumed that those ovules which are most unlike the modern ones represent the most primitive type. This may or may not be true, but it is the only available criterion; and by using it, we obtain the following result. The oldest ovule had a single integument entirely free from the nucellus; in testa-formation this integument differentiated into three layers, the outer fleshy, the stony, and the inner fleshy; the ovule was supplied with two sets of vascular strands, the outer set traversing the outer fleshy layer, and the inner set traversing the peripheral region of the nucellus; and the beaked tip of the nucellus broke down more or less completely within the firm and resistant epidermis to form a pollen chamber. If these are really the features of the most primitive known ovules, the changes become very apparent, and they represent general tendencies, for they appear in every phylum.

In the first place, the integument and nucellus, instead of remaining separate, develop separately only in the region of the nucellar beak. So early was this change that it probably represents the condition of the majority of paleozoic ovules, a condition which has persisted ever since. The method of development is very evident, the integument appearing first as a distinct annular growth about the base of the young nucellus, but later its basal meristematic zone becoming indistinguishable from that of the nucellus. In all probability the change was brought about by the earlier appearance of the integument, and the result has been more or less variability in the amount of freedom from the nucellus.

The three-layered testa persists remarkably throughout gymnosperms, varying chiefly in the amount of development of the outer fleshy layer. The stony layer is always strongly developed, and at the maturity of the seed the inner fleshy layer always forms for it a papery lining. A strong development of the outer fleshy layer, resulting in fleshy seeds, continues throughout the cycadophyte phylum



and the Ginkgoales, and is a feature of some of the Taxaceae. Among the Pinaceae the outer fleshy layer perhaps is represented in the young integument, but does not develop, so that the stony layer is the conspicuous superficial feature of the seed. The probability is that the stony layer would not develop superficially in any event, so that it would not be necessary to regard a layer or two of cells overlying it as representing the outer fleshy layer. The development of the outer fleshy layer among the Cycadales and Ginkgoales is phylogenetically continuous from the Cycadofilicales and Cordaitales; but among the Taxaceae there is probably no such continuity, but a reappearance of the activity of this layer in certain genera. Among the Gnetales, and apparently in certain Cordaitales, the single integument of the other gymnosperms is replaced by two integuments, the inner fleshy layer having become differentiated as a delicate inner integument, which appears earlier than the heavier outer integument, which gives rise to the outer fleshy and stony layers. In *Gnetum* the outer fleshy layer develops the pulpy investment characteristic of the primitive seeds; but in *Ephedra* this layer behaves as among the Pinaceae. If any general tendencies can be inferred from these facts in reference to the integument and testa, they are seen in the abortion of the outer fleshy layer in the largest group of living gymnosperms, and in the differentiation of the three-layered integument into two integuments.

The vascular supply of the ovule exhibits a very evident progressive change. When the integument and nucellus become free only in the region of the nucellar beak, the inner set of vascular strands is shifted from the peripheral region of the nucellus to the inner fleshy layer, and this situation persists among the cycadophytes. Curiously enough, it reappears in *Gnetum*, but in that case it is associated with the presence of the two integuments. Among Ginkgoales the outer set of strands is suppressed; among Taxaceae the inner set is suppressed; and among Pinaceae both sets have disappeared. The general tendency, therefore, is to eliminate the vascular strands from the ovule; but it is puzzling to find both sets absent from the older Abietineae, and one set still present among the younger Taxineae.

The presence of a pollen chamber is one of the most conspicuous

features of the primitive ovule, and its association with fertilization by ciliated sperms is so evident that it is natural that the two disappeared simultaneously with the establishment of Coniferales, but the abruptness of the disappearance is evidently more apparent than real. The presence of an extraordinarily deep pollen chamber in *Ephedra* can hardly be regarded as a contradiction to this general statement, for in that case it is evidently of secondary origin, associated with a remarkably massive archegonium neck.

#### THE FEMALE GAMETOPHYTE

The female gametophyte of gymnosperms exhibits a progressive series of changes which is significant because it leads toward the angiosperm condition. At this point the very important historical record fails, and the entire testimony must be obtained from living forms, which do not represent a series, but the ends of many series. For this reason, and also because such progress is always very unequal in different forms, various stages of advancement may be expected to be found in forms grouped in a single alliance. The series, therefore, is not so much one which conforms to recognized groups, as a series of stages each of which may be exhibited by members of various groups.

The general development of the gametophyte is quite uniform; and since the same sequence of events occurs among the heterosporous pteridophytes, it may be inferred that a knowledge of the ancient gymnosperms would not materially change this situation. The general sequence referred to in the development of the gametophyte is as follows: free nuclear division, usually accompanied by vacuolation which results at some stage in parietal placing; the formation of walls, resulting in a parietal tissue; the centripetal growth of this tissue until it reaches the center of the embryo sac; and the final growth of the gametophyte until it reaches its mature size. In certain cases there may be no parietal placing, the free nuclei remaining distributed throughout the embryo sac; and therefore there is no centripetal growth, but general wall-formation throughout the sac. The details of the formation of permanent endosperm tissue from the primary walled cells are variable and perhaps very important from the evolutionary point of view, but the range of forms from which

these details have been obtained is far too small to make them of present service in this connection.

The general tendency which runs through gymnosperms as a whole, and which reaches its extreme expression among angiosperms, is to mature the eggs earlier and earlier in the ontogeny of the gametophyte. In the most primitive condition of the gametophyte, the eggs do not appear until the endosperm is nearly full grown; and other gametophytes can be selected and arranged in a series showing the gradual slipping-back of the egg in the ontogeny of the gametophyte, until in such a form as *Torreya* the archegonium initial is differentiated as soon as wall-formation has taken place. A conspicuous illustration of the inequality of response to such a general tendency among related forms is furnished by *Torreya* and *Cephalotaxus*, the archegonia not appearing in the latter genus until the gametophyte is well grown. The next stage is illustrated by the situation in *Welwitschia*, in which eggs are matured before wall-formation is complete, resulting in the elimination of archegonia. The extreme stage in this progressive series of changes among gymnosperms is illustrated by *Gnetum*, in which eggs are matured at the stage of free nuclear division, the most embryonic stage of the female gametophyte.

So far as the living forms are concerned, the Cycadales and Ginkgoales show little, if any, response to this tendency; and therefore possess the most primitive type of female gametophyte among living gymnosperms. Among the Coniferales, on the other hand, all the stages are found, up to the one just preceding the elimination of archegonia; and this stage is attained by *Welwitschia* and *Gnetum*.

The general tendency of the archegonia among gymnosperms is to eliminate the ventral canal cell. The gymnosperms are distinguished from the pteridophytes by the complete elimination of neck canal cells, and this tendency to suppress all of the axial row except the egg continues among gymnosperms. Among the living forms a walled ventral canal cell is retained only among the Abietineae and by *Ginkgo*, so far as known; but it seems to be a safe inference that it was present among the ancient gymnosperms. In the other living groups the wall has disappeared, and the ventral canal cell is represented by a free nucleus. In certain forms even this nucleus may

have disappeared; and of course there is no trace of it when the archegonia are eliminated.

The distribution of archegonia may be considered in this connection, although the tendencies do not appear to be general. It is becoming evident that the position of archegonia is related to the position of the pollen tube, which sometimes reaches the embryo sac before the archegonium initials are selected. In cases where the pollen tube assumes a lateral position in reference to the gametophyte (as in *Sequoia* and *Widdringtonia*), it has been demonstrated that the latter responds by the selection of numerous deep-seated and laterally placed archegonium initials. It may be inferred, therefore, that the usual micropylar position of archegonia is due to the usual micropylar position of the tip of the pollen tube. It may be that numerous scattered and rather indefinitely placed archegonia were a feature of ancient gymnosperms, but there is no evidence for it; on the contrary, the few sections of paleozoic ovules that reveal archegonia, and also the archegonia of heterosporous pteridophytes, suggest the opposite conclusion. In any event, they tend to become definite in number and are then organized in two ways: either as individual archegonia, each with its own jacket and chamber; or as an archegonial complex, with a common jacket and chamber. The latter may seem to be a specialized condition, exhibited chiefly by Cupressineae, but it also seems to be the natural condition from which to derive the free eggs of *Welwitschia* and *Gnetum* when archegonia are eliminated from the ontogeny.

#### THE MALE GAMETOPHYTE

It is perhaps impossible as yet to determine the character of the male gametophyte of the paleozoic gymnosperms. The evidence is accumulating that it comprised many more cells than do the gametophytes of most living gymnosperms; but it is not demonstrable whether these supernumerary cells were vegetative or spermatogenous. There are instances of supernumerary cells of both kinds among living gymnosperms, so that they furnish no clue; and the same is true of heterosporous pteridophytes. The balance of probability, however, is in favor of the view that they were in the main spermatogenous.



In any event, starting with the known condition among heterosporous pteridophytes, the tendency among gymnosperms has been to reduce and finally to eliminate the vegetative (prothallial) tissue, and to reduce the sperm mother cells to two.

In certain groups (as Abietineae) the prothallial cells are two in number; in others (as cycads) there is one prothallial cell; and in still others (as Taxodineae, Cupressineae, and Taxineae) prothallial tissue has been eliminated. Such prothallial cells as do appear are sometimes persistent and sometimes ephemeral; so that the evidence of a disappearing tissue is complete, and it actually has disappeared in what are recognized as the most modern groups. The situation common to Podocarpaceae and Araucarieae is usually cited as an illustration of a more extensive and therefore a more ancient prothallial tissue, which connects directly with the "multicellular" pollen grains of Cordaitales. This may be true, but all of the extra cells are derived from two primary ones, which hold a definite place in the ontogeny of the gametophyte; and therefore the extra cells may represent a secondary tissue that holds no phylogenetic relation to the more extensive prothallial tissue of older forms. In any event it is ephemeral, breaking down and liberating its nuclei.

The number of sperm mother cells is so rigidly two, that this reduction may be said to have been accomplished by all living gymnosperms, whatever may be the fact in reference to the paleozoic gymnosperms. It is interesting to note that the very few instances of a greater number of sperm mother cells occur in a group characterized by its retention of ancient features (Cycadales), and in another group characterized by its very modern features (Cupressineae). While phylogenetic continuity of multiple sperms is safely claimed for *Microcycas*, no such claim could be maintained for Cupressineae.

The greatest epoch in the history of the male gametophyte of gymnosperms, however, was the abandonment of ciliated sperms, and this occurred in connection with the establishment of Coniferales. It is not generally appreciated that five of the seven recognized primary groups of gymnosperms possess ciliated sperms, and that the modern type or truly terrestrial type of sperm was introduced by the conifers. It must not be supposed that the earliest conifers necessarily did not possess ciliated sperms, for these may have persisted among the

mesozoic conifers. In fact, in certain living forms the sperms resemble very closely those of cycads with cilia lacking. The abandonment of ciliated sperms also affected the pollen chamber, the pollen tube, and the cell generations in spermatogenesis. The pollen chamber disappeared; the pollen tube ceased to be exclusively a branching haustorial organ and became a sperm-carrier; while the last cell-generation in spermatogenesis was omitted. It is this condition of spermatogenesis that is carried forward by angiosperms to a still greater stage of reduction. Just what cells are eliminated and what cells remain is a question of small importance. The significant fact is that spermatogenesis is shortened, and the ultimate cells, although non-ciliated, are physiologically sperms.

#### FERTILIZATION

We have reserved for this topic, in addition to what it specifically includes, a more detailed discussion of the sperm of gymnosperms and certain related phenomena of spermatogenesis and oogenesis. Using the term sperm in a physiological sense, what appears to be a reduction series can be arranged, extending from the highly differentiated motile sperms of cycads and *Ginkgo*, presumably representative of the sperms of the extinct groups, to the free male nuclei of *Pinus*. Among the Taxodineae, Cupressineae, Taxineae, and Podocarpineae (certainly in *Phyllocladus*) the sperm is a distinctly organized cell ("male cell"). In such genera as *Sequoia* and *Thuja* these male cells closely resemble the young sperms of a cycad immediately after the division of the body cell. No vestiges of blepharoplasts have been found in the so-called male cells, but this negative evidence is not yet convincing. In every case, also, they have been reported as arising directly by division of the body cell, which means that they are not formed as sperms within a sperm mother cell. It must be remembered, however, that apparently competent observation maintained for a time this same origin for the sperms of one of the cycads. Therefore, it is not an unreasonable expectation that some of the male cells may be found to be formed within sperm mother cells. In some genera, as *Taxus* and *Torreya*, the two male cells have become unequal, one being much smaller than the other and not functioning. The inference is that reduction

is proceeding in the direction of the elimination of one of the male cells. Among the Abietineae and Araucarineae the sperms are not distinctly organized cells, but are male nuclei lying free in the cytoplasm of the body cell, and this cytoplasm is not always sharply delimited from that of the pollen tube. That male cells and male nuclei have been derived from swimming sperms is a reasonable inference, and if our proposed phylogeny is true, this series of changes has taken place in the evolution of Coniferales. Such changes do not indicate necessarily the relative ages of the groups in which they are observed, but rather their relative rapidity in different groups.

Oogenesis among gymnosperms does not cover so great a range of reduction, but it is none the less evident. What must be regarded as the most primitive condition among gymnosperms is the association of a definite ventral canal cell with the egg, as in *Ginkgo* and *Pinus*. Among cycads and many conifers, however, the wall between nuclei of the ventral canal cell and of the egg has been eliminated, so that finally the former cell is represented only by its nucleus; and in *Torreya* it is probable that even this nucleus does not appear. A further simplification of oogenesis is shown by *Welwitschia* and *Gnetum*, in which no definite eggs are formed, but the egg is represented only by a nucleus in a more or less definite sheath of cytoplasm.

There are certain combinations of characters among the Coniferales that may prove to be correlations, but the range of observation is too limited as yet to establish such a claim. In any event, they deserve consideration. From those forms (*Thuja*, for example) with definitely organized male cells (the most primitive condition of the sperm among conifers) both the male prothallial cells and the wall separating ventral and egg nuclei have been eliminated (probably the most advanced condition of these structures among conifers). On the other hand, those forms (*Pinus*, for example) which do not organize definite male cells have retained the male prothallial cells. Three structures are concerned in these combinations, and in all of them there is evident a tendency toward elimination, or at least simplification. It is further evident that this tendency is not shown by all three structures simultaneously. The inferences are that the several lines have proceeded independently, and that the condition of no one of these structures indicates the relative age of the plant to which it

belongs, but does indicate the relative rapidity of the changes. For example, it cannot be claimed that *Pinus* is ancient because it has male prothallial cells, or that it is modern because its sperms are only male nuclei; the only claim that can be made from these facts is that the simplification of sperms has gone on more rapidly in the *Pinus* line than the elimination of male prothallial cells. Doubtless the same conclusion applies to all characters used in phylogeny, even to those derived from vascular anatomy. The relative position of any form in a scheme of classification can be determined only by averaging all its characters; and its relative age in a scheme of phylogeny can be determined only by the sure testimony of history.

The behavior of the chromatin in the final stages of oogenesis in gymnosperms seems to be unique. At the nuclear division giving rise to ventral and egg nuclei the chromosomes are very small. The ventral nucleus soon disintegrates, but the chromosomes of the egg nucleus form a spirem. A period of maturation follows, for which there is no satisfactory account of the behavior of the chromatin. The coarse reticulum of the egg is not chromatin, for most of it may remain after chromatin again becomes demonstrable. Whatever may be the suggested explanation, it is certain that chromatin has not yet been traced from the telophase of the ventral nucleus mitosis to the spirem of the resting egg nucleus with any such certainty as has been done among pteridophytes and angiosperms.

Fertilization has been studied more thoroughly in *Pinus* than in any other gymnosperm, and perhaps it represents the general situation. In this case the discharge of the pollen tube injects all of its contents into the cytoplasm of the egg. One of the male nuclei comes into contact with the female nucleus and the nuclear membranes at the surface of contact break down, so that the chromatin of the two nuclei becomes surrounded by the membrane of the egg nucleus. A spirem is formed from the chromatin network of each of the sex nuclei, and each spirem segments into 12 chromosomes. In the fusion nucleus, therefore, there are 12 male and 12 female chromosomes, which do not fuse, but which become so mixed that they cannot be distinguished. Each chromosome splits and finally 24 chromosomes pass to each pole to form the first two nuclei of the sporophyte generation. In this so-called act of fertilization, therefore, there is no blending of the



chromatin contributed by the two parents. Whether a blending occurs as the two groups of chromosomes pass from the telophase of the first mitosis into the resting reticulums of the daughter nuclei has not been determined, but it is possible that the male and female chromatin may remain distinct throughout the life history.

In all the genera investigated, more or less cytoplasm enters the egg with the male nucleus. In the cycads the entire sperm enters the egg, and the cilia may continue to move in this environment, but the nucleus soon slips out from its cytoplasmic sheath and advances toward the egg nucleus. In other forms, as *Torreya*, *Juniperus*, and *Taxodium*, the cytoplasm of the male cell invests the fusion nucleus and takes part in the formation of the proembryo. In most genera, however, no such cytoplasm is visible, and the proembryo is formed from a rather small portion of the basal region of the egg, quite remote from any cytoplasm that may have entered the egg with the male nucleus.

#### THE EMBRYO

The absence of embryos from the seeds of paleozoic gymnosperms has been taken to indicate that some great change connected with embryo-formation was introduced by the mesozoic gymnosperms. It would be of extreme interest to know the ancient condition, but we know only what it has become. In fact, the evidence is by no means clear that the embryogeny of paleozoic gymnosperms differed in any general way from that of later gymnosperms. Attention has been called (p. 47) to the fact that the paleozoic seeds sectioned had dropped from their plants just as abortive seeds do, and that no sections of paleozoic seeds in connection with their plants have been obtained. Among Bennettitales attached seeds are the only ones sectioned, and they contain embryos. Until sections of attached paleozoic seeds persistently show the absence of embryos, it is not profitable to imagine what may have been the changes in embryo-development in passing from the Paleozoic into the Mesozoic. Whatever may have been the changes, if any, the proembryo has become the structure showing steady and progressive changes.

The first stage in the development of the proembryo is free nuclear division, followed by wall-formation; and in the most primitive

condition the free nuclei are so numerous that wall-formation results in a tissue that fills the egg. The tendency is to reduce the number of free nuclear divisions, resulting in a reduction of the amount of proembryonic tissue, so that more and more of the general cytoplasm of the egg is left free from the tissue. The proembryo of *Ginkgo* has retained a very primitive character, and illustrations of early stages in the reduction of the proembryo may be observed among the cycads. In *Zamia*, for example, which illustrates the extreme amount of reduction among cycads, the proembryo is a relatively small amount of tissue at the base of the egg. Among the Coniferales this reduction has been carried forward to a much greater extent, sixteen free nuclei appearing sometimes, eight free nuclei being the prevailing number, and four free nuclei being occasionally attained. This results in a proembryo consisting of a small and definite number of cells, with distinctly distributed functions. Now and then among gymnosperms (as in *Sequoia*) there is no free nuclear division, but these are interesting rather than significant exceptions. Even among the Gnetales it is found that a certain amount of free nuclear division precedes wall-formation. That this reduction of the free nuclei before wall-formation is significant is shown by the fact that among angiosperms free nuclei have disappeared, and wall-formation accompanies the first division of the fusion nucleus.

The vascular structure of seedlings, and especially the vascular plate with its cotyledonary connections, has become so important a factor in discussions of phylogeny, that at our request SISTER HELEN ANGELA has prepared the following brief comparative statement of the situation among gymnosperms.

"Since the hypocotyl, cotyledons, and primary root are the first organs formed in the embryo proper, it is reasonable to suppose that they depart less widely from the generalized condition than do those structures which develop later under the influence of the various external factors that tend to create diversity. If in addition we could say that developmental factors are the same within all seeds, and that all embryos develop under similar conditions, we should have strong ground for broad generalizations. But such a statement, of course, would be far from the truth. Conspicuous examples of the factors which must be reckoned with in any such attempt are the

varying amounts of endosperm-formation in different seeds, the great diversity in thickness and induration of seed coats, the presence or absence of the phenomenon of rest, the slowness or rapidity of germination. And the extremes of hypogeal and epigeal development are found side by side in the oldest living gymnosperms, *Ginkgo* and *Pinus*, with no historical evidence as to which is the more primitive method.

"Taking the facts as we find them, however, we cannot but be impressed by the fairly harmonious testimony of certain evolutionary tendencies manifested not only by the group as a whole, but by each of the living orders. An inspection of the diagrams (fig. 462) will help to make these tendencies apparent. The most obvious tendency, perhaps, is that to reduce the cotyledons to the fixed number two. Series *A* represents conditions as they are found among the Cycadales, which, though younger than the Coniferales, are conceded to have retained more primitive anatomical features. Though the order as a whole is dicotyledonous, its more fernlike members are frequently observed to be polycotyledonous; and cases of cotyledonary lobing have been reported of many genera. The number of cotyledons when fixed is fixed at two. *Ceratozamia* cannot be regarded as an exception, for it is dicotyledonous in the proper sense of that term. Among the Coniferales the tendency to reduce the cotyledons to the fixed number two is even more striking, as indicated by series *B* of fig. 462. *Cupressus*, *Sequoia*, and the Abietineae, which must be regarded as the oldest members of the Pinaceae, are characteristically polycotyledonous; while the more modern members of that family, as well as all the Taxaceae investigated, are dicotyledonous. *Ginkgo*, though older than the Cycadales and as old as the Abietineae, resembles the former order in having fewer cotyledons; three is not an uncommon number, but two is the usual one. In the modern order Gnetales the fixed number is two. The inclination to revert to the apparently primitive condition has not been lost by the angiosperms; *Anemone*, *Salicornia*, and *Oenothera* are frequently found with three cotyledons.

"A second tendency that appears from comparative study is the tendency to reduce the root poles to the fixed number two. In the most primitive Abietineae and the more fernlike members of the

Cycadales, the primary root is polyarch. Even *Araucaria*, which is exceptional in many respects, has been reported with six root poles, although two is the usual number. In the Coniferales the reduction in number of root poles is closely related to the reduction in number




FIG. 462.—Diagrams illustrating the cotyledonary node of gymnosperms and its vascular connections with the cotyledons: the lobes indicate cotyledons.—Prepared by SISTER HELEN ANGELA.

Series A, Cycadales: 1, *Dioon spinulosum* (occasional); 2, *D. edule* (occasional); 3, *D. spinulosum*, *Ceratozamia*, *Microcycas*; 4, *D. edule*; 5, *Zamia floridana*, *Cycas* spp.; 6, *Cycas siamensis*; 7, *C. Seemannii*.

Series B, Coniferales: 1-6, various species of the Pinaceae; 7, *Libocedrus*, *Taxus*, *Cephalotaxus*.

Series C, Ginkgoales, Gnetales, and exceptional Coniferales: 1, 2, *Ginkgo biloba*; 3, 4, *Araucaria* spp.; 5, *Podocarpus*; 6, 7, Gnetales.

of cotyledons, for when the dicotyledonous condition is reached, the root is diarch. Among the Cycadales, on the other hand, although some have reached the diarch state, the characteristic root is tetrarch, the intercotyledonary poles persisting after the dicotyledonous condition is attained. An important consideration here, however, is the fact that there is often a reduction in the number of poles in



individual roots, the first-formed portion being tetrarch and the tip diarch. In *Ginkgo* the diarch root is the one commonly found, though here also tetrarchy and triarchy sometimes occur. The root of Gnetales is diarch.

"At this point, also, comparison with the angiosperms is instructive. Both tetrarch and diarch roots occur among the Archichlamydeae. According to Miss THOMAS, the anatomy of the cotyledonary node of *Liriodendron tulipifera*, *Clematis Hendersonii*, species of *Quercus*, of *Ricinus*, and even some Compositae, resembles in every respect that of *Cycas* and *Dioon*.

"A third tendency made apparent by this comparison of seedling anatomy is that to reduce the cotyledonary vascular strands to the fixed number two. The Coniferales are the only order to work out this tendency to the end; the dicotyledonous conifers (except *Araucaria* and *Podocarpus*) have just two such strands, one for each cotyledon. The Cycadales, although they have not reached that condition, show a tendency toward it in two ways: by restricting the branching of both median and lateral strands, and by eliminating the lateral ones altogether; and both of these tendencies are carried into the angiosperms. The cotyledon in *Ginkgo* and the Gnetales receives two strands, which often dichotomize.

"Two very interesting facts are brought out by the diagram in the third row of fig. 462 (series C). One of these is the strong resemblance between *Ginkgo* and the Gnetales; the other is the disclosure that in this feature of seedling anatomy, as well as in many other respects, *Araucaria* and *Podocarpus* stand aloof from the other conifers and show a marked resemblance to *Ginkgo*. These two facts may or may not be significant; the series was constructed merely to show that they exist."

## SUMMARY OF LITERATURE CITED

- ALLEN, C. E., The early stages of spindle formation in the pollen mother cells of *Larix*. *Annals of Botany* **17**:218-312. *pls.* 14, 15. 1903.
- ANGELA, SISTER HELEN, The embryo of *Ceratozamia*; a physiological study. *Bot. Gazette* **45**:412-416. *figs.* 7. 1908.
- , The seedling of *Ceratozamia*. *Bot. Gazette* **46**:203-220. *pls.* 12-16. 1908.
- , Vascular anatomy of the seedling of *Microcycas calocoma*. *Bot. Gazette* **47**:139-147. *pls.* 5, 6. 1909.
- , The extrafascicular cambium of *Ceratozamia*. *Bot. Gazette* **47**:150-152. *pl.* 7. 1909.
- ARBER, E. A. NEWELL, On some new species of *Lagenostoma*, a type of pteridospermous seed from the Coal-measures. *Annals of Botany* **19**:326-328. 1905 (abstract).
- , On the past history of ferns. *Annals of Botany* **20**:215-232. 1906.
- , "The origin of gymnosperms"; a discussion at the Linnean Society. *New Phytologist* **5**:68-76, 141-148. 1906.
- , and PARKIN, JOHN, On the origin of angiosperms. *Jour. Linn. Soc. London Bot.* **38**:29-80. 1907.
- , On a new pteridosperm possessing the *Sphenopteris* type of foliage. *Annals of Botany* **22**:57-62. *pl.* 6. 1908.
- , and PARKIN, JOHN, Studies in the evolution of the angiosperms: the relationship of the angiosperms to the Gnetales. *Annals of Botany* **22**:489-515. 1908.
- ARNOLDI, W., Beiträge zur Morphologie einiger Gymnospermen. I. Die Entwicklung des Endosperms bei *Sequoia sempervirens*. *Bull. Soc. Imp. Nat. Moscou* 1899: pp. 13. *pls.* 7, 8.
- , Beiträge zur Morphologie und Entwicklungsgeschichte einiger Gymnospermen. II. Ueber die Corpuscula und Pollenschlauche bei *Sequoia sempervirens*. *Bull. Soc. Imp. Nat. Moscou* 1899: pp. 8. *pls.* 10, 11.
- , Beiträge zur Morphologie der Gymnospermen. III. Embryogenie von *Cephalotaxus Fortunei*. *Flora* **87**:46-63. *pls.* 1-3. 1900.
- , Beiträge zur Morphologie der Gymnospermen. IV. Was sind die "Keimbläschen" oder "Hofmeister's-Körperchen" in der Eizelle der Abietineen? *Flora* **87**:194-204. *pls.* 6, 7. 1900.
- , Beiträge zur Morphologie einiger Gymnospermen. V. Weitere Untersuchungen der Embryogenie in der Familie der Sequoiaceen. *Bull. Soc. Imp. Nat. Moscou* 1901: pp. 28. *pls.* 2.
- , Beiträge zur Morphologie der Gymnospermen. VI. Ueber den Bau der Zellkerne im Embryo von *Ginkgo biloba*. VII. Die Embryobildung bei *Ginkgo biloba*. *Ann. Inst. Agronomique et Forestière à Nowo-Alexandria* **16**:1-22. 1903.

- BAILEY, IRVING W., The structure of the wood in the Pineae. Bot. Gazette 48:47-55. *pl.* 5. 1909.
- BAILLON, H., Recherches organogéniques sur la fleur femelle des Conifères. Ann. Sci. Nat. Bot. IV. 14:186-199. *pls.* 12, 13. 1860.
- BARTHOLOMEW, MARY, Abnormal prothalli of *Pinus sylvestris*. Notes Roy. Bot. Gard. Edinburgh 4:253-255. *pl.* 49. 1909.
- BECCARI, O., Della organogenia dei fiori feminei del *Gnetum Gnemon* L. Nuovo Giorn. Bot. Ital. 7:91-99. 1877.
- BELAJEFF, W., Zur Lehre von dem Pollenschlauche der Gymnospermen. Ber. Deutsch. Bot. Gesell. 9:280-286. *pl.* 18. 1891.
- , Zur Lehre von dem Pollenschlauche der Gymnospermen (Zweite Mittheilung). Ber. Deutsch. Bot. Gesell. 11:194-201. *pl.* 12. 1893.
- BENSON, MARGARET, On a new lycopodiaceous seedlike organ. New Phytologist 1:58, 59. *fig.* 3. 1902.
- , The fructification of *Lyginodendron Oldhamium*. Annals of Botany 16:575, 576. *figs.* 31. 1902.
- , *Telangium Scottii*, a new species of *Telangium* (*Calymmatotheca*) showing structure. Annals of Botany 18:161-177. *pl.* 11. 1904.
- , On the contents of the pollen chamber of a specimen of *Lagenostoma ovoides*. Bot. Gazette 45:409-412. *figs.* 2. 1908.
- , Report of Proc. Roy. Soc. London in Nature 80:239. 1909.
- BERRIDGE, ETHEL M., and SANDAY, ELIZABETH, Oogenesis and embryogeny in *Ephedra distachya*. New Phytologist 6:128-134, 167-174. *pls.* 3, 4. 1907.
- BERRY, EDWARD W., Some araucarian remains from the Atlantic coastal plain. Bull. Torr. Bot. Club 35:249-260. *pls.* 11-16. 1908.
- , A mid-cretaceous species of *Torreya*. Amer. Jour. Sci. 25:382-386. 1908.
- BERTRAND, C. E., et RENAULT, B., Recherches sur les Poroxylons. Archiv. Bot. Nord. France 3: pp. 47. *figs.* 79. 1886.
- BESSEY, CHARLES E., The morphology of the pine cone. Bot. Gazette 33:157-159. *pl.* 8. 1902.
- BESSEY, E. A., Notes on the spermatozoids of *Ginkgo*. Science 13:255. 1901.
- BLACKMAN, V. H., On the cytological features of fertilization and related phenomena in *Pinus silvestris* L. Phil. Trans. Roy. Soc. London B 190:395-426. *pls.* 12-14. 1898.
- BOWER, F. O., On the germination and histology of the seedlings of *Welwitschia mirabilis*. Quart. Jour. Micr. Sci. 21:15-30. *pls.* 3, 4. 1881.
- , On the further development of *Welwitschia mirabilis*. Quart. Jour. Micr. Sci. 21:571-594. *pls.* 22, 23. 1881.
- , The germination and embryology of *Gnetum Gnemon*. Quart. Jour. Micr. Sci. 22:278-298. *pl.* 25. 1882.
- BRAUN, A., Vortrag auf dem Congrès scientifique de France, 10th session (Strassburg), pp. 171, 172. 1842 (communicated in BRAUN'S *Leben von C. METTENIUS*, p. 335. Berlin. 1882).

- BRONGNIART, A., Recherches sur l'organisation des tiges des Cycadées. Ann. Sci. Nat. Bot. I. 16:389-402. pls. 20-22. 1829.
- , Recherches sur les graines fossiles silicifiées. Paris. 1881.
- BROOKS, F. T., and STILES, W., The structure of *Podocarpus spinulosa* (Smith) R. Br. Annals of Botany 24:305-318. pl. 21. 1910.
- BROWN, ROBERT, Character and description of *Kingia*, a new genus of plants found on the S.W. coast of New Holland, with observations on the structure of its unimpregnated ovulum and the female flower in Cycadeae and Coniferae. 1827. Included also in BROWN'S Miscellaneous botanical works 1:1866.
- BROWNE, LADY ISABEL, The phylogeny and interrelationships of the Pteridophyta. V. Filicales. New Phytologist 7:230-253. 1908.
- BURLINGAME, L. L., The staminate cone and male gametophyte of *Podocarpus*. Bot. Gazette 46:161-178. pls. 8, 9. figs. 9. 1908.
- BUTTERWORTH, J., Some further investigation of fossil seeds of the genus *Lagenostoma* (Williamson) from the Lower Coal-measures. Mem. and Proc. Manchester Lit. and Phil. Soc. 41:1-4. 1897.
- CALDWELL, OTIS W., *Microcycas calocoma*. Bot. Gazette 44:118-141. pls. 10-13. figs. 14. 1907.
- CAMPBELL, D. H., Mosses and ferns. New York. 1895.
- CAROTHERS, IDA ELEANOR, The development of the ovule and the female gametophyte in *Ginkgo biloba*. Bot. Gazette 43:116-130. pls. 5, 6. 1907.
- CARRUTHERS, W., On gymnospermatus fruits from the secondary rocks of Britain. Journal of Botany 5:1-21. 1867.
- , On fossil cycadean stems from the secondary rocks of Great Britain. Trans. Linn. Soc. Bot. 26:675-708. pls. 54-63. 1870.
- CASPARY, R., De Abietinearum floris feminei structura morphologica. Ann. Sci. Nat. Bot. IV. 14:200-209. 1860.
- ČELAKOVSKÝ, L., Zur Gymnospermie der Coniferen. Flora 62:257-264, 272-283. 1879.
- , Zur Kritik der Ansichten von der Fruchtschuppe der Abietineen. Abhandl. Königl. Böhm. Gesell. Wiss. VI. 11:1882.
- , Die Gymnospermen: eine morphologisch-phylogenetische Studie. Abhandl. Königl. Böhm. Gesell. Wiss. VII. 4:1-48. 1890.
- , Die Vermehrung der Sporangien von *Ginkgo biloba* L. Oesterreich. Bot. Zeitsch. 50:229-237, 276-283, 337-341. 1900.
- , Nachtrag zu meiner Schrift über die Gymnospermen. ENGLER'S Bot. Jahrb. 24:202-231. 1898.
- CHAMBERLAIN, CHARLES J., Winter characters of certain sporangia. Bot. Gazette 25:125-128. pl. 11. 1898.
- , Oogenesis in *Pinus Laricio*. Bot. Gazette 27:268-280. pls. 4-6. 1899.
- (with COULTER, J. M.), The embryogeny of *Zamia*. Bot. Gazette 35:184-194. pls. 6-8. 1903.
- , The ovule and female gametophyte of *Dioon*. Bot. Gazette 42:321-358. pls. 13-15. figs. 9. 1906.



- CHAMBERLAIN, CHARLES J., Preliminary note on *Ceratozamia*. Bot. Gazette **43**:137. 1907.
- , Spermatogenesis in *Dioon edule*. Bot. Gazette **47**:215-236. pls. 15-18. figs. 3. 1909.
- , *Dioon spinulosum*. Bot. Gazette **48**:401-413. figs. 7. 1909.
- , Fertilization and embryogeny of *Dioon edule*. Bot. Gazette **50**:Dec. 1910.
- CHAUVEAUD, G., Passage de la disposition primitive à la disposition secondaire dans les cotylédons du Pin maritime. Extr. Bull. Mus. Hist. Nat. Paris. 1902.
- , Le liber précurseur dans le sapin pinsapo. Ann. Sci. Nat. Bot. VIII. **19**:321-333. 1904.
- , Origine secondaire du double faisceau foliaire chez les sapins (*Abies*) et les pins (*Pinus*). Ann. Sci. Nat. Bot. VIII. **19**:335-348. 1904.
- CHICK, EDITH, The seedling of *Torreya myristica*. New Phytologist **2**:83-91. pls. 7, 8. 1903.
- CHRYSLER, M. A. (with COULTER, J. M.), Regeneration in *Zamia*. Bot. Gazette **38**:452-458. figs. 8. 1904.
- (with JEFFREY, E. C.), On cretaceous Pityoxyla. Bot. Gazette **42**:1-15. pls. 1, 2. 1906.
- (with JEFFREY, E. C.), The microgametophyte of the Podocarpaceae. Amer. Nat. **41**:355-364. figs. 5. 1907.
- , Tyloses in tracheids of conifers. New Phytologist **7**:198-204. pl. 5. 1908.
- COKER, W. C., Observations on the gametophyte and embryo of *Taxodium distichum*. Johns Hopkins Univ. Circ. **19**:45, 46. 1900.
- , Notes on the gametophytes and embryo of *Podocarpus*. Bot. Gazette **33**:89-107. pls. 5-7. 1902.
- , On the gametophytes and embryo of *Taxodium*. Bot. Gazette **36**:1-27, 114-140. pls. I-II. 1903.
- , On the spores of certain Coniferae. Science N.S. **19**:424. 1904.
- , On the spores of certain Coniferae. Bot. Gazette **38**:206-213. figs. 24. 1904.
- , Fertilization and embryogeny in *Cephalotaxus Fortunei*. Bot. Gazette **43**:1-10. pl. I. figs. 5. 1907.
- COMPTON, R. H. (with SOUTH, F. W.), On the anatomy of *Dioon edule* Lindl. New Phytologist **7**:222-229. 1908.
- CONSTANTIN, J., et MOROT, L., Sur l'origine des faisceaux libéro-ligneux super-numéraires dans la tige des Cycadées. Bull. Soc. Bot. France **32**:173. 1885.
- COOK, MEL T., Polyembryony in *Ginkgo*. Bot. Gazette **34**:64, 65. fig. 1. 1902.
- , Polyembryony in *Ginkgo*. Bot. Gazette **36**:142. 1903.
- COULTER, JOHN M., Notes on the fertilization and embryogeny of conifers. Bot. Gazette **23**:40-43. pl. 6. 1897.
- , and CHAMBERLAIN, C. J., The embryogeny of *Zamia*. Bot. Gazette **35**:184-194. pls. 6-8. 1903.

- COULTER, JOHN M., and CHRYSLER, M. A., Regeneration in *Zamia*. Bot. Gazette **38**:452-458. *figs. 8*. 1904.
- , and LAND, W. J. G., Gametophytes and embryo of *Torreya taxifolia*. Bot. Gazette **39**:161-178. *pls. A, 1-3*. 1905.
- , The embryo sac and embryo of *Gnetum Gneumon*. Bot. Gazette **46**:43-49. *pl. 7*. 1908.
- , Evolutionary tendencies among gymnosperms. Bot. Gazette **48**:81-97. 1909.
- , BARNES, C. R., and COWLES, H. C., Text book of botany. New York. 1910.
- DANGEARD, P. A., La mode d'union de la tige et de la racine chez les Gymnospermes. Compt. Rend. Acad. Sci. Paris **110**:253, 254. 1890.
- , Recherches sur les plantules des Conifères. La Botaniste **3**:126-204. *pls. 13-17*. 1892.
- DEBARY, A., Comparative anatomy of the vegetative organs of the phanerogams and ferns. English translation. 1884.
- DE FRAINE, E. (with HILL, T. G.), On the seedling structure of gymnosperms. Annals of Botany **20**:471-473. 1906.
- (with HILL, T. G.), On the seedling structure of gymnosperms. I. Annals of Botany **22**:689-712. *pl. 35. figs. 8*. 1908.
- (with HILL, T. G.), On the seedling structure of gymnosperms. II. Annals of Botany **23**:189-227. *pl. 15. figs. 11*. 1909.
- (with HILL, T. G.), On the seedling structure of gymnosperms. III. Annals of Botany **23**:433-458. *pl. 30*. 1909.
- (with HILL, T. G.), On the seedling structure of gymnosperms. IV. Gnetales: Annals of Botany **24**:319-333. *pls. 22, 23*. 1910.
- DICKSON, A., Observations on some bisexual cones occurring in the spruce fir (*Abies excelsa*). Trans. Edinburgh Bot. Soc. **6**:418-422. 1860.
- DIXON, H. N., Fertilization of *Pinus silvestris*. Annals of Botany **8**:21-34. *pls. 3-5*. 1894.
- DORETY, HELEN A., see ANGELA, SISTER HELEN.
- DOULIOT, H. (with VAN TIEGHEM, PH.), Sur la polystélie. Ann. Sci. Nat. Bot. VII. **3**:275-322. *pls. 13, 14*. 1886.
- DUCHARTRE, P. E., Mémoire sur les embryons qui ont été décrits comme polycotylés. Ann. Sci. Nat. Bot. III. **10**:207-237. *pls. 7-10*. 1848.
- EICHLER, A. W., Ueber *Welwitschia mirabilis*, etc. Flora **47**:459-464, 473-479, 489-496, 508-510, 513-520. 1863.
- , Sind die Coniferen gymnosperm oder nicht? Flora **56**:241-247, 260-272. 1873.
- , Coniferae in ENGLER und PRANTL'S Natürlichen Pflanzenfamilien **2**<sup>1</sup>: 108. 1889.
- ENGELMANN, G., Morphology of the carpellary scales of Coniferae. Amer. Jour. Sci. III. **12**:469, 470. 1876.

- ENRICO, C. V., Contribuzione alla conoscenza della morphologia e dello sviluppo del fascio vascolare delle foglie delle Cicadacee. *Annales di Bot.* 1:109-121. *pls.* 8, 9. 1903.
- FANKHAUSER, J., Entwicklung des Stenzels und Blattes von *Ginkgo*. Bern. 1882.
- FARMER, J. B., On the occurrence of two prothallia in the embryo sac of *Pinus*. *Annals of Botany* 6:213, 214. *fig.* 5. 1892.
- FAULL, J. H., The anatomy of the Osmundaceae. *Bot. Gazette* 32:381-420. *pls.* 14-17. 1901.
- FERGUSON, MARGARET C., The development of the pollen tube and the division of the generative nucleus in certain species of pines. *Annals of Botany* 15:193-223. *pls.* 12-14. 1901.
- , The development of the egg and fertilization in *Pinus Strobus*. *Annals of Botany* 15:435-479. *pls.* 23-25. 1901.
- , Contributions to the life history of *Pinus*, with special reference to sporogenesis, the development of the gametophytes, and fertilization. *Proc. Wash. Acad. Sci.* 6:1-202. *pls.* 1-24. 1904.
- FLICHE, P. (with ZEILLER, R.), Découverte de strobiles de *Sequoia* et de Pin dans le Portlandien des environs de Boulogne-sur-Mer. *Compt. Rend. Acad. Sci. Paris* 137:1020-1022. 1903.
- , et ZEILLER, R., Note sur un florule portlandienne des environs de Boulogne-sur-Mer. *Bull. Soc. Geol. France IV.* 4:787-812. 1904.
- FORD, SIBILLE C. (with SEWARD, A. C.), The Araucarieae, recent and extinct. Abstract read before Roy. Soc. London, December 1905.
- (with SEWARD, A. C.), The Araucarieae, recent and extinct. *Phil. Trans. Roy. Soc. London B* 198:305-411. *pls.* 23, 24. *figs.* 28. 1906.
- FRAINE, E. DE, see DE FRAINE.
- FUJII, K., On the different views hitherto proposed regarding the morphology of the flowers of *Ginkgo biloba*. *Bot. Mag. Tokyo* 10:15-25, 104-110. *pl.* 1. 1896.
- , (Has the spermatozoid of *Ginkgo* a tail or not?). *Bot. Mag. Tokyo* 12:287-290. 1898. (Japanese)
- , (On the morphology of the spermatozoid of *Ginkgo*). *Bot. Mag. Tokyo* 13:260-266. *pl.* 7. 1899. (Japanese)
- , (Account of a sperm with two spiral bands). *Bot. Mag. Tokyo* 14:16, 17. Jan. 1900. (Japanese)
- (with STOPES, MARIE C.), The nutritive relations of the surrounding tissues to the archegonia in gymnosperms. *Beih. Bot. Centralbl.* 20:1-24. *pl.* 1. 1906.
- (with STOPES, MARIE C.), Studies on the structure and affinities of cretaceous plants. *Phil. Trans. Roy. Soc. London B* 201:1-90. *pls.* 1-9. 1910; abstract in *Annals of Botany* 24:231, 232. 1910.
- GERRY, E., The distribution of the "bars of Sanio" in the Coniferales. *Annals of Botany* 24:119-124. *pl.* 13. 1910.

- GOEBEL, K., Outlines of classification and special morphology. English translation. 1887.
- , Organography of plants. English translation. 1900.
- , Morphologische und biologische Bemerkungen. 13. Ueber die Pollenentleerung bei einiger Gymnospermem. *Flora* **91**:237-263. *figs.* 19. 1902.
- GOROSCHANKIN, J., Zur Kenntniss der Corpuscula bei den Gymnospermem. *Bot. Zeit.* **41**:825-831. *pl.* 7A. 1883; Ueber den Befruchtung-Process bei *Pinus Pumilio*. 1883.
- GOTHAN, W., Zur Anatomie lebender und fossiler Gymnospermenhölzer. Abhandl. Preuss. Geol. Landesanstalt. Neue Folge. Heft 44. 1905.
- GOWAN, MISS J. (with SEWARD, A. C.), The maidenhair tree (*Ginkgo biloba* L.). *Annals of Botany* **14**:109-154. *pls.* 8-10. 1900.
- GRAND'EURY, C., La flore carbonifère du Département de la Loire. *Mém. Acad. Sci.* **24**<sup>1</sup>: pp. 624. *pls.* 38. 1877.
- , Sur les rhizomes et les racines des fougères fossiles et des Cycadofilices. *Compt. Rend. Acad. Sci. Paris* **138**:607-610. 1904.
- , Sur les graines des Neuropteridées. *Compt. Rend. Acad. Sci. Paris* **139**:23-27, 782-786. 1904.
- , Sur les graines trouvées attachées au *Pecopteris Pluckenetii* Schlot. *Compt. Rend. Acad. Sci. Paris* **140**:920-923. *figs.* 2. 1905.
- , Sur les *Rhabdocarpus*, les graines et l'évolution des Cordaitées. *Compt. Rend. Acad. Sci. Paris* **140**:995-998. 1905.
- , Sur les graines de *Sphenopteris*, sur l'attribution des *Codonospermum*, et sur l'extrême variété des graines de fougères. *Compt. Rend. Acad. Sci. Paris* **141**:812-815. 1905.
- , Sur les inflorescences des fougères avec graines, etc. *Compt. Rend. Acad. Sci. Paris* **143**:764. 1906.
- HAYATA, B., *Taiwania*, a new genus of conifers. *Jour. Linn. Soc. Bot.* **32**:330-332. *pl.* 16. 1906.
- , On *Taiwania* and its affinity to other genera. *Bot. Mag. Tokyo* **21**:21-27. *pl.* 1. 1907.
- HAYDON, WALTER T., The seed production of *Pinus sylvestris*. *Proc. and Trans. Liverpool Biol. Soc.* **22**:1-32. *figs.* 16. 1907.
- HEER, O., Zur Geschichte der *Ginkgo*-artigen Bäume. *ENGLER'S Bot. Jahrb.* **1**:1-13. 1880.
- , *Flora fossilis arctica*. 1868-1883.
- HILL, T. G., On secondary thickening in recent Pteridophyta. *New Phytologist* **5**:208-214. 1906.
- , and DE FRAINE, E., On the seedling structure of gymnosperms. *Annals of Botany* **20**:471-473. 1906.
- , The germination of *Gnetum Gnemon* L. *Jour. Roy. Hort. Soc.* **34**:1, 2. 1908.
- , and DE FRAINE, E., On the seedling structure of gymnosperms. I. *Annals of Botany* **22**:689-712. *pl.* 35. *figs.* 8. 1908.



- HILL, T. G., and DE FRAINE, E., On the seedling structure of gymnosperms. II. Annals of Botany **23**:189-227. *pl.* 15. *figs.* 11. 1909.
- , and DE FRAINE, E., On the seedling structure of gymnosperms. III. Annals of Botany **23**:433-458. *pl.* 30. 1909.
- , and DE FRAINE, E., On the seedling structure of gymnosperms. IV. Gnetales. Annals of Botany **24**:319-333. *pls.* 22, 23. 1910.
- HIRASÉ, S., Études sur la fécondation et l'embryogénie du *Ginkgo biloba*. Jour. Coll. Sci. Imp. Univ. Tokyo **8**:307-322. *pls.* 31, 32. 1895.
- , (Announcement of the spermatozoid of *Ginkgo*). Bot. Mag. Tokyo **10**:171, 172. May 1896. (Japanese)
- , (Preliminary report on the spermatozoid of *Ginkgo*). Bot. Mag. Tokyo **10**:325-328. Oct. 1896. (Japanese)
- , Études sur la fécondation et l'embryogénie du *Ginkgo biloba*. Jour. Coll. Sci. Imp. Univ. Tokyo **12**:103-149. *pls.* 7-9. 1898.
- HOFMEISTER, W., Vergleichende Untersuchungen der Keimung, Entfaltung, und Fruchtbildung höherer Kryptogamen und der Samenbildung der Coniferen. pp. 179. *pls.* 33. Leipzig. 1851. English translation. London. 1863.
- , Embryobildung der Phanerogamen. Jahrb. Wiss. Bot. **1**:82-188. *pls.* 7-10. 1858.
- , Lehre der Pflanzenzelle. 1867.
- HOLLICK, A., and JEFFREY, E. C., Affinities of certain cretaceous plant remains commonly referred to the genera *Dammara* and *Brachyphyllum*. Amer. Nat. **40**:189-215. *pls.* 1-5. 1906.
- , and JEFFREY, E. C., Studies of cretaceous coniferous remains from Kreischerville, New York. Mem. N.Y. Bot. Garden **3**:1-138. *pls.* 1-29. 1909.
- HOOKE, J. D., On *Welwitschia*, a new genus of Gnetaceae. Trans. Linn. Soc. London **24**:1-48. *pls.* 1-14. 1863.
- HUTTON, J. (with LINDLEY, J.), Fossil flora of Great Britain. 1830.
- IKENO, S., Das Spermatozoid von *Cycas revoluta*. Bot. Mag. Tokyo **10**:367, 368. 1896.
- , Vorläufige Mittheilung über die Spermatozoiden bei *Cycas revoluta*. Bot. Centralbl. **69**:1-3. 1897.
- , Untersuchungen über die Entwicklung der Geschlechtsorgane und den Vorgang der Befruchtung bei *Cycas revoluta*. Jahrb. Wiss. Bot. **32**:557-602. *pls.* 8-10. 1898.
- , Contribution à l'étude de la fécondation chez le *Ginkgo biloba*. Ann. Sci. Nat. Bot. VIII. **13**:305-318. *pls.* 2, 3. 1901.
- JACCARD, P., Le développement du pollen de l'*Ephedra helvetica*. Archiv. Sci. Phys. et Nat. III. **30**:280-282. 1893; rev. in Bot. Centralbl. Beih. **4**:230. 1894.
- , Recherches embryologiques sur l'*Ephedra helvetica*. Bull. Soc. Vaudoise Sci. Nat. **30**: *pls.* 10. 1894; rev. in Bot. Centralbl. **61**:111-113. 1895.

- JÄGER, L., Beiträge zur Kenntniss der Endosperm-bildung und zur Embryologie von *Taxus baccata*. Flora **86**:241-288. pls. 15-19. 1899.
- JEFFREY, E. C., The structure and development of the stem in the Pteridophyta and Gymnosperms. Phil. Trans. Roy. Soc. London B **195**:119-146. pls. 6. 1902.
- , Comparative anatomy of gymnosperms in COULTER and CHAMBERLAIN'S Morphology of angiosperms. New York. 1903.
- , The comparative anatomy of the Coniferales. I. The genus *Sequoia*. Mem. Boston Soc. Hist. **5**:441-459. pls. 68-71. 1903.
- , A fossil *Sequoia* from the Sierra Nevada. Bot. Gazette **38**:321-332. pls. 18, 19. 1904.
- , The comparative anatomy of the Coniferales. II. The Abietineae. Mem. Boston Soc. Nat. Hist. **6**:1-37. pls. 1-7. 1904.
- (with HOLLICK, A.), Affinities of certain cretaceous plant remains commonly referred to the genera *Dammara* and *Brachyphyllum*. Amer. Nat. **40**:189-215. pls. 1-5. 1906.
- , and CHRYSLER, M. A., On cretaceous Pityoxyla. Bot. Gazette **42**:1-15. pls. 1, 2. 1906.
- , *Araucariopitys*, a new genus of araucarians. Bot. Gazette **44**:435-444. pls. 27-30. 1907.
- , and CHRYSLER, M. A., The microgametophyte of the Podocarpaceae. Amer. Nat. **41**:102-107. pls. 8, 9. 1907.
- , On the structure of the leaf in cretaceous pines. Annals of Botany **22**:207-220. pls. 13, 14. 1908.
- , Traumatic ray tracheids in *Cunninghamia sinensis*. Annals of Botany **22**:593-602. pl. 31. 1908.
- , Are there foliar gaps in the Lycopsidea? Bot. Gazette **46**:241-258. pls. 17, 18. 1908.
- (with HOLLICK ARTHUR), Studies of cretaceous coniferous remains from Kreischerville, New York. Mem. N.Y. Bot. Garden **3**:1-138. pls. 1-29. 1909.
- JUEL, H. O., Beiträge zur Kenntniss der Tetradenbildung. Jahrb. Wiss. Bot. **35**:626-659. pls. 15, 16. 1900.
- , Ueber den Pollenschlauch von *Cupressus*. Flora **93**:56-62. pl. 3. 1904.
- JURANYI, L., Bau und Entwicklung des Pollens bei *Ceratozamia longifolia* Miq. Jahrb. Wiss. Bot. **8**:382-400. pls. 31-34. 1872.
- KARSTEN, G., Beiträge zur Entwicklungsgeschichte der Gattung *Gnetum*. Bot. Zeit. **50**:205-215, 221-231, 237-246. pls. 5, 6. 1892.
- , Untersuchungen über die Gattung *Gnetum*. Ann. Jard. Bot. Buitenzorg **11**:195-218. pls. 17-19. 1893.
- , Zur Entwicklungsgeschichte der Gattung *Gnetum*. COHN'S Beitr. Biol. Pflanz. **6**:337-382. pls. 8-11. 1893.
- KERNER VON MARILAUN, Das Pflanzenleben. Leipzig and Vienna. 1896.

- KIDSTON, R., On the fructifications of some ferns from the Carboniferous formation. Trans. Roy. Soc. Edinburgh **33**:137-156. pls. 8. figs. 7. 1887.
- , On the various divisions of British Carboniferous rocks, as determined by their fossil floras. Proc. Roy. Soc. Edinburgh **12**:183-257. 1893-1894.
- , On the fructification of *Neuropteris heterophylla* Brongniart. Proc. Roy. Soc. London **72**:487. 1904 (abstract); Phil. Trans. Roy. Soc. London B **197**:1-5. pl. 1. 1904 (full paper).
- , Preliminary note on the occurrence of microsporangia in organic connection with the foliage of *Lyginodendron*. Proc. Roy. Soc. London **76**:358-360. pl. 6. 1905.
- , The early history of seed-bearing plants as recorded in the carboniferous flora. Wilde Lecture. Mem. and Proc. Manchester Lit. and Phil. Soc. **49**: no. 12. pp. 32. pls. 3. 1905.
- , On the microsporangia of the Pteridospermae, with remarks on their relationships to existing groups. Phil. Trans. Roy. Soc. London B **198**: 413-445. pls. 25-28. 1906.
- KILDAHL, N. JOHANNA, Development of the walls in the proembryo of *Pinus Laricio*. Bot. Gazette **44**:102-107. pls. 8, 9. 1907.
- , The morphology of *Phyllocladus alpina*. Bot. Gazette **46**:339-348. pls. 20-22. 1908.
- , Affinities of *Phyllocladus*. Bot. Gazette **46**:464, 465. 1908.
- KUBART, BRUNO, Die weibliche Blüthe von *Juniperus communis* L. Sitzungsber. Kais. Akad. Wiss. Wien **114**: pp. 29. pls. 2. 1905.
- LAND, W. J. G., A morphological study of *Thuja*. Bot. Gazette **34**:249-259. pls. 6-8. 1902.
- , Spermatogenesis and oogenesis in *Ephedra trifurca*. Bot. Gazette **38**: 1-18. pls. 1-4. 1904.
- (with COULTER, J. M.), Gametophytes and embryo of *Torreya taxifolia*. Bot. Gazette **39**:161-178. pls. A, 1-3. 1905.
- , Fertilization and embryogeny in *Ephedra trifurca*. Bot. Gazette **44**:273-292. pls. 20-22. 1907.
- LANG, W. H., Studies in the development and morphology of cycadean sporangia. I. The microsporangia of *Stangeria paradoxa*. Annals of Botany **11**:421-438. pl. 22. 1897.
- , Studies in the development and morphology of cycadean sporangia. II. The ovule of *Stangeria paradoxa*. Annals of Botany **14**:281-306. pls. 17, 18. 1900.
- LAWSON, A. A., The gametophyte, archegonia, fertilization, and embryo of *Sequoia sempervirens*. Annals of Botany **18**:1-28. pls. 1-4. 1904.
- , The gametophyte, fertilization, and embryo of *Cryptomeria japonica*. Annals of Botany **18**:417-444. pls. 27-30. 1904.
- , The gametophytes, fertilization, and embryo of *Cephalotaxus drupacea*. Annals of Botany **21**:1-23. pls. 1-4. 1907.

- LAWSON, A. A., The gametophytes and embryo of the Cupressineae, with special reference to *Libocedrus decurrens*. *Annals of Botany* 21:281-301. *pls.* 24-26. 1907.
- , The gametophytes and embryo of *Pseudotsuga Douglasii*. *Annals of Botany* 23:163-180. *pls.* 12-14. 1909.
- , The gametophytes and embryo of *Sciadopitys verticillata*. *Annals of Botany* 24:403-421. *pls.* 29-31. 1910.
- LIFE, A. C., The tubercle-like roots of *Cycas revoluta*. *Bot. Gazette* 31:265-271. *figs.* 10. 1901.
- LIGNIER, O., Le fruit du *Williamsonia gigas* Carr. et les Bennettitales, documents nouveaux et notes critiques. *Mém. Soc. Linn. Normandie* 21:19-56. *figs.* 9. 1903.
- , La fleur des Gnétacées est-elle intermédiaire entre celle des gymnospermes et celle des angiospermes? *Bull. Soc. Linn. Normandie* V. 7:55-71. 1903.
- , Notes complémentaires sur la structure du *Bennettites Morieri*. *Bull. Soc. Linn. Normandie* V. 8:3-7. *figs.* 3. 1905.
- , Le fruit des Bennettitées et l'ascendance des Angiospermes. *Bull. Soc. Bot. France* IV. 8:1-17. 1908.
- , Végétaux fossiles de Normandie. IV. Flore jurassique de Mamers (Sarthe). *Université de Caen*. pp. 48. *pls.* 2. 1910 (?).
- LINDLEY, J., and HUTTON, J., Fossil flora of Great Britain. 1830.
- LOYD, FRANCIS E., Vivipary in *Podocarpus*. *Torreya* 2:113-117. *figs.* 3. 1902.
- LOMAX, J., Some new features in relation to *Lyginodendron Oldhamium*. *Annals of Botany* 16:601, 602. 1902.
- LOPRIORE, G., Ueber die Vielkörnigkeit der Pollenkörner von *Araucaria Bidwillii*. Vorläufige Mitteilung. *Ber. Deutsch. Bot. Gesell.* 23:335-346. *pl.* 15. 1905.
- LOTSY, J. P., Contributions to the life history of the genus *Gnetum*. *Ann. Jard. Bot. Buitenzorg* II. 1:46-114. *pls.* 2-11. 1899.
- , Parthenogenesis bei *Gnetum Ula* Brongn. *Flora* 92:397-404. *pls.* 9, 10. 1903.
- LYON, HAROLD L., The embryogeny of *Ginkgo*. *Minn. Bot. Studies* 3:275-290. *pls.* 29-43. 1904.
- MACMILLAN, CONWAY, Note on some British Columbian dwarf trees. *Bot. Gazette* 38:379-381. *figs.* 3. 1904.
- MASLEN, ARTHUR J. (with SCOTT, D. H.), The structure of the paleozoic seeds *Trigonocarpus Parkinsonii* Brongniart and *Trigonocarpus Oliveri*, sp. nov. I. *Annals of Botany* 21:89-134. *pls.* 11-14. 1907.
- (with SCOTT, D. H.), On *Mesoxylon*, a new genus of Cordaitales (preliminary note). *Annals of Botany* 24:236-239. 1910.
- MASTERS, MAXWELL T., Comparative morphology, anatomy, and life history of the Coniferae. *Jour. Linn. Soc. London Bot.* 27:226-332. *figs.* 29. 1891.
- , On the conifers of China. *Jour. Linn. Soc. London Bot.* 37:410-424. 1906.



- MASTERS, MAXWELL T., On the distribution of the species of conifers in the several districts of China, and on the occurrence of the same species in neighboring countries. Jour. Linn. Soc. London Bot. **38**:198-205. 1908.
- MATTE, H., Une anomalie de structure dans l'écaille ovulifère de *Ceratozamia mexicana*. Bull. Soc. Linn. Normandie V. **7**:52-54. 1903.
- , Recherches sur l'appareil libéro-ligneux des Cycadées. pp. 233. pls. 16. figs. 264. 1904.
- , Compléments à la structure mériphytaire du *Bowenia spectabilis* Hord. Compt. Rend. Assoc. Fr. Adv. Sci. **1905**:409-416.
- , Sur la structure de l'embryon et des germinations du genre *Zamia* L. Bull. Soc. Sci. et Méd. de l'Ouest **18**: nos. 2 and 3. 1909.
- METTENIUS, G. H., Beiträge zur Anatomie der Cycadeen. Abh. K. Sachs. Gesell. Wiss. **7**:565-608. pls. 1-5. 1861.
- MIQUEL, F. A. W., Monographia Cycadearum. 1841.
- MIYAKE, K., (On the spermatozoid of *Ginkgo*). Bot. Mag. Tokyo **12**:33-39. 1898. (Japanese)
- , The spermatozoid of *Ginkgo*. Jour. Applied Micr. **5**:1773-1780. figs. 10. 1902.
- , On the development of the sexual organs and fertilization in *Picea excelsa*. Annals of Botany **17**:351-372. pls. 16, 17. 1903.
- , Contribution to the fertilization and embryogeny of *Abies balsamea*. Beih. Bot. Centralbl. **14**:134-144. pls. 6-8. 1903.
- , Ueber die Spermatozoiden von *Cycas revoluta*. Ber. Deutsch. Bot. Gesell. **24**:78-83. pl. 6. 1906.
- , The development of the gametophytes and embryogeny of *Cunninghamia* (preliminary note). Bot. Mag. Tokyo **22**:45-50. figs. 14. 1908.
- , The development of the gametophytes and embryogeny of *Cunninghamia sinensis* (full paper). Beih. Bot. Centralbl. **27**:1-25. pls. 1-5. figs. 2. 1910.
- MOROT, L. (with CONSTANTIN, J.), Sur l'origine des faisceaux libéro-ligneux supernuméraires dans la tige des Cycadées. Bull. Soc. Bot. France **32**:173. 1885.
- MOTTIER, D. M., On the archegonium and apical growth of the stem in *Tsuga canadensis* and *Pinus silvestris*. Bot. Gazette **17**:141-143. pl. 8. 1892.
- MURRILL, W. A., The development of the archegonium and fertilization in the hemlock spruce (*Tsuga canadensis*). Annals of Botany **14**:583-607. pls. 31, 32. 1900.
- NATHORST, A. G., Beiträge zur Kenntnis einiger mesozoischen Cycadophyten. Handl. Kgl. Svensk. Vetensk.-Akad. **36**:1-28. pls. 1-3. 1902.
- , Palaeobotanische Mitteilungen. I. *Pseudocycas*, eine neue Cycadophytengattung aus den cenomanen Kreideablagerungen Grönlands. Handl. Kgl. Svensk. Vetensk.-Akad. **42**:1-11. pls. 1-3. 1907.
- , Palaeobotanische Mitteilungen. III. *Lycostrobus Scottii*, eine grosse Sporophyllähre aus den rhätischen Ablagerungen Schonens. Handl. Kgl. Svensk. Vetensk.-Akad. **43**:1-12. pls. 1, 2. 1908.

- NATHORST, A. G., Palaeobotanische Mitteilungen. IV. Ueber die Untersuchung kutinierter fossiler Pflanzenteile. Handl. Kgl. Svensk. Vetensk.-Akad. **43**: 1-13. pls. 1, 2. 1908.
- , Palaeobotanische Mitteilungen. VI. *Antholithus Zeilleri*, n. sp., mit noch erhaltenen Pollenkörnern aus den rhätischen Ablagerungen Schonens. Handl. Kgl. Svensk. Vetensk.-Akad. **43**: 20-24. pls. 2, 4. 1908.
- , Palaeobotanische Mitteilungen. VII. Handl. Kgl. Svensk. Vetensk.-Akad. **43**: no. 8. 1909.
- , Palaeobotanische Mitteilungen. VIII. Handl. Kgl. Svensk. Vetensk.-Akad. **45**: no. 4. 1910.
- NICHOLS, GEORGE E., A morphological study of *Juniperus communis* var. *depressa*. Beih. Bot. Centralbl. **25**: 201-241. pls. 8-17. figs. 4. 1910.
- NORÉN, C. O., Ueber Befruchtung bei *Juniperus communis*. Vorläufige Mitteilungen. Arkiv. Bot. Svensk. Vetensk.-Akad. **3**: pp. 11. 1904.
- , Zur Entwicklungsgeschichte des *Juniperus communis*. Uppsala Universitets Arsskrift 1907: pp. 64. pls. 4.
- , Zur Kenntnis der Entwicklung von *Saxegothaea conspicua* Lindl. Svensk. Bot. Tidsskr. **2**: 101-122. pls. 7-9. 1908.
- OERSTED, A. S., Bidrag til Naaletroeernes Morphologi. Vidensk. Meddel. Nat. Foren. Copenhagen. 1864.
- OLIVER, F. W., On some points of apparent resemblance in certain fossil and recent gymnospermous seeds. New Phytologist **1**: 145-154. figs. 4-6. 1902.
- , The ovules of the older gymnosperms. Annals of Botany **17**: 451-476. pl. 24. figs. 20. 1903.
- , and SCOTT, D. H., On *Lagenostoma Lomaxii*, the seed of *Lyginodendron*. Proc. Roy. Soc. London **71**: 477-481. 1903; reprint in Annals of Botany **17**: 625-629. 1903.
- , A new pteridosperm. New Phytologist **3**: 32. 1904.
- , Notes on *Trigonocarpum* Brongn. and *Polylophospermum* Brongn., two genera of paleozoic seeds. New Phytologist **3**: 96-104. pl. 2. 1904.
- , On the structure and affinities of *Stephanospermum* Brongniart, a genus of fossil gymnosperm seeds. Trans. Linn. Soc. London Bot. II. **6**: 361-400. pls. 41-44. 1904.
- , and SCOTT, D. H., On the structure of the paleozoic seed *Lagenostoma Lomaxii*, with a statement of the evidence upon which it is referred to *Lyginodendron*. Proc. Roy. Soc. London. Jan. **21**, 1904 (abstract preprint); Phil. Trans. Roy. Soc. London B **197**: 193-247. pls. 4-10. 1904 (full paper).
- , Ueber die neuentdeckten Samen der Steinkohlenflaure. Biol. Centralbl. **25**: 401-418. figs. 6. 1905.
- , "The origin of gymnosperms"; a discussion at the Linnean Society. New Phytologist **5**: 68-76, 141-148. 1906.
- , Pteridosperms and angiosperms. New Phytologist **5**: 232-242. 1906.
- , On *Physostoma elegans* Williamson, an archaic type of seed from the Paleozoic rocks. Annals of Botany **23**: 73-116. pls. 5-7. figs. 10. 1909.

- OSBORN, T. G. B., The lateral roots of *Amyelon radicans* Will., and their mycorrhiza. *Annals of Botany* **23**:603-611. *pls.* 46, 47. 1909.
- OTTLEY, ALICE M., The development of the gametophytes and fertilization in *Juniperus communis* and *Juniperus virginiana*. *Bot. Gazette* **48**:31-46. *pls.* 1-4. 1909.
- PARKIN, JOHN (with ARBER, E. A. NEWELL), On the origin of angiosperms. *Jour. Linn. Soc. London Bot.* **38**:29-80. 1907.
- (with ARBER, E. A. NEWELL), Studies in the evolution of the angiosperms: the relationship of the angiosperms to the Gnetales. *Annals of Botany* **22**:489-515. 1908.
- PARLATORE, F., Studi organografici sui fiori e sui frutti delle Conifere. *Opuscula botanica*. 1864.
- PAVOLINI, A. F., La *Stangeria paradoxa* Th. Moore. *Nuovo Giorn. Bot. Ital.* **16**:335-351. 1909.
- PAX, F., Allgemeine Morphologie der Pflanzen mit besonderer Berücksichtigung der Blütenmorphologie. 1890.
- PEARSON, H. H. W., Notes on the South African cycads. I. *Trans. S. African Phil. Soc.* **16**:341-354. *pls.* 6-8. 1906.
- , Some observations on *Welwitschia mirabilis* Hooker. *Phil. Trans. Roy. Soc. London B* **198**:246. 1906.
- , Further observations on *Welwitschia*. *Phil. Trans. Roy. Soc. London B* **200**:331-402. *pls.* 22-30. 1909.
- PENHALLOW, D. P., The anatomy of the North American Coniferales, together with certain exotic species from Japan and Australia. *Amer. Nat.* **38**:243-273, 331-359, 523-554, 691-723. 1904.
- , A manual of the North American gymnosperms, exclusive of the Cycadales but together with certain exotic species. Boston. 1907.
- PILGER, R., Taxaceae in ENGLER'S *Das Pflanzenreich*. 1903.
- POLLOCK, JAMES B., Variations in the pollen grain of *Picea excelsa*. *Amer. Nat.* **49**:253-286. *pl.* 1. 1906.
- POTONIÉ, H., *Lehrbuch der Pflanzenpalaeontologie*. Berlin. 1899.
- , Cycadofilices in ENGLER und PRANTL'S *Natürlichen Pflanzenfamilien* **2**:780-798. 1902.
- REINKE, J., Parasitische *Anabaena* in Wurzeln der Cycadean. *Gött. Nachr.* **107**. 1872.
- RENAULT, B., Recherches sur la fructification de quelques végétaux provenant des gisements silicifiés d'Autun et de Saint Etienne. *Ann. Sci. Nat. Bot. VI.* **3**:5-29. *pls.* 1-4. 1876.
- , Structure comparée de quelques tiges de la flore carbonifère. *Nouv. Arch. Mus. Hist. Nat. II.* **2**:213-348. *pls.* 8. 1879.
- , Cours de botanique fossile. Paris. 1880-1884.
- (with BERTRAND, C. E.), Recherches sur les Poroxyloons. *Archiv. Bot. Nord. France* **2**: pp. 147. *figs.* 79. 1886.

- RENAULT, B., Note sur le genre *Aetheotesta*. Mém. Soc. Hist. Nat. Saône-et-Loire, pp. 156, 158. 1887.
- , Bassin houiller et Permien d'Autun et d'Épinac. IV. Flore fossile. Part II. pp. 578. *pls.* 62. Paris. 1896.
- RENNER, OTTO, Ueber Zwitterblüthen bei *Juniperus communis*. Flora 93:297-300. *figs.* 3. 1904.
- ROBERTSON, AGNES, Spore formation in *Torreya californica*. New Phytologist 3:133-148. *pls.* 3, 4. 1904.
- , Studies in the morphology of *Torreya californica*. II. The sexual organs and fertilization. New Phytologist 3:205-216. *pls.* 7-9. 1904.
- , Some points in the morphology of *Phyllocladus alpina* Hook. Annals of Botany 20:259-265. *pls.* 17, 18. 1906.
- , The Taxoideae; a phylogenetic study. New Phytologist 6:92-102. *pl.* 1. 1907.
- SABLON, LECLERC DU, Recherches sur la tige des fougères. Ann. Sci. Nat. Bot. VII. 11:1-16. *pls.* 1, 2. 1890.
- SACHS, J., Lehrbuch. 1868.
- , Textbook of botany. Second English edition. 1882.
- SANDAY, ELIZABETH (with BERRIDGE, ETHEL M.), Oogenesis and embryogeny in *Ephedra distachya*. New Phytologist 6:128-134, 167-174. *pls.* 3, 4. 1907.
- SAXTON, W. T., Parthenogenesis in *Pinus Pinaster*. Bot. Gazette 47:406-409. *figs.* 7. 1909.
- , Development of the embryo in *Pinus Pinaster* Soland., with some notes on the life history of the species in Cape Colony. S. African Jour. Sci. 6:52-59. *pl.* 2. 1909.
- , Preliminary account of the development of the ovule, gametophytes, and embryo of *Widdringtonia cupressoides* Endl. Bot. Gazette 48:161-178. *pl.* 11. *figs.* 3. 1909.
- , The development of the embryo of *Encephalartos*. Bot. Gazette 49:13-18. *pl.* 2. 1910.
- , Contributions to the life history of *Widdringtonia cupressoides*. Bot. Gazette 50:30-48. *pls.* 1-3. 1910.
- , Contributions to the life history of *Callitris*. Annals of Botany 24:July 1910.
- , Notes on the anatomy of *Widdringtonia* and *Callitris*. S. African Jour. Sci. 282-286. *figs.* 11. May 1910.
- SCHLEIDEN, M. J., Sur la signification morphologique du placentaire. Ann. Sci. Nat. Bot. II. 12:373-376. 1839.
- SCHNEIDER, A., Mutualistic symbiosis of algae and bacteria with *Cycas revoluta*. Bot. Gazette 19:25-32. *pl.* 3. 1894.
- SCOTT, D. H. (with WILLIAMSON, W. C.), Further observations on the organization of the fossil plants from the Coal-measures. III. *Lyginodendron* and *Heterangium*. Phil. Trans. Roy. Soc. London B 186:703-779. *pls.* 18-21. 1896.



- SCOTT, D. H., The anatomical characters presented by the peduncles of Cycadaceae. *Annals of Botany* **11**:399-419. *pls.* 20, 21. 1897.
- , On the structure and affinities of fossil plants from the paleozoic rocks. III. *Medullosa anglica*, a new representative of the Cycadofilices. *Proc. Roy. Soc. London* **64**:249-253. 1899 (abstract); *Phil. Trans. Roy. Soc. London B* **191**:81-126. *pls.* 5-13. 1899 (full paper).
- , On the primary wood of certain araucarioxylons. *Annals of Botany* **13**:615-619. 1899.
- , Note on the occurrences of a seedlike fructification in certain paleozoic lycopods. *Proc. Roy. Soc. London* **67**:306-309. 1900.
- , Studies in fossil botany. London. 1900.
- , On the structure and affinities of fossil plants from the paleozoic rocks. IV. The seedlike fructification of *Lepidocarpon*, a genus of lycopodiaceous cones from the Carboniferous formation. *Phil. Trans. Roy. Soc. London B* **194**:291-333. *pls.* 38-43. 1901.
- , Primary structure of certain paleozoic stems. *Trans. Roy. Soc. Edinburgh* **40**:331-365. *pls.* 1-6. *figs.* 5. 1902.
- , The old wood and the new. *New Phytologist* **1**:25-30. 1902.
- (with OLIVER, F. W.), On *Lagenostoma Lomaxii*, the seed of *Lyginodendron*. *Proc. Roy. Soc. London* **71**:477-481. 1903; reprint in *Annals of Botany* **17**:625-629. 1903.
- (with OLIVER, F. W.), On the structure of the paleozoic seed *Lagenostoma Lomaxii*, with a statement of the evidence upon which it is referred to *Lyginodendron*. *Proc. Roy. Soc. London*. Jan. 21, 1904 (abstract preprint); *Phil. Trans. Roy. Soc. London B* **197**:193-247. *pls.* 4-10. 1904 (full paper).
- , What were the carboniferous ferns? *Jour. Roy. Micr. Soc.* **1905**<sup>2</sup>: 137-149. *pls.* 1-3. *figs.* 32, 33.
- , The sporangia of *Stauropteris Oldhamia* Binney. *New Phytologist* **4**:114-120. *figs.* 2. 1905.
- , The fernlike seed plants of the carboniferous flora. *Sci. papers Internat. Bot. Congress Vienna*. 1905.
- , The early history of seed-bearing plants, as recorded in the carboniferous flora (The Wilde Lecture). *Mem. and Proc. Manchester Lit. and Phil. Soc.* **49**<sup>3</sup>: pp. 32. *pls.* 3. 1905.
- , "The origin of gymnosperms"; a discussion at the Linnean Society. *New Phytologist* **5**:68-76, 141-148. 1906.
- , On *Sutcliffia insignis*, a new type of Medulloseae from the Lower Coal-measures. *Trans. Linn. Soc. London II*. **7**:45-68. *pl.* 4. 1906.
- , The present position of paleozoic botany. *Progressus rei botanicae* (J. P. LORSY) **1**<sup>1</sup>:139-217. *figs.* 37. 1906.
- , The occurrence of germinating spores in *Stauropteris Oldhamia*. *New Phytologist* **5**:170-172. 1906.

- SCOTT, D. H., and MASLEN, A. J., The structure of the paleozoic seeds *Trigonocarpus Parkinsonii* Brongniart and *Trigonocarpus Oliveri*, sp. nov. I. *Annals of Botany* **21**:89-134. *pls.* 11-14. 1907.
- , Studies in fossil botany. Second edition. Vol. I. London. 1908.
- , The paleontological record. II. Plants. Darwin and modern science, pp. 200-222. Cambridge University Press. 1909.
- , Studies in fossil botany. Second edition. Vol. II. London. 1909.
- , and MASLEN, A. J., On *Mesoxylon*, a new genus of Cordaitales (preliminary note). *Annals of Botany* **24**:236-239. 1910.
- SELLARDS, E. H., *Codonotheca*, a new type of spore-bearing organ from the Coal-measures. *Amer. Jour. Sci.* **IV**. **16**:87-95. *pl.* 8. 1903.
- , Notes on the spore-bearing organ *Codonotheca* and its relationship with Cycadofilices. *New Phytologist* **6**:175-178. 1907.
- SEWARD, A. C., Notes on the Binney collection of Coal-measure plants. II. *Megaloxydon*, gen. nov. *Proc. Cambridge Phil. Soc.* **10**:158-174. *pls.* 5-7. 1899.
- , and GOWAN, MISS J., The maidenhair tree (*Ginkgo biloba* L.). *Annals of Botany* **14**:109-154. *pls.* 8-10. 1900.
- , Floras of the past; their composition and distribution. *Rept. British Assoc. Sci. Section K* 1903: pp. 25.
- , and FORD, SIBILLE O., The Araucarieae, recent and extinct. Abstract read before Roy. Soc. London, December 1905.
- , Notes on cycads. *Proc. Cambridge Phil. Soc.* **13**:293-302. 1906.
- , "The origin of gymnosperms"; a discussion at the Linnean Society. *New Phytologist* **5**:68-76, 141-148. 1906.
- , and FORD, SIBILLE O., The Araucarieae, recent and extinct. *Phil. Trans. Roy. Soc. London B* **198**:305-411. *pls.* 23, 24. *figs.* 28. 1906.
- SHAW, F. J. F., A contribution to the anatomy of *Ginkgo biloba*. *New Phytologist* **7**:85-92. *figs.* 16-18. 1908.
- , The seedling structure of *Araucaria Bidwillii*. *Annals of Botany* **23**:321-334. *pl.* 21. *figs.* 6. 1909.
- SHAW, W. R., Contribution to the life history of *Sequoia*. *Bot. Gazette* **21**:332-339. *pl.* 24. 1896.
- SINNOTT, E. A. W., *Paracedroxylon*, a new type of araucarian wood. *Rhodora* **11**:165-173. *pls.* 80, 81. 1909.
- SLUDSKY, N., Ueber die Entwicklungsgeschichte des *Juniperus communis*. Vorläufige Mitteilung. *Ber. Deutsch. Bot. Gesell.* **23**:212-216. *pl.* 6. 1905.
- SMITH, FRANCES GRACE, Morphology of the trunk and development of the microsporangium of cycads. *Bot. Gazette* **43**:187-204. *pl.* 10. 1907.
- , Development of the ovulate strobilus and young ovule of *Zamia floridana*. *Bot. Gazette* **50**:128-141. *figs.* 22. 1910.
- SMITH, ISABEL S., The nutrition of the egg in *Zamia*. *Bot. Gazette* **37**:346-352. *figs.* 6. 1904.

- SOKOLOWA, MILE C., Naissance de l'endosperme dans le sac embryonnaire de quelques gymnospermes. Moscou. 1880.
- SOLMS-LAUBACH, H., Die Sprossfolge der *Stangeria* und der übrigen Cycadeen. Bot. Zeit. **48**:177-187, 193-199, 209-215, 225-230. 1890.
- , Ueber die Fructification von *Bennettites Gibsonianus* Carr. Bot. Zeit. **48**:789-798, 805-815, 821-833, 843-847. pls. 9, 10. 1890.
- , Fossil botany. English translation. 1891.
- SOUTH, F. W., and COMPTON, R. H., On the anatomy of *Dioon edule* Lindl. New Phytologist **7**:222-229. 1908.
- SPRECHER, ANDREAS, Le *Ginkgo biloba* L. pp. 208. figs. 225. Genève. 1907.
- STARR, ANNA M., The microsporophylls of *Ginkgo*. Bot. Gazette **49**:51-55. pl. 7. 1910.
- STENZEL, G., Beobachtungen an durchwachsenen Fichtenzapfen. Ein Beitrag zur Morphologie der Nadelhölzer. Nov. Act. Nat. Cur. **38**:289-350. pls. 12-15. 1876.
- STERZEL, J. T. (with WEBER, O.), Beiträge zur Kenntniss der Medulloseae. XIII. Ber. Naturwiss. Gesell. Chemnitz. pp. 102. pls. 9: figs. 33. 1896.
- STILES, W., The anatomy of *Saxegothaea conspicua* Lindl. Svensk. Bot. Tidsskr. **2**:101-122. pls. 7-9. 1908.
- (with BROOKS, F. T.), The structure of *Podocarpus spinulosa* (Smith) R. Br. Annals of Botany **24**:305-318. pl. 21. 1910.
- STOPES, MARIE C., On the leaf structure of *Cordaites*. New Phytologist **2**:91-98. pl. 9. 1903.
- , Beiträge zur Kenntniss der Fortpflanzungsorgane der Cycadeen. Flora **93**:435-482. figs. 37. 1904.
- , On the double nature of the cycadean integument. Annals of Botany **19**:561-566. 1905.
- , A new fern from the Coal-measures: *Tubicaulis Sutcliffii* spec. nov. Mem. and Proc. Manchester Lit. and Phil. Soc. **50**:1-30. pls. 1-3. 1906.
- , and FUJII, K., The nutritive relations of the surrounding tissues to the archegonia in gymnosperms. Beih. Bot. Centralbl. **20**:1-24. pl. 1. 1906.
- , and FUJII, K., Studies on the structure and affinities of cretaceous plants. Phil. Trans. Roy. Soc. London B **201**:1-90. pls. 1-9. 1910; abstract in Annals of Botany **24**:231, 232. 1910.
- STRASBURGER, E., Die Befruchtung bei den Coniferen. 1869.
- , Die Coniferen und die Gnetaceen. 1872.
- , Ueber Zellbildung und Zelltheilung. 1876.
- , Die Befruchtung und Zelltheilung. Jen. Zeitsch. **2**:435-536. pls. 27-35. 1877.
- , Befruchtung und Zelltheilung. 1878.
- , Die Angiospermen und die Gymnospermen. 1879.
- , Neue Untersuchungen, etc. 1884.
- , Histologische Beiträge **3**:151. 1891.

- STRASBURGER, E., Ueber das Verhalten des Pollens und die Befruchtungsvorgänge bei den Gymnospermen. 1892.
- , Anlage des Embryosackes und Prothalliumbildung bei der Eibe nebst anschliessenden Erörterungen. Festschrift zum siebzigsten Geburtstag von ERNST HAECKEL. pp. 18. *pls.* 2. Jena. 1904.
- STUR, D., Zur Morphologie und Systematik der Kulm- und Karbonfarne. Sitzungsab. Akad. Wiss. Wien **88**: pp. 214. *figs.* 4. 1883.
- TANSLEY, A. G., Lectures on the evolution of the filicinean vascular system. II. The Botryopteridae. New Phytologist **6**: 53-68. *figs.* 22. 1907.
- THIBOUT, E., Recherches sur l'appareil mâle des gymnospermes. pp. 265. *pls.* 16. Lille. 1896.
- THIESSEN, REINHARDT, The vascular anatomy of the seedling of *Dioon edule*. Bot. Gazette **46**: 357-380. *pls.* 23-29. 1908.
- THOMAS, ETHEL N., "The origin of gymnosperms"; a discussion at the Linnean Society. New Phytologist **5**: 68-76, 141-148. 1906.
- , A theory of the double leaf trace founded on seedling structure. New Phytologist **6**: 77-91. *figs.* 4. 1907.
- THOMPSON, W. P., On the origin of ray tracheids in the Coniferae. Bot. Gazette **50**: 101-116. *figs.* 16. 1910.
- THOMSON, R. B., Preliminary note on the Araucarineae. Science N.S. **22**: 88. 1905.
- , The megaspore membrane of the gymnosperms. Univ. Toronto Biol. Series no. 4. pp. 64. *pls.* 5. 1905.
- , "The origin of gymnosperms"; a discussion at the Linnean Society. New Phytologist **5**: 68-76, 141-148. 1906.
- , Note on the pollen of *Microcachrys*. Bot. Gazette **46**: 465, 466. 1908.
- , On the pollen of *Microcachrys tetragona*. Bot. Gazette **47**: 26-29. *pls.* 1, 2. 1909.
- , The megasporophyll of *Saxegothaea* and *Microcachrys*. Bot. Gazette **47**: 345-354. *pls.* 21-25. 1909.
- TISON, A., Le nucelle stigmatifère et la pollination chez le *Saxegothaea conspicua*. Compt. Rend. Acad. Sci. Paris **147**: 137-139. 1908.
- , Sur le *Saxegothaea* Lindl. Mém. Soc. Linn. Normandie **23**: 139-160. *pls.* 9, 10. 1909.
- TREUB, M., Recherches sur les Cycadées. Ann. Jard. Bot. Buitenzorg **2**: 32-53. *pls.* 1-7. 1881 (date of preprint, volume date being 1885).
- , Recherches sur les Cycadées. 3. Embryogenie du *Cycas circinalis*. Ann. Jard. Bot. Buitenzorg **4**: 1-11. *pls.* 1-3. 1884.
- VAN TIEGHEM, PH., Anatomie comparée de la fleur femelle et du fruit des Cycadées, des Conifères, et des Gnetacées. Ann. Sci. Nat. Bot. V. **10**: 269-304. *pls.* 13-16. 1869.
- , Recherches sur le symétrie de structure des plantes vasculaires. Ann. Sci. Nat. Bot. V. **13**: 1-314. *pls.* 3-8. 1870.



- VAN TIEGHEM, PH.; et DOULIOT, H., Sur la polystélie. Ann. Sci. Nat. Bot. VII. 3:275-322. pls. 13, 14. 1886.
- , Traité de botanique. Paris. 1891.
- VIERHAPPER, F., Entwurf eines neuen Systemes der Coniferen. Abhandl. K. K. Zool.-Bot. Gesell. Wien 5:1-56. 1910.
- VON MOHL, HUGO, Ueber den Bau des Cycadeenstammes. Abh. K. Acad. München 1:397-442. 1832; republished and revised in Vermischte Schriften, pp. 195-211. 1845.
- , Ueber die männlichen Blüten der Coniferen. Verm. Bot. Schriften, pp. 45-61. 1845. (Published as a dissertation, 1837.)
- , Morphologische Betrachtung der Blätter von *Sciadopitys*. Bot. Zeit. 29:17-23. 1871.
- WARD, LESTER F., The Cretaceous formation of the Black Hills as indicated by the fossil plants. 19th Annual Report U.S. Geol. Survey. 1900.
- , Description of a new genus and twenty new species of fossil cycadean trunks from the Jurassic of Wyoming. Proc. Wash. Acad. Sci. 1:253-300. pls. 14-21. 1900.
- , Elaboration of the fossil cycads in the Yale Museum. Amer. Jour. Sci. IV. 10:327-345. pls. 2-4. 1900.
- WARMING, E., Recherches et remarques sur les Cycadées. Oversigter Vidensk. Selsk. Forh. 1877.
- , Contributions à l'histoire naturelle des Cycadées. Oversigter Vidensk. Selsk. Forh. 1879.
- WATSON, SERENO, Botany King's Exp. 1871.
- WEBBER, H. J., Peculiar structures occurring in the pollen tube of *Zamia*. Bot. Gazette 23:453-459. pl. 40. 1897.
- , The development of the antherozoids of *Zamia*. Bot. Gazette 24:16-22. 1897.
- , Notes on the fecundation of *Zamia* and the pollen tube apparatus of *Ginkgo*. Bot. Gazette 24:225-235. pl. 10. 1897.
- , Spermatogenesis and fecundation of *Zamia*. U.S. Dept. Agric., Bur. Pl. Ind., Bull. 2. pp. 100. pls. 7. 1901.
- WEBER, O., und STERZEL, J. T., Beiträge zur Kenntniss der Medulloseae. XIII. Ber. Naturwiss. Gesell. Chemnitz. pp. 102. pls. 9. figs. 33. 1896.
- WEISS, F. E., "The origin of gymnosperms"; a discussion at the Linnean Society. New Phytologist 5:68-76, 141-148. 1906.
- WETTSTEIN, R. VON, Der Ursprung des Pollenschlauches. Naturw. Rundschau 21:12. 1906.
- WHITE, DAVID, The seeds of *Aneimites*. Smithson. Miscell. Coll. 47:322-331. pls. 47, 48. 1904.
- , Fossil plants of the group Cycadofilices. Smithson. Miscell. Coll. 47:377-390. pls. 53-55. 1904.
- WIELAND, G. R., A study of some American fossil cycads. I. The male flower of *Cycadeoidea*. Amer. Jour. Sci. IV. 7:223-226. pls. 2-4. 1899.

- WIELAND, G. R., A study of some American fossil cycads. II. The leaf structure of *Cycadeoidea*. Amer. Jour. Sci. IV. 7:305-308. *pl.* 7. 1899.
- , A study of some American fossil cycads. III. The female fructification of *Cycadeoidea*. Amer. Jour. Sci. IV. 7:383-391. *pls.* 8-10. 1899.
- , The Yale collection of fossil cycads. Yale Sci. Monthly 6:1-11. *pl.* 1. 1900.
- , A study of some American fossil cycads. IV. On the microsporangiate fructification of *Cycadeoidea*. Amer. Jour. Sci. IV. 11:423-436. 1901.
- , The proembryo of Bennettitaceae. Amer. Jour. Sci. IV. 18:445-447. *pl.* 20. 1904.
- , American fossil cycads. Publ. no. 34, Carnegie Institution of Washington. pp. 296. *pls.* 50. *figs.* 138. 1906.
- , Historic fossil cycads. Amer. Jour. Sci. IV. 25:93-101. 1908.
- , The Williamsonias of the "Mixteca Alta." Bot. Gazette 48:427-441. *figs.* 10. 1909.
- WIGGLESWORTH, GRACE, The cotyledons of *Ginkgo biloba* and *Cycas revoluta*. Annals of Botany 17:789-791. 1903.
- WILD, G., On *Trigonocarpum olivaeforme*. Trans. Manchester Geol. Soc. 26: pp. 16. *pl.* 2. 1900.
- WILLIAMSON, W. C., On the structure and affinities of the plants hitherto known as Sternbergiae. Mem. Manchester Lit. and Phil. Soc. 14:340-358. *pl.* 10. 1851.
- , Contributions towards the history of *Zamia gigas*. Trans. Linn. Soc. Bot. 26:663-674. *pls.* 52, 53. 1870.
- , On the organization of the fossil plants of the Coal-measures. IV. *Dictyoxylon*, *Lyginodendron*, and *Heterangium*. Phil. Trans. Roy. Soc. London B 163:377-408. *pls.* 22-31. 1873.
- , On some fossil seeds from the Lower Carboniferous beds of Lancashire. Rep. 45th Meeting British Assoc. (1875): 159-160. 1876.
- , On the organization, etc. VIII. Ferns (continued) and gymnospermous stems and seeds. Ann. Mag. Nat. Hist. 18:268-273. 1876 (preliminary notice); Proc. Roy. Soc. London 25:68-73. 1877 (abstract); Phil. Trans. Roy. Soc. London B 167:213-270. *pls.* 5-16. 1878 (full paper).
- , On the organization, etc. X. Phil. Trans. Roy. Soc. London B 171: 493-539. *pls.* 14-21. 1880.
- , On the organization, etc. XII. Phil. Trans. Roy. Soc. London B 174: 459-475. *pls.* 27-34. 1883.
- , On the organization, etc. XIII. Phil. Trans. Roy. Soc. London B 178:289-304. *pls.* 21-24. 1887 (p. 299).
- , On the organization, etc. XVII. Phil. Trans. Roy. Soc. London B 181:89-106. *pls.* 12-15. 1890.
- , and SCOTT, D. H., Further observations on the organization of the fossil plants from the Coal-measures. III. *Lyginodendron* and *Heterangium*. Phil. Trans. Roy. Soc. London B 186:703-779. *pls.* 18-21. 1896.

- WORSDELL, W. C., Anatomy of stems of *Macrozamia* compared with that of other genera of Cycadeae. *Annals of Botany* **10**:601-620. *pls.* 27, 28. 1896.
- , On transfusion tissue; its origin and function in the leaves of gymnospermous plants. *Trans. Linn. Soc. Bot. II*. **5**:301-319. *pls.* 23-26. 1897.
- , The structure of the female "flower" in Coniferae. *Annals of Botany* **14**:39-82. 1900.
- , The anatomical structure of *Bowenia spectabilis*. *Annals of Botany* **14**:159, 160. 1900.
- , The vascular structure of the ovule of *Cephalotaxus*. *Annals of Botany* **14**:317, 318. 1900.
- , The affinities of the mesozoic fossil *Bennettites Gibsonianus*. *Annals of Botany* **14**:717-721. 1900.
- , The evolution of the vascular tissue of plants. *Bot. Gazette* **34**:216-223. *figs.* 7. 1902.
- , The structure and origin of the Cycadaceae. *Annals of Botany* **20**:129-159. *figs.* 17. 1906.
- , "The origin of gymnosperms"; a discussion at the Linnean Society. *New Phytologist* **5**:68-76, 141-148. 1906.
- WOYCICKI, Z., (On fertilization in Coniferae). pp. 57. *pls.* 2. 1899. (Russian)
- YOUNG, MARY S., The male gametophyte of *Dacrydium*. *Bot. Gazette* **44**:189-196. *pl.* 19. 1907.
- , The morphology of the Podocarpaceae. *Bot. Gazette* **50**:81-100. *pls.* 4-6. 1910.
- ZACH, FRANZ, Studie über Phagocytose in den Wurzelknöllchen der Cycadeen. *Oesterreich. Bot. Zeitsch.* **60**:49-55. *pl.* 2. 1910.
- ZEILLER, R., *Elements de palaeobotanique*. 1900.
- , et FLICHE, P., Découverte de strobiles de *Sequoia* et de Pin dans le Portlandien des environs de Boulogne-sur-Mer. *Compt. Rend. Acad. Sci. Paris* **137**:1020-1022. 1903.
- (with FLICHE, P.), Note sur un florule portlandienne des environs de Boulogne-sur-Mer. *Bull. Soc. Geol. France IV*. **4**:787-812. 1904.
- , Une nouvelle classe de Gymnospermes: les Pteridospermées. *Rev. Gen. Sci.* **16**:718-727. *figs.* 7. 1905.

## INDEX

Pages containing illustrations are indicated by italic figures.

### A

- Abies*, strobilus 239, 246  
*Abietineae* 220; archegonium 267; distribution 301; history 303; proembryo 288, 289, 290; prothallial tissue 277  
*Adiantum*, amphiphloic siphonostele 6; leaf gap 10  
*Agathis*, microsporangium 240; shoot 236; strobilus 240, 324  
*Amphiphloic siphonostele* 5; *Adiantum* 6  
*Amyelon* 171  
*Aneimites* 24; seed 39, 40  
*Angiocyads* 74  
*Antholithus* 193  
*Anthostrobilus* 74  
*Araucaria*, embryo 297, 298; habit 225; ovuliferous bract 248; prothallial tissue 278; strobilus 240, 247, 324  
*Araucarineae* 221; archegonium 271; distribution 302; history 305; prothallial tissue 277, 278  
*Araucariopitys* 306, 308  
*Archegonium*, *Abietineae* 267; *Araucarineae* 271; *Cordaitales* 179; *Cupressineae* 269; *Cycadales* 133, 135, 136, 137, 138; evolutionary tendencies 420; *Ginkgoales* 205, 208, 211; *Gnetales* 385, 386; *Pinaceae* 263, 264, 266, 267; *Taxaceae* 330; *Taxodineae* 268

### B

- Baiera*, leaf 189  
*Bars of Sanio*, *Pinaceae* 235  
*Bennettitales* 65; distribution 85; embryo 67; history 85; leaf 71; male gametophyte 82; megasporangium 78; microsporangium 75; relationship 86; strobilus 72, 73, 76, 79, 80, 81, 82; vascular anatomy 70; vegetative organs 66

- Bennettites*, seed 83, 84; strobilus 79  
*Blepharoplast* 142  
*Botryopterideae* 54  
*Botryopteris* 54  
*Brachyoxylon* 306, 308  
*Brachyphyllum* 308

### C

- Calamopitys* 20  
*Calymmatotheca* 27  
*Cephalotaxus*, embryo 299; male cell 339; pollination drops 275  
*Ceratozamia*, embryo 155; megaspore 127; megasporophyll 124, 131; vascular plate 99, 100, 101, 103  
*Chromosomes*, *Gnetales* 384; *Pinaceae* 259; *Taxaceae* 329  
*Cladosiphonic siphonostele* 9  
*Cladoxylon* 20  
*Codonotheca* 28, 29  
*Colpoxylon* 20  
*Coniferales* 220; archegonium 263, 264, 270, 330; chromosomes 259, 329; distribution 301, 349; embryo 287, 288, 289, 290, 291, 292, 293, 294, 295, 296, 297, 298, 299, 346, 347, 349; female gametophyte 259, 260, 261, 329, 330, 337; fertilization 284, 286, 287, 344, 345; history 303, 349; interrelationship of tribes 308; juvenile leaves 227; leaf 235, 236, 237, 317, 318; list of genera 353; male gametophyte 272, 273, 276, 335, 336, 337, 339, 340, 342; megasporangium 244, 254, 255, 256, 321, 327; megaspore 257, 258; megaspore membrane 271; microsporangium 239, 240, 241, 243, 272, 319; microspore 274; microsporophyll 239, 240; relationship 309, 350; seed 300; seedling 231; stamen 319; strobilus 238, 239, 240, 244, 246, 247, 319, 320,



- 321, 322, 323, 324; vascular anatomy 228, 315; vegetative organs 222, 315; ventral canal cell 266, 267
- Coniferophytes 59
- Conostoma 37
- Cordaianthus 173, 175; ovules 176, 177; microspore 177; stamen 174
- Cordaitales 163; archegonium 179; distribution 180; embryo 180; female gametophyte 179; history 180; leaf 168, 169, 170; male gametophyte 177, 178; megasporangium 174; microsporangium 172, 173, 174; microspore 177; relationship 180; root 171; stamen 174; strobilus 172, 173, 175; vascular anatomy 165; vegetative organs 164
- Cordaites, leaf 169, 170; root 171; stem section 165, 166, 167; strobilus 172
- Cotyledon, evolutionary tendencies 428, 429; Pinaceae 297
- Crossotheca 25, 26, 27, 28, 29
- Cryptomeria, female gametophyte 261; male gametophyte 279; strobilus 324
- Cunninghamia, male gametophyte 279; proembryo 291; strobilus 324
- Cupressineae 221; archegonia 269, 270; distribution 301; history 305; male cell 280; proembryo 293, 294; prothallial tissue 277
- Cupressus, male gametophyte 280; strobilus 324
- Cycadales 91; archegonium 133, 135; distribution 156; embryo 150, 151, 152, 153, 154, 155; female gametophyte 132, 137; fertilization 148, 150; history 156; leaf 108, 109, 110; male gametophyte 139, 141, 143, 144; megasporangium 121; megaspore 127; megaspore membrane 139; megasporophyll 124, 131; microsporangium 114, 118, 119, 120; microspore 140; microsporophyll 116, 117; relationship 157; root 112, 113; seedling structure 98, 99, 100, 101, 102, 103, 104, 105, 106; sperm 145, 146, 147; strobilus 114, 122, 123, 125; vascular anatomy 93; vegetative organs 93
- Cycadella, ramentum 70
- Cycadeoidea, microsporophyll 77; seed 84; strobilus 73, 76, 80, 81, 82; synangium 78; trunk 57
- Cycadinocarpus, ovule section 179
- Cycadofilicales 1; distribution 51; embryo 46; female gametophyte 48; history 51; leaf 1, 21, 22, 24; male gametophyte 49; megasporangium 31; microsporangium 25, 26, 27, 28, 29; microspore 49, 50; origin 55; relationship 51, 58; seed 31, 32, 33, 34, 35, 36, 38, 39, 40, 42, 43, 44, 45; vascular anatomy 12; vegetative organs 3
- Cycadophytes 59
- Cycadoxylon 16, 17
- Cycas, archegonium 135; embryo 152; leaf 109, 111; male gametophyte 143; megaspore membrane 139; megasporophyll 124; microsporophyll 117; root tubercle 113; seed 130; sperm 145; strobilus 123; ventral nucleus 136

## D

- Dacrydium, male gametophyte 340
- Dadoxylon 168
- Dioon, archegonium 133, 135, 138; embryo 153, 154; female gametophyte 132; fertilization 149; habit 92, 94; leaf 110, 111; male gametophyte 141; megaspore membrane 139; megasporophyll 124; microsporangium 120; microsporophyll 116; ovule 126, 128, 129; pollen tube 128; seedling structure 104, 105; sperm 146; strobilus 122, 125; ventral nucleus 136
- Dorycordaites 164

## E

- Ectophloic siphonostele 5; Osmunda 7
- Embryo, Bennettitales 83, 84; Cordaitales 180; Cycadales 150, 151, 152, 153, 154, 155; Cycadofilicales 46; evolutionary tendencies 426; Ginkgoales 210, 211, 212, 213; Gnetales 393, 394, 395, 397, 398, 400; Pinaceae 287, 288, 289, 290, 291, 292, 293, 294, 295, 296, 297, 298, 299; Taxaceae 346, 347, 348, 349

- Embryonal tubes, Pinaceae 295, 296, 297
- Encephalartos, archegonium 135; megasporophyll 124, 131
- Endarch 10, 11
- Endosperm, *see* female gametophyte
- Ephedra, archegonium 386; embryo 394, 395, 397; female gametophyte 377, 384; fertilization 392; habit 364; male gametophyte 390, 391; megaspore 385; ovule 377; strobilus 372
- Euanthostrobilus 74
- Evolutionary tendencies 406
- Exarch 10, 11
- F
- Female gametophyte, Cordaitales 179; Cycadales 132; Cycadofilicales 48; evolutionary tendencies 419; Ginkgoales 203, 204, 208; Gnetales 375, 377, 379, 382, 383, 384; Pinaceae 259, 260, 261; Taxaceae 329, 330, 337
- Ferns, paleozoic 52; relationship to Cycadofilicales 51
- Fertilization, Cycadales 148, 150; evolutionary tendencies 423; Ginkgoales 209; Gnetales 391, 392; Pinaceae 284, 286, 287; Taxaceae 344, 345
- Flower, Gnetales 371, 372, 373, 375, 377, 380
- G
- Gametophytes, *see* male gametophyte and female gametophyte
- Ginkgo, archegonium 208, 211; cotyledon section 188; embryo 211, 212, 213; female gametophyte 204, 208; habit 186; leaf 187, 190, 199; male gametophyte 207; ovulate strobilus 195, 196, 197, 198; ovule 195, 196, 197, 198, 200, 201, 202; peduncle section 199; seedling 190; staminate strobilus 191, 192, 193
- Ginkgoales, archegonium 205, 208, 211; distribution 215; embryo 210, 211, 212, 213; female gametophyte 203, 204, 208; history 215; leaf 187, 189, 190, 199; male gametophyte 206, 207; megasporangium 194, 200, 201, 202; megaspore membrane 204, 205; microsporangium 191, 192, 193; microsporophyll 191, 192, 193; peduncle section 199; relationship 216; seedling 188, 190; strobilus 190, 191, 192, 193, 195, 196, 197, 198; vascular anatomy 187; vegetative organs 185
- Gleichenia, protostele 5
- Gnetales 363; archegonium 385, 386; chromosomes 384; distribution 402; embryo 393, 394, 395, 397, 398, 400; female gametophyte 375, 377, 379, 382, 383, 384; fertilization 391, 392; history 402; leaf 369; male gametophyte 389, 390, 391; megasporangium 375, 376, 377; megaspore 384; ovule 376, 377, 380, 382; microsporangium 371; relationship 402; seedling 399; stamen 380; strobilus 370, 372, 374, 375, 376, 380; vascular anatomy 366; vegetative organs 364
- Gnetopsis 37
- Gnetum, embryo 400; female gametophyte 375, 382, 383; flower 375; habit 367, 370; megasporangium 375; ovule 376, 380, 382; strobilus 375, 376, 380
- H
- Hemiangiosperms 74
- Heterangium 12
- J
- Juniperus, fertilization 287; proembryo 294
- K
- Kaloxylon 14
- L
- Lagenostoma 31, 32, 33, 34, 35; microspore 49
- Larix, megasporangium 255; strobilus 246
- Leaf gap 9; Adiantum 10
- Leaf, Bennettitales 71; Cordaitales 168, 169, 170; Cycadales 108, 109, 110; Cycadofilicales 1, 21, 22, 24; evolutionary tendencies 412; Ginkgoales 187, 189, 190; Gnetales 369, 370;

Pinaceae 235, 236, 237; Taxaceae  
317, 318  
Libocedrus, male gametophyte 280  
Lyginodendron 13, 14, 15, 16

## M

Male cell, evolutionary tendencies 423;  
Pinaceae 276, 277, 279, 280; Taxineae  
338, 339  
Male gametophyte, Bennettitales 82;  
Cordaitales 177, 178; Cycadales 139,  
141, 143, 144; Cycadofilicales 49;  
evolutionary tendencies 421; Gink-  
goales 206, 207; Gnetales 389, 390,  
391; Pinaceae 273, 276; Podocarpi-  
neae 339, 340, 342; Taxaceae 335,  
337, 339, 340, 342; Taxineae 335, 337  
Marattiaceae, paleozoic 53  
Medullary ray, Pinaceae 232  
Medullosa 17, 18, 19; seed 38, 40  
Megaloxylon 15  
Megasporangium, Bennettitales 78; Cor-  
daitales 174; Cycadales 121; Cycad-  
ofilicales 31; Ginkgoales 194, 200,  
201, 202; Pinaceae 244, 254, 255,  
256; Taxaceae 321, 327  
Megaspore, Cycadales 127; Pinaceae  
257, 258; Gnetales 384  
Megaspore membrane, Cycadales 139;  
Ginkgoales 204, 205; Pinaceae 271;  
Taxaceae 332  
Megasporophyll, Cycadales 124, 130, 131  
Mesarch 10, 11  
Microcachrys, male gametophyte 341;  
strobilus 320, 324  
Microcycas, female gametophyte 137;  
megasporophyll 131; seedling struc-  
ture 106; sperm 147  
Microsporangium, Bennettitales 75; Cor-  
daitales 172; Cycadales 114, 118,  
119, 120; Cycadofilicales 25, 26, 27,  
28, 29; Ginkgoales 191, 192, 193;  
Gnetales 371; Pinaceae 239, 240, 241,  
243, 272; Taxaceae 319  
Microspore, Cordaitales 177; Cycadales  
140; Pinaceae 274  
Microsporophyll, Bennettitales 77; Cycad-  
dales 116, 117; Pinaceae 239, 240, 241

## N

Neuropteris 23, 24; frond 4; seed 38, 40

## O

Osmunda, ectophloic siphonostele 7  
Ovule, Cordaitales 174, 175, 176, 177;  
Cycas 130; Dioon 126, 128, 129;  
evolutionary tendencies 416; Gink-  
goales 195, 196, 197, 198, 200, 201, 202;  
Gnetales 376, 377, 380, 382; Pinaceae  
245, 251, 254; Taxaceae 322, 323, 324

## P

Pachytista 41  
Paleozoic ferns 52; seeds 42  
Parthenogenesis, Pinaceae 300  
Pecopteris 23; seed 40  
Phyllocladus, archegonium 342, 343;  
fertilization 345; juvenile leaves 227;  
male gametophyte 341, 342; pollen  
tube 343; shoot 316  
Phyllosiphonic siphonostele 9  
Phylogeny 407, 408, 409  
Physostoma 34, 36; microspore 50  
Pinaceae 220; archegonium 263, 264,  
270; chromosomes 259; distribution  
301; embryo 287, 288, 289, 290, 291,  
292, 293, 294, 295, 296, 297, 298, 299;  
female gametophyte 259, 260, 261;  
fertilization 284, 286, 287; history 303;  
interrelationship of tribes 308; juvenile  
forms 222, 227; leaf 235, 236, 237;  
male gametophyte 272, 273, 276;  
megasporangium 244, 254, 255, 256;  
megaspore 257, 258; megaspore mem-  
brane 271; microsporangium 239,  
240, 241, 243, 272; microspore 274;  
microsporophyll 239, 240; ovule 251,  
254; prothallial tissue 277, 278; rela-  
tionship 309; seed 300; seedling 231;  
strobilus 238, 239, 240, 244, 246, 247,  
252; vascular anatomy 228; vegetative  
organs 222; ventral canal cell 266,  
267  
Pinus, archegonium 263, 264; embryo  
288, 289, 290, 296; female gametophyte  
260; fertilization 286; leaf section  
237; male gametophyte 273, 276;

- megasporangium 256; megaspore 257;  
 microsporangium 243, 272; micro-  
 spore 274; ovule 245, 254; secondary  
 wood section 229; seed 300; strobilus  
 238, 245, 246, 252; ventral canal cell  
 266, 267  
 Pitys 168  
 Pityoxylon 304  
 Platysperms 42  
 Podocarpaceae 313; archegonium 331;  
 male gametophyte 339, 340, 342  
 Podocarpus, habit 314; leaf 318; male  
 gametophyte 341; strobilus 324  
 Polycotyledony 297  
 Polystele 5, 8  
 Poroxylon, stem 166  
 Prepinus 304, 308  
 Primofilices 54  
 Proangiosperms 75  
 Proanthostrobilus 74  
 Proembryo, Ephedra 395; Pinaceae 288,  
 289, 290, 291, 292, 293, 294; Taxaceae  
 346, 347, 349  
 Prothallial tissue, Pinaceae 277, 278;  
 Podocarpaceae 339  
 Protoitys 20  
 Protostele 4; Gleichenia 5  
 Pseudotsuga, habit 223  
 Pteridophytes, vascular anatomy 4  
 Pteridostrobilus 75  
 Pteris, polystele 8
- R
- Rachiopteris 13  
 Radiosperms 42  
 Resin canal, Pinaceae 233  
 Retinospora 225  
 Root, Cycadales 112, 113
- S
- Saxegothaea, male gametophyte 341;  
 ovule 327  
 Sciadopitys, proembryo 292  
 Seed, Cycadofilicales 31, 32, 33, 34, 35,  
 36, 38, 39, 40; paleozoic 42; Pinaceae  
 300; Stephanospermum 42, 43; Tax-  
 aceae 325; Torreya 332, 333  
 Seedling, Cycadales 98, 99, 100, 101,  
 102, 103, 104, 105, 106; evolutionary  
 tendencies 427; Ginkgoales 188, 190;  
 Pinaceae 231; Welwitschia 399  
 Sequoia, habit 224; megaspore 258;  
 proembryo 292  
 Siphonostele 4; amphiphloic 5, 6;  
 cladosiphonic 9; ectophloic 5, 7;  
 phyllosiphonic 9  
 Solenostele 5  
 Sperm, Cycadales 145, 146, 147; evolu-  
 tionary tendencies 423  
 Sphaerostoma 37  
 Sphenopteris 22  
 Spicular cells, Welwitschia 369  
 Stamen, Cordaitales 174; evolutionary  
 tendencies 415; Ginkgoales 191, 192,  
 193; Gnetales 371, 380; Pinaceae  
 241; Taxaceae 319  
 Stangeria, megaspore 127; megasporo-  
 phyll 130; microsporangium 119  
 Stauropteris 30  
 Stephanospermum 42, 43; microspore  
 49, 50  
 Strobilus, Bennettitales 72, 73, 76, 79,  
 80, 81, 82; Cordaitales 172, 173, 175;  
 Cycadales 114, 122, 123, 125; evolu-  
 tionary tendencies 413; Ginkgoales  
 190, 191, 192, 193, 195, 196, 197, 198;  
 Gnetales 370, 372, 374, 375, 376, 380;  
 Pinaceae 238, 239, 240, 244, 246, 247,  
 252; Taxaceae 319, 320, 321, 322,  
 323, 324  
 Suspensor, Pinaceae 295; Taxaceae 348,  
 349  
 Sutcliffia 20  
 Syngangium, Cycadeoidea 78
- T
- Taxaceae 220; archegonium 330; chro-  
 mosomes 329; distribution 349; em-  
 bryo 346, 347, 348, 349; female game-  
 tophte 329, 330, 337; fertilization  
 344, 345; history 349; leaf 317, 318;  
 megasporangium 321, 327; megaspore  
 membrane 332; microsporangium 319;  
 relationship 350; stamen 319; stro-  
 bilus 319, 320, 321, 322, 323, 324;  
 vascular anatomy 315; vegetative  
 organs 315



Taxineae 313; archegonia 332; male cell 337, 338, 339; male gametophyte 335, 336, 337

Taxodineae 221; archegonium 268; distribution 301; history 304; male cell 279; proembryo 291, 292; prothallial tissue 277

Taxodium, embryo 297; habit 226; male gametophyte 279; proembryo 291

Taxus, female gametophyte 330; male cell 338; megasporangium 328; microsporangium 243

Thuja, archegonium 270; juvenile leaves 227; male gametophyte 280; proembryo 293

Torreya, embryo 347, 349; female gametophyte 337; male gametophyte 336, 337; microspore 336; ovulate branch 322; ovulate strobilus 323; seed 332, 333

Trigonocarpum 41, 44, 45

Tumboa 363

Tyloses, Pinaceae 235

## V

Vascular anatomy, Bennettitales 70; Cordaitales 165; Cycadales 93; Cycadofilicales 12; endarch 10, 11; evolutionary tendencies 411; exarch 10, 11;

Ginkgoales 187; Gnetales 366; leaf gap 9, 10; mesarch 10, 11; Pinaceae 228; polystele 5, 8; protostele 4, 5; Pteridophytes 4; siphonostele 4, 6, 7, 9; solenostele 5; Taxaceae 315

Ventral canal cell, Pinaceae 265, 266, 267; Taxaceae 331

Ventral nucleus, Cycadales 136

## W

Welwitschia, embryo 398; female gametophyte 379; flower 373; habit 365, 366; seedling 399; spicular cells 369; strobilus 374

Williamsonia, habit 68, 69

## Y

Yezonia 307

Yezostrobus 307

## Z

Zamia, embryo 151; fertilization 150; habit 112; leaf 110; male gametophyte 144; megaspore 127; megasporophyll 124; microspore 140; microsporophyll 117; sperm 145; stem apex 115; stem section 96

Zygopteris 54; sporangium 55













